VIDHYASAATHY

Saathy Chapter Library

Every chapter you gave me — maths and social science — arranged, bookmarked and compressed into one book.

Ganita Manjari — Part 1
Chapters 1–8 · Mathematics

Ganita Manjari — Part 2
Chapters 9–14 · Mathematics

Social Science — Part 1
India and Beyond · Ch 3, 8, 9

Social Science — Part 2
India and Beyond · Ch 1–6

23	578	1
CHAPTERS	PAGES	FILE

Contents

Ganita Manjari · Part 1

1. Orienting Yourself: The Use of Coordinates — 3
2. Introduction to Linear Polynomials — 18
3. The World of Numbers — 43
4. Exploring Algebraic Identities — 70
5. I'm Up and Down, and Round and Round — 94
6. Measuring Space: Perimeter and Area — 120
7. The Mathematics of Maybe: Introduction to… — 157
8. Predicting What Comes Next: Sequences and… — 176

Ganita Manjari · Part 2

9. Propositions and their Converses — 203
10. How Quantities Combine: Understanding Data — 210
11. The World of Algorithms — 239
12. Quadrilaterals — 253
13. Two Variables, One Line — 287
14. Math of Space: Surface Area and Volume — 325

Social Science · Part 1

3. Atmosphere and Climate — 367
8. Building Blocks in Economics: The Problem… — 389
9. The Price Puzzle: What Drives the Market — 401

Social Science · Part 2

1. Oceans and Life — 427
2. Life on Earth — 447
3. Resistance and Resilience (1000–1700 CE) — 471
4. Governance and Public Policy — 507
5. Managing Your Personal Finances — 533
6. From Ideas to Startups — 551

1 Orienting Yourself: The Use of Coordinates

0804CH01

1.1 Introduction

A system of coordinates is a structured framework (like the grid lines on a map or graph paper) that enables us to use numbers to describe the exact physical locations of points or objects.

The idea of 'grid-based thinking' and the geometry required to define the locations of points in space—indeed has deep roots in Bhārat. The first systematic use of grids occurred thousands of years ago — on a massive urban scale—in the Sindhu-Sarasvatī Civilisation, where city streets were constructed with striking precision in North–South and East–West directions at uniform distances of about 10 metres apart. This was a coordinate system in practice: a merchant could find a shop or a warehouse by counting North–South and East–West units of distance from the city centre. Baudhāyana (c. 800 C.E.), as we have seen, later used East–West and North–South lines for his deep geometric constructions, developing the Baudhāyana–Pythagoras Theorem and thus laying the foundation of coordinate geometry.

Putting coordinates on the Earth's surface later became important for navigation. Ujjayinī was described in the ancient world—at least as early as the 4th century BCE in the early Siddhāntas—as the point marking the central longitude meridian from which all other locations were measured. The Greek mathematician Ptolemy (c. 150 BCE), building on earlier works including that of Hipparchus, later described the latitudes and longitudes of thousands of locations, including 'Ozine' (Ujjayinī). Āryabhaṭa (c. 499 CE) replaced the Greek 'chords' with 'sines', making it much easier to calculate the coordinates of a star or a city. He mapped the sky using Celestial Coordinates, measuring coordinate distances from the ecliptic (the path of the sun).

Brahmagupta (c. 628 CE) formalised the notion and use of zero and the negative numbers as algebraic entities; in modern coordinate systems, the 'origin' is zero and the 'negative axes' represent values less than zero. Without Brahmagupta's work, the four-quadrant Cartesian plane, as we will study in this chapter, would be impossible.

Brahmagupta's work was translated into Arabic (as the Sindhind), and the Ujjayinī meridian entered Arabic geography under the name 'Arin,' serving as the zero-longitude reference for early Arabic maps which also then made use of negative numbers. The influential Arab scholar Al-Bīrūnī (c. 1000 CE) travelled to India, studied the Siddhāntas, and used Indian trigonometric methods to calculate the coordinates of various cities across Asia. Al-Bīrūnī also later perfected the 'astrolabe', a handheld device that allowed sailors to find their coordinates by looking at the stars. Ömar Khayyām (c. 1100 CE), who had become an expert in the Indian decimal system and algebraic formalism, was the first mathematician to solve algebraic problems using geometry by interpreting them in terms of coordinates in the plane.

These concepts eventually reached Europe in the 12th century. The final leap occurred when following the related work of Fermat (1636 CE), René Descartes (1637 CE) formalised the fact that any point in a two-dimensional plane could be defined by simply two numbers—representing the point's distances from two perpendicular axes. Points and more complex geometric shapes could then be described precisely using algebra and equations, thus bringing the areas of geometry and algebra even closer together.

In Grades 9 and 10, you will have a chance to study this amazing coordinate system which has such a rich history in human thought and endeavour. You will be able to locate objects with pinpoint accuracy. You will also see how using coordinates enables us to visualise algebraic equations as geometric shapes, and vice versa.

We begin our study of coordinates with a story that will help you understand these new terms better.

1.2 Settling In

It is the beginning of the academic year and Reiaan is both excited and nervous. The family has just moved to a new city. He and his sister, Shalini, will be attending a new school. Today, Shalini will help him settle into the new environment. When someone is not able to see, this can be a very big challenge, but with their mother's transferable job, the siblings have done it often, and it has become easier with each move.

Shalini has just completed Grade 9 and this time, she decided to put to use what she has learnt in Coordinate Geometry in Mathematics to guide Reiaan.

Shalini wanted Reiaan to feel the directions, so she used a rectangular grid on which she had fixed pins and threads. This showed

© NCERT not to be republished

the floor of the room. Points in the sketch were marked using pins. Shalini was using a scale of 1 cm : 1 foot. She used pins to mark out various key points of the room. Points representing the corners of objects were connected with thick wool so that Reiaan could feel their positions with his fingers.



Fig. 1.1: Sketch of Reiaan's room

Let us examine Fig. 1.1 to understand the layout of the room. Notice that this only shows the map of the floor. Do you see why the position of the windows cannot be marked on this map?

1.3 The 2-D Cartesian Coordinate System

In the chapters on integers, rational numbers, and decimals in earlier grades, you studied the number line which is one-dimensional. The two-dimensional coordinate system uses two lines at right angles to each other to mark points in two-dimensional space (short form: 2-D space). For convenience, we consider one of the lines to be horizontal; it is called the x-axis. The other line is vertical; it is called the y-axis. The point of intersection of the x-axis and y-axis is called the origin O; its coordinates are (0, 0). Coordinate axes (this is the plural of 'axis') help us to locate any point in 2-D space using the point's 'coordinates'. Distances from O are marked off in equal units, on both the axes. Distances to the right of O or upwards from O are considered positive, and distances to the left of O or downwards from O are considered negative (Fig. 1.2).

© NCERT not to be republished



Fig. 1.2: Structure of the coordinate plane

Point B is on the x-axis and 4.5 units to the right of O, its coordinates are (4.5, 0). This fact is written as B = (4.5, 0). Point G is on the y-axis and 4.5 units downward from O, its coordinates are (0, −4.5), that is, G = (0, −4.5). Point H is also on the y-axis but 4 units above O, its coordinates are (0, 4), that is, H = (0, 4).

A point P = (x, 0) lies on the x-axis. If x is positive, then P lies to the right of O. If x is negative, P lies to the left of O. A point P = (0, y) lies on the y-axis. If y is positive, P lies above O; if y is negative, P lies below O.

While writing the coordinates of a point, it is often convenient to drop the '=' sign and write P = (x, y) simply as P (x, y). This is especially true while marking points on a graph.

Exercise Set 1.1

Fig. 1.3 shows Reiaan's room with points OABC marking its corners. The x- and y-axes are marked in the figure. Point O is the origin.

© NCERT not to be republished



Fig. 1.3

Referring to Fig. 1.3, answer the following questions:

(i) If D_1R_1 represents the door to Reiaan's room, how far is the door from the left wall (the y-axis) of the room? How far is the door from the x-axis?

(ii) What are the coordinates of D_1?

(iii) If R_1 is the point (11.5, 0), how wide is the door? Do you think this is a comfortable width for the room door? If a person in a wheelchair wants to enter the room, will he/she be able to do so easily?

(iv) If B_1 (0, 1.5) and B_2 (0, 4) represent the ends of the bathroom door, is the bathroom door narrower or wider than the room door?

Think and Reflect

1. What are the standard widths for a room door? Look around your home and in school.
2. Are the doors in your school suitable for people in wheelchairs?

© NCERT not to be republished

So far, we have only considered points on the two coordinate axes. What can you say about the coordinates of points that are not on either axes? The plane in which the axes are situated is called the **Cartesian plane**, the **coordinate plane** or the **xy-plane**. The axes divide the plane into four parts, called **quadrants**. They are numbered as shown in Fig. 1.4.

Using the conventions that we have stated earlier:

(i) Points in Quadrant I have both x- and y-coordinates positive.

(ii) Points in Quadrant II have negative x-coordinate and positive y-coordinate.

(iii) Points in Quadrant III have both x- and y-coordinates negative.

(iv) Points in Quadrant IV have positive x-coordinate and negative y-coordinate.

Can you now see the meaning of the coordinates of a point in 2-D space? In general, the coordinates of a point P in 2-D space are represented by (x, y). Here, x represents the perpendicular distance of P from the y-axis, measured along the x-axis, and y is the perpendicular distance of P from the x-axis, measured along the y-axis. x is the x-coordinate and y is the y-coordinate of the point (x, y).



Fig. 1.4

© NCERT not to be republished

For example, in Fig. 1.4, point S (3, –5) is in Quadrant IV, the x-coordinate is 3 units and the y-coordinate is –5 units. What about point Q (–5, 3)? It is in the second quadrant, with x-coordinate –5 and y-coordinate 3. Copy Fig. 1.4 and mark S and Q in your diagram. Mark any point P in Quadrant I and any point R in Quadrant III, and write down their coordinates.

Think and Reflect

1. What is the x-coordinate of a point on the y-axis?
2. Is there a similar generalisation for a point on the x-axis?
3. Does point Q (y, x) ever coincide with point P (x, y)? Justify your answer.
4. If $x \neq y$, then $(x, y) \neq (y, x)$; and $(x, y) = (y, x)$ if and only if $x = y$. Is this claim true?

Exercise Set 1.2

On a graph sheet, mark the x-axis and y-axis and the origin O. Mark points from (–7, 0) to (13, 0) on the x-axis and from (0, –15) to (0, 12) on the y-axis. (Use the scale 1 cm = 1 unit.) Using Fig. 1.5, answer the given questions.



Fig. 1.5

© NCERT not to be republished

1. Place Reiaan's rectangular study table with three of its feet at the points (8, 9), (11, 9) and (11, 7).
   (i) Where will the fourth foot of the table be?
   (ii) Is this a good spot for the table?
   (iii) What is the width of the table? The length? Can you make out the height of the table?
2. If the bathroom door has a hinge at B_1 and opens into the bedroom, will it hit the wardrobe? Are there any changes you would suggest if the door is made wider?
3. Look at Reiaan's bathroom.
   (i) What are the coordinates of the four corners O, F, R, and P of the bathroom?
   (ii) What is the shape of the showering area SHWR in Reiaan's bathroom? Write the coordinates of the four corners.
   (iii) Mark off a 3 ft × 2 ft space for the washbasin and a 2 ft × 3 ft space for the toilet. Write the coordinates of the corners of these spaces.
4. Other rooms in the house:
   (i) Reiaan's room door leads from the dining room which has the length 18 ft and width 15 ft. The length of the dining room extends from point P to point A. Sketch the dining room and mark the coordinates of its corners.
   (ii) Place a rectangular 5 ft × 3 ft dining table precisely in the centre of the dining room. Write down the coordinates of the feet of the table.

1.4 Distance Between Two Points in the 2-D Plane

We know how to find the distance between two points if they are on the axes or if they form a line segment parallel to the axes. For example, in Fig. 1.5 we can find the distances W_1W_2 and S_1S_2. What should we do if the segment joining the points is not parallel to either axis? We can use the Baudhāyana–Pythagoras theorem which you have studied in Grade 8. We can use this result to find the distance between any two points in the xy-plane.

© NCERT not to be republished

Look at triangle ADM in Fig. 1.6.



Fig. 1.6

Triangle ADM is an acute angled triangle in the first quadrant. How do we find the lengths of its sides AD, DM and MA?

Think and Reflect

1. In moving from A (3, 4) to D (7, 1), what distance has been covered along the x-axis? What about the distance along the y-axis?
2. Can these distances help you find the distance AD?

Fig. 1.7 gives us a clue. The distance moved along the x-axis is given by CD.

CD = x-coordinate of D – x-coordinate of A = 7 – 3 = 4.

The distance moved along the y-axis is given by AC.

AC = y-coordinate of A – y-coordinate of D = 4 – 1 = 3.

Using the Baudhāyana–Pythagoras Theorem, we get the distance

$$AD = \sqrt{4^2 + 3^2} = 5 \text{ units.}$$

© NCERT not to be republished



Fig. 1.7

We similarly find the distances DM and MA:

$$\text{DM} = \sqrt{2^2 + 5^2} = \sqrt{29} \text{ units.}$$

$$\text{MA} = \sqrt{6^2 + 2^2} = \sqrt{40} \text{ units.}$$

In general, the distance between the points (x_1, y_1) and (x_2, y_2) is given by

$$\sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}$$

and is calculated as shown in Fig. 1.8.



Fig. 1.8

© NCERT not to be republished

It makes no difference whether $(x_2 - x_1)$ and $(y_2 - y_1)$ are positive or negative, as we are simply measuring the shifts along the two axes.

What if, x_1, x_2, y_1, y_2 take negative values? In Fig. 1.9, triangle AMD is reflected in the y-axis. What are the coordinates of the images of points A, M, and D?



Fig. 1.9

C'D' = x-coordinate of A' – x-coordinate of D' = –3 – (–7) = 4.

A'C' = y-coordinate of A' – y-coordinate of D' = 4 – 1 = 3.

Using the Baudhāyana–Pythagoras Theorem, we get AD = $\sqrt{4^2 + 3^2} = 5$ units.

You can similarly calculate both D'M' and M'A':

$$D'M' = \sqrt{(-2)^2 + 5^2} = \sqrt{29} \text{ units}$$

$$M'A' = \sqrt{(-6)^2 + 2^2} = \sqrt{40} \text{ units.}$$

We see that reflection has preserved the lengths of the sides of the triangles.

Think and Reflect

1. What has remained the same and what has changed with this reflection?
2. Would these observations be the same if ΔADM is reflected in the x-axis (instead of the y-axis)?

© NCERT not to be republished

End-of-Chapter Exercises

1. What are the x-coordinate and y-coordinate of the point of intersection of the two axes?
2. Point W has x-coordinate equal to –5. Can you predict the coordinates of point H which is on the line through W parallel to the y-axis? Which quadrants can H lie in?
3. Consider the points R (3, 0), A (0, –2), M (–5, –2) and P (–5, 2). If they are joined in the same order, predict:
   (i) Two sides of RAMP that are perpendicular to each other.
   (ii) One side of RAMP that is parallel to one of the axes.
   (iii) Two points that are mirror images of each other in one axis. Which axis will this be?

   Now plot the points and verify your predictions.
4. Plot point Z (5, –6) on the Cartesian plane. Construct a right-angled triangle IZN and find the lengths of the three sides.

   (**Comment:** Answers may differ from person to person.)
5. What would a system of coordinates be like if we did not have negative numbers? Would this system allow us to locate all the points on a 2-D plane?

*6. Are the points M (–3, –4), A (0, 0) and G (6, 8) on the same straight line? Suggest a method to check this without plotting and joining the points.

*7. Use your method (from Problem 6) to check if the points R (–5, –1), B (–2, –5) and C (4, –12) are on the same straight line. Now plot both sets of points and check your answers.

*8. Using the origin as one vertex, plot the vertices of:
   (i) A right-angled isosceles triangle.
   (ii) An isosceles triangle with one vertex in Quadrant III and the other in Quadrant IV.

*9. The following table shows the coordinates of points S, M and T. In each case, state whether M is the midpoint of segment ST. Justify your answer.

© NCERT not to be republished

S	M	T	Is M the midpoint of ST? Yes or No	Reason for your answer
(–3, 0)	(0, 0)	(3, 0)		
(2, 3)	(3, 4)	(4, 5)		
(0, 0)	(0, 5)	(0, –10)		
(–8, 7)	(0, –2)	(6, –3)		

When M is the mid-point of ST, can you find any connection between the coordinates of M, S and T?

*10. Use the connection you found to find the coordinates of B given that M (–7, 1) is the midpoint of A (3, – 4) and B (x, y).

*11. Let P, Q be points of trisection of AB, with P closer to A, and Q closer to B. Using your knowledge of how to find the coordinates of the midpoint of a segment, how would you find the coordinates of P and Q? Do this for the case when the points are A (4, 7) and B (16, –2).

*12. (i) Given the points A (1, – 8), B (– 4, 7) and C (–7, – 4), show that they lie on a circle K whose center is the origin O (0, 0). What is the radius of circle K?

(ii) Given the points D (–5, 6) and E (0, 9), check whether D and E lie within the circle, on the circle, or outside the circle K.

*13. The midpoints of the sides of triangle ABC are the points D, E, and F. Given that the coordinates of D, E, and F are (5, 1), (6, 5), and (0, 3), respectively, find the coordinates of A, B and C.

14. A city has two main roads which cross each other at the centre of the city. These two roads are along the North–South (N–S) direction and East–West (E–W) direction. All the other streets of the city run parallel to these roads and are 200 m apart. There are 10 streets in each direction.

(i) Using 1 cm = 200 m, draw a model of the city in your notebook. Represent the roads/streets by single lines.

(ii) There are street intersections in the model. Each street intersection is formed by two streets — one running in the N–S direction and another in the E–W direction. Each street

© NCERT not to be republished

intersection is referred to in the following manner: If the second street running in the N–S direction and 5th street in the E–W direction meet at some crossing, then we call this street intersection (2, 5). Using this convention, find:

(a) how many street intersections can be referred to as (4, 3).

(b) how many street intersections can be referred to as (3, 4).

15. A computer graphics program displays images on a rectangular screen whose coordinate system has the origin at the bottom-left corner. The screen is 800 pixels wide and 600 pixels high. A circular icon of radius 80 pixels is drawn with its centre at the point A (100, 150). Another circular icon of radius 100 pixels is drawn with its centre at the point B (250, 230). Determine:

(i) whether any part of either circle lies outside the screen.

(ii) whether the two circles intersect each other.

16. Plot the points A (2, 1), B (–1, 2), C (–2, –1), and D (1, –2) in the coordinate plane. Is ABCD a square? Can you explain why? What is the area of this square?

Chapter Summary

- To locate the position of an object or a point in a plane, we require two perpendicular lines — One of them is horizontal, and the other is vertical.
- The plane is called the **cartesian plane**, the **coordinate plane** or the **xy-plane** and the lines are called the coordinate axes.
- The horizontal line is called the **x-axis** and the vertical line is called the **y-axis**.
- The coordinate axes divide the plane into four parts called **quadrants**.
- The point of intersection of the axes is called the **origin**.
- The distance of a point from the y-axis is its **x-coordinate** and the distance of the point from the x-axis is its **y-coordinate**. If the x-coordinate of a point is x, and the y-coordinate is y, then (x, y) are called the **coordinates** of the point.

© NCERT not to be republished

- The coordinates of a point on the x-axis are of the form $(x, 0)$, and those of the points on the y-axis are of the form $(0, y)$.
- The coordinates of the origin are (0, 0).
- The coordinates of a point are of the form (+, +) in the first quadrant, (–, +) in the second quadrant, (–, –) in the third quadrant and (+, –) in the fourth quadrant.
- If $x = y$, then $(x, y) = (y, x)$. If $x \neq y$, then $(x, y) \neq (y, x)$.
- The distance between points (x_1, y) and (x_2, y) is the absolute value $|x_2 - x_1|$ of the difference between x_1 and x_2.
- The distance between points (x, y_1) and (x, y_2) is the absolute value $|y_2 - y_1|$ of the difference between y_1 and y_2.
- By the Baudhāyana–Pythagoras Theorem, the distance between points (x_1, y_1) and (x_2, y_2) is $\sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}$.

© NCERT not to be republished

2 Introduction to Linear Polynomials

0904CH02

2.1 Introduction

We have learnt about algebraic expressions in earlier grades. In this chapter, we will learn about the special types of algebraic expressions called **linear polynomials**. Let us first consider a few examples of algebraic expressions.

Example 1: Raju went to a shop where there were sealed boxes of different colours on sale. The shop owner told him that the red boxes have 4 pens each and the blue boxes have 5 pencils each. Now, if Raju bought x red boxes and y blue boxes, how can he quickly figure out the total quantity of pens and pencils? Also, if he got 3 extra pens free, how many pens and pencils did he get altogether?



Fig. 2.1

Observe that x red boxes will have $4x$ pens and y blue boxes will have $5y$ pencils. Also, he got 3 extra pens free. Thus, the total number of pens and pencils is given by the algebraic expression $4x + 5y + 3$. In this example, $4x$, $5y$ and 3 are **terms** of the expression, x and y are letter-numbers, the numbers 4 and 5 are the **coefficients** of x and y, respectively, and 3 is a **constant**. From now onwards, we will use a widely used alternate word for letter-numbers: **variables**. Thus in the expression $4x + 5y + 3$, we say that the variables used are x and y.

Example 2: A rectangular garden of length l metres and width w metres has to be fenced and decorated. A wire fence is to be laid along the length costing ₹100 per metre and a wooden fence is to be built along the width costing ₹80 per metre. Special seeds have to be sown throughout the garden which will cost ₹50 per square metre.

© NCERT not to be republished



Fig. 2.2

What will be the total cost incurred?

Cost of wire fencing along the garden length = $2l \times 100$ = ₹$200l$

Cost of wooden fencing along the garden width = $2w \times 80$ = ₹$160w$

Cost of sowing seeds throughout the entire garden (depends on the area) = $50 \times l \times w$ = ₹$50lw$

Total cost = ₹ $(200l + 160w + 50lw)$.

Thus, $200l + 160w + 50lw$ is the algebraic expression for the total cost.

Think and Reflect

1. Can you identify the terms, variables and coefficients of this algebraic expression?
2. How is it different from the algebraic expression in Example 1?

Example 3: A wire of length 20 cm is bent in different ways to form rectangles. For example, we can have a rectangle with length 7 cm and width 3 cm. We can also have one of length 5.5 cm and width 4.5 cm. (Think of a few more ways of forming such rectangles.) Can you write an expression for the area of such rectangles?

If the length of the rectangle is x cm, then the width is $(10 - x)$ cm. The expression for the area of these rectangles is $x(10 - x)$ or $10x - x^2$.

Think and Reflect

1. Can you identify the terms, variables and coefficients of this algebraic expression?
2. Can you point out any similarity or difference between the algebraic expressions obtained in Examples 1 and 3?

© NCERT not to be republished

Note that the algebraic expressions in Example 1 and Example 2 involve two variables, whereas the algebraic expression in Example 3 involves only one variable.

Expressions such as $4x$, $x^2 + 1$, $2y - 5$, $5y^3 + y^2 + 2y - 1$, $3z + 7$ are algebraic expressions that involve only one variable: x, y or z. In this chapter, we will restrict our discussion to algebraic expressions involving only one variable. You may have noticed that in an algebraic expression, the powers of a variable also appear. For example, in the expression $x^2 + 5x + 1$, the highest power of x is 2, whereas in the expression $5y^3 + y^2 - 8$, the highest power of the variable y is 3. Further, in the expression $5y^3 + y^2 + 2y - 1$, the coefficient of y^3 is 5, that of y^2 is 1, that of y is 2 and the constant term is –1. Such algebraic expressions involving one variable and its powers are called **one-variable polynomials**, **univariate polynomials**, or when the context is clear, simply **polynomials**. ('univariate' means 'having one variable'). The highest power of the variable in a polynomial is called its **degree**. For example:

(i) $5y^3 + y^2 + 2y - 1$ is a polynomial of degree 3. Such polynomials are called **cubic polynomials**.

(ii) $x^2 + 5x + 1$ is a polynomial of degree 2. Such polynomials are called **quadratic polynomials**.

(iii) $3z + 7$ is a polynomial of degree 1. Such polynomials are called **linear polynomials**.

(iv) The constant 8 is a polynomial of degree 0 as it can be written as $8x^0$ in which the power of the variable x is 0. Such polynomials are called **constant polynomials**.

Exercise Set 2.1

1. Find the degrees of the following polynomials:
   (i) $2x^2 - 5x + 3$
   (ii) $y^3 + 2y - 1$
   (iii) -9
   (iv) $4z - 3$
2. Write polynomials of degrees 1, 2 and 3.
3. What are the coefficients of x^2 and x^3 in the polynomial $x^4 - 3x^3 + 6x^2 - 2x + 7$?

© NCERT not to be republished

4. What is the coefficient of z in the polynomial $4z^3 + 5z^2 - 11$?
5. What is the constant term of the polynomial $9x^3 + 5x^2 - 8x - 10$?

Recall that polynomials of degree 1 are called **linear polynomials**. In this chapter, we shall study linear polynomials.

2.2 Linear Polynomials

We begin with some examples involving linear polynomials.

Example 4: The perimeter of a square of side x is $4x$, which is a linear polynomial in the variable x.

Think and Reflect

Find the perimeter of squares with sides 1 cm, 1.5 cm, 2 cm, 2.5 cm and 3 cm. What will happen to the perimeters if the sides increase by 0.5 cm?

Example 5: A chess club charges a joining fee of ₹200 plus ₹50 for every match played. The following table shows the amount a player will have to pay as the number of matches varies.

Number of matches played	1	2	3	4	5	...	m
Amount paid (₹)	250	300	350	400	450	...	200 + 50m

Hence, if m is the number of matches played, the total cost will be ₹$(200 + 50m)$. Observe that $200 + 50m$ is a linear polynomial in the variable m. The amount paid increases by the constant value of ₹50 for every additional match played.

Think and Reflect

If a player paid ₹750, how many matches did he play?

The examples given above highlight a characteristic feature of linear polynomials — that the difference between the successive values at integers is constant. In Example 4, the perimeters increase by 2 cm each time the side of the square increases by 0.5 cm. Similarly in Example 5,

© NCERT not to be republished

the amount paid by a player increases by ₹50 for every additional match played. Such patterns are called **linear patterns**.

When we equate a linear polynomial in one variable to a constant, we get a **linear equation**. Let us consider the following example.

Example 6: The sum of two numbers is 64. One of the numbers is 10 more than the other. What are the two numbers?

Let the smaller number be x. Then the larger number must be $x + 10$. Since their sum is 64, we have the linear equation $x + (x + 10) = 64$. This implies that $2x + 10 = 64$. Note that $2x + 10$ is a linear polynomial. By equating it to 64 we get a linear equation $2x = 54$ or $x = 27$. The numbers are therefore, 27 and 37.

Polynomials can also be thought of as input-output processes. For instance, consider the linear polynomial $2x + 3$. For every x, there is a corresponding value of the polynomial $2x + 3$. For instance, if $x = 4$, we substitute 4 in the expression to get $2 \times 4 + 3 = 11$.

If $x = -6$, then we substitute -6 in the expression to get $2 \times -6 + 3 = -9$.

Fig. 2.3 shows this process as an input-output machine where the input is the value of x and the output is the value of $2x + 3$. This process can be referred to as a **function** where the expression $2x + 3$ is a function of the variable x. You will learn more about functions in later grades.



Fig. 2.3: A linear expression as an input-output process

Think and Reflect

We have learnt that to evaluate the value of an algebraic expression, we substitute a value of the variable in the given expression. Consider Example 3, where the wire is bent to form a rectangle. Here, the area of the rectangle, $10x - x^2$, is a function of x. Can you interpret this as an input-output process? What value does the expression take when $x = 6$ cm?

Note that $2x + 3$ is a linear function, whereas $10x - x^2$ is a quadratic function.

Exercise Set 2.2

1. Find the value of the linear polynomial $5x - 3$ if:
   (i) $x = 0$ (ii) $x = -1$ (iii) $x = 2$
2. Find the value of the quadratic polynomial $7s^2 - 4s + 6$ if:
   (i) $s = 0$ (ii) $s = -3$ (iii) $s = 4$
3. The present age of Salil's mother is three times Salil's present age. After 5 years, their ages will add up to 70 years. Find their present ages.
4. The difference between two positive integers is 63. The ratio of the two integers is 2:5. Find the two integers.
5. Ruby has 3 times as many two-rupee coins as she has five rupee-coins. If she has a total ₹88, how many coins does she have of each type?
6. A farmer cuts a 300 feet fence into two pieces of different sizes. The longer piece is four times as long as the shorter piece. How long are the two pieces?
7. If the length of a rectangle is three more than twice its width and its perimeter is 24 cm, what are the dimensions of the rectangle?

2.3 Exploring Linear Patterns

Observe the following growing pattern of square tiles.



Fig. 2.4: A growing pattern of square tiles

© NCERT not to be republished

Think and Reflect

Predict the number of squares in the next three stages of the pattern and write the sequence of numbers up to Stage 7 of the pattern.

Each stage is obtained by adding two more tiles to the previous stage. The table mentions the number of tiles for the first seven stages.

Stage	1	2	3	4	5	6	7
Number of the square tiles	1	3	5	7	9	11	13

To generalise this pattern, we observe that the number of squares at each stage is one less than twice the number of the term. For example, in Term 2, the number of squares is $2 \times 2 - 1 = 3$, in Term 5, the number of squares is $2 \times 5 - 1 = 9$ and so on.

This leads us to conclude that the number of squares at Stage n is given by $2n - 1$.

The polynomial $2n - 1$ has degree 1. Hence, it is an example of a linear polynomial. Also, the difference between consecutive terms in the sequence of the number of squares, that is, 1, 3, 5, 7, 9 ... is the constant value 2. Thus, with each stage, the number of squares increases by 2. The relationship between the number of the stage and the number of square tiles is a **linear relationship**.

Think and Reflect

Using the expression $2n - 1$, can you find out how many tiles will be there in the 15th stage and the 26th stage of the pattern? Also, which stage will contain 21 tiles and 47 tiles?

Example 7: Bela has ₹100 for pocket money. She spends ₹5 every day. After how many days will she be left with ₹40?

Day Number	0	1	2	3	4
Amount left (₹)	100	$100 - 1 \times 5$ $= 95$	$100 - 2 \times 5$ $= 90$	$100 - 3 \times 5$ $= 85$	$100 - 4 \times 5$ $= 80$

© NCERT not to be republished

Observe that the amount left on the n^{th} day will be ₹$(100 - 5n)$. Therefore, on the 12th day the amount left will be ₹$(100 - 12 \times 5)$ = ₹40.

Think and Reflect

What amount will be left on the 15th day? How many days will it take for the entire amount to be spent?

Example 8: An auto-rikshaw fare starts at ₹25 and remains the same for the initial 2 km. Then it increases by ₹15 per km. What will be the fare for a travel of 10 km?

For the initial 2 km, the fare is ₹25. For every kilometre (km) thereafter, the fare will increase by ₹15. Therefore, the total fare for a travel of 10 km will be ₹$25 + 15 \times 8$ = ₹145.

Km travelled	1	2	3	4	5	6
Fare (₹)	25	25	$25 + 1 \times 15$ $= 40$	$25 + 2 \times 15$ $= 55$	$25 + 3 \times 15$ $= 70$	$25 + 4 \times 15$ $= 85$

Observe that the total fare for a travel of n km will be ₹$25 + 15 \times (n - 2) = 15n - 5$, when $n \geq 2$. Here, the fare for a specific distance covered is a function of the distance n km.

Think and Reflect

For how many km will the fare be ₹130?

Note that in all the above examples, the n^{th} term is a linear expression in n. A **linear pattern** is a sequence of numbers where the difference between two consecutive terms is constant. We will learn more about linear patterns in the chapter on Sequences and Progressions.

Exercise Set 2.3

Solve the following:

1. A student has ₹500 in her savings bank account. She gets ₹150 every month as pocket money. How much money will she have at the end of every month from the second month onwards? Find a linear expression to represent the amount she will have in the n^{th} month.

© NCERT not to be republished

2. A rally starts with 120 members. Each hour, 9 members drop out of the group. How many members will remain after 1, 2, 3, ... hours? Find a linear expression to represent the number of members at the end of the n^{th} hour.
3. Suppose the length of a rectangle is 13 cm. Find the area if the breadth is (i) 12 cm, (ii) 10 cm, (iii) 8 cm. Find the linear pattern representing the area of the rectangle.
4. Suppose the length of a rectangular box is 7 cm and breadth is 11 cm. Find the volume if the height is (i) 5 cm, (ii) 9 cm, (iii) 13 cm. Find the linear pattern representing the volume of the rectangular box.
5. Sarita is reading a book of 500 pages. She reads 20 pages every day. How many pages will be left after 15 days? Express this as a linear pattern.

2.4. Linear growth and linear decay

Linear expressions help to model situations or phenomena where there is growth or decline. Consider the following examples:

Example 9: The cost of a journey is given by the linear function $C(d) = 100 + 60d$, where C indicates total cost in rupees and d the distance travelled in km. Let us make a table of values for d varying from 0 to 10 km and show how the cost increases for every km.

Distance travelled, *d* (km)	0	1	2	3	4	5
Cost, *C* (₹)	100	160	220	280	340	400

In this example, as the value of d increases by one km, the value of the cost function C, increases by a fixed amount of ₹60. This is an example of **linear growth.**

Think and Reflect

What is the cost for travelling 15 km? For how many kilometres will the cost of the journey be ₹700?

Example 10: The height of water in a cylindrical tank is 3 m at the start of summer. The height h m at the end of t months is given by the linear function $h(t) = 3 – 0.5t$.

© NCERT not to be republished

Month, *t*	0	1	2	3	4
Height, *h* (*m*)	3	2.5	2	1.5	1

In the example above, as the value of t increases by a fixed number (one month), the value of the height h decreases by a fixed number (0.5). Therefore, this example represents **linear decay**.

Think and Reflect

What will be the height of the water at the end of 5 months?

Linear growth describes a linear pattern where a quantity increases by a constant amount over equal intervals. Similarly, linear decay describes a linear pattern where a quantity decreases by a constant amount over equal intervals.

Exercise Set 2.4

1. Suppose a plant has height 1.75 feet and it grows by 0.5 feet each month.
   (i) Find the height after 7 months.
   (ii) Make a table of values for t varying from 0 to 10 months and show how the height, h, increases every month.
   (iii) Find an expression that relates h and t, and explain why it represents linear growth.
2. A mobile phone is bought for ₹10,000. Its value decreases by ₹800 every year.
   (i) Find the value of the phone after 3 years.
   (ii) Make a table of values for t varying from 0 to 8 years and show how the value of the phone, v, depreciates with time.
   (iii) Find an expression that relates v and t, and explain why it represents linear decay.
3. The initial population of a village is 750. Every year, 50 people move from a nearby city to the village.
   (i) Find the population of the village after 6 years.

© NCERT not to be republished

(ii) Make a table of values for t varying from 0 to 10 years and show how the population, P, increases every year.

(iii) Find an expression that relates P and t, and explain why it represents linear growth.

4. A telecom company charges ₹600 for a certain recharge scheme. This prepaid balance is reduced by ₹15 each day after the recharge.

(i) Write an equation that models the remaining balance $b(x)$ after using the scheme for x days. Explain why it represents linear decay.

(ii) After how many days will the balance run out?

(iii) Make a table of values for x varying from 1 to 10 days and show how the balance $b(x)$, reduces with time.

2.5 Linear Relationships

A linear relationship represents the relationship between two variables x and y, and can be expressed as $y = ax + b$.

Let us revisit the growing pattern of square tiles in Fig. 2.4. If x represents the number of the term and y represents the numbers of square tiles, then the linear relationship between x and y is expressed as $y = 2x - 1$.

Sometimes, we may be required to find the linear relationship between two quantities.

Example 11: A telecom company charges a fixed monthly fee and an additional cost per GB of the internet data used. A student observes that when she used 10 GB, her bill was ₹350. When she used 20 GB, her bill was ₹550. If the monthly bill y depends on the amount of data used, x (in GB), according to the relation $y = ax + b$, find the values of a and b.

Note that x = number of GB of the internet data used and y = total monthly cost in Rupees.

To find the linear relationship $y = ax + b$, we note that when $x = 10$, $y = 350$. Also, when $x = 20$, $y = 550$. We substitute these in $y = ax + b$ to arrive at the following equations.

$$350 = 10a + b \text{ and } 550 = 20a + b$$

We solve these as follows: Let $b = 350 - 10a$ (from the first equation). We substitute this in the second equation to obtain

$$550 = 20a + (350 - 10a)$$

Thus, $550 = 10a + 350$ or $10a = 200$. So, $a = 20$. This leads to $b = 350 - 10a = 350 - 200 = 150$.

© NCERT not to be republished

We substitute the values of a and b in the equation $y = ax + b$ to obtain $y = 20x + 150$.

Thus, $y = 20x + 150$ represents the linear relationship between y, the bill amount in Rupees, and x, the number of GB of the internet data used.

Think and Reflect

Can you guess what the numbers 20 and 150 in the equation $y = 20x + 150$ represent?

Exercise Set 2.5

1. A learning platform charges a fixed monthly fee and an additional cost per digital learning module accessed. A student observes that when she accessed 10 modules, her bill was ₹400. When she accessed 14 modules, her bill was ₹500. If the monthly bill y depends on the number of modules accessed, x, according to the relation $y = ax + b$, find the values of a and b.
2. A gym charges a fixed monthly fee and an additional cost per hour for using the badminton court. A student using the gym observed that when she used the badminton court for 10 hours, her bill was ₹800. When she used it for 15 hours, her bill was ₹1100. If the monthly bill y depends on the hours of the use of the badminton court, x, according to the relation $y = ax + b$, find the values of a and b.
3. Consider the relationship between temperature measured in degrees Celsius (°C) and degrees Fahrenheit (°F), which is given by °C = a °F + b. Find a and b, given that ice melts at 0 degrees Celsius and 32 degrees Fahrenheit, and water boils at 100 degrees Celsius and 212 degrees Fahrenheit.
   (**Hint:** When °C = 0, °F = 32 and when °C = 100, °F = 212. Use this information to find a and b, and thus, the linear relationship between °C and °F.)

2.6 Visualising Linear Relationships

As we have seen in many examples in this chapter, a linear pattern or relationship can be expressed in the form of an equation $y = ax + b$. Now we shall learn to plot such an equation as a straight line.

To plot a linear equation, we need to identify any two points on the line. For example, to plot $y = 2x + 1$, we may identify two points as follows:

© NCERT not to be republished

When $x = 0$, $y = 1$, so (0, 1) is a point on the line. We can call this point A. We say that the x-coordinate of A is 0 and the y-coordinate is 1. Also, when $x = 3$, $y = 7$. Thus, B (3, 7) is another point on the line. We plot these points on the coordinate plane, join them and extend the line in both directions as shown in Fig. 2.5.



Fig. 2.5: The straight line $y = 2x + 1$

Think and Reflect

Identify other points on the line by completing the following table.

x	1	2	5	7	9	12	20
y	3			15			

Note that (1, 3) and (7, 15) are also the points on the line $y = 2x + 1$. Plot the points on the line. You may use a graph paper for this task. Observe that if a point lies on a line, its coordinates must satisfy the equation of the line. Thus, we can verify that (7, 15) lies on the line $y = 2x + 1$ by substituting $x = 7$ and $y = 15$ in the equation.

Example 12: Let us plot the points (–1, –3), (0, 0), (1, 3), (3, 9), (4, 12) in the coordinate plane on a graph paper as shown in Fig. 2.6. Join the points (–1, –3) and (4, 12) using a ruler. Doing so, observe that all five points lie on a straight line. Can you guess the equation of this line by looking at the relationship between the x and y coordinates of each point?

© NCERT not to be republished



Fig. 2.6

For each point, the value of the y-coordinate is three times that of the x-coordinate. We can therefore say that $y = 3x$.

Example 13: Let us plot the points (–3, 6), (–2, 4), (0, 0), (1, –2), (2, –4), (3, –6) in the coordinate plane on a graph paper as shown in Fig. 2.7. Join the points (–3, 6) and (3, –6) using a ruler. Doing so, observe that all five points lie on a straight line. Can you guess the equation of this line by looking at the relationship between the x and y coordinates of each point?



Fig. 2.7

Example 14: Draw the graphs of $y = \frac{1}{2}x$, $y = x$, $y = 2x$ by selecting suitable points on these lines.

(**Hint:** In order to graph $y = \frac{1}{2}x$, we could take the points (0, 0) and (4, 2). Can you verify that these lie on the line?)

© NCERT not to be republished

Fig. 2.8 shows the graphs of these linear equations without any points labelled.



Fig. 2.8

© NCERT not to be republished

Fig. 2.9 shows all the three graphs on the same axes. Does this help you to conclude anything about the linear equation y = ax, a > 0 as a varies? What happens when a > 1 and when a < 1?

(**Hint:** You may also plot the equations $y = 3x$ and $y = \frac{1}{3}x$ on the same axes.)



Fig. 2.9

First of all, we observe that the straight lines representing an equation of the form $y = ax$, always pass through the origin (0, 0). Further, when $a > 1$, the line is steeper than the line $y = x$, which is equally inclined to both axes. However, when $a < 1$, the line is less steep than the line $y = x$. In fact, a is referred to as the **slope** of the line $y = ax$. We will learn more about the concept of the **slope** of a line in the chapter on linear equations.

For now, we focus on another important observation. A linear growth is represented by a straight line with *positive* slope while a linear decay is represented by a straight line with negative slope. Note that the number of square tiles in the pattern in Fig. 2.4 leads to the sequence 1, 3, 5, 7, ... in which the difference of consecutive terms is the constant 2. The slope of the line representing the linear relationship between the term number and the number of square tiles is $y = 2x - 1$ is 2. Hence, the slope represents the constant difference between consecutive terms of the sequence.

Example 15: Now let us draw the graphs of $y = \frac{-1}{3}x$, $y = -x$, $y = -3x$ by selecting suitable points on these lines. Fig. 2.10 shows the graphs of these linear equations without any points labelled on them.

© NCERT not to be republished



Fig. 2.10

© NCERT not to be republished

Fig. 2.11 shows all the three graphs on the same axes. Does this help you to conclude anything about the linear equation $y = -ax$, $a > 0$, as a varies? What will happen when $a > 1$ and when $a < 1$?



Fig. 2.11

Think and Reflect

Differentiate between the graphs of the equations $y = 3x + 1$, and $y = -3x + 1$.

Example 16: Let us now draw the graphs of $y = 2x - 1$, $y = 2x + 1$, $y = 2x + 5$, first individually (as shown in Fig. 2.12) and then on the same axes (as shown in Fig. 2.13).



Fig. 2.12A

© NCERT not to be republished



Fig. 2.12 B



Fig. 2.12 C



Fig. 2.13

© NCERT not to be republished

Think and Reflect

Does this help you to conclude anything about the linear equation $y = ax + b$ when a is fixed but b varies?

(**Hint:** In these equations $a = 2$, and b takes the values –1, 1 and 5, respectively.)

Now let us draw the graphs of the equations $y = x + 3$, $y = 2x + 5$ and $y = 3x – 2$. See Fig. 2.14 and observe where these lines cut the y-axis.



Fig. 2.14

We see that,

$y = 2x + 5$ cuts the y-axis at A (0, 5),

$y = x + 3$ cuts the y-axis at B (0, 3), and

$y = 3x – 2$ cuts the y-axis at C (0, –2).

We observe that any straight line written in the form $y = ax + b$ cuts the y-axis at the point (0, b). The length b is referred to as the y-intercept of the line. Thus, the y-intercept of the line $y = x + 3$ is 3. This means that the line cuts the y-axis at a distance of 3 units from the origin in the positive direction. Similarly, the y-intercept of the line $y = 3x – 2$ is – 2.

© NCERT not to be republished

This means that the line cuts the y-axis at a distance of 2 units from the origin in the negative direction.

After observing the graphs in Figures 2.8 to 2.14, we may conclude the following:

(i) In the equation $y = ax + b$, a represents the slope of the line and b represents the y-intercept.

(ii) If we change the values of a, keeping b fixed, the slope of the line changes while the y-intercept remains fixed.

(iii) If we change the values of b keeping the value of a fixed, the lines shift but remain parallel to the original line. Thus, lines with equal slopes but different y-intercepts are parallel to each other.

Exercise Set 2.6

1. Draw the graphs of the following sets of lines. In each case, reflect on the role of 'a' and 'b'.
   (i) $y = 4x, y = 2x, y = x$
   (ii) $y = -6x, y = -3x, y = -x$
   (iii) $y = 5x, y = -5x$
   (iv) $y = 3x - 1, y = 3x, y = 3x + 1$
   (v) $y = -2x - 3, y = -2x, y = 2x + 3$

End-of-Chapter Exercises

1. Write a polynomial of degree 3 in the variable x, in which the coefficient of the x^2 term is –7.
2. Find the values of the following polynomials at the indicated values of the variables.
   (i) $5x^2 - 3x + 7$ if $x = 1$
   (ii) $4t^3 - t^2 + 6$ if $t = a$

© NCERT not to be republished

3. If we multiply a number by $\frac{5}{2}$ and add $\frac{2}{3}$ to the product, we get $\frac{-7}{12}$. Find the number.
4. A positive number is 5 times another number. If 21 is added to both the numbers, then one of the new numbers becomes twice the other new number. What are the numbers?
5. If you have ₹800 and you save ₹250 every month, find the amount you have after (i) 6 months (ii) 2 years. Express this as a linear pattern.

*6. The digits of a two-digit number differ by 3. If the digits are interchanged, and the resulting number is added to the original number, we get 143. Find both the numbers.

*7. Draw the graph of the following equations, and identify their slopes and y-intercepts. Also, find the coordinates of the points where these lines cut the y-axis.

(i) $y = -3x + 4$

(ii) $2y = 4x + 7$

(iii) $5y = 6x - 10$

(iv) $3y = 6x - 11$

Are any of the lines parallel?

*8. If the temperature of a liquid can be measured in Kelvin units as x K and in Fahrenheit units as y °F, the relation between the two systems of measurement of temperature is given by the linear equation $y = \frac{9}{5}(x - 273) + 32$.

(i) Find the temperature of the liquid in Fahrenheit if the temperature of the liquid is 313 K.

(ii) If the temperature is 158 °F, then find the temperature in Kelvin.

*9. The work done by a body on the application of a constant force is the product of the constant force and the distance travelled by the body in the direction of the force. Express this in the form of a linear equation in two variables (work w and distance d), and draw its graph by taking the constant force as 3 units. What is

© NCERT not to be republished

the work done when the distance travelled is 2 units? Verify it by plotting it on the graph.

*10. The graph of a linear polynomial $p(x)$ passes through the points (1, 5) and (3, 11).

(i) Find the polynomial $p(x)$.

(ii) Find the coordinates where the graph of $p(x)$ cuts the axes.

(iii) Draw the graph of $p(x)$ and verify your answers.

*11. Let $p(x) = ax + b$ and $q(x) = cx + d$ be two linear polynomials such that:

(i) $p(0) = 5$.

(ii) The polynomial $p(x) – q(x)$ cuts the x-axis at (3, 0).

(iii) The sum $p(x) + q(x)$ is equal to $6x + 4$ for all real x.

Find the polynomials $p(x)$ and $q(x)$.

*12. Look at the first three stages of a growing pattern of hexagons made using matchsticks. A new hexagon gets added at every stage which shares a side with the last hexagon of the previous stage.



Stage 1 Stage 2 Stage 3

(i) Draw the next two stages of the pattern. How many matchsticks will be required at these stages?

(ii) Complete the following table.

Stage Number	1	2	3	4	5	...	*n*
Number of matchsticks							

(iii) Find a rule to determine the number of matchsticks required for the n^{th} stage.

© NCERT not to be republished

(iv) How many matchsticks will be required for the 15th stage of the pattern?

(v) Can 200 matchsticks form a stage in this pattern? Justify your answer.

*13. Let $p(x) = ax + b$ and $q(x) = cx + d$ be two linear polynomials such that:

(i) The graph of $p(x)$ passes through the points (2, 3) and (6, 11).

(ii) The graph of $q(x)$ passes through the point (4, –1).

(iii) The graph of $q(x)$ is parallel to the graph of $p(x)$.

Find the polynomials $p(x)$ and $q(x)$. Also, find the coordinates of the point where these lines meet the x-axis.

*14. What do all linear functions of the form $f(x) = ax + a$, $a > 0$, have in common?

CHAPTER SUMMARY

- An **algebraic expression** combines numbers, variables, and operation symbols. For example, $2x^2 + 5xy - 3y^2$ is an algebraic expression in the variables x and y. $2x^2$, $5xy$ and $-3y^2$ are the **terms** of the algebraic expression, and the numbers 2, 5 and –3 are **coefficients** of the terms.
- **Univariate Polynomials** are algebraic expressions in one variable. Thus $x^2 + 5x + 3$ and $3y^3 - 4y^2 + 5$ are univariate polynomials in x and y, respectively. The highest power of the variable in a univariate polynomial is called its **degree**. Thus, $x^2 + 5x + 3$ is of degree 2 while $3y^3 - 4y^2 + 5$ is of degree 3.
- A polynomial of degree one is called a **linear polynomial**. Hence, $2x + 3$ and $5 - 4y$ are linear polynomials in the variables x and y, respectively.
- **Linear growth** refers to a pattern in which a quantity increases by a fixed amount over equal intervals. In contrast, **linear decay** describes a pattern in which a quantity decreases by a fixed amount over equal intervals.

© NCERT not to be republished

- A **linear pattern** is a sequence of numbers where the difference between consecutive terms is constant.
- A **linear relationship** between two variables x and y is represented by a straight line $y = ax + b$. The slope of this line is a. The constant b is called the y-intercept which is the distance from the origin where the line cuts the y-axis. When $b = 0$, the equation of the line becomes $y = ax$ and the line passes through the origin.
- **Linear growth** is represented by a straight line with positive slope and **linear decay** is represented by a straight line with negative slope.
- Parallel lines are of the form $y = ax + b$, where the slope a is fixed while b, the y-intercept, varies.

© NCERT not to be republished

3 The World of Numbers

0904CH03

3.1. The Dawn of Mathematics: The Human Need to Count

Long before humanity built cities, formulated laws, or studied the stars, there existed a fundamental, practical necessity: the need to keep count. Mathematics did not begin in a classroom with equations on a board; it began in the dirt, on the bark of trees, and on bones.

Imagine you are living thousands of years ago in a small agricultural settlement along the banks of the Saraswati river. You have a herd of cattle. Every morning, they go out into the dense forests to graze, and every evening, they return. How do you ensure that a calf has not wandered off? Without words for numbers, and without written symbols, early humans solved this through a concept called **one-to-one correspondence**.

For every cow that left the settlement, the herder might place one pebble in a clay pot. In the evening, for every cow that returned, one pebble was removed. If the pot was empty at the end of the day, the herd was safe. If pebbles remained, cows were missing. This simple act of matching one object to another was the birth of the **Natural Numbers** ($\mathbb{N} = \{1, 2, 3, 4, \ldots\}$).

3.1.1 A History Written in Bone

While the decimal place-value system we use today was perfected in the Indian subcontinent, the earliest physical evidence of humanity recording natural numbers takes us deep into the heart of Africa. The first mathematicians did not use paper; they used tally marks carved into bone.

The **Lebombo Bone**, discovered in the Lebombo Mountains between South Africa and Swaziland, dates back approximately 35,000 years. It is a bone featuring 29 distinct, deliberately-carved uniformly-sized notches. Anthropologists and mathematicians believe this was not just random scratching, but a tool used as a lunar phase counter or a menstrual calendar, indicating that early humans were tracking time through natural numbers.

© NCERT not to be republished

Even more fascinating is the **Ishango bone**, found near the headwaters of the Nile River in the Democratic Republic of Congo, dating to around 20,000 BCE. This bone contains three columns of asymmetrical notches. What makes the Ishango bone a mathematical marvel is the specific grouping of the tallies. One of the columns groups notches into 11, 13, 17, and 19 — the prime numbers between 10 and 20. Another column seems to demonstrate the concept of multiplication by 2 (doubling). These artefacts indicate that the abstract concept of a 'number' is indeed tens of thousands of years old.

Fig. 3.1: Representation of the prime number tally groupings found on the Ishango bone.

3.1.2 The Indian Context: Trade and Astronomy

As civilisations advanced, so did the need for larger numbers. In the ancient urban centers of the Indus Valley Civilisation, such as Lothal and Harappa, standardised weights and measures were crucial for trade. A merchant trading terracotta pottery, lapis lazuli, or cotton with Mesopotamia needed a robust system of accounting.

During Vedic times, Indian philosophers were fascinated by and deeply pondered large numbers. In the *Vedas*, which go back thousands of years, names were given to all powers of 10 up to 10^{12} (which was called *parārdha*). In the *Lalitavistara* in the 4th century BCE, Buddha describes names up to 10^{53}, which is called *tallakṣhaṇa*.

Expressing quantities in terms of powers of 10 was explicitly used in the *Ṛigveda*, thus setting the stage for the number system based on powers of 10 to be developed in India in the ensuing years, and which we now use around the world today. The development of the Indian numeral system in terms of place values and powers of 10 also helped pave the way for what is perhaps the most important mathematical invention in human history: the concept of zero.

© NCERT not to be republished

Exercise Set 3.1

1. A merchant in the port city of Lothal is exchanging bags of spices for copper ingots. He receives 15 ingots for every 2 bags of spices. If he brings 12 bags of spices to the market, how many copper ingots will he leave with?
2. Look at the sequence of numbers on one column of the Ishango bone: 11, 13, 17, 19. What do these numbers have in common? List the next three numbers that fit this pattern.
3. We know that Natural Numbers are closed under addition (the sum of any two natural numbers is always a natural number). Are they closed under subtraction? Provide a couple of examples to justify your answer.

*4. Ancient Indians used the joints of their fingers to count, a practice still seen today. Each finger has 3 joints, and the thumb is used to count them. How many can you count on one hand? How does this relate to the ancient base-12 counting systems?

3.2 The Revolution of Śhūnya: When Nothing Became Something

For millennia, the number line started at 1. If you had five apples and gave all five away, you did not have a number to represent your state; you simply had a void, a lack of apples. Civilisations like the Babylonians and Mayans used placeholders — symbols to indicate an empty column in a number — but they did not treat 'nothing' as a number that you could add, subtract, and multiply.

It was in the work of Brahmagupta (628 CE) that the void was formally transformed into a number, which truly transformed mathematics. This monumental leap was in turn inspired by Indian philosophical traditions.

3.2.1 From Philosophy to Mathematics: The Concept of Śhūnyatā

In the *Upanishads* and in the vast Buddhist literature starting well before the 7th century BCE, the concept of **Śhūnyatā** (emptiness or nothingness)

© NCERT not to be republished

was a profound state that was the goal of yoga and meditation. The word *śhūnya* means zero, and the word **śhūnyatā** (zeroness) was used extensively in these works to describe the state that one is trying to reach during meditation — that of emptying one's mind of all *vṛttis* (fluctuations of the mind) to achieve the state of perfect stillness and tranquility. Patanjali in the Yoga Sutras around the 3rd century BCE also describes how *śhūnyatā* can help lead to control over one's mind, body, and senses.

Because Indian thinkers revered this state of 'emptiness', they possessed the conceptual framework necessary to welcome 'nothingness' as a concept in philosophy. This concept of zeroness then found its way into many fields, such as architecture, literature, linguistics, and eventually made its way into mathematics in the works of Āryabhaṭa and finally Brahmagupta.

Thus, the philosophical concept of emptiness crystallised into the mathematical zero.

3.2.2 The Bakhśhālī Manuscript and Brahmagupta's Rules

In the Hindu Number System that we use today, the physical transition from a blank space to a symbol can be seen in the **Bakhśhālī Manuscript**. Dated to the early centuries CE, it features a bold dot (*bindu*) used to represent zero.

However, a symbol is just a mark on a page until it has rules. The transformation of zero into a fully operational number occurred in the work of **Brahmagupta**. In his seminal work, the *Brāhmasphuṭasiddhānta* (628 CE), he explicitly defined zero as the result of subtracting a number from itself ($a - a = 0$).

Brahmagupta then laid down the fundamental laws of arithmetic with *śhūnya*:

Brahmagupta's Rules for Zero

- When zero is added to a number, the number remains unchanged: $a + 0 = a$.
- When zero is subtracted from a number, the number remains unchanged: $a - 0 = a$.
- When any number is multiplied by zero, the result is zero: $a \times 0 = 0$.

© NCERT not to be republished

3.3 Integers: Expanding the Horizon

Brahmagupta did not stop at zero. He realised that if subtraction of a number from itself can result in zero (5 – 5 = 0), then what would happen if we subtracted a larger number from a smaller one (3 – 5 = ☐)?

To answer this, Brahmagupta grounded his mathematics in the reality of commerce and life.

He recognised two states:

- **Fortunes (*Dhana*):** Positive numbers, representing wealth or assets.
- **Debts (*Ṛiṇa*):** Negative numbers, representing debts.

By moving to the left of zero on the number line, Brahmagupta formally introduced **Negative Numbers** to the world. The combination of positive natural numbers, their negative counterparts, and zero creates the set of **Integers**, denoted by the symbol ℤ (from the German word *Zahlen*, meaning numbers).



Fig. 3.2

3.3.1 The Arithmetic of Integers

Brahmagupta gave explicit rules for adding and multiplying these integers, which we still use exactly as he wrote them over 1,300 years ago:

1. **A fortune plus a fortune is a fortune:** 5 + 4 = 9.
2. **A debt plus a debt is a debt:** (–5) + (–4) = –9. (If you owe ₹5 and borrow ₹4 more, you owe ₹9.)
3. **A fortune minus zero is a fortune, a debt minus zero is a debt:** 7 – 0 = 7, and – 6 – 0 = – 6.
4. **The product of a debt and a fortune is a debt:** (–3) × 4 = –12. (If you take on 4 debts of ₹3, your total debt is ₹12.)
5. **The product of two debts is a fortune:** (–3) × (–4) = 12.

© NCERT not to be republished

Think and Reflect

Why does a negative times a negative equal a positive? Think of it in terms of action and debt. If a negative number represents a debt, then multiplying by a negative number represents the removal of that debt.

(**Hint:** If someone takes away (–) four of your debts that are each worth ₹3 (that is, –3), you are effectively ₹12 richer! Therefore, (–3) × (–4) = +12.)

Exercise Set 3.2

1. The temperature in the high-altitude desert of Ladakh is recorded as 4 °C at noon. By midnight, it drops by 15 °C. What is the midnight temperature?
2. A spice trader takes a loan (debt) of ₹850. The next day, he makes a profit (fortune) of ₹1,200. The following week, he incurs a loss of ₹450. Write this sequence as an equation using integers and calculate his final financial standing.
3. Calculate the following using Brahmagupta's laws:

   (i) (–12) × 5 (ii) (–8) × (–7)

   (iii) 0 – (–14) (iv) (–20) ÷ 4
4. Explain, using a real-world example of debt, why subtracting a negative number is the same as adding a positive number (e.g., 10 – (–5) = 15).

3.4 Filling the Spaces: Fractions and Rational Numbers

As society grew more complex, measuring became just as important as counting. If a farmer divides a field of wheat among his three children, how much does each get? If a recipe calls for half a cup of ghee, how do we represent that mathematically?

Numbers that represent parts of a whole are called **fractions**. Just as every natural number has an additive inverse (3 has –3, 19 has –19, etc.), we can conceive of additive inverses for every positive fraction: $-\frac{3}{4}$ for $\frac{3}{4}$, $-\frac{19}{7}$ for $\frac{19}{7}$, etc. Let us refer to such additive inverses of positive

© NCERT not to be republished

fractions as negative fractions. Note that in a negative fraction, the '–' sign can also be placed with either the numerator or denominator, as follows: $-\frac{1}{5} = \frac{-1}{5} = \frac{1}{-5}$.

When we combine all integers and all fractions (both positive and negative), we get the set of **Rational Numbers**, denoted by $\mathbb{Q}$ (for quotient).

A **rational number** is defined as any number that can be expressed in the form $\frac{p}{q}$, where p and q are integers and $q \neq 0$.

Think and Reflect

Can you explain why we need $q \neq 0$ in the definition of a rational number?

We must make some important observations at this stage.

- All rational numbers can be written in the form $\frac{p}{q}$, where p and q are integers and $q \neq 0$. For example, 5 and –10 can be written as $\frac{5}{1}$ and $\frac{-10}{1}$, respectively. What this means is that the rational numbers also include the natural numbers, whole numbers and integers.
- Rational numbers do not have a unique representation in the form $\frac{p}{q}$, where p and q are integers and $q \neq 0$. For example, we have $-\frac{1}{3} = -\frac{2}{6} = -\frac{3}{9} = -\frac{10}{30} = -\frac{2026}{6078}$ and so on. These are equivalent rational numbers (or equivalent fractions). This fact allows us to freely divide any common factor between the numerator and the denominator of a given fraction. The resulting fraction is then equivalent to the original one. For example, $\frac{12}{30}$ is equivalent to $\frac{2}{5}$. Here, we have divided both the numerator and the denominator by 6.
- The common understanding is that when we say that $\frac{p}{q}$ is a rational number, or when we represent $\frac{p}{q}$ on the number line, we assume that $q \neq 0$ and that p and q have no common factors other than

© NCERT not to be republished

1 (that is, p and q are **co-prime**). So, on the number line, among the infinitely many fractions equivalent to $\frac{1}{2}$ (i.e., the fractions $\frac{1}{2}$, $\frac{2}{4}, \frac{3}{9}, \frac{6}{12}, \ldots, \frac{1013}{2026}, \ldots$), we choose $\frac{1}{2}$ to represent all of them.

As you will remember from Grades 6 and 7, Brahmagupta also gave rules for addition, subtraction, multiplication, and division of fractions. He noted that these rules also apply to both positive and negative fractions which together constitute the rational numbers.

Here are the various laws:

1. **Equality:** Two rational numbers $\frac{a}{b}$ and $\frac{c}{d}$ are said to be equal if $ad = bc$.
2. **Addition and subtraction of two rational numbers**: We first express the two rational numbers as fractions $\frac{a}{b}$ and $\frac{c}{b}$ with the same denominator, b. Then we use the rules $\frac{a}{b} + \frac{c}{b} = \frac{a+c}{b}$ and $\frac{a}{b} - \frac{c}{b} = \frac{a-c}{b}$.
3. **Multiplication and division of two rational numbers**: We use the rules $\frac{a}{b} \times \frac{c}{d} = \frac{ac}{bd}$ provided that ($b \neq 0$, $d \neq 0$) and $\frac{a}{b} \div \frac{c}{d} = \frac{a}{b} \times \frac{d}{c} = \frac{ad}{bc}$ provided that ($b \neq 0$, $d \neq 0$, $c \neq 0$).
4. With the arithmetic laws defined as above, addition and multiplication are both commutative (i.e., $\frac{a}{b} + \frac{c}{d} = \frac{c}{d} + \frac{a}{b}$ and $\frac{a}{b} \times \frac{c}{d} = \frac{c}{d} \times \frac{a}{b}$, and they follow the law of distributivity: if p, q and r are rational numbers, then $p(q + r) = pq + pr$.

Rational numbers are closed under addition, subtraction, and multiplication; that is, if one adds two rational numbers, or subtracts two rational numbers, or multiplies two rational numbers, a rational number is again obtained. Rational numbers are also closed under division, provided that one does not divide by zero. That is, the quotient of two rational numbers is again a rational number, as long as one does not divide by zero.

© NCERT not to be republished

Think and Reflect

1. While adding or subtracting two rational numbers having different denominators, how will you make the denominators equal?
2. Verify the distributive law for rational numbers.

Exercise Set 3.3

1. Prove that the following rational numbers are equal:

   (i) $\frac{2}{3}$ and $\frac{4}{6}$ (ii) $\frac{5}{4}$ and $\frac{10}{8}$

   (iii) $-\frac{3}{5}$ and $-\frac{6}{10}$ (iv) $\frac{9}{3}$ and 3

2. Find the sum:

   (i) $\frac{2}{5}+\frac{3}{10}$ (ii) $\frac{7}{12}+\frac{5}{8}$

   (iii) $-\frac{4}{7}+\frac{3}{14}$

3. Find the difference:

   (i) $\frac{5}{6}-\frac{1}{4}$ (ii) $\frac{11}{8}-\frac{3}{4}$

   (iii) $-\frac{7}{9}-\left(-\frac{2}{3}\right)$

4. Find the product:

   (i) $\frac{2}{3}\times\frac{3}{10}$ (ii) $\frac{7}{11}\times\frac{5}{8}$

   (iii) $-\frac{4}{7}\times\frac{5}{14}$

5. Find the quotient:

   (i) $\frac{2}{3}\div\frac{3}{10}$ (ii) $\frac{7}{11}\div\frac{5}{8}$

© NCERT not to be republished

(iii) $-\frac{4}{7} \div \frac{5}{14}$

6. Show that: $\left(\frac{1}{2}+\frac{3}{4}\right)\times\frac{8}{3}=\frac{1}{2}\times\frac{8}{3}+\frac{3}{4}\times\frac{8}{3}$.

7. Simplify the following using the distributive property:
$\frac{7}{9}\left(\frac{6}{7}-\frac{3}{4}\right)$.

8. Find the rational number x such that: $\frac{5}{6}\left(x+\frac{3}{5}\right)=\frac{5}{6}x+\frac{1}{2}$.

3.4.1 Representation of Rational Numbers on the Number Line

We already know that integers can be represented on a number line. To do this, we first choose a point and mark it as 0, called the origin. Moving one unit to the right gives the point representing 1, two units to the right gives 2, and so on. Similarly, moving one unit to the left of the origin gives –1, two units to the left gives –2, and so on. Each integer lies at an equal distance from the next one. This is represented in Fig. 3.3.



Fig. 3.3

Rational numbers can also be represented on the number line. Unlike integers, they may lie between two integers. For example, $\frac{1}{2}$ lies exactly halfway between 0 and 1, and $-\frac{3}{4}$ lies between –1 and 0 as shown in Fig. 3.4.



Fig. 3.4

To represent a rational number $\frac{p}{q}$, $q \neq 0$, on the number line, divide the unit interval (the distance between two consecutive integers) into q equal parts. Then move p parts from 0 to the right if the number is positive, and to the left if it is negative.

© NCERT not to be republished

For example, to represent $\frac{3}{4}$, divide the interval between 0 and 1 into four equal parts and move three parts to the right from 0.



Fig. 3.5

Even fractions greater than 1 can be located on the number line in this way. For example, $\frac{9}{4} = 2\frac{1}{4}$ so it lies between 2 and 3. We divide the interval between 2 and 3 into four equal parts and move one part to the right of 2. See Fig. 3.6.



Fig. 3.6

Think and Reflect

Try and represent $\frac{8}{5}$ and $-\frac{7}{4}$ on a number line.



Fig. 3.7: Some integers and rational numbers on a number line

Absolute value of a rational number

The **absolute value** of a rational number x, written as $|x|$, represents its distance from 0 on the number line.

Example 1: $\left|\frac{5}{3}\right| = \frac{5}{3}$, $\left|-\frac{5}{3}\right|$ is also equal to $\frac{5}{3}$ and $|0| = 0$.

Thus, the absolute value of a positive number is the number itself. The absolute value of a negative number is its positive value. Therefore, the absolute value of any rational number is always non-negative, that is, $|x| \geq 0$.

© NCERT not to be republished

For two rational numbers a and b, the distance between them on the number line is given by $|a - b|$. Fig. 3.8 represents the distance between the integers –4 and 3.



Fig. 3.8

3.4.2 The Density of Rational Numbers

One of the most magical properties of rational numbers is that they are dense. Between any two integers, say 1 and 2, there is a rational number $\frac{3}{2}$. Between 1 and $\frac{3}{2}$, there is another rational number $\frac{5}{4}$.

No matter how close two rational numbers are on the number line, you can always find another rational number between them by taking their average. For example, a rational number between 1 and $\frac{3}{2}$ can be found by taking their average: $\frac{1+\frac{3}{2}}{2} = \frac{5}{4}$. Try to explain why the average of two rational numbers a and b, which equals $\frac{(a+b)}{2}$, is always a rational number between a and b.



Fig. 3.9

This means that there are infinitely many rational numbers between any two points. It feels as though the rational numbers must completely fill the number line, leaving no gaps whatsoever. But do they?

Exercise Set 3.4

1. Represent the rational numbers $\frac{2}{3}$, $-\frac{5}{4}$ and $1\frac{1}{2}$ on a single number line.
2. Find three distinct rational numbers that lie strictly between $-\frac{1}{2}$ and $\frac{1}{4}$.

© NCERT not to be republished

3. Simplify the expression: $\left(-\frac{1}{4}\right)+\left(\frac{5}{12}\right)$.
4. A tailor has $15\frac{3}{4}$ metres of fine silk. If making one kurta requires $2\frac{1}{4}$ metres of silk, exactly how many kurtas can he make?
5. Find three rational numbers between 3.1415 and 3.1416.

*6. Can you think of other way(s) to find a rational number between any two rational numbers?

3.5 Irrational Numbers

For centuries, mathematicians believed that every measurable length in the universe could be represented as a ratio of two integers. However, when Baudhāyana composed his *Śhulbasūtra* (a manual for constructing complex geometric fire altars) in around 800 BCE, he quickly encountered lengths that defied fractions. The ancient Greeks encountered the same crisis a few centuries later.



Fig. 3.10

Consider a square where each side is exactly 1 unit long. By the Baudhāyana–Pythagoras Theorem, the length of the diagonal d is given by $1^2 + 1^2 = d^2$, so $d^2 = 2$. Therefore, the length of the diagonal is $\sqrt{2}$.

Think and Reflect

Can $\sqrt{2}$ be written as a rational number $\frac{p}{q}$?

As you learned in Grade 8, the answer is a resounding NO! We will soon again see why! Numbers on the number line that cannot be expressed as a ratio of integers are called **Irrational Numbers**.

3.5.1 The Proof of Irrationality of $\sqrt{2}$

The first proof of the irrationality of $\sqrt{2}$ is due to a mathematician named Hippasus who was a member of the Pythagorean school (*c.* 400 BCE). To explain why $\sqrt{2}$ is irrational, he employed a brilliant

© NCERT not to be republished

technique called **Proof by Contradiction**. Namely, we assume the opposite of what we want to prove, and show that this assumption leads to a logical disaster.

Proof: We shall explain the proof in steps.

Step 1: Assumption: Assume $\sqrt{2}$ is a rational number. Therefore, it can be written as a fraction $\frac{p}{q}$, $q \neq 0$ in its simplest form. (This means p and q are integers that share no common factors other than 1, that is, they are co-prime.)

$$\sqrt{2} = \frac{p}{q}$$

Step 2: Square both sides of the equation:

$$2 = \frac{p^2}{q^2}$$

Step 3: Multiply both sides by q^2:

$$2q^2 = p^2$$

Step 4: Deduction for p:

Because p^2 is equal to 2 times some integer, p^2 must be an even number. If the square of a number is even, the number itself must be even. Therefore, p is an even integer. Let us say $p = 2k$ (where k is an integer).

Step 5: Substitute $p = 2k$ back into our equation from Step 3:

$$2q^2 = (2k)^2$$
$$2q^2 = 4k^2$$

Step 6: Divide both sides by 2:

$$q^2 = 2k^2$$

Step 7: Deduction for q: Now we see that q^2 is equal to 2 times some integer k^2. This means q^2 is even, and therefore, q must also be an even integer.

Step 8: The Contradiction: We deduced that p is even and q is even. This means they both share a common factor of 2. However, in Step 1, we stated that $\frac{p}{q}$ was in simplest form, sharing no common factors!

© NCERT not to be republished

Because our logical steps are flawless, our initial assumption must be wrong. Therefore, $\sqrt{2}$ cannot be expressed as a fraction. It is irrational.



Think and Reflect

Try to prove the irrationality of $\sqrt{3}$ using the approach of proof by contradiction. Will the same approach work for $\sqrt{5}$, $\sqrt{7}$, or $\sqrt{10}$?

3.5.2 Construction of Length $\sqrt{n}$

Think and Reflect

We have seen how to obtain a line whose length is a rational number. How do we obtain lines whose lengths are irrational?

For example, to construct a line segment of length $\sqrt{2}$ and mark its position on the number line, we may proceed as follows.

Step 1: On the number line (see Fig. 3.11), we measure OA = 1 unit and draw a perpendicular on OA through A.

© NCERT not to be republished

Step 2: On this perpendicular line we mark the point B such that AB = 1 unit and join the origin to B. Clearly, OB = $\sqrt{2}$ units.

Step 3: With O as centre and OB as radius, with a compass we draw an arc which intersects the number line at P. Clearly, OP = $\sqrt{2}$ units. Hence, P represents the irrational number $\sqrt{2}$.



Fig. 3.11: Constructing irrational lengths and locating them on the number line

Think and Reflect

Try to extend this method for constructing line segments of lengths $\sqrt{3}$ and $\sqrt{5}$ using a ruler and a compass. Generalise this method to construct a line segment of any length of the form $\sqrt{n}$, where n is a positive integer.

3.5.3 The Story of Pi (π) and Madhava's Infinite Series

Another famous irrational number is π, the ratio of a circle's circumference to its diameter. For centuries, mathematicians sought better and better fractional approximations for π. Āryabhaṭa (499 CE) gave the highly accurate approximation $\frac{3927}{1250}$ = 3.1416, but stated that this was only an *asanna* (approximation), and indicated that an exact fraction could likely not be found.

However, because π is irrational (as was formally proven by Lambert in 1761), no single fraction (or finitely many fractions) can ever provide a perfect formula for π. An exact formula for π was first unlocked in the 14th century by **Mādhava of Sangamagrama**, who launched the Kerala School of Mathematics. Mādhava realised that to express an irrational number, you cannot use a single fraction; you must use an infinite sum. He discovered the profound infinite series:

$$\pi = 4 \times \left(1 - \frac{1}{3} + \frac{1}{5} - \frac{1}{7} + \ldots\right).$$

We know what it means to add 2, 100, or even a lakh terms. What does it mean to add an infinite number of terms? It means finding the

© NCERT not to be republished

value that we get "closer" and "closer" to as we add more and more terms of the infinite sum, starting from the first term. You will learn more about infinite series in higher grades.

Thus, the number line is not only filled with rational numbers but also contains irrational numbers. We have seen how to mark some irrationals, and will simply conceive the rest of the irrationals to lie on the line.



Fig. 3.12

3.6 Real Numbers: Decimals and Cyclic Patterns

When we unite the dense web of Rational Numbers with the unfillable gaps of Irrational Numbers, we create the unbroken, continuous line of the Real Numbers ($\mathbb{R}$).

The easiest way to distinguish a rational number from an irrational number is to look at its decimal expansion.

3.6.1 Rational Decimals: Terminating and Repeating

If you divide the numerator of a rational number by its denominator, exactly one of two things will happen:

1. **It terminates:** The division eventually leaves a remainder of 0. The decimal stops.

   Example 2: $\frac{3}{8} = 0.375$. (Can you tell for which rational numbers the decimal will be terminating?)
2. **It repeats:** The division never reaches a remainder of 0, but the sequence of digits begins to loop infinitely.

   Example 3: $\frac{5}{11} = 0.454545 \ldots = 0.\overline{45}$.

Think and Reflect

Try to find the decimal expansions of $\frac{10}{3}$ and $\frac{11}{12}$. What do you observe about the repetition of the digits after the decimal point?

© NCERT not to be republished

Why do some rational numbers have repeating decimal representations? Imagine calculating $\frac{1}{7}$ using long division. You are dividing by 7. What are the possible remainders at each step? They can only be 1, 2, 3, 4, 5, or 6 (why not 0?). Because there is a limited number of possible remainders eventually, a remainder must show up a second time. Once a remainder repeats, the entire division process loops, creating a repeating decimal!

Predicting the Type of Decimal Expansion

The interesting thing is that we can predict whether the decimal expansion of a rational number will terminate or go on forever without actually doing the long division process!

For this, we resort to finding the **prime factors** of the denominator.

Let $\frac{p}{q}$, $q \neq 0$, be a rational number in its lowest terms (that is, p and q have no common factor other than 1).

Consider the fraction $\frac{3}{20}$. The prime factorisation of 20 is $2^2 \times 5$.

Hence, $\frac{3}{20} = \frac{3}{2^2 \times 5} = \frac{3 \times 5}{2^2 \times 5 \times 5} = \frac{15}{100} = 0.15$.

We multiply the numerator and denominator by 5 to get 100 and arrive at 0.15 which is a terminating decimal.

Think and Reflect

The decimal expansion of $\frac{p}{q}$ will be terminating precisely when the prime factors of q are only 2, only 5 or both 2 and 5. Can you explain why?

This is because in such cases, we can make the denominator a power of 10 by multiplying both numerator and denominator by a suitable number.

Converting Rational Decimals into the Form $\frac{p}{q}$

Case 1: Terminating decimals

We have already seen in earlier grades how to convert terminating decimals into the form $\frac{p}{q}$.

© NCERT not to be republished

Example 4: Convert 0.35 into the form $\frac{p}{q}$.

We know that $0.35 = \frac{35}{100} = \frac{7}{20}$.

Now, let us understand how to convert non-terminating repeating decimals into the form $\frac{p}{q}$.

Case 2: Pure repeating decimals

A pure repeating decimal is one in which a digit or a sequence of digits begins repeating immediately after the decimal point.

Example 5: Convert $0.\overline{6}$ into the form $\frac{p}{q}$.

Step 1: Let $x = 0.\overline{6}$

Step 2: Since one-digit repeats, multiply both sides by $10^1 = 10$, we get $10x = 6.\overline{6}$

Step 3: Subtract the first equation from the second:

$10x - x = 6.\overline{6} - 0.\overline{6} = 6$.

Step 4: Solve for x: $9x = 6$. Thus, $x = \frac{6}{9} = \frac{2}{3}$.

Example 6: Convert $0.\overline{45}$ into the form $\frac{p}{q}$. Let $x = 0.\overline{45}$.

Since two digits repeat, multiply by $10^2 = 100$. We get $100x = 45.\overline{45}$. Subtracting the two equations, we get $99x = 45$.

So, $x = \frac{45}{99} = \frac{5}{11}$.

Case 3: General repeating decimals

A general repeating decimal has some non-repeating digits just after the decimal point, followed by a repeating block.

Example 7: Convert $0.1\overline{6}$ into the form $\frac{p}{q}$.

Step 1: Let $x = 0.1\overline{6}$.

Step 2: First, shift the decimal to place the repeating part immediately after the decimal point.

© NCERT not to be republished

Since one digit is non-repeating, we multiply by $10^1 = 10$ and obtain $10x = 1.\overline{6}$

Step 3: Now, to move one full repeating cycle (1 digit repeating), we multiply by $10^1 = 10$ again and get $100x = 16.\overline{6}$.

Step 4: Subtracting the first shifted equation from the second, we get, $100x - 10x = 16.\overline{6} - 1.\overline{6}$, or $90x = 15$. Thus, $x = \frac{15}{90} = \frac{1}{6}$.

Example 8: Convert $2.35\overline{7}$ into the form $\frac{p}{q}$.

Step 1: Let $x = 2.35\overline{7}$.

Step 2: Here, '35' is non-repeating (2 digits), '7' repeats (1 digit). Firstly, we multiply by $10^2 = 100$ to move the non-repeating digits before the decimal and we obtain $100x = 235.\overline{7}$.

Step 3: Now, we multiply by $10^1 = 10$ to move the full repeating cycle and get $1000x = 2357.\overline{7}$.

Step 4: Subtracting, we obtain $1000x - 100x = 2357.\overline{7} - 235.\overline{7}$.

Hence, $900x = 2122$ and $x = \frac{2122}{900} = \frac{1061}{450}$.

Example 9: Convert $2.45\overline{37}$ into the form $\frac{p}{q}$.

Step 1: Let $x = 2.45\overline{37}$.

Step 2: Here, '45' is non-repeating (2 digits), '37' repeats (2 digits). Firstly, we multiply by $10^2 = 100$ to move the non-repeating digits before the decimal and we obtain $100x = 245.\overline{37}$.

Step 3: Now, we multiply by $10^2 = 100$ to move the full repeating cycle and get $10000x = 24537.\overline{37}$.

Step 4: Subtracting, we obtain $10000x - 100x = 24537.\overline{37} - 245.\overline{37}$.

Hence, $9900x = 24292$ and $x = \frac{24292}{9900} = \frac{6073}{2475}$.

Summary Table for Conversion

Decimal type	Steps to follow
Pure repeating	• Let x = the decimal number. • Multiply by 10^n where n = the number of repeating digits, • Subtract from the original equation, and solve for x.

© NCERT not to be republished

General repeating	• Let x = the decimal number. • Multiply by 10^m where m = the number of non-repeating digits, then multiply by 10^n where n = the number of repeating digits. • Subtract from the previous equation, and solve for x.

3.6.2 The Magic of Cyclic Numbers

When we calculate the decimal for $\frac{1}{7}$ we get 0.142857142857... or $0.\overline{142857}$. The repeating block, 142857, is one of mathematics' most fascinating gem — a **cyclic number**. Watch what happens when we multiply it by the digits 1 through 6:

$$142857 \times 1 = 142857$$
$$142857 \times 2 = 285714$$
$$142857 \times 3 = 428571$$
$$142857 \times 4 = 571428$$
$$142857 \times 5 = 714285$$
$$142857 \times 6 = 857142$$

The same digits simply shift in a cyclic circle! This beautiful internal structure is a hallmark of the rational number $\frac{1}{7}$.

3.6.3 Irrational Decimals: Chaos and Infinity

Irrational numbers, however, possess decimal expansions that never end and never repeat. There is no cyclic block, no pattern that loops forever. Examples include:

$$\sqrt{2} = 1.4142135623730950488\ldots$$
$$\pi = 3.1415926535897932384\ldots$$

Exercise Set 3.5

1. Without performing long division, determine which of the following rational numbers will have terminating decimals and which will be repeating: $\frac{7}{20}, \frac{4}{15}$ and $\frac{13}{250}$. Then check your answers

© NCERT not to be republished

by explicitly performing the long divisions and expressing these rational numbers as decimals.

2. Perform the long division for $\frac{1}{13}$. Identify the repeating block of digits. Does it show cyclic properties if you evaluate $\frac{2}{13}$? Now compute $\frac{3}{13}$, $\frac{4}{13}$, etc. What do you notice?
3. Classify the following numbers as rational or irrational:
   (i) $\sqrt{81}$
   (ii) $\sqrt{12}$
   (iii) 0.33333 ...
   (iv) 0.123451234512345 ...
   (v) 1.01001000100001 ... (Notice the pattern: Is it repeating a single block?)
   (vi) 23.5601856122398747901 20
   Find the explicit fractions in case they are rational.
4. The number $0.\overline{9}$ (which means 0.99999 ...) is a rational number. Using algebra (let $x = 0.\overline{9}$, multiply by 10, and subtract), explain why $0.\overline{9}$ is exactly equal to 1.

*5. We have seen that the repeating block of $\frac{1}{7}$ is a cyclic number. Try to find more numbers (n) whose reciprocals $\left(\frac{1}{n}\right)$ produce decimals with repeating blocks that are cyclic.

Non-uniqueness of decimal representations. Just as $1 = \frac{10}{10} = \frac{100}{100}$, rational numbers can have two decimal forms. Any terminating decimal has an alternative with repeating 9s: 1.000 ... = 0.999 ..., 2.47000 ... = 2.46999 ....

Is it not surprising that 0.999 ... = 1? Many would have guessed that it is slightly less than 1.

3.7 Conclusion: The Never-Ending Journey

We have travelled an immense distance. From the simple notches carved into the Ishango bone to track the passing days, to the

© NCERT not to be republished

profound philosophical void of *Śhūnya* in ancient India. We crossed the threshold of zero into the realm of debts and negative numbers with Brahmagupta. We found that the space between numbers is infinitely dense with fractions, yet fundamentally interspersed with the infinite-nonrepeating-decimal irrational numbers like $\sqrt{2}$ and π. By uniting the rational and the irrational, we built the continuous, unbroken **Real Number Line**. Every length, every temperature, every real physical measurement in the known universe has a home on this line.

The Evolution of Our World of Numbers

Our world of numbers has grown in stages over thousands of years, to meet the needs of humanity:

- **Natural Numbers (ℕ):** The basic counting numbers {1, 2, 3, ...}. These are contained in the collection of integers.
- **Integers (ℤ):** These include also zero and the negative numbers {..., -2, -1, 0, 1, 2, ...}. These in turn are contained in the collection of rational numbers.
- **Rational Numbers (ℚ):** These include all fractions $\frac{p}{q}$, where p, q are integers and $q \neq 0$. They also correspond to those numbers with terminating decimals like 0.135 and repeating decimals like $0.\overline{142857}$.
- **Irrational Numbers (𝕀):** These are separate from the above. They are numbers that cannot be written as fractions (e.g., $\sqrt{2}$, π, $\sqrt{10}$) and do not have terminating or repeating decimals.
- **Real Numbers (ℝ):** Together, the **rational** and **irrational** numbers make up the entire real number line.



Fig. 3.13

© NCERT not to be republished

Is the journey over? Are there more numbers waiting to be discovered beyond the Real Number line?

Think and Reflect

Consider this puzzle: What is the square root of –1? We know that 1 × 1 = 1. We also know that (–1) × (–1) = 1. There is no Real Number that, when multiplied by itself, results in a negative number. Thus, $\sqrt{-1}$ cannot exist on number line.

To solve this, mathematicians stepped completely off the line and invented a new dimension of numbers, denoted by the letter *i*, standing for **Imaginary Numbers**. While they sound like fiction, they are essential for modern electrical engineering, quantum mechanics, and the technology that powers your mobile phone. But that is a journey for another year. For now, master the Real Numbers. The universe is largely written in their language.

End-of-Chapter Exercises

1. Convert the following rational numbers in the form of a terminating decimal or non-terminating and repeating decimal, whichever the case may be, by the process of long division:

   (i) $\frac{3}{50}$ (ii) $\frac{2}{9}$

2. Prove that $\sqrt{5}$ is an irrational number.

3. Convert the following decimal numbers in the form of $\frac{p}{q}$.

   (i) 12.6 (ii) 0.0120 (iii) $3.0\overline{52}$

   (iv) $1.2\overline{35}$ (v) $0.\overline{23}$ (vi) $2.0\overline{5}$

   (vii) $2.12\overline{5}$ (viii) $3.12\overline{5}$ (ix) $2.\overline{1625}$

4. Locate the following rational numbers on the number line.

   (i) 0.532 (ii) $1.1\overline{5}$

© NCERT not to be republished

5. Find 6 rational numbers between 3 and 4.
6. Find 5 rational numbers between $\frac{2}{5}$ and $\frac{3}{5}$.
7. Find 5 rational numbers between $\frac{1}{6}$ and $\frac{2}{5}$.
8. If $\frac{x}{3}+\frac{x}{5}=\frac{16}{15}$, find the rational number x.
9. Let a and b be two non-zero rational numbers such that $a+\frac{1}{b}=0$. Without assigning any numerical values, determine whether ab is positive or negative. Justify your answer.
10. A rational number has a terminating decimal expansion whose last non-zero digit occurs in the 4th decimal place. Show that such a number can be written in the form $\frac{p}{10^4}$, where p is an integer not divisible by 10. Is it necessary that the denominator of this rational number, when written in the lowest form, is divisible by 2^4 or 5^4? Give reasons.
11. Without performing division, determine whether the decimal expansion of $\frac{18}{125}$ is terminating or non-terminating. If it terminates, state the number of decimal places.
12. A rational number in its lowest form has denominator $2^3 \times 5$. How many decimal places will its decimal expansion have? Explain your answer.

*13. Let $a = \frac{7}{12}$ and $b = \frac{5}{6}$. Express both a and b in the form $\frac{k_1}{m}$ and $\frac{k_2}{m}$ where k_1, k_2 and m are integers and $k_2 - k_1 > 6$. Using the same denominator m, write exactly five distinct rational numbers lying between a and b keeping an integer numerator. Explain why the condition $k_2 - k_1 > n + 1$ is necessary to find n such rational numbers between the two rational numbers a and b using this method.

*14. Three rational numbers x, y, z satisfy $x + y + z = 0$ and $xy + yz + zx = 0$. Show that all the rational numbers x, y, z must be simultaneously zero.

© NCERT not to be republished

*15. Show that the rational number $\frac{(a+b)}{2}$ lies between the rational numbers a and b.

16. Find the lengths of the hypotenuses of all the right triangles in Fig. 3.14 which is referred to as the square root spiral.



Fig 3. 14: Square root spiral

Chapter Summary

In this chapter you have learnt the following concepts:

- **Natural Numbers** ($\mathbb{N}$) are the counting numbers {1, 2, 3, ... } that emerged at least tens of thousands of years ago due to humanity's need to count.
- The **Concept of Zero (Śhūnya)** was formalised in India by philosophers and then brought into mathematics formally by Brahmagupta (629 CE), who transformed the philosophical state of 'nothingness' (*Śhūnyatā*) into an actual number on which one could perform arithmetic operations. Brahmagupta also introduced the negative numbers, i.e., numbers less than zero.
- **Integers** ($\mathbb{Z}$) extend the number line to the left of 1 to include zero as well as the negative numbers, which Brahmagupta historically categorised as 'debts' (*ṛiṇa*) in contrast with the positive number 'fortunes' (*dhana*).

© NCERT not to be republished

- **Brahmagupta's Laws** provided the first rigorous framework for arithmetic with signed numbers, establishing rules such as 'the product of two debts is a fortune' (– × – = +), as well as the rules for zero.
- **Rational Numbers** ($\mathbb{Q}$) are defined as any number that can be expressed as a ratio $\frac{p}{q}$ (where p and q are integers and $q \neq 0$). Brahmagupta also gave the formal rules for addition, subtraction, multiplication, and division of rational numbers.
- **Rational numbers** are **dense**, meaning a rational number always exists between any two other rational numbers.
- **Irrational Numbers** are values like $\sqrt{2}$ and π that cannot be written as fractions. Their existence proves that the number line contains gaps that rational ratios alone cannot fill. The first proof of the irrationality of a number was that of $\sqrt{2}$, by Hippasus (*c*. 400 BCE). It was a proof by contradiction. A proof that π is irrational (as it was suspected to be by Āryabhaṭa in 499 CE) was given by the Swiss mathematician Johann Lambert in 1761.
- **Real Numbers** ($\mathbb{R}$) represent the total union of all rational and irrational numbers, forming a perfectly continuous and unbroken line where every real physical measurement has a corresponding point.
- **Decimal expansions** serve as a mathematical signature for rational vs. irrational: rational numbers always result in terminating or repeating decimals, while irrational numbers produce non-repeating decimals that continue infinitely.
- **Cyclic Numbers**, such as the digits found in the repeating block of $\frac{1}{7}$ (i.e., 142857), reveal the elegant and symmetrical internal patterns hidden within the rational numbers.
- **Imaginary Numbers** are introduced as a final conceptual frontier to handle operations like $\sqrt{-1}$, which cannot be solved on the real number line and require a new dimension of mathematics.

© NCERT not to be republished

4 Exploring Algebraic Identities

0904CH04

4.1 Introduction

In earlier chapters, you learnt about linear polynomials and how they can be used to represent and solve real-life problems. You also studied linear equations and discovered how they describe relationships between quantities.

In this chapter, we will take the next step by exploring algebraic identities. These are special mathematical rules that not only make it easier to simplify complicated calculations but also help us work efficiently with algebraic expressions.

Let us begin by exploring a few simple patterns.

Example 1: Consider any three consecutive square numbers. For example, 1, 4, and 9. Add the smallest and the largest squares. Thus, 1 + 9 = 10. Then subtract twice the middle square from this sum. This leads to 10 – (2 × 4) = 10 – 8 = 2.

Now try the same process with another set of three consecutive square numbers. Say 9, 16, 25.



For example, consider the consecutive squares 25, 36, 49.

Applying the same rule we get (25 + 49) – (2 × 36) = 74 – 72 = 2.

Repeat this process with other sets of three consecutive square numbers. The result always seems to be 2!

The pattern may look surprising, but soon we will uncover the reason behind it using algebra.

© NCERT not to be republished

Think and Reflect

Try and find other patterns like this one. For example, you could consider 4 consecutive squares and see if you can find a pattern.

4.2 Visualising Identities

In this section we will revisit some algebraic identities that we have studied in earlier grades and try to visualise them using geometrical models. In particular, we will use squares and rectangles to represent terms.

Consider two line segments of lengths a and b units, respectively, and make a longer line segment of length $(a + b)$ units as shown in Fig. 4.1.



Fig. 4.1

We can now construct a square of side $(a + b)$ units and partition it into smaller squares and rectangles as shown in Fig. 4.2.



Fig. 4.2: Square of side $(a + b)$ units

Observe that the area of the outer square is $(a + b)^2$. The area of the larger square inside the outer square is a^2 while the area of the smaller

© NCERT not to be republished

square is b^2. The areas of the two rectangles are ab each. Together they make the bigger square; hence we can conclude that

$$(a + b)^2 = a^2 + 2ab + b^2.$$

From Fig. 4.2 it is clear that $(a + b)^2 = a^2 + 2ab + b^2$ for all a and b when a and b are lengths of line segments.

Think of numbers a and b where a and b do not represent lengths of line segments. What if a and b are negative numbers? Let us check for some negative numbers and see if this equation still works.

Example 2: Let $a = -2$ and $b = -3$.

Then $(a + b) = -5$ and $(a + b)^2 = 25$.

Also $a^2 = 4$, $b^2 = 9$ and $2ab = 12$.

Thus $a^2 + 2ab + b^2 = 4 + 12 + 9 = 25$.

Hence, $a^2 + 2ab + b^2 = (a + b)^2$ again!

Now suppose a and b are rational numbers, say $a = -\frac{2}{3}$ and $b = \frac{3}{4}$

Then $(a + b) = \left(-\frac{2}{3} + \frac{3}{4}\right) = \frac{1}{12}$.

$$(a+b)^2 = \frac{1}{144}.$$

$$a^2 + 2ab + b^2 = \left(\frac{-2}{3}\right)^2 + 2\left(-\frac{2}{3}\right)\left(\frac{3}{4}\right) + \left(\frac{3}{4}\right)^2$$

$$= \frac{4}{9} - 1 + \frac{9}{16} = \frac{64 - 144 + 81}{144} = \frac{145 - 144}{144} = \frac{1}{144}.$$

So, $a^2 + 2ab + b^2 = (a + b)^2$ seems to be true for rational numbers too. But we are still not sure if it is true for all numbers. To verify this, let us investigate further using the distributive property of numbers:

$(a + b)^2 = (a + b)\,(a + b) = a(a + b) + b(a + b)$

$= a^2 + ab + ba + b^2 = a^2 + 2ab + b^2$.

Recall that in Grade 8 you were introduced to $(a + b)^2 = a^2 + 2ab + b^2$ as an *identity*.

What is the difference between an equation and an identity?

An **algebraic identity** is an equation that is true for all values of the variables occurring in it, while an equation need not be true for all values.

© NCERT not to be republished

For example, $x^2 - 1 = 24$ is true for only $x = 5$ or -5. Hence, it is an equation.

But $(x + y)^2 = x^2 + 2xy + y^2$ is true for all values of x and y. Therefore, this equation is also an identity.

By now you must have observed that $(a + b)^2 \neq a^2 + b^2$. But can you find out which one of them will be greater?

For example, if $a = 10$ and $b = 2$, what are the values of $(a + b)^2$ and $a^2 + b^2$?

$(a + b)^2 = (10 + 2)^2 = 12^2 = 144$ and $a^2 + b^2 = 10^2 + 2^2 = 104$.

So in this case, $(a + b)^2 > a^2 + b^2$

But is it true for all numbers a and b?

Think and Reflect

1. What can you say about a and b if $(a + b)^2 < a^2 + b^2$?
2. What can you say about a and b if $(a + b)^2 > a^2 + b^2$?
3. When will $(a + b)^2$ be equal to $a^2 + b^2$?

Did you observe that $(a + b)^2$ and $a^2 + b^2$ are both positive? What term will decide which is larger? Use the expansion of $(a + b)^2$ to decide.

We can use the identity $(a + b)^2 = a^2 + 2ab + b^2$ to find the square of general binomial expressions.

Example 3: Let us try to expand $(5x + 2y)^2$. Here $a = 5x$ and $b = 2y$.

Then $(5x + 2y)^2 = (5x)^2 + 2(5x)(2y) + (2y)^2 = 25x^2 + 20xy + 4y^2$.

We can also use the identity to help us with numerical calculations.

Example 4: To calculate 43^2, we can write it as

$(40 + 3)^2 = 40^2 + 2 \times 40 \times 3 + 3^2 = 1600 + 240 + 9 = 1849$.

Exercise Set 4.1

1. Using the identity $(a + b)^2 = a^2 + 2ab + b^2$, expand the following:

(i) $(7x + 4y)^2$ (ii) $\left(\frac{7}{5}x + \frac{3}{2}y\right)^2$ (iii) $(2.5p + 1.5q)^2$

© NCERT not to be republished

(iv) $\left(\frac{3}{4}s+8t\right)^2$ (v) $\left(x+\frac{1}{2y}\right)^2$ (vi) $\left(\frac{1}{x}+\frac{1}{y}\right)^2$

2. Using the same identity, find the values of the following:
   (i) $(64)^2$ (ii) $(105)^2$ (iii) $(205)^2$

4.3 Factorisation of Algebraic Expressions Using Identities

The identity $(a + b)^2 = a^2 + 2ab + b^2$ can also be used to find factors of some algebraic expressions.

Example 5: Consider the algebraic expression $x^2 + 4x + 4$.

We observe that

$x^2 = (x)^2$, $4 = 2^2$ and $4x = 2(2)(x)$.

Hence, $x^2 + 4x + 4 = x^2 + 2(x)(2) + 2^2$ can be compared with $a^2 + 2(a)(b) + b^2$, where $a = x$ and $b = 2$.

We conclude that $x^2 + 4x + 4 = (x + 2)^2$. Therefore, we can say that $(x + 2)$ is a factor of $x^2 + 4x + 4$.

Example 6: Let us try to find factors of another algebraic expression:

$36x^2 + 12x + 1$.

Writing this in the form $a^2 + 2ab + b^2$ we get

$36x^2 + 12x + 1 = (6x)^2 + 2(6x)(1) + 1^2$,

where $a = 6x$ and $b = 1$. Therefore, $36x^2 + 12x + 1 = (6x + 1)^2$.

Thus $(6x + 1)$ is a factor of $36x^2 + 12x + 1$.

Example 7: Let us try to factor $50p^2 + 60pq + 18q^2$. What will a and b be in this case?

Try to think of a term whose square is $50p^2$. It is $\sqrt{50}p$. But if we want to avoid using the square root symbol we may proceed as follows:

We observe that 2 is a common factor of the terms

$50p^2$, $60pq$, $18q^2$.

Thus $50p^2 + 60pq + 18q^2 = 2(25p^2 + 30pq + 9q^2)$.

© NCERT not to be republished

Now let us focus on the expression $25p^2 + 30pq + 9q^2$.

Think of a term whose square is $25p^2$. What about $9q^2$?

$50p^2 + 60pq + 18q^2$

$= 2\left[(5p)^2 + 2(5p)(3q) + (3q)^2\right]$

$= 2\,(5p + 3q)^2$.

Here we have used the identity $(a + b)^2 = a^2 + 2ab + b^2$ to factor the expression $25p^2 + 30pq + 9q^2$, after taking 2 as a common factor.

In all the examples described so far, we have used the identity $(a + b)^2 = a^2 + 2ab + b^2$ to find factors of different algebraic expressions.

Think and Reflect

What if we replace b by $-b$ in $(a + b)^2 = a^2 + 2ab + b^2$?

We get $(a - b)^2 = a^2 - 2ab + b^2$, which is also an identity and can be used in ways similar to $(a + b)^2 = a^2 + 2ab + b^2$.

Let us revisit the pattern we observed in Example 1. Any three consecutive numbers can be taken as $(n - 1)$, n and $(n + 1)$. Their respective squares are of the form $(n - 1)^2$, n^2 and $(n + 1)^2$.

The sum of the smallest and largest squares is

$$(n - 1)^2 + (n + 1)^2 = n^2 - 2n + 1 + n^2 + 2n + 1 = 2n^2 + 2.$$

Subtracting $2n^2$ from this leads to 2. Hence you always get 2! This is in fact a proof of the fact that if we add the smallest and largest of any three consecutive square numbers and subtract two times the middle square number, we will always arrive at 2.

Just as the identity $(a + b)^2 = a^2 + 2ab + b^2$ can be used to find the squares of numbers, we can also use $(a - b)^2 = a^2 - 2ab + b^2$ in a similar manner.

Example 8: Suppose we have to calculate 29^2. We can express this as $(30 - 1)^2 = 30^2 - 2 \times 30 \times 1 + 1^2 = 900 - 60 + 1 = 841$.

To visualise the identity $(a - b)^2 = a^2 - 2ab + b^2$, let us draw a square of side a units and split a in two parts, one of length $(a - b)$ units and another of length b units. Then the figure will look like this.

© NCERT not to be republished



Fig. 4.3: A square of side a units

The area of the big square is a^2 square units. The small square has an area of $(a-b)^2$ square units. The larger rectangle has area ab square units while the smaller rectangle has area $b\,(a-b)$ square units. Thus, to obtain $(a-b)^2$ we can subtract the areas of the rectangles from the big square.

We obtain $(a-b)^2 = a^2 - ab - b(a-b) = a^2 - ab - ba + b^2$

$= a^2 - 2ab + b^2$.

Exercise Set 4.2

1. Factor completely:

   (i) $9x^2 + 24xy + 16y^2$

   (ii) $4s^2 + 20st + 25t^2$

© NCERT not to be republished

(iii) $49x^2 + 28xy + 4y^2$

(iv) $64p^2 + \frac{32}{3}pq + \frac{4}{9}q^2$

*(v) $3a^2 + 4ab + \frac{4}{3}b^2$

*(vi) $\frac{9}{5}s^2 + 6sv + 5v^2$

(**Hint:** 2 was taken out as a common factor in Example 7. Is it possible to do something similar in Exercises (v) and (vi) above?)

2. Find the values of the following using the identity
$(a - b)^2 = a^2 - 2ab + b^2$.

(i) $(79)^2$ (ii) $(193)^2$ (iii) $(299)^2$

4.4. More Identities

What will happen if we want to find the square of the sum of three numbers a, b and c, that is, $(a + b + c)^2$?

Let us replace $b + c$ by d.

We already know, $(a + d)^2 = a^2 + 2ad + d^2$.

Thus, replacing d by $(b + c)$, we get $a^2 + 2ad + d^2 = a^2 + 2a(b + c) + (b + c)^2$.

So, $(a + b + c)^2 = a^2 + 2ab + 2ac + b^2 + 2bc + c^2$.

It may be more convenient to remember this as.

$(a + b + c)^2 = a^2 + b^2 + c^2 + 2ab + 2bc + 2ca.$

Let us interpret this geometrically by drawing a square of side $a + b + c$ as shown in Fig. 4.4.





© NCERT not to be republished



Fig. 4.4: A geometrical model representing the identity $(a + b + c)^2 = a^2 + b^2 + c^2 + 2ab + 2bc + 2ca$

Think and Reflect

Label the squares and rectangles in Fig. 4.4 so that it represents the identity $(a + b + c)^2 = a^2 + b^2 + c^2 + 2ab + 2bc + 2ca$.

Example 9: Let us use this identity to find the square of a number, say 119:

$$119^2 = (100 + 10 + 9)^2$$
$$= 100^2 + 10^2 + 9^2 + 2(100)(10) + 2(100)(9) + 2(10)(9)$$
$$= 10000 + 100 + 81 + 2000 + 1800 + 180 = 14161.$$

So far we have verified the following three identities and used them for performing calculations and manipulating algebraic expressions:

1. $(a + b)^2 = a^2 + 2ab + b^2$
2. $(a – b)^2 = a^2 – 2ab + b^2$
3. $(a + b + c)^2 = a^2 + b^2 + c^2 + 2ab + 2bc + 2ca$

Exercise Set 4.3

1. Find the following squares using one of the above identities. Determine which of these identities will make these calculations easier.

   (i) 117^2 (ii) 78^2 (iii) 198^2

   (iv) 214^2 (v) 1104^2 (vi) 1120^2

© NCERT not to be republished

2. Factor using suitable identities:

   (i) $16y^2 - 24y + 9$ (ii) $\frac{9}{4}s^2 + 6st + 4t^2$

   (iii) $\frac{m^2}{9} + \frac{mk}{3} + \frac{k^2}{4} + 3nk + 2mn + 9n^2$ (iv) $\frac{p^2}{16} - 2 + \frac{16}{p^2}$

   (v) $9a^2 + 4b^2 + c^2 - 12ab + 6ac - 4bc$

3. Expand the following using the identity

   $(a + b + c)^2 = a^2 + b^2 + c^2 + 2ab + 2bc + 2ca$:

   (i) $(p + 3q + 7r)^2$ (ii) $(3x - 2y + 4z)^2$

4. Is this an identity?

   $(a+b-c)^2 + (a-b+c)^2 + (a-b-c)^2 = 2a^2 + 2b^2 + 2c^2$.

In Grade 8, you were introduced to yet another identity, $a^2 - b^2 = (a + b)(a - b)$.

This can be quite useful if it is rewritten as $a^2 = (a + b)(a - b) + b^2$.

Look at the following figure. Justify the identity $a^2 = (a + b)(a - b) + b^2$ for yourself.



Fig. 4.5

In 750 CE, this identity was proposed by Śhrīdharāchārya as a method to quickly compute the squares of numbers. For example,

$55^2 = (55 + 5)(55 - 5) + 5^2$

$= 60 \times 50 + 25$

$= 3000 + 25 = 3025.$

© NCERT not to be republished

Think and Reflect

1. Try to evaluate the following using a suitable identity:
   (i) 35^2 (ii) 65^2 (iii) 85^2 (iv) 105^2
   Do you observe any interesting pattern?
2. Observe the two rows of figures below. They represent an algebraic identity. Try to identify it.



Fig. 4.6

© NCERT not to be republished

4.5 Factorisation Using Algebra Tiles

Consider a rectangle with sides $x + 3$ and $x + 4$ units.

We know that the area of such a rectangle is $(x + 3)(x + 4)$ sq. units.

Using distributivity, we get

$$(x + 3)(x + 4) = x^2 + 3x + 4x + 12 = x^2 + 7x + 12.$$



Fig. 4.7: Factorisation of $x^2 + 7x + 12$

Fig. 4.7 helps to visualise the product of $x + 3$ and $x + 4$ using algebra tiles. The expression $x + 3$ is represented using an x-tile and three unit tiles. Similarly $x + 4$ is represented using an x-tile and four unit tiles. The product of these two linear factors is shown in the inner rectangle comprising the x^2-tile, the 7 x-tiles, and 12 unit tiles.

Note that the $7x$ in $x^2 + 7x + 12$ has been split as $3x + 4x$. This is represented by the fact that three x-tiles are placed on the right side of the x^2-tile and four x-tiles are arranged below it. Also, the 12 unit tiles are arranged in a 3 by 4 array. Once the rectangular arrangement is formed, we observe that the dimensions of the rectangle are $x + 3$ and $x + 4$ units respectively.

Think and Reflect

Suppose $7x$ is split as $2x + 5x$; can a similar rectangular arrangement be formed? Consider other possibilities and check.

Fig. 4.7 helps us to visualise two algebraic identities:

(i) The linear expressions $x + 3$ and $x + 4$ can be multiplied to obtain the identity $(x + 3)(x + 4) = x^2 + 7x + 12$.

(ii) Also the expression $x^2 + 7x + 12$ can be factored into the linear factors $(x + 3)$ and $(x + 4)$, giving the same identity $x^2 + 7x + 12 = (x + 3)(x + 4)$.

Think and Reflect

Algebra tiles can be used to represent products and find factors.

1. Figure out the product of $x + 2$ and $x + 3$ using algebra tiles.
2. Lay out algebra tiles for $x^2 + 11x + 30$ in such a way that you will see its factors.

© NCERT not to be republished

Think and Reflect

We have seen that $(x + 3)(x + 4) = x^2 + 7x + 12$.

Also $(x + 6)(x + 7) = x^2 + 13x + 42$.

Generalise the pattern to get an expression for $(x + a)(x + b)$.

Now consider the case where we have a rectangle of sidelengths $2x + 3$ and $3x + 1$, as shown in Fig. 4.8. What can you say about its area $(2x + 3)(3x + 1)$?



Fig. 4.8: Using algebra tiles to represent $(2x + 3) \times (3x + 1)$

Fill in the blanks with the appropriate expressions to make the equation true.

$$(px + a)(qx + b) = (_____)x^2 + (_____)x + _____ .$$

Also, verify your answer using the distributive property.

4.6 Factorisation Without Using Algebra Tiles

Consider the algebraic expression $x^2 + 7x + 12$ which was obtained by multiplying the linear terms $x + 3$ and $x + 4$. We also saw in Fig. 4.7 that $7x$ was split as $3x + 4x$ so that a rectangle could be formed using the algebra tiles. But how do we achieve this 'splitting of the x term' without using tiles?

© NCERT not to be republished

Example 10: Let us begin with $x^2 + 7x + 12 = x^2 + (a + b)x + ab$.

Comparing the coefficients of the x-term and the constant terms on both sides of the equation, we get $a + b = 7$ and $ab = 12$. Note that this is only possible when $a = 3$ and $b = 4$, or $a = 4$ and $b = 3$. Thus, we choose one of these two possibilities and write the factors as

$(x + a)\,(x + b)$, that is, $(x + 3)\,(x + 4)$.

Example 11: Let us try to factor $x^2 + 11x + 30$ in a similar manner.

$$x^2 + 11x + 30 = x^2 + (a + b)x + ab.$$

This leads to $a + b = 11$ and $ab = 30$. We need to choose values of a and b appropriately, so that $a + b = 11$ and $ab = 30$ are both satisfied. What if we choose $a = 2$ and $b = 15$? Or $a = 3$ and b = 10? Clearly these will not work as $a + b$ is not equal to 11 even though $ab = 30$. So, we look at the factors of 30 and arrive at $a = 5$ and $b = 6$ or vice-versa. This way the x-term, $11x$, can be split as $5x + 6x$.

Thus, $x^2 + 11x + 30 = x^2 + (5 + 6)x + 30 = (x + 5)(x + 6)$.

Example 12: In order to factor $x^2 - 5x + 6$, we first note that the coefficient of x is negative. Once again comparing $x^2 - 5x + 6$ with $x^2 + (a + b)x + ab$, we get $a + b = -5$ and $ab = 6$. Note that these two equations can be satisfied together only when $a = -2$ and $b = -3$ or vice-versa.

Exercise Set 4.4

1. Fill in the blanks to complete the following identities:
   (i) $s^2 - 11s + 24 =$ (_____) (_____)
   (ii) (_____) $(x + 1) = (3x^2 - 4x - 7)$
   (iii) $10x^2 - 11x - 6 = (2x -$ ___) (___ + 2)
   (iv) $6x^2 + 7x + 2 =$ (_____) (_____)
2. Select and use the identity that will help you to find the following products without multiplying directly:
   (i) $(41)^2$ (ii) $(27)^2$
   (iii) (23×17) (iv) $(135)^2$

© NCERT not to be republished

(v) $(97)^2$ (vi) (18×29)

(vii) (34×43) (viii) $(205)^2$

3. Factor the following:

(i) $9a^2 + b^2 + 4c^2 - 6ab + 12ac - 4bc$ (ii) $16s^2 + 25t^2 - 40st$

(iii) $r^2 - r - 42$ (iv) $49g^2 + 14gh + h^2$

(v) $64u^2 + 121v^2 + 4w^2 - 176uv - 32uw + 44vw$

Think and Reflect

James and Reshma were talking about algebraic identities they learnt in school.

James: $(a - b)^2 (a + b) = (a^2 - 2ab + b^2)(a + b)$

Reshma: I have a different idea. $(a - b)^2 (a + b) = (a - b)\,[(a - b)\,(a + b)]$

$= (a - b)(a^2 - b^2)$

I will find this product to get the answer.

According to you, who is correct and why?

Try to combine more such identities and find new results.

4.7 Finding New Identities

In this section we will play around with algebraic expressions to see if we can arrive at new identities.

What do you think $(a + b)^3$ will look like?

Let us find out the answer using the distributive property:

$$(a + b)^3 = (a + b)(a^2 + 2ab + b^2) = a^3 + 3a^2b + 3ab^2 + b^3.$$

Here we have found a new identity, namely,

$$(a + b)^3 = a^3 + 3a^2b + 3ab^2 + b^3.$$

Let us try to visualise this identity. We saw that a square of side $a + b$ can be divided into squares and rectangles. This led us to the identity, $(a + b)^2 = a^2 + 2ab + b^2$. What if we have a cube of edge $a + b$? Can we divide a cube of edge $(a + b)$ into smaller cubes and cuboids and represent this new identity?



Fig. 4.9: A cube of edge a + b

© NCERT not to be republished

We know that the volume of this cube is $(a + b)^3$. Let us split this cube into smaller cubes and cuboids.



Fig. 4.10: Representation of the identity
$(a + b)^3 = a^3 + 3a^2b + 3ab^2 + b^3$

Notice that the larger cube can be split into two cubes and six cuboids. The cubes have volumes, a^3 and b^3 cubic units, respectively.

Amongst the other six cuboids, three have dimensions a units × a units × b units and other three have dimensions a units × b units × b units, and so their volumes are a^2b and ab^2 cubic units, respectively. Hence the total volume of the six cuboids is $3a^2b + 3ab^2$.

© NCERT not to be republished

This gives us, $(a + b)^3 = (a + b)(a^2 + 2ab + b^2) = a^3 + 3a^2 b + 3ab^2 + b^3$.

Here we have found a new identity, namely,

$$(a+b)^3 = a^3 + 3a^2b + 3ab^2 + b^3.$$

What happens when we replace b with $-b$ in this new identity?

$$[a+(-b)]^3 = a^3 + 3a^2(-b) + 3a(-b)^2 + (-b)^3.$$

This leads to the identity $(a-b)^3 = a^3 - 3a^2b + 3ab^2 - b^3$. Note that out of the four terms, two are positive and two are negative. They appear alternately in the expression.

Let us see how we can use these new identities.

Example 13: What is the side of the cube whose volume is $p^3 + 6p^2q + 12pq^2 + 8q^3$ cubic units?

Comparing $p^3 + 6p^2q + 12pq^2 + 8q^3$ with the right side of the identity $(a+b)^3 = a^3 + 3a^2b + 3ab^2 + b^3$, we may rewrite it as

$$(p)^3 + 3\,(p)^2(2q) + 3(p)(2q)^2 + (2q)^3$$

which is $(p + 2q)^3$, so that $a = p$ and $b = 2q$. Hence a side of the cube will be $p + 2q$ units.

Example 14: Now consider the expression

$$8n^3 - 60n^2m + 150nm^2 - 125m^3.$$

If you write it in the form $(a - b)^3$, what will be a and b?

Rewriting the expression $8n^3 - 60n^2m + 150nm^2 - 125m^3$ as

$(2n)^3 - 3(2n)^2(5m) + 3(2n)(5m)^2 - (5m)^3$ and comparing it with

$a^3 - 3a^2b + 3ab^2 - b^3 = (a-b)^3$, we get $(2n - 5m)^3$. Hence $a = 2n$ and $b = 5m$.

Now let us play with known identities to discover more identities. Try to multiply the following using the distributive property.

1. $(x - y)(x^2 + xy + y^2)$
2. $(x + y)(x^2 - xy + y^2)$

Let us work out the product of the first one.

$$(x-y)(x^2+xy+y^2) = x^3 + x^2y + xy^2 - x^2y - xy^2 - y^3$$

$$= x^3 + x^2y + xy^2 - x^2y - xy^2 - y^3 = x^3 - y^3.$$

© NCERT not to be republished

Thus $(x - y)(x^2 + xy + y^2) = x^3 - y^3$. This is also an identity!

Verify this for yourself by choosing different values of x and y.

Predict what $(x + y)(x^2 - xy + y^2)$ will be.

Think and Reflect

We already know that $x^2 - y^2 = (x - y)(x + y)$.

Further, we have verified that $x^3 - y^3 = (x - y)(x^2 + xy + y^2)$.

Observe that $x - y$ is a common factor of $x^2 - y^2$ and $x^3 - y^3$.

Do you think $x - y$ is also a factor of $x^4 - y^4$?

Note that $x^4 - y^4 = (x^2)^2 - (y^2)^2 = (x^2 - y^2)(x^2 + y^2)$.

Can you see how $x - y$ is a factor of $x^4 - y^4$?

How about $x^5 - y^5$? Does this also have $x - y$ as a factor?

Exploring further, let us multiply $(x + y + z)$ and $(x^2 + y^2 + z^2 - xy - xz - yz)$.

$(x + y + z)(x^2 + y^2 + z^2 - xy - xz - yz)$

$= (x^3 + xy^2 + xz^2 - x^2y - x^2z - xyz) + (x^2y + y^3 + yz^2 - xy^2 - xyz - y^2z)$

$\quad + (x^2z + y^2z + z^3 - xyz - xz^2 - yz^2)$

$= (x^3 + \cancel{xy^2} + \cancel{xz^2} - \cancel{x^2y} - \cancel{x^2z} - xyz) + (\cancel{x^2y} + y^3 + \cancel{yz^2} - \cancel{xy^2} - xyz - \cancel{y^2z})$

$\quad + (\cancel{x^2z} + \cancel{y^2z} + z^3 - xyz - \cancel{xz^2} - \cancel{yz^2})$

$= x^3 + y^3 + z^3 - 3xyz.$

So, $(x + y + z)(x^2 + y^2 + z^2 - xy - xz - yz) = x^3 + y^3 + z^3 - 3xyz.$

This is yet another identity. Let us explore some of its applications.

Example 15: The sum of three numbers is 10 and their product is 25. The sum of their squares is 38. Try to use the previous identity to find the sum of the cubes of these three numbers.

Let the three numbers be x, y and z, respectively. According to the problem $x + y + z = 10$, $xyz = 25$ and $x^2 + y^2 + z^2 = 38$.

Substituting in the identity

$(x + y + z)(x^2 + y^2 + z^2 - xy - xz - yz) = x^3 + y^3 + z^3 - 3xyz$, we get

$(10)(38 - xy - xz - yz) = x^3 + y^3 + z^3 - 3(25)$.

Thus, $x^3 + y^3 + z^3 = 380 - 10(xy + xz + yz) + 75 = 455 - 10(xy + xz + yz)$.

© NCERT not to be republished

To find $(xy + xz + yz)$, we need to use the identity $(x + y + z)^2 = x^2 + y^2 + z^2 + 2xy + 2xz + 2yz$.

We get $100 = 38 + 2(xy + xz + yz)$. Thus $xy + xz + yz = 31$.

Now, substituting this into our earlier equation, we obtain

$x^3 + y^3 + z^3 = 455 - 10(xy + xz + yz) = 455 - 10(31) = 455 - 310 = 145$.

4.8 Simplifying Rational Expressions

In the earlier sections of this chapter, we have learnt how to factorise algebraic expressions. Let us see how we can simplify some rational algebraic expressions using factorisation.

Example 16: Simplify the rational expression $\frac{x^2 - 7x + 12}{5x^2 + 5x - 100}$, assuming that $5x^2 + 5x - 100 \neq 0$.

In order to simplify this rational expression, we need to cancel the common factors between the expressions in the numerator and denominator.

We will need to use algebraic identities to simplify this rational expression.

First, let us look at the numerator $x^2 - 7x + 12$. We need to find a and b such that $a + b = -7$ and $ab = 12$. Can you think of two such numbers? They are -3 and -4. Factor the expression, we get $x^2 - 7x + 12 = (x - 3)(x - 4)$.

Now let us look at the denominator $5x^2 + 5x - 100$. We can see that all the three terms are multiples of 5 so we can take 5 as a common factor and simplify the expression: $5x^2 + 5x - 100 = 5(x^2 + x - 20)$. Now we need to find a and b such that, $a + b = 1$ and $ab = -20$. Try to think of two such numbers. They are 5 and -4. Thus, we have $5x^2 + 5x - 100 = 5(x - 4)(x + 5)$.

Substituting the factored expressions in the numerator and denominator, we arrive at

$$\frac{x^2 - 7x + 12}{5x^2 + 5x - 100} = \frac{x^2 - 7x + 12}{5(x^2 + x - 20)} = \frac{(x-4)(x-3)}{5(x-4)(x+5)}.$$

Thus, the common factor $x - 4$ can be cancelled as it is not equal to 0. We know this because $5x^2 + 5x - 100 \neq 0$. Thus,

$$\frac{x^2 - 7x + 12}{5x^2 + 5x - 100} = \frac{x-3}{5(x+5)}.$$

© NCERT not to be republished

Think and Reflect

Try to simplify the following rational expression:

$$\frac{36s^2-12st+t^2}{t^2+2ts-48s^2}=\frac{(6s-t)^2}{(__+__)(__+__)}.$$

(**Hint:** Factor $t^2 + 2ts - 48s^2$ and simplify the rational expressions assuming that $t^2 + 2ts - 48s^2 \neq 0$).

Exercise Set 4.5

1. Simplify the following rational expressions assuming that the expressions in the denominators are not equal to zero:

(i) $\dfrac{3p^2-3pq-18q^2}{p^2+3pq-10q^2}$ (ii) $\dfrac{n^3-3n^2m+3nm^2-m^3}{5m^2-10mn+5n^2}$

(iii) $\dfrac{w^3-v^3+x^3+3wvx}{w^2+v^2+x^2-2wv-2vx+2wx}$ (iv) $\dfrac{4y^2-20yz+25z^2}{\left(25z^2-4y^2\right)}$

(v) $\dfrac{\left(x^2+x-6\right)\left(x^2-7x+12\right)}{(x^2-6x+8)\left(x^2-9\right)}$ (vi) $\dfrac{p^4-16}{p^2-4p+4}$

Example 17: Saira has arranged a square of side x units, 8 rectangular strips of sides x units and width 1 unit, and 15 squares of side 1 unit to form a bigger rectangle. Find the length and breadth of the rectangle in terms of x.

Area covered by a square of side x units = x^2 sq. units

Area covered by rectangle of sides x units and 1 unit = x sq. units

Total area covered by 8 such rectangles = $8x$ sq. units

Area covered by a square of side 1 unit = 1 sq. units

Total area covered by 15 such squares = 15 sq. units

Total area covered by all the squares and rectangles

= $x^2 + 8x + 15$ sq. units.

Area of Saira's rectangle = $x^2 + 8x + 15$ sq. units.

We can factor $x^2 + 8x + 15$ to obtain the dimensions of the rectangle prepared by Saira.

© NCERT not to be republished

For factoring $x^2 + 8x + 15$, we need a and b such that $a + b = 8$ and $ab = 15$

So, $a = 3$ and $b = 5$ is one possibility. The possible length and breadth of Saira's rectangle in terms of x are: length = $x + 5$ units and breadth = $x + 3$ units.

Now draw Saira's rectangle using these pieces.

Example 18: A rectangular pool is such that its breadth is 4 metres less than its length and its area is 96 sq. metres. Find the length and breadth of the pool.

Let the length of the pool be x metres. Then the breadth of the pool is $x - 4$ metres.

Since the area is given to be 96 sq. metres, we get $x(x - 4) = 96$.

$$x^2 - 4x = 96 \text{ or } x^2 - 4x - 96 = 0.$$

We choose appropriate factors of -96 to split the term $-4x$. We know that, $(-12) \times 8 = 96$ and $(-12) + 8 = -4$. Hence $-4x$ can be written as $-12x + 8x$.

$$x^2 - 4x - 96 = x^2 - 12x + 8x - 96 = x(x - 12) + 8(x - 12) = (x - 12)(x + 8) = 0.$$

Thus, $x^2 - 4x - 96 = 0$ implies that $(x - 12)(x + 8) = 0$.

This means either $x - 12 = 0$ or $x + 8 = 0$.

That is, $x = 12$ or $x = -8$. Since x is the length of the pool, it cannot be negative. Therefore, we ignore $x = -8$ and $x = 12$ metres must be the length of the pool. The breadth of the pool = $x - 4 = 12 - 4 = 8$ metres.

End-of-Chapter Exercises

1. Use suitable identities to find the following products:

(i) $(-3x + 4)^2$

(ii) $(2s + 7)(2s - 7)$

(iii) $\left(p^2 + \frac{1}{2}\right)\left(p^2 - \frac{1}{2}\right)$

(iv) $(2n + 7)(2n - 7)$

(v) $(s - 2t)(s^2 + 2st + 4t^2)$

(vi) $\left(\frac{1}{2r} - 4r\right)^2$

(vii) $(-3m + 4k - l)^2$

(viii) $\left(x - \frac{1}{3}y\right)^3$

(ix) $\left(\frac{7}{2}k - \frac{2}{3}m\right)^3$

© NCERT not to be republished

2. Find the values using suitable identities:

(i) 17×21 (ii) 104×96

(iii) 24×16 (iv) 147^3

(v) 199^3 (vi) 127^3

(vii) $(-107)^3$ (viii) $(-299)^3$

3. Factor the following algebraic expressions:

(i) $4y^2 + 1 + \frac{1}{16y^2}$ (ii) $9m^2 - \frac{1}{25n^2}$

(iii) $27b^3 - \frac{1}{64b^3}$ (iv) $x^2 + \frac{5x}{6} + \frac{1}{6}$

(v) $27u^3 - \frac{1}{125} - \frac{27u^2}{5} + \frac{9u}{25}$ (vi) $64y^3 + \frac{1}{125}z^3$

(vii) $p^3 + 27q^3 + r^3 - 9pqr$ (viii) $9m^2 - 12m + 4$

(ix) $9x^3 - \frac{8}{3}y^3 + \frac{z^3}{3} + 6xyz$

(x) $4x^2 + 9y^2 + 36z^2 + 12xz + 36yz + 24xy$

(xi) $27u^3 - \frac{1}{216} - \frac{9u^2}{2} + \frac{u}{4}$

4. Simplify the following:

(i) $\frac{4x^2 + 4x + 1}{4x^2 - 1}$ (ii) $\frac{9\left(3a^3 - 24b^3\right)}{9a^2 - 36b^2}$ (iii) $\frac{s^3 + 125t^3}{s^2 - 2st - 35t^2}$

Note: Assume that the denominators are not equal to 0.

5. Find possible expressions for the length and breadth of each of the following rectangles whose areas are given by the following expressions in square units.

(i) $25a^2 - 30ab + 9b^2$ (ii) $36s^2 - 49t^2$

6. Find possible expressions for the length, breadth, and heights of each of the following cuboids whose volumes are given by the following expressions in cubic units.

(i) $6a^2 - 24b^2$ (ii) $3ps^2 - 15ps + 12p$

© NCERT not to be republished

7. The village playground is shaped as a square of side 40 metres. A path of width s metres is created around the playground for people to walk. Find an expression for the area of the path in terms of s.
8. If a number plus its reciprocal equals $\frac{10}{3}$, find the number.
9. A rectangular pool has area $2x^2 + 7x + 3$ square *hastas*. If its width is $2x + 1$ *hastas*, find its length. *Hasta* was a unit used to measure length.

*10. If both $x - 2$ and $x - \frac{1}{2}$ are factors of $px^2 + 5x + r$, show that $p = r$.

*11. If $a + b + c = 5$ and $ab + bc + ca = 10$, then prove that $a^3 + b^3 + c^3 - 3abc = -25$.

*12. By factoring the expression, check that $n^3 - n$ is always divisible by 6 for all natural numbers n. Give reasons.

*13. Find the value of
(i) $x^3 + y^3 - 12xy + 64$, when $x + y = -4$
(ii) $x^3 - 8y^3 - 36xy - 216$, when $x = 2y + 6$

Chapter Summary

- **Identities** are equations that are true for all values of the variables.
- One of the ways to visualise identities is using geometrical models or algebra tiles.
- Identities can also be used to factor algebraic expressions.
- Factorisation of quadratic expressions may be visualised by means of algebra tiles.
- Identities can also be used to simplify calculations such as squaring numbers or evaluating products of numbers.
- Rational algebraic expressions may be simplified by factorisation and removing the common factors in the numerator and denominator, provided such a factor exists and it is not equal to zero.

© NCERT not to be republished

- We have studied the following identities in this chapter:
  - $(x + y)^2 = x^2 + 2xy + y^2$
  - $(x – y)^2 = x^2 – 2xy + y^2$
  - $(x + y + z)^2 = x^2 + y^2 + z^2 + 2xy + 2yz + 2zx$
  - $(x + y)\,(x – y) = x^2 – y^2$
  - $(x + a)\,(x + b) = x^2 + (a + b)\,x + ab$
  - $(ax + b)\,(cx + d) = acx^2 + (ad + bc)\,x + bd$
  - $x^3 – y^3 = (x – y)\,(x^2 + xy + y^2)$
  - $x^3 + y^3 = (x + y)\,(x^2 – xy + y^2)$
  - $(x + y)^3 = x^3 + 3x^2y + 3xy^2 + y^3$
  - $(x – y)^3 = x^3 – 3x^2y + 3xy^2 – y^3$
  - $x^3 + y^3 + z^3 – 3xyz = (x + y + z)(x^2 + y^2 + z^2 – xy – xz – yz)$

© NCERT not to be republished

5 I'm Up and Down, and Round and Round

0904CH05

Humanity has always been fascinated by the shapes of the things around them. In some early cave paintings, the sun is depicted as a circle. In the cave paintings of Gudahandi in Odisha, one sees numerous geometric patterns including triangles, squares, circles, and ovals. These shapes were likely inspired by what humans saw in nature.

Can you recognise the origin of the shapes in Fig. 5.1?

Fig. 5.1

Circles form when raindrops fall on water. The cross-section of a plant stem and the inflorescence of a sunflower are also circular in shape. The full moon and sun also look circular.

Moon

Sun (during a total solar eclipse)

Fig 5.2

What properties are common to all circles, big and small? You have studied one such property in Grade 7. Humans must have noticed it after observing many circular patterns in nature. Every circle has a centre. All points on the circle are at equal distance from the centre. We turn this observation around and make it the definition of a circle.

Activity: List some objects from nature that resemble a circle.

Think and Reflect

Jamuna has a circular piece of paper. She is trying to locate its centre. Amina gives her a suggestion. She follows the instructions and is thrilled to find that it works. Can you guess what Amina told her?

5.1 Definitions

When we talk of mathematical shapes such as circles, triangles and squares, we always assume that the figures are drawn on a piece of paper — a two-dimensional plane.



Fig. 5.3: Circle, Centre A, Chord BC

A **circle** is the set of all points on the plane that are equidistant from a given point on that plane. The set of points that satisfy a given condition is also called the **locus** of points that satisfy the condition. Using this term, a circle can also be described as the locus of points that are equidistant from a given point. The given point is the **centre** of the circle. The distance from the centre to any point on the circle is the **radius** of the circle.

In Fig 5.3, A is the centre of the circle. All points on the plane at a distance equal to the length of AB from A form a circle with centre A and radius equal to the length of AB.

Let B and C be two points on the circle. The line segment BC is called a **chord** of the circle. The angle subtended by the chord BC at the centre is angle BAC. A chord passing through the centre of a circle is called a **diameter**.

© NCERT not to be republished

5.2 Symmetries of a Circle

What makes circles so appealing is that they are perfectly symmetrical. Say you are looking at a wheel of a vehicle. You see a point of the wheel touching the ground. When you look at the wheel again after some time, you again see a point of the wheel touching the ground. Can you tell if the two points are the same point? There is no way you can tell; a rotating wheel looks the same at all times! We say the circle has complete rotational symmetry: rotate it by any angle and it looks exactly the same.

Draw a circle on the paper and cut along the circle. Fold the circular paper so that the boundaries overlap, then open it. You see a crease; it is a line of reflection symmetry of the circle. Does this line pass through the centre of the circle? It does. It is a **diameter** of the circle. All diameters are lines of reflection symmetry.

Think and Reflect

1. What are the rotational symmetries of a square? How many lines of reflection symmetry does it have? What about a regular pentagon? A regular hexagon?
2. What is the length of the longest chord in a circle of radius 5 units? Is there a smallest chord?
3. The locus of points at a given distance from a given point is a circle. What can we say about the locus of points equidistant from two given points?

   (**Hint:** We know that any point that is equidistant from two given points A and B lies on the perpendicular bisector of AB. Does this make the perpendicular bisector the locus? For this, we have to show that all the points on the perpendicular bisector are equidistant from A and B.)

5.3 How Many Circles?

Now that we have defined a circle and listed some of its properties, let us ask this question: Given two points A and B on a plane, how many circles pass through A and B?

If a circle passes through A and B, it has a centre, say O. The lengths OA and OB are equal. Is there another point with this property? Yes, the midpoint of segment AB. With the midpoint as centre, a circle passing through A and B can be drawn. Its radius is half the length of AB, and AB is a diameter.

© NCERT not to be republished

Are there more circles passing through both A and B? Clearly, any point equidistant from A and B can be the centre of a circle passing through A and B. Do you know of such points? We have seen that the perpendicular bisector of the line segment AB is the locus of points equidistant from A and B. Every point on the perpendicular bisector is equidistant from A and B, and every point that is equidistant from A and B is on the perpendicular bisector! So, the centres of all circles through A and B lie on the perpendicular bisector of AB.



Fig. 5.4: Circles through two points

In Fig. 5.4, we see circles through points A and B, and through C and D, and the perpendicular bisector of CD. Every point on the perpendicular bisector is the centre of a circle passing through C and D. So we have circles with centres K, J and L containing points C and D.

Think and Reflect

1. How many circles pass through two points on a plane?
2. Are there circles of all possible radii passing through A and B? What is the radius of the smallest circle passing through A and B? What is the radius of the largest circle passing through A and B?
3. As you move away from segment AB along its perpendicular bisector, do the radii of the circles containing A and B increase or decrease?
4. As you go along the perpendicular bisector, will the circle drawn from that point through A and B appear more curved or less curved?
5. You are given two points A and B on a plane. How many squares can you draw on the same plane with A and B on the boundary? How many squares can you draw on the plane with A and B as the corners of the square?

© NCERT not to be republished

It is natural to ask: How many circles can you draw through three distinct points A, B and C on a plane? Is there always at least one such circle? Not necessarily! What if A, B and C lie on a straight line, i.e., are **collinear**? Can you explain why, in this case, there is no circle through A, B and C?

Let us assume that A, B and C are not collinear. Is there always a circle passing through A, B and C? Can there be more than one circle through A, B and C?

Theorem 1: *There is a unique circle passing through three non-collinear points.*

Why is this true? If there is a circle that passes through non-collinear A, B and C, the circle must have a centre. Let's call that centre O (we will discover O soon).

Since OA = OB, we know that O lies on the perpendicular bisector of AB.

Since OA = OC, we know that O lies on the perpendicular bisector of AC as well.

But A, B and C are **not** collinear. So, the perpendicular bisectors of AB and AC will intersect at a unique point, since two intersecting lines meet at exactly one point on the plane. That point must be O.

Using O as the centre we can draw a circle with radius equal to the length of OA. That will pass through A, B and C. This explains why the statement is true.

Now three non-collinear points also determine a triangle. What we have described above is the construction of a circle that passes through the vertices of the triangle.



Fig. 5.5: The circumcircle of triangle ABC

© NCERT not to be republished

The centre O of the circle that passes through the vertices A, B and C of ΔABC is called the **circumcentre** of ΔABC (Fig. 5.5). The circle is called the **circumcircle** and is said to circumscribe the triangle. Conversely, the triangle is said to be inscribed in the circle. Since, the intersection of the perpendicular bisectors of AB and BC is a single point, there is just one such circle for a given triangle. Further, for an acute-angled triangle, the circumcentre lies inside the triangle (see Fig. 5.5). For an obtuse-angled triangle, the circumcentre lies outside the triangle (Fig. 5.6). And for a right-angled triangle, the circumcentre lies at the midpoint of the hypotenuse (Fig. 5.7).



Fig. 5.6: Obtuse-angled triangle: Circumcentre O is outside the triangle



Fig. 5.7: Right-angled triangle: Circumcentre O is at the midpoint of the hypotenuse

© NCERT not to be republished

Exercise Set 5.1

1. Draw ΔABC with AB = 5 cm, ∠A = 70° and ∠B = 60°. Draw the circumcircle of ΔABC. Is the centre inside or outside the triangle?
2. Draw ΔABC with AB = 5 cm, ∠A = 100°, AC = 4 cm. Draw the circumcircle of ΔABC. Is the centre inside or outside the triangle?
3. Draw ΔABC, with AB = 6 cm, BC = 7 cm and CA = 7 cm. Draw the circumcircle of ΔABC. Let the circumcentre be O. Measure OA, OB, OC.
4. What is the least possible radius of a circle through two points A and B?

Think, Draw and Infer

1. A, B and C are three collinear points. Can you find a point P such that PA = PB = PC? What can you say about the perpendicular bisectors of AB and BC? Draw and check. Can you show that for three collinear points A, B and C, the perpendicular bisector of AB and BC are parallel? Is it possible for a circle to pass through collinear points? Can you draw a line that cuts a given circle in three distinct points?
2. The circumcircle of a given ΔABC is drawn. Can there be other triangles congruent to ΔABC that share the same circumcircle?

5.4 Chords and the Angles They Subtend

You may want to know when 4 points lie on the same circle. That will have to wait till the end of this chapter. We need to do some more work to get there.

Fig. 5.8: Chords and radii

Tie a thread at two points on a wheel; pull it tight (Fig. 5.8). The thread can be thought of as a chord of the wheel (a circle). Imagine joining the end points of the thread to the centre. The thread subtends an angle at the centre. Now, rotate the wheel. The thread rotates around the centre along with the wheel.

© NCERT not to be republished

In the new position, the thread is another chord on the circle. What is common to the first and second chords? They have the same length, equal to the length of the thread. What about the angle subtended by the second chord at the centre? It must surely be the same as the angle subtended by the first chord at the centre. We now explain why this is true.

Theorem 2: *Equal chords of a circle subtend equal angles at the centre of the circle.*

What does the theorem say? It talks of two chords of the circle with equal length. In geometry, it always helps to draw a figure! (See Fig. 5.9). AB and DE are chords of the same length. We need to explain why ∠ACB is equal to ∠DCE. What are we given? AB = DE.

To explain why two angles in two different triangles are equal, we use congruence of triangles. If the angles which we want to show equal are corresponding angles, then our task would be done!



Fig. 5.9

Given: AB = DE.

To show: ∠ACB = ∠DCE.

Why is this true? First, we see that CA = CB = r, the radius of the circle.

Also, CD = CE = r. So, CA = CD and CB = CE.

But AB = DE is given! By the SSS congruence, ΔCAB is congruent to ΔCDE. So, ∠ACB is equal to ∠DCE, i.e., the angles subtended at the centre are equal.

Now suppose we have two chords that subtend equal angles at the centre. Are the chords equal? What does our intuition tell us? Let the chords be AB and DE. Let us use our imagination. Assume that B, A, E, and D are located clockwise on the circle as shown in Fig 5.10.



Fig. 5.10

Imagine you are standing at the centre C of a circle. Stretch your arms so that they are at a certain angle. Let your arms intersect the circle at A, B. The distance between your arm ends must be the length of chord AB. Now let the floor rotate magically. You start rotating (say clockwise) about C. Don't change the angle your arms make! At some point your left arm meets point E.

© NCERT not to be republished

Where will your right hand be? It should be at D, should it not? That is because we assumed that angles ACB and DCF are equal, and you have not moved your hands. The distance between the ends of your arms must be the length of DE as well. Let us now explain why this is true.

Theorem 3: *Chords of a circle that subtend equal angles at the centre are equal.*

Let us draw the figure, as in Fig. 5.11.



Fig. 5.11

Given: ∠ACB = ∠DCE.

To show: AB = ED.

Why is this true? We see that AC = BC = the radius of the circle. Likewise, EC = DC = the radius. So, AC = DC and BC = EC.

Since, ∠ACB = ∠DCE, by the SAS congruence, ΔACB ≅ ΔDCE. Hence, AB = ED.

Exercise Set 5.2

1. Show that the triangle formed by a chord and the centre of the circle is isosceles.
2. Show that if two such isosceles triangles (occurring in the previous question) have equal base length, they are congruent to each other.

5.5 Midpoints and Perpendicular Bisectors of Chords

We will explore more properties of chords. Do we get something special when we draw a line segment from the centre of a circle to the midpoint of a chord? What if we draw the perpendicular bisector of a chord? Does it pass through a special point?

© NCERT not to be republished

Theorem 4: *The line joining the centre of a circle and the midpoint of a chord of the circle is perpendicular to the chord.*



Fig. 5.12

Let us see why this is true. Draw a circle with centre C (Fig. 5.12). Draw any chord AB. Let M be the midpoint of AB. We must show that CM is perpendicular to AB.

Explanation: CAB is an isosceles triangle. AB is the base and CA = CB. So, $\angle A = \angle B$.

M is the midpoint of AB. So, AM = BM.

By the SAS congruence, Δ CMA is congruent to Δ CMB. So, $\angle CMB = \angle CMA$.

But $\angle CMB + \angle CMA = 180°$ (angles on a line).

So, both angles are 90°. That is, CM is perpendicular to AB.

Exercise Set 5.3

1. Can you explain why the converse to Theorem 4 is true, i.e., why does the perpendicular from the centre of a circle to a chord of the circle bisect the chord?

   (**Hint:** Use Fig. 5.12. You are told that $\angle CMA = \angle CMB = 90°$. You need to show that AM = BM.)
2. An isosceles triangle ABC is inscribed in a circle, with AB = AC. Show that the altitude from A to BC passes through the centre of the circle.
3. Two parallel chords of lengths 6 cm and 8 cm are on opposite sides of the centre of a circle. If the radius of the circle is 5 cm, find the distance between the midpoints of the chords.

© NCERT not to be republished

From Question 1 above, we have the following result.

Theorem 5: *The perpendicular from the centre of a circle to a chord of the circle bisects the chord.*

5.6 Distance of Chords from the Centre

Activity: Take a paper circle. Fold the circle from the boundary, inwards. Open the fold. The crease is now a chord (see Fig. 5.13B). Now fold the paper again, so that the end points of the chord meet. Open the fold (see Fig. 5.13C).

Fig. 5.13A

Fig. 5.13B

Fig. 5.13C

Measure the lengths of the parts into which the chord is divided. The chord gets bisected where the folds intersect. Measure the angle between the creases. The crease of the second fold is along the perpendicular from the centre to the chord. Measure the distance from the centre to the midpoint of the chord. It is the distance from the centre to the chord.

Now draw another chord of the same length. How will you do this? We will let you figure this out yourself. Join the centre to the midpoint of the new chord and measure its length. Is it the same as distance from the centre to the first chord?

Now take a tracing paper and draw a circle on it with the same radius. Place the circle on the tracing paper on top of the circle paper so that the circles overlap. Trace the chord on the circle paper, and the perpendicular to it from its centre, onto the tracing paper circle. Now rotate the tracing paper. You will see the chord through the tracing paper — it looks like a different chord of the same length on the circle paper.

The circle is a symmetric figure. So, rotating the circle around its centre does not change the circle. As we rotate the circle, our chosen chord will also rotate, to give a new chord of the same length. Along with it, the perpendicular from the centre to the chord also moves! Equal chords appear to be equidistant from the centre.

© NCERT not to be republished

Is this a totally convincing explanation? No, we have only given examples where our guess holds true. A statement may be true on a large number of examples, but it does not mean the statement is true in general. So let us explain why the statement is true.

Theorem 6: *Chords of a circle having the same length are all at the same distance from the centre of the circle.*

Draw the figure (Fig. 5.14).



Fig. 5.14

Given: Circle with centre C; AB = FG; E, H are midpoints of AB, FG respectively.

To show: CE = CH.

Why is this true? From Theorem 5, CE and CH are the perpendiculars from C to the chords AB and FG respectively.

So, CE and CH are the distances from the centre C to the chords AB and FG respectively.

We shall explain this result in two different ways.

(1) Triangles CAB and CFG are congruent.

CA = CF (both are equal to the radius of the circle). Likewise, CB = CG.

We are given that AB = FG. So, by the SSS congruence, $\Delta CAB \cong \Delta CFG$.

Hence the altitudes of the congruent triangles are congruent. CE = CH. Therefore, the chords AB and FG are equidistant from the centre C.

(2) Consider triangles CEA and CHF.

From Theorem 5, the perpendicular from the centre bisects the chord.

Hence, E and H are the midpoints of the chords AB and FG respectively.

© NCERT not to be republished

AE = FH (since AB = FG, and E and H are midpoints of AB and FG).

$\angle CEA = \angle CHF = 90°$.

CF = CA, as they are radii of the circle.

By the RHS congruence, $\Delta CEA \cong \Delta CHF$.

So, CE = CH. Thus the chords of equal length are equidistant from the centre.

Exercise Set 5.4

1. Use the Baudhāyana–Pythagoras theorem to show why Theorem 6 must be true.
2. Consider Fig. 5.15. If CE is perpendicular to AB, CH is perpendicular to GH, and CE = CH, show that AB = GF.
3. Solve the previous question using the Baudhāyana–Pythagoras theorem.



Fig. 5.15

Question 2 in the exercise above establishes the following result.

Theorem 7: *Chords of a circle that are equidistant from the centre have equal length.*

5.6.1 Which of the two unequal chords is farther from the centre?

You have two chords on a circle. One is longer than the other. Which chord is closer to the centre? Can you guess?

Activity: Draw a circle. Draw chords of various lengths. Drop a perpendicular to each chord from the centre. Record the length of the chord and its distance from the centre in a table.

Table 1

Length of Chord			
Distance from Centre			

© NCERT not to be republished

What do you observe? The longer the chord, the closer it is to the centre. Let us try to understand why this is true.

Theorem 8: *Let AB and DE be two chords of a circle with centre C. Suppose AB > DE. Then the distance from C to AB is less than the distance from C to DE.*

As always, we draw the figure. Remember: by 'distance from C to AB' we mean the perpendicular distance. So, we drop perpendiculars CF and CG from C to AB and DE, respectively.



Fig. 5.16

Given: AB > DE.

To show that: CF < CG.

Why is this true? In Fig. 5.16, both AC and CD are radii. So, AC = CD. By the Baudhāyana–Pythagoras Theorem, $CD^2 = CG^2 + GD^2$ and $AC^2 = CF^2 + AF^2$.

So, $CF^2 + AF^2 = CG^2 + GD^2$.

Now AB is greater than DE. So AF is greater than GD (because F and G are the midpoints of AB and DE).

Since $AF^2 > GD^2$ we have $CF^2 < CG^2$.

So, CF < CG.

Comment: The chord nearest to the centre is the chord containing the centre. Its distance to C is zero! So the diameter is the greatest chord.

If one pushes the chord away from the centre, at some stage the chord becomes a single point, its length is zero, and the distance of C from this chord is the radius.

Exercise Set 5.5

1. Find the length of the chord of a circle where the radius is 7 cm and perpendicular distance is 6 cm.
2. Explain why the following statement is true: If the perpendicular distance of a chord from the centre is d and the radius is r, then the chord length is $2\sqrt{r^2 - d^2}$.

© NCERT not to be republished

*3. In a circle, if the distance of chord AB from the centre is twice the distance of another chord CD from the centre, then can we conclude that CD = 2 AB? Give reasons for your answer.

5.7 Angles Subtended by an Arc

An **arc** of a circle is a connected portion of the circle. It is defined by two points on the circle, called the **end points** of the arc, and the curve connecting them along the circle's edge.



Fig. 5.17: Major arc AYB and minor arc AXB

Look at Fig. 5.17. A and B are two points on the circle. There are two ways of going from A to B. One goes via point X and one goes via point Y. The bigger of the two is called the major arc, and the smaller of the two is called the minor arc.

We define the **angle subtended** by the arc AB at the centre to be the measure of the angle AOB, as we sweep along the arc — so we move from OA to OB along the arc and measure the angle swept. The minor arc subtends the ∠AOB — here you move from OA to OB via X. The major arc subtends the angle we get as we move from OA to OB via Y (see Fig. 5.18).



Fig. 5.18

© NCERT not to be republished

Exercise: A circle with centre O is drawn, and A, B, C, D are points on the circle (see Fig. 5.19). Measure the angles subtended by arc AKB and arc CLD at the centre O. If the angle at the centre is less than 180°, it is a minor arc. If the angle at the centre is greater than 180°, it is a major arc. State whether arcs AKB and CLD are minor arcs or major arcs.



Fig. 5.19

5.7.1 Angle subtended by an arc at a point on the circle outside the arc

By 'angle subtended by arc AXB at a point on the circle outside the arc' we mean the angle ACB where C is any point on the circle but not on arc AXB. Remarkably, the measure of this angle does not depend upon which specific point C we pick, so long as it is on the circle and outside the arc!

Activity: Draw a circle and a chord AB. Fix an arc AKB formed by AB and a point K between A, B on the circle. Measure the angle subtended at the centre by arc AKB. Take three points P, Q, R on the circle outside arc AKB. Measure the angles subtended by arc AKB at points P, Q, R. What do you notice?

Repeat this activity for a different arc AKB. Based on this activity, we can make a statement about the angles subtended by an arc of a circle at the centre and at a point of the circle outside the arc. We shall show that the following is true.



Fig. 5.20

© NCERT not to be republished

Theorem 9: *The angle subtended by an arc at the centre of the circle is double the angle subtended by the arc at any point on the circle outside the arc.*



Fig. 5.21: Angle subtended by arc AFB

Given: AFB is an arc. ∠ACB is the angle subtended by arc AFB at centre C. D is a point on the circle outside arc AFB (see Fig. 5.21).

We will assume for now that D is such that DC when extended cuts the circle at some point E on arc AFB, as shown.

We will consider the other case later.

To show: ∠BCA = 2 ∠BDA.

Why is this true? Join D to C and extend DC to cut the circle at a point E on arc AFB. Now ΔDCB is isosceles with CB = CD. So, ∠CBD = ∠CDB.

∠BCE is the exterior angle of ΔBCD. By the exterior angle theorem,

$$\angle BCE = \angle CBD + \angle CDB = 2\angle BDC.$$

Similarly, ΔADC is an isosceles triangle with CA = CD.

So, $\angle CAD = \angle CDA$

∠ACE is the exterior angle of ΔADC. By the exterior angle theorem,

$$\angle ACE = \angle CAD + \angle CDA = 2\angle CDA.$$

Now ∠BCA = ∠BCE + ∠ECA, and ∠BDA = ∠BDE + ∠EDA.

Hence $\angle BCA = 2(\angle BDC + \angle CDA) = 2\angle BDA.$

So, $\angle BCA = 2\angle BDA.$

The explanation we have given does not work if the situation is as shown in Fig. 5.22, where the extension of DC meets the circle at a point E outside the arc AFB. We must rework the explanation for this case.

© NCERT not to be republished



Fig 5.22: Angle subtended by arc AFB

Given: AFB is an arc. ∠ACB is the angle subtended by arc AFB at centre C. D is a point on the circle outside arc AFB such that when we extend DC it cuts the circle at some point E outside the arc AFB, as shown (Fig. 5.22).

We shall again make use of the properties of isosceles triangles.

∠ACE = ∠ADC + ∠CAD = 2 ∠ADC, since CA = CD (and so ∠ADC = ∠CAD).

Similarly, ∠BCE = ∠BDC + ∠CBD = 2 ∠BDC.

Also, ∠ACB = ∠ACE – ∠BCE, and ∠ADB = ∠ADC – ∠BDC.

Hence ∠ACB = 2 ∠ADB.



Fig. 5.23: Angles subtended by an arc are equal

Something very interesting comes out of this. This is what the activity before Theorem 9 suggested. Take an arc AB. Decide how you want to go from A to B along the arc. Take any point D on the circle, outside arc AB.

Then, no matter where D is, so long as it is outside the arc and on the circle, ∠ADB is the same!

Let us understand this better using Fig. 5.23. Consider the arc of the circle going from A to B via X. The points on the circle outside this arc are points you cross as you go from A to B via E. The angle subtended by AXB at the centre is the angle swept by CA as we move from CA to CB via X. Points E, F and D are all not on AXB. The theorem tells us that ∠AEB = ∠ADB = ∠AFB = $\frac{1}{2}$ ∠ACB.

© NCERT not to be republished

Corollary: The angle subtended by a diameter at any point on the circle is 90°.

Corollary: A corollary is a fact that follows immediately from an already proved result.



Fig. 5.24

Why is this true? Let AB be a diameter (Fig. 5.24). We must show that ∠ADB is 90°. The arc from A to B we take is the arc not containing D. What is the angle subtended by that arc at C? We have to move from A along that arc till we reach B. So, the angle subtended is ∠ACB, a straight angle, 180°. Hence, $\angle ADB = \frac{1}{2} \angle ACB = 90°$.



Fig. 5.25: Points and the chord

This fact that the angles in the same arc segment are all equal is a beautiful fact that distinguishes the circle from all other shapes.

In Fig. 5.25, the angles that arc AB subtends at the points F, G outside the circle are different. For the points inside the circle, ∠AIB, ∠ACB and ∠AHB are all different. But for all points P on arc AB, the subtended angles are the same. Thus, for points D, E, ∠ADB = ∠AEB.

Exercise Set 5.6

1. In a circle with centre O, the central angle AOB is 60°. If the radius of the circle is 12 cm, what is the length of the chord AB?

© NCERT not to be republished

2. Let A and B be two points on a circle with centre O.
   (i) Are there points X, Y on the circle, on the same side of AB, such that ∠AXB is different from ∠AYB?
   (ii) Is it true that if ∠AXB = ∠AYB, then X and Y lie on the same side of the circle?
   (iii) If ∠AXB = ∠AYB, and X and Y do not lie on the circle, does the circle through A, B and X also pass through Y?



Fig. 5.26

3. Find *x* in Fig. 5.26.

5.8 Concyclicity of Points

Now we address the question about when 4 points lie on the same circle. And we will let you explore the question for 5 points, 6 points and so on! We call points that are on the same circle **concyclic**.

Theorem 10: *If a line segment* AB *joining two points* A, B *subtends equal angles at two other points* C, D *that lie on the same side of* AB, *then the four points lie on a circle.*

As always we draw the picture first.

Given: Consider segment AB. Points C and D lie on the same side of AB; points C and D are not on the line AB; and ∠ACB = ∠ADB.

To show: A, B, C, D lie on the same circle.

Why is this true? The points A, B, C are noncollinear points. So, using Theorem 1, there is a circle passing through A, B, C.

Let us show that D also lies on that circle. For this, let us draw the circle through A, B and C.

Suppose D is not on the circle; then it is either inside or outside the circle. Join AD.



Fig. 5.27A



Fig. 5.27B

© NCERT not to be republished

If D is outside the circle, then AD intersects the circle at E; see Fig. 5.27A. If D is inside the circle, extend AD to meet the circle at E; see Fig. 5.27B. Now C, E are on the same segment of the arc formed by chord AB. So, ∠ACB = ∠AEB.

If D were outside the circle, then ∠AEB is an exterior angle of the ΔBED, so ∠AEB > ∠ADB. Also, ∠AEB = ∠ACB (angles in the same segment of a circle), and ∠ACB = ∠ADB (given). This leads to ∠ACB being greater than itself, which is obviously not possible.

If D were inside as in Fig. 5.27B, then ∠ADB is an exterior angle of BED. In the same way that we argued above, we reach an impossible conclusion.

So, we must eliminate both of these options (D being outside the circle and D being inside the circle). So, D must be on the circle passing through A, B, C. In other words, A, B, C, D are concyclic.

When the vertices of a quadrilateral (which we also call a **4-gon**) are concyclic, the quadrilateral is called a **cyclic** quadrilateral.

We use this to show another nice property of circles!

Theorem 11: *The sum of two opposite angles of a cyclic quadrilateral is* 180°.



Fig. 5.28

Given: A, B, C, D are the vertices of a cyclic 4-gon (Fig. 5.28). This means that there is a circle passing through A, B, C, D. Let its centre be O.

To show: ∠BAD + ∠BCD = 180°.

How shall we show that this is true? Consider arc BCD; point A is on the circle and it lies outside the arc BCD. So ∠BAD is half the angle that arc BCD subtends at the centre O. Since we move from OB to OD along C, this is the reflex angle BOD (dotted). So, $\angle BAD = \frac{1}{2}$ (reflex angle BOD).

© NCERT not to be republished

Similarly, $\angle BCD$ is half the angle subtended by the arc BAD at O. This is the angle denoted by the double arc BOD. Since C is on arc BCD, we need to move from OB to OD via A. So, $\angle BCD = \frac{1}{2}(\angle BOD)$.

So, $\angle BAD + \angle BCD = \frac{1}{2}$ (complete angle at the centre O)

A complete rotation at O is 360°.

Hence, $\angle BAD + \angle BCD = \frac{1}{2} \times (360°) = 180°$.

So, the opposite angles of a cyclic 4-gon add up to 180°.

The converse of this theorem also holds.

Exercise: A cyclic quadrilateral has angles measuring $\angle A = 80°$, $\angle B = 110°$, $\angle C = 100°$, and $\angle D = 70°$. Can such a quadrilateral be drawn? Explain why or why not.

Theorem 12: *If two opposite angles of a quadrilateral add up to 180°, then the vertices of the quadrilateral lie on a circle, i.e., they are concyclic.*



Fig. 5.29

Given: ABCD is a 4-gon (Fig. 5.29).

$\angle BAD + \angle BCD = 180°$.

$\angle ABC + \angle CDA = 180°$.

To show that: ABCD is cyclic.

Why is this true? Suppose ABCD is not cyclic. Since A, D, B are not collinear, there is a circle passing through the three points. If that circle does not pass through C, there are two cases: C is outside or C is inside the circle.

We deal only with the first case and leave the other to the reader.

Let E be the point where CD meets the circle (see Fig. 5.29). Then ABED is a cyclic 4-gon. So from Theorem 11, $\angle BAD + \angle BED = 180°$.

We are also given $\angle BAD + \angle DCB = 180°$.

So $\angle BCD = \angle BED$. But this is not possible as $\angle BED$ is the exterior angle of BEC and hence greater than $\angle BCE$, i.e., greater than $\angle BCD$.

So, points A, B, C, D all lie on a circle.

© NCERT not to be republished

The circle is a beautiful and tantalising shape. After mastering these basic properties, you will get a feel for the symmetries of a circle and the properties of chords, the angles they subtend, the distances of chords from the centre, and angles subtended by arcs at the centre.

Next year you will study many more interesting and beautiful such results about circles. Stay tuned — the best is yet to come!

End-of-Chapter Exercises

1. In a circle, a chord is 5 cm away from the centre. If the radius of the circle is 13 cm, what is the length of the chord?
2. An arc of a circle subtends an angle of 70° at the centre. What is the measure of the angle subtended by the arc at a point on the circle?
3. The diameter of a circle is 26 cm. A chord of length 24 cm is drawn in the circle. Find the distance from the centre of the circle to the chord.
4. A circle has a radius of 15 cm. A chord is drawn. The distance from the centre of the circle to the chord is 9 cm. What is the length of the chord?
5. Prove that the perpendicular bisector of a chord passes through the centre of the circle.
6. The diameter of a circle is AB. Point C is on the circumference. What is the measure of the ∠ACB? Explain your reasoning.
7. ABCD is a cyclic quadrilateral inscribed in a circle. If ∠A measures 75°, what is the measure of ∠C? If ∠B measures 110°, what is the measure of ∠D?
8. Quadrilateral PQRS is inscribed in a circle. If $\angle P = (2x + 10)°$ and $\angle R = (3x - 20)°$, find the value of x and the measures of ∠P and ∠R.
9. The distance of a chord of length 16 cm from the centre of a circle is 6 cm. Find the radius of the circle.
10. A cyclic quadrilateral has sides 5, 5, 12, 12 units. Find its area.

*11. Consider a cyclic quadrilateral. Without drawing its circumcircle, how can we find out whether the centre of the circumcircle lies

© NCERT not to be republished

inside the quadrilateral or outside? What is the best way of finding out?

*12. When two chords intersect, each of them is divided into two line segments. Show that if the intersecting chords are of equal length, then the line segments of one chord are equal to the corresponding line segments of the other chord.

*13. Draw a circle in which a chord of 6 cm length stands at a distance of 3 cm from the centre.

(**Hint:** Is it a circumcircle of a suitable triangle?)

*14. Show that rectangle is the only parallelogram that can be inscribed in a circle.

*15. Show that if a rectangle is inscribed in a circle, then the point of intersection of its diagonals must lie at the centre of the circle.

*16. Consider all chords of a circle of a fixed length. What is the shape formed by the midpoints of all these chords?

*17. In a circle with centre O, chords AB and AC are congruent. Explain why this statement is true: "The centre of the circle lies on the angle bisector of ∠BAC".

18. Two parallel chords of lengths 10 cm and 24 cm are on the same side of the centre of a circle. The distance between the chords is 7 cm. Find the radius of the circle.

*19. A regular hexagon is inscribed in a circle of radius r. Find the length of the sides of the hexagon and the distance of each side from the centre of the circle.

20. A quadrilateral MNOP is inscribed in a circle. If MN is a diameter, what can you say about ∠MOP and ∠MNP? Explain your reasoning.

21. Let ABCD be a cyclic quadrilateral. Explain why the exterior angle at any vertex is equal to the interior opposite angle (e.g., ∠CDE = ∠ABC, where E is a point on the extension of side CD).

*22. "There is no chord of a circle that is longer than its diameter." How do you justify this statement?

*23. Let A be any point within a given circle with centre O. Show that the shortest chord of the circle that passes through point A is the one that is perpendicular to OA.

© NCERT not to be republished

24. How would you use the following figure to justify the statement that the angle in a semicircle is 90°?



Fig. 5.30

*25. In a circle, two chords CC' and DD' are drawn perpendicular to a diameter AB. Prove that the segment MM' joining the midpoints of the chords CD and C' D' is perpendicular to AB.

*26. How would you use the following figure to justify the statement that the sum of the opposite angles of a cyclic quadrilateral is 180°?



Fig. 5.31

Chapter Summary

- A **circle** is the set of all points in a plane that lie at a given distance (the **radius**) from a fixed point called its **centre**.
- A circle has **reflection symmetry** across any diameter.

© NCERT not to be republished

- A circle has **rotational symmetry** about its centre, through any angle.
- Infinitely many circles can be drawn through two given points. The centres of these circles lie on the perpendicular bisector of the line segment joining the two given points.
- Given any three points not on a straight line, a **unique circle** can be drawn through them; it is called the **circumcircle** of the triangle whose vertices are the three given points. The centre of this circle is called the **circumcentre** of the three points, lies at the intersection of the perpendicular bisectors of the line segments joining the points.
- Equal chords subtend equal angles at the centre of the circle. Conversely, if two chords subtend equal angles at the centre, the chords are equal in length.
- A line drawn from the centre to the midpoint of a chord is perpendicular to that chord. Conversely, a perpendicular from the centre to a chord bisects it.
- Chords of equal length lie at equal distance from the centre. Conversely, chords that lie at the same distance from the centre are equal in length.
- Given two unequal chords, the longer chord is closer to the centre.
- The angle subtended by an arc at the centre of a circle is twice the angle it subtends at any point on the remaining part of the circle.
- The angle subtended by a diameter at any point on the circle is 90°.
- If a line segment between two points subtends equal angles at two other points on the same side of the segment, all four points lie on a single circle (i.e., the points are **concyclic**).
- A quadrilateral inscribed in a circle is called **cyclic**. In a cyclic quadrilateral, the sum of opposite pairs of angles is 180°. Conversely, if two opposite angles of a quadrilateral add up to 180°, then it is a cyclic quadrilateral.

© NCERT not to be republished

6 Measuring Space: Perimeter and Area

Fig. 6.1: Athletes at the start of 4 × 100 m relay race

In Fig. 6.1, you see athletes assembled at the start of a 4 × 100 m relay race. The tracks are laid out, and the athletes are all set to go racing down the tracks. Do you notice that the athletes are not at the same starting line?

Those in the outer lanes seem to be starting ahead of those in the inner lanes while the finish line is the same for all of them. What could be the reason for this? The distance between the starting points of adjacent lanes is called the 'stagger'. Notice that the stagger continues all the way to the outermost lane. Do you think the stagger gives anyone (those in the outer lanes or in the inner lanes) an unfair advantage? Why or why not? On what basis can the organisers work out the length of the stagger between lanes?

Think and Reflect

In my school, the playground is too small to have a 400 m track, so the school constructed a 200 m track instead. Does this mean that we need a smaller stagger for the race tracks in my school (i.e., smaller than the stagger used in the Olympics), for the same 4 × 100 m relay race?

To answer the question about the lane staggers required on a 4 × 100 m athletics track, we need to know how to find the length around a circle.

6.1 Perimeter of a Shape

Given any shape, its **perimeter** is the total length around its border. Imagine a tiny insect going for a walk around its border, never turning around, till it returns to its starting point. The perimeter of the shape is the total distance it travels.

So, a square with side a units has perimeter $4a$ units. An equilateral triangle with side a units has perimeter $3a$ units.



Fig. 6.2A



Fig. 6.2B

The perimeter of a rectangle with length a units and width b units is $2(a + b)$ units. Note that the formula for the perimeter of a square is a 'special case' of the formula for the perimeter of a rectangle with $a = b$.



Fig. 6.3

Here we see a circle with radius r units.
What is its perimeter? How do we find out?

Think and Reflect

What is the connection between this question and the one about the 400 m athletics track?

To answer the question about the perimeter of the circle, we must go step by step.

What happens to the perimeter of a square if we double its side? It doubles too. The ratio of perimeter to the side is 4:1; this is so for all squares. As the side of the square gets larger (or smaller), the ratio of perimeter to side stays fixed at 4:1.



Fig. 6.4: Ratio of perimeter to side is 4:1

© NCERT not to be republished

For equilateral triangles, the ratio of perimeter to the side is 3:1. As the side of the equilateral triangle gets larger (or smaller), the ratio of perimeter to side stays fixed at 3:1.



Fig. 6.5

What about a circle? What is its perimeter (usually called the **circumference**) in terms of its diameter?

Is the ratio of circumference (C) to diameter (D) the same for circles of all sizes (Fig. 6.5)? What do you think?

6.2 Perimeter of a Circle—The C/D Ratio

In ancient days people realised that the ratio of the circumference to the diameter of the circle does not change if we change the size of the circle.

Let's call this ratio the 'C/D ratio' of the circle.

What is the value of the C/D ratio?

How would you estimate this ratio?

HOME MEASUREMENT

You can do a simple measurement at home to estimate the C/D ratio. Take a cotton reel with thin thread around it. Measure the diameter D of the reel as accurately as possible. Unwrap and then tightly wrap the thread around the reel 20 times. Unwrap it again; measure its length L, and calculate $\frac{L}{20\,D}$. This is the ratio we want. For accuracy, the thread should be very thin. Please do the experiment! Do you get a ratio between 3 and 4? Between 3.1 and 3.2?

It is also possible to estimate the C/D ratio using pure geometry, i.e., without any measurements at all! Can you imagine how?

C/D's Adventurous Journey: From Ancient Approximations to the Exact Formula of Mādhava

Mathematicians have been fascinated by circles, and the C/D ratio, since ancient times and across geographical regions. This constant,

© NCERT not to be republished

which we now call π (we say 'pi' as in 'pie' and not as in 'pizza'), represents a bridge between many different areas of mathematics, and connects the straight-edged world of polygons with the infinite curves of nature. While early civilisations relied on practical, 'good-enough' values for construction and trade, the pursuit of this ratio eventually became an important pastime of mathematicians that helped to benchmark the sophistication of mathematical theories.

In Mesopotamia (c. 1900 BCE), mathematicians moved beyond the crude integer value of 3. They realised that a circle had a perimeter that was slightly larger than the hexagon inscribed within it. They concluded that π should therefore be larger than 3, and they set the value of π to be $3 + \frac{1}{8} = 3.125$.



Fig. 6.6 The Mesopotamian Hexagon-to-Circle comparison. Can you see why this shows that π > 3?

By **250 BCE, Archimedes of Syracuse** brought a new level of rigor to the problem. He 'trapped' the value of π between the perimeters of inscribed and circumscribed polygons. By using both an inscribed and circumscribed hexagon, Archimedes showed that π is between 3 and $2\sqrt{3} \approx 3.46$. Working his way up to 96-sided polygons, Archimedes found that $3\frac{10}{71} < \pi < 3\frac{1}{7}$.



*Fig. 6.7: Archimedes' method utilising inscribed and circumscribed polygons. Can you see why this diagram of an inscribed and circumscribed hexagon tells us that π is between 3 and $2\sqrt{3}$? (**Hint:** Use the Baudhāyana–Pythagoras Theorem.)*

© NCERT not to be republished

In about 150 CE, Ptolemy of Alexandria refined Archimedes computations for use in his astronomical tables, giving the ratio $\frac{377}{120} \approx 3.14167$ for π.

Shortly thereafter, in China, a 'circle-cutting method' of **Liu Hui** (263 CE) laid the groundwork for two breakthroughs due to **Zu Chongzhi** (480 CE). Zu pushed the polygon approximation method to 24,576 sides! He used this to discover the Yuelü (Approximate Ratio) of $\frac{22}{7} \approx 3.1428$ for π, and also the *Miü* (Close Ratio) of $\frac{355}{113} \approx 3.1415929$ for π. The rational fraction $\frac{355}{113}$ is so close to π that it remained the most accurate value for π in the world for over 800 years; it is now known that no single rational fraction with denominator less than 15,000 can be as close to π as this fraction!

In 499 CE, Āryabhaṭa provided a value of $\frac{62832}{20000} = 3.1416$ for π. Crucially, he described this value as *asanna*, i.e., 'approaching' or 'approximate' — a profound insight suggesting that the ratio could not be given exactly as one simple fraction. Meanwhile, **Brahmagupta** (628 CE) suggested the use of the value $\sqrt{10} \approx 3.1622$ for π; while slightly less accurate, he chose it for its mathematical elegance and the ease with which it could be manipulated in equations, a preference that saw $\sqrt{10}$ become the dominant approximation in the Arab world and medieval Europe for centuries after.

Over the ensuing years, many great mathematicians studied π, including its approximations; but no approximation was as accurate as Zu's $\frac{355}{113}$ — or as algebraically simple as $\frac{22}{7}$, 3.1416, and $\sqrt{10}$ — until the work of Mādhava of Sangamagrāma, who changed the game forever. Mādhava realised that π was not just a number to be approximated by fractions and other finite algebraic expressions, but a limit to be reached. Mādhava thereby discovered the first exact formula for π:

$$\frac{\pi}{4} = 1 - \frac{1}{3} + \frac{1}{5} - \frac{1}{7} + \cdots$$

Is that not a beautiful formula? Mādhava's formula — given in the form of an 'infinite series' — was a tectonic shift for mathematics. By moving from the geometric cutting of circles to the analytical summing of numbers, Mādhava birthed the area of mathematics

© NCERT not to be republished

known as calculus. His infinite series enabled him to calculate π to 11 decimal places (3.14159265358), proving that the relationship between a circle's circumference and its diameter was a window into an entirely new area of mathematics.

Better and better infinite series were developed over time that gave more and more digits of π even more quickly. The key breakthroughs on the problem after Mādhava were due to Nīlakaṇṭha (c. 1500), Machin (1706), Ramanujan (1914), and the Chudnovsky brothers (1988) who skilfully extended the ideas of Ramanujan. Today, using their algorithms, we now know π to neels (100s of trillions) of digits! We will learn more about the area of calculus in later grades.

In 1706, the Welsh mathematician William Jones used the Greek symbol π to denote the C/D ratio, because π is the first letter of the Greek word *perimetros* for perimeter. The symbol was made popular by the Swiss German mathematician Leonhard Euler (pronounced 'oiler'). We continue to use the same symbol today!

6.3 π Is Irrational

The digits of π go on forever, with no visible pattern. You already know that fractions give rise to decimal expansions with a rhythmic pattern, e.g.,

$$\frac{1}{3} = 0.33333..., \frac{1}{11} = 0.09090909..., \frac{1}{7} = 0.142857\ 142857...$$

But for π, there is no such pattern! It turns out that π cannot be written as a ratio of two integers. Such numbers are called *irrational*. Remember: A rational number is a number that can be written as a fraction $\frac{a}{b}$ where a, b are integers with b not equal to 0, e.g., numbers such as $1\frac{2}{3}$, $\frac{-7}{11}$ and 1.4.

In Grade 8, you learned that $\sqrt{2}$ is an irrational number. From their writings, it seems that Āryabhaṭa and Zu Chongzhi regarded π as irrational. Centuries later (1761), the mathematician Lambert showed that this is so; π is irrational. But to prove this requires more advanced mathematics, which we will learn much later.

© NCERT not to be republished

Since π is irrational, there is no 'best fraction' for π. If there is any fraction that is close to π, we can find another fraction that is closer.

The well-known fraction $\frac{22}{7}$ is good enough for most practical uses. But it is important to note that π is not equal to $\frac{22}{7}$ (they are 'close but not equal'). So we write $\pi \approx \frac{22}{7}$ and also $\pi \neq \frac{22}{7}$. In the same way, we can write $\sqrt{2} \approx 1.414$ and also $\sqrt{2} \neq 1.414$.

As noted earlier, a much better approximation for π is $\frac{355}{113}$.

Fun Fact

Here's a fun way to remember the first few digits of π:

How I wish I could recollect pi.

Count the number of letters in each word (3, 1, 4, 1, 5, 9, 2) and you get the digits of π! So, π ≈ 3.141592...

Since $\pi \approx 3.14$ and also $\pi \approx \frac{22}{7}$, March 14 (written '3-14' in North America) is celebrated each year as **Pi Day**, and 22 July (written '22-7' in

© NCERT not to be republished

India) is celebrated each year as **Pi Approximation Day**.

6.4 Length of an Arc of a Circle



Fig. 6.8: Two semicircles making a full circle

The circumference of a circle of diameter d is $\pi\ d$. Since the diameter is twice the radius, we can also write the circumference of a circle as $2\pi r$, where r is the radius.

What will be the length of a **semicircle** with the same radius r (see Fig. 6.8)?

If we reflect the circle in the diameter AB, the red semicircle and the blue semicircle exchange places. This means that they have equal length, which is $2\pi r \div 2 = \pi r$.

Instead of reflecting the figure in the diameter AB, we can also imagine rotating the whole figure around the centre O through an angle of 180°, i.e., through a half-turn. The effect is the same, and we get the same formula for the length of the semicircular arc.



Fig. 6.9: Four quarter circles make a full circle

What will be the length of a **quarter circle** with the same radius (Fig. 6.9)?

Imagine rotating the entire figure through 90°, clockwise or anticlockwise. Each quarter circle moves and covers another quarter circle. So each quarter circle has the same arc length, and this is equal to $2\pi r \div 4 = \frac{\pi r}{2}$.

Note the following:

- The formula for the length of a semicircle may also be written as $2\pi r \times \frac{180^o}{360^o}$.

© NCERT not to be republished

- The formula for the length of a quarter circle may also be written as $2\pi r \times \frac{90^o}{360^o}$.

From these, we can guess the formula for the length of an arc of a circle in terms of the angle it makes (i.e., the angle it 'subtends') at the centre of the circle.



Fig. 6.10: Length of an arc of a circle

If the arc is AB, and it subtends an angle $\theta°$ at the centre O of the circle, the length of the arc is $2\pi r \times \frac{\theta°}{360°}$.

A Closer Look at a 400 m Athletics Track



Fig. 6.11: Schematic diagram of a 400 m athletics track

© NCERT not to be republished

Fig. 6.11 depicts a 400 m athletics track. You can see two straight sections of length 84.39 m each, and two curved portions, which are semicircles with a common centre (points A and B); the innermost semicircle on each side has radius 36.5 m. The width of each lane is 1.22 m.

Let an athlete make one complete circuit of the track. What is the total distance she runs?

- Let us assume that she runs at a distance of 0.3 m from the inner border.
- She runs two straight sections of length 84.39 m each, a total of 168.78 m.
- She also runs two semicircles of radius (36.5 + 0.3) m, i.e., 36.8 m.
- The two semicircles together make up a complete circle.
- Its circumference is $2 \times \pi \times 36.8 = 2 \times 3.1416 \times 36.8 = 231.22$ m.
- The total distance run by the athlete is therefore 168.78 + 231.22 = 400 m.

Now consider two runners, one in the innermost lane, the other in the second lane. On the straight stretch the two runners run the same distance. But on the curved portions the runner in the second lane runs a greater distance, because her semicircle has a larger radius. It is to compensate for this that staggers are needed.

Think and Reflect

What is the difference in radius between the first and second lanes? Use the Fig. 6.11 to find the stagger needed by the runner in the second lane. Will an equal stagger be needed between the third and second lanes?

6.5 Problems, Puzzles, and Paradoxes on Perimeter

We close this section by looking at a sprinkling of interesting problems around the theme of perimeter.

Example 1: Two circles of equal radius are located such that each circle passes through the centre of the other circle (Fig. 6.12).

Given that the radius of each circle is r units, find the perimeter of the shape formed by the two circles in terms of r units. (Ignore the dotted portions that lie within the circles.)

© NCERT not to be republished



Fig. 6.12

Here, we have two congruent circles centered at A and B. Each one passes through the centre of the other one. The circles intersect at C and D. We need to find the total length of the two red arcs shown here, in terms of the radius r unit.

Consider the triangle with vertices A, B, C. Since AB = r, AC = r, BC = r, the triangle is equilateral, hence ∠CAB = 60° = ∠CBA.

Similarly ∠BAD = 60° = ∠ABD. It follows that ∠CAD = 120° = ∠CBD.

Hence, each dotted arc is $\frac{1}{3}$ of the circumference of the circle on which it lies. Hence, the total length of the two red arcs is $2\times\frac{2}{3}\times 2\pi r = \frac{8}{3}\pi r$.



Fig. 6.13

Example 2: In Fig. 6.13, we see points P and Q and two paths connecting them. The first path is made up of the semicircle a. The other path is made up of three semicircles (b, c and d). Which path is longer? Choose one: (i) Path a is longer. (ii) Path $b + c + d$ is longer. (iii) The two paths have equal length. (Try to answer this before reading on.)

Let us solve the problem using algebra. Let the radii of the semicircles a, b, c, d be denoted by a', b', c' and d'. Then the length of semicircle a is $\frac{1}{2}(2\pi)\ a' = \pi a'$. Similarly, the lengths of the semicircles b, c, and d are $\pi b'$, $\pi c'$ and $\pi d'$. So, the length of the second path is $\pi(b' + c' + d')$, and that of the first path is $\pi a'$.

Which is bigger, $b' + c' + d'$ or a'? Do you see that neither one is bigger? They are equal! Because, the length of PQ is $2a'$ and it is also equal to $2b' + 2c' + 2d'$. It follows that $a' = b' + c' + d'$. Hence, the two paths have equal length!

© NCERT not to be republished

Exercise Set 6.1

Unless stated otherwise, use the approximation $\frac{22}{7}$ for π.

1. The perimeter of a circle is 44 cm. What is its radius?
2. Calculate, correct to 3 significant figures, the circumference of a circle with: (i) radius 7 cm (ii) radius 10 cm (iii) radius 12 cm.
3. Calculate the length of the arc of a circle if: (i) the radius is 3.5 cm and the angle at the centre is 60°, and (ii) the radius is 6.3 m and the angle at the centre is 120°.
4. Find the perimeter of a sector (i.e., the curved portion as well as the two straight portions) of a circle of radius 14 cm and sector angle 75°.
5. Find the perimeters of the following shapes (taking the arcs to be quarter or half or three-quarters of a circle, as appropriate) (Fig. 6.14i to 6.14ix):



Fig. 6.14

© NCERT not to be republished

6. If the diameter of a car tyre is 56 cm, then: (i) How far does the car need to travel for the tyre to complete one revolution? (ii) How many revolutions does the tyre make if the car travels 10 km?

7. Find the total perimeter of all the petals in each of the given flowers.

(i)



Fig. 6.15A: The centres of the arcs are the midpoints of the sides of the square

(ii)



Fig. 6.15B: The centres of the arcs are the vertices of the hexagon

8. The ratio of the perimeters of two circles is 5:4. What is the ratio of their radii?

6.6 Area of a Rectangle

From perimeter, we move to area, i.e., to the 'amount of space' occupied by a two-dimensional region in a plane.

Measurement is always relative to something we call a unit. For area, the unit is a 1 × 1 square; its area is taken to be 1 unit^2 (also written as 1 sq. unit). You know from Grade 8 that the area of a rectangle with sides a units and b units is ab sq. units (Fig. 6.16).



Fig. 6.16: Area of square and rectangle

6.7 Area of a Parallelogram

You also know from Grade 8 the formula for the area of a parallelogram.

© NCERT not to be republished



Fig. 6.17: Area of a parallelogram. Here, A'B'C'D' is a copy of ABCD.

Fig. 6.17 shows how to transform a parallelogram ABCD into a rectangle EB'C'F (at right; here, parallelogram A'B'C'D' is a copy of ABCD) with the same base b and same height h. Though the two shapes are different, their areas are the same. So, the area of the parallelogram is equal to base × height = bh.

Think and Reflect

What happens if the parallelogram is 'thin' (Fig. 6.18) and the foot of the perpendicular from C to AD does not lie on side AD? The construction then does not seem to work. How do we fix this 'gap'?



Fig. 6.18

Here is a hint on how the problem of the 'thin parallelogram' can be solved.



Fig. 6.19: The thin parallelogram

Select a point D' on DA, close to D, and a point A' on DA extended, with A'A = D'D (Fig. 6.19). Then A'BCD' is a parallelogram, and since $\Delta CDD' \cong \Delta BAA'$, its area is the same as that of ABCD. Now repeat this step as many times as needed.

Think and Reflect

The area of a rectangle can be found when we know the lengths of its sides. Is the same true for a parallelogram? That is, can we find the area of a parallelogram when we know the lengths of its sides? Why or why not?

© NCERT not to be republished

(**Hint**: What happens to the area of a parallelogram if we decrease or increase the angle between the adjacent sides while keeping the lengths fixed?)

6.8 Area of a Triangle

Next, we work out a formula for the area of a triangle. (You have seen the formula in Grade 8, but we will go over the idea again, briefly.) One way to proceed is to first consider the case of a right-angled triangle and then other triangles. In both cases, we enclose the triangle in a rectangle; then we use the formula for area of a rectangle. (See Fig. 6.20A. Notice that FG = FJ + JG and so $b = b_1 + b_2$.) We find as a result that the area of a triangle with base b units and height h units is half the area of the rectangle with base b units and height h units. That is, the area is equal to $\frac{1}{2}bh$ sq. units.

You may wonder, like earlier, is there a gap in our argument? What would we do if angle EFG is obtuse and the triangle were shaped like triangle EFG in Fig. 6.20B? Please work out the answer to this question.



Fig. 6.20A: Area of a triangle



Fig. 6.20B

A nicer way of working out the formula for the area of a triangle is by seeing that two congruent copies of a triangle can be fitted together to make a parallelogram.



Fig. 6.21A



Fig. 6.21B

In Fig. 6.21A, triangles ABC and A'B'C' are congruent. They fit together as in Fig. 6.21B to make a parallelogram.

© NCERT not to be republished

Do you see why the two triangles fit together to make a parallelogram? (If you study the angles in the figure (e.g., ∠B'C'A' and ∠BCA), you will see why this is so. Keep in mind the criterion by which we check whether two lines are parallel.)

We already know, area of a parallelogram: base × height = bh.

So, the formula for the area a triangle is $\frac{1}{2}$ (base × height) = $\frac{1}{2}\,bh$.

A property of the median of a triangle. From the above formula we reach a simple but beautiful conclusion about any of the medians of a triangle.



Fig. 6.22

A *median* is the line segment joining a vertex of the triangle to the midpoint of the opposite side. In Fig. 6.22, AD is a median of ΔABC.

Consider ΔABD and ΔACD. Their bases are equal (BD = DC), and they have equal height h. Using the formula for the area of a triangle, we see that they have equal area $\frac{ah}{2}$ sq. units!

We state this as a theorem.

Theorem: *A median of a triangle divides it into two triangles with equal area.*

Does this come as a surprise? It should! After all, ΔABD and ΔACD are (in general) differently shaped (i.e., not congruent to each other). But we have just proved that they have the same area!

Think and Reflect

Since ΔABD and ΔACD have equal area, you may wonder — Can we divide ΔABD using straight cuts into two or more pieces that we can then rearrange to exactly cover ΔACD? What do you think? Is it possible?

We shall spoil the surprise by revealing that it is possible. But we will not tell you the least number of pieces required. Try to find the answer!

© NCERT not to be republished

Think and Reflect

Suppose we are given two polygons P and Q with equal area. Will it always be possible to divide one of them using straight cuts into two or more pieces and then rearrange the pieces to exactly cover the other polygon? Try this out for familiar shapes, e.g.,

1. A square and non-square rectangle with equal area,
2. Two triangles with different shapes but equal area,
3. A triangle and a square with equal area. Formulate a conjecture of your own about this.

Think of various rectangles with perimeter 40 units (the sides do not have to be integers).

1. How many such rectangles are there?
2. Among them, is there one whose area is the largest? What are its dimensions?
3. Among all these rectangles, is there one whose area is the smallest? What are its dimensions? Do either of these answers come as a surprise to you?

6.8.1 Heron's formula

You already know a formula for the area of a triangle (half base times height). Are there other formulas for the area of a triangle? There are several. For now we mention Heron's formula, discovered by the Greek mathematics and inventor, Heron. He taught at the Museum in Alexandria, a city in ancient Egypt located on the banks of the Nile.

The formula states that if ΔABC has side lengths BC = a, CA = b, and AB = c, then its area can be found as follows. First, we compute the semi-perimeter, s which is half the perimeter: $s = \frac{1}{2}(a+b+c)$. Then the area (ΔABC) is given by

$$\sqrt{s(s-a)(s-b)(s-c)}.$$

I am sure you will find the formula extremely surprising and strange looking! Let us test it against some known cases.

Example 3: An equilateral triangle with side a units.

© NCERT not to be republished

All three sides have length a, so the semi-perimeter is $s = \frac{1}{2}(a+a+a) = \frac{3}{2}a$ units. Heron's formula now yields,

$$\text{area of triangle} = \sqrt{\frac{3}{2}a\left(\frac{1}{2}a\right)\left(\frac{1}{2}a\right)\left(\frac{1}{2}a\right)} = \frac{\sqrt{3}}{4}a^2 \text{ sq. units}$$



Fig. 6.23

Let us check this against the 'half base times height' formula. Let h units be the height of the triangle. Then, by the Baudhāyana–Pythagoras theorem,

$$a^2 - h^2 = \frac{a^2}{4}, \quad \therefore h^2 = \frac{3a^2}{4}, \quad \therefore h = \frac{\sqrt{3}}{2}a.$$

So the area is $\frac{1}{2} \times \frac{\sqrt{3}}{2}a \times a = \frac{\sqrt{3}}{4}a^2$ sq. units. Same formula!

Note: Notice the symbol '$\therefore$'. This symbol is used regularly by mathematicians; it means and is read as 'therefore'.

Example 4: An isosceles triangle with equal sides a units and base $2b$ units.

The semi-perimeter is $s = \frac{1}{2}(a+a+2b) = a+b$ units. Heron's formula now yields,

$$\text{area of the triangle} = \sqrt{(a+b)(a+b-a)(a+b-a)(a+b-2b)} = b\sqrt{a^2-b^2} \text{ sq. units.}$$



Fig. 6.24

Let us check this against the 'half base times height' formula. Let h units be the height of the triangle. Then, by the Baudhāyana–Pythagoras theorem,

$$a^2 - h^2 = b^2, \quad \therefore h^2 = a^2 - b^2, h = \sqrt{a^2-b^2}.$$

So the area is $\frac{1}{2} \times \sqrt{a^2-b^2} \times 2b = b\sqrt{a^2-b^2}$ sq. units, the same as earlier.

© NCERT not to be republished

Example 5: A triangle with sides 3 units, 4 units and 5 units.

The semi-perimeter is $s = \frac{1}{2}(3+4+5) = 6$ units. Heron's formula now yields,

$$\text{area of triangle} = \sqrt{6\times(6-3)\times(6-4)\times(6-5)} = \sqrt{6\times3\times2} = 6 \text{ sq. units.}$$



Fig. 6.25

Let us check this against the 'half base times height' formula. See Fig. 6.25; note that $3^2 + 4^2 = 5^2$. Therefore, by the converse of the Baudhāyana–Pythagoras hypotenuse theorem, ΔABC is right-angled at B. So,

base = 3 units, height = 4 units,

so the area is $\frac{1}{2}(\text{base}\times\text{height}) = \frac{1}{2}(3\times4) = 6$ sq. units, the same as earlier.

We get the correct result in each case.

You may wonder how Heron's formula is proved. There are many proofs known; one of them uses the Baudhāyana–Pythagoras theorem and repeated use of the 'difference-of-two-squares' formula $a^2 - b^2 = (a - b)(a + b)$. We will study some of these proofs in Grade 10.

There are two other such formulas for the area of a triangle. Both have a connection with circles. See Fig. 6.26.

Given any triangle ABC, there is exactly one circle that passes through its three vertices. This is called the **circumcircle** of ΔABC.

There is also exactly one circle that fits tightly in the triangle, touching its three sides. This is called the **incircle** of ΔABC.



Fig. 6.26

Let the sides of ΔABC be a, b, and c. Let the radius of the circumcircle be R. Let the radius of the incircle be r. Then we have the following two formulas for the area:

$$\text{Area of } \Delta ABC = \frac{abc}{4R}$$

$$\text{Area of } \Delta ABC = \frac{r(a+b+c)}{2}$$

© NCERT not to be republished

Both formulas have a beautiful symmetry about them! The proof of the second formula requires a result that you will study in Grade 10.

Brahmagupta's Formula for the Area of a Cyclic 4-gon

We have seen how to find the area of a triangle given the lengths of its three sides. The natural question then is: how can we find the area of a 4-gon given the lengths of its four sides?

Earlier we asked, can we find the area of a parallelogram if we know only the lengths of its sides? The answer is: No. In the same way we ask: can we find the area of a 4-gon if we only know the lengths of its sides? The figures below reveal the answer to this question.

The problem (Fig. 6.27) is about a 4-gon whose sides are known to be 3, 3, 3, 3 (it is a 'rhombus'). As you can see, the areas of the three figures are different. (We drew the figures using *GeoGebra* and found the areas using the 'Area' tool. Please try this exercise yourself, or by using four rods joined together at their ends.)



Fig. 6.27: The area of a 4-gon cannot be found only from the lengths of its sides

So we cannot find the area of a 4-gon only from the lengths of its four sides; we need more information. This could be one angle of the 4-gon, or the length of one diagonal, or the angle at which the diagonals cut each other, etc.

Or it could be a key geometric property of the figure.

One such property is that the 4-gon is a cyclic 4-gon. In 628 CE, Brahmagupta (598–668 CE) discovered a wonderful formula for the area of a **cyclic** 4-gon.

© NCERT not to be republished



Fig. 6.28: A cyclic 4-gon

The formula states that if the sides of the cyclic 4-gon have lengths a, b, c, d, and the semi-perimeter s is $s = \frac{1}{2}(a+b+c+d)$, then:

$$\text{Area of 4-gon} = \sqrt{(s-a)(s-b)(s-c)(s-d)}.$$

It is an amazing and beautiful formula!

Does it not remind us of Heron's formula for the area of a triangle?

We can verify that the formula works out correctly in various special cases.

Example 6: Verify Brahmagupta's formula for the case of a rectangle.

All rectangles are cyclic, so Brahmagupta's formula should apply. Let the sides of the rectangle be a, b. Then $s = \frac{1}{2}(2a+2b) = a+b$, so the formula yields:

$$\text{Area} = \sqrt{(a+b-a)(a+b-b)(a+b-a)(a+b-b)} = \sqrt{ab \cdot ab} = ab,$$

which is correct. Please check out the formula against other special cases.

Example 7: Verify Brahmagupta's formula for the case of an isosceles trapezium.



Fig. 6.29: Isosceles trapezium

All isosceles trapezia are cyclic, hence the formula should apply. The perimeter is $2a + 2b + 2c$, so $s = a + b + c$. Hence, the area as given by the formula should be

$$\sqrt{(s-2a)(s-2b)(s-c)(s-c)}.$$

Since $s - 2a = c + b - a$, $s - 2b = c + a - 2b$, $s - c = a + b$ the above formula simplifies to

$$(a+b)\sqrt{(c+b-a)(c+a-b)} = (a+b)\sqrt{c^2-(b-a)^2}.$$

© NCERT not to be republished

If we imagine a perpendicular dropped from B to the base CD, its length (recall the Baudhāyana–Pythagoras theorem) is $\sqrt{c^2-(b-a)^2}$. Hence, the area is $(a + b)h$. We get exactly the same formula if we recall that the area of an isosceles trapezium is half the sum of the parallel sides times the distance between the parallel sides.

Special Cases and Generalisation in Mathematics

The notion of a 'special case' occurs often in higher mathematics. A special case results from a general result whenever we apply some extra condition. We list a few such examples.

The general result is also called a **generalisation** of the special case. The process of generalisation is an extremely important part of mathematics.

Example: A square is a special case of a rectangle.

So, the formula for the area of a square ($A = a^2$) is a special case of the formula for the area of a rectangle ($A = ab$) obtained by putting $b = a$.

Similarly, the formula for the perimeter of a square is a special case of the formula for the perimeter of a rectangle.

Example: An isosceles right-angled triangle is a special case of a right-angled triangle.

So, from any theorem about all right-angled triangles, we can extract a special case that applies to isosceles, right-angled triangles.

Take a right-angled triangle ABC with $\angle C = 90°$; then we have $a^2 + b^2 = c^2$ (this is the Baudhāyana–Pythagoras theorem). Let us take a special case of this with $a = b$ (this corresponds to the triangle being isosceles). We get $a^2 + b^2 = c^2$, i.e., $c^2 = 2a^2$ and so $c = a\sqrt{2}$. The general theorem ($a^2 + b^2 = c^2$) has reduced to this special case ($c = a\sqrt{2}$) for isosceles right-angled triangles (with $a = b$).

Here is another example. Compare the following identities from algebra:

$$(a+b)^2 = a^2 + b^2 + 2ab,$$

$$(a+b+c)^2 = a^2 + b^2 + c^2 + 2ab + 2bc + 2ca.$$

Can you see that the first identity is a special case of the second one (put $c = 0$ in the second identity), and the second identity is a generalisation of the first one?

You will meet many examples of special cases and generalisation in later years.

© NCERT not to be republished

Brahmagupta's Formula Generalises Heron's Formula

The similarity in appearance between Heron's formula and Brahmagupta's formula is not an accident. How? Brahmagupta's formula generalises Heron's formula. That is, we can think of Heron's formula as a special case of Brahmagupta's formula.

A triangle with sides a, b, c can be regarded as a 'special case' of a 4-gon ABCD whose fourth side d has zero length ($d = 0$). So we have AB = a, BC = b, CD = c, which means in effect that vertices A and D coincide.

(If the vertices represent planets, then this would be a case of two planets colliding with each other and forming a single large planet! This actually happened in the early history of the solar system.)

Since any triangle is cyclic (given any three points not in a straight line, we can draw a circle through them), this 4-gon is cyclic too. So, Brahmagupta's formula must apply to this 4-gon.

Let us see what emerges from this. We first compute the semi-perimeter of the 4-gon (keep in mind that $d = 0$):

$$s = \frac{1}{2}(a+b+c+0) = \frac{1}{2}(a+b+c).$$

We see that s is the same as the semi-perimeter of the given triangle. Now we apply Brahmagupta's formula:

$$\text{Area of triangle} = \sqrt{(s-a)(s-b)(s-c)(s-d)}$$

$$= \sqrt{s(s-a)(s-b)(s-c)} \quad \text{since } d = 0.$$

This is Heron's formula!

Brahmagupta's formula may thus be viewed as a generalisation of Heron's formula.

6.9 Squaring a Rectangle

In ancient times, to 'square a given shape' meant to 'construct a square equal in area to that shape'. The shape could be a rectangle or a triangle or a circle. Here, we show how the ancient Indian mathematician Baudhāyana squared a rectangle. The construction, from his *Śhulbasūtra* (800 BCE), shows how to square a rectangle with sides a units and b units where $a > b$. This means that we must construct

© NCERT not to be republished

a square with area *ab* sq. units. Here is a slightly simplified form of Baudhāyana's construction (Fig. 6.30).



Fig. 6.30: Rectangle ABCD with AD = a, AB = b

- Given: rectangle ABCD with AD = *a*, AB = *b* where $a > b$.
- Locate E on AD so that AE = AB.
- Locate the midpoint F of ED.
- Draw square AFGH with side AF and vertex H on AB produced.
- Draw arc AG with centre H. Let arc AG cut side BC at K.
- Draw a line through K parallel to AH. Let it cut GH at P.
- Draw square HPQS with HP as side. Then square HPQS has the same area as rectangle ABCD.

Try to work out why this method works. You will find that it is a geometrical translation of the formula $\left(\frac{a+b}{2}\right)^2 - \left(\frac{a-b}{2}\right)^2 = ab$.

*Why does this method work?

Refer to Fig. 6.30. From *AE* = *b* we get $\text{AF} = \frac{\text{AE} + \text{AD}}{2} = \frac{a+b}{2}$. Hence, $\text{HG} = \frac{a+b}{2} = \text{HK}$ as HK is a radius of the circle.

Next, $\text{BH} = \text{AH} - \text{AB} = \text{AF} - \text{AB} = \frac{a+b}{2} - b = \frac{a-b}{2}$.

Now consider the right-angled triangle HKP. Using the Baudhāyana–Pythagoras theorem we get

$$\text{HP}^2 = \text{HK}^2 - \text{BH}^2 = \left(\frac{a+b}{2}\right)^2 - \left(\frac{a-b}{2}\right)^2 =$$

$$\frac{a^2 + 2ab + b^2}{4} - \frac{a^2 - 2ab + b^2}{4} = \frac{ab}{2} + \frac{ab}{2} = ab.$$

Therefore square HPQS has the same area as rectangle ABCD.

© NCERT not to be republished

Think and Reflect

What procedure would you use to square a given triangle? Here, the task is to construct a square whose area is equal to the area of some given triangle. Think carefully. How would you proceed?

Exercise Set 6.2

1. Find the area of triangle ADE in Fig. 6.31.



Fig. 6.31

2. The parallel sides of a trapezium are 40 cm and 20 cm. If its non-parallel sides are both equal, each being 26 cm, find the area of the trapezium.
3. Find the area of a triangle, given that its sides are 8 cm and 11 cm long, and its perimeter is 32 cm.
4. The sides of a triangular plot are in the ratio 3: 5: 7; its perimeter is 300 m. Find its area.
5. One diagonal of a rhombus is twice as long as the other diagonal. If the rhombus has area 128 cm^2, find the length of the shorter diagonal.
6. ABCD is a parallelogram. P and Q are any two points on side AB. What can you say about the ratio area (ΔPCD): area (ΔQCD)?
7. O is any point on the diagonal PR of a parallelogram PQRS. Prove that the areas of triangles PSO and PQO are equal.
8. If the mid-points of the sides of a 4-gon (also known as a quadrilateral, but we prefer to call it a '4-gon') are joined in order, prove that the area of the parallelogram thus formed will be half of the area of the given 4-gon. (You may wonder whether

© NCERT not to be republished

the 4-gon thus formed is always a parallelogram, and if so, why? These questions will be tackled and answered in the chapter on quadrilaterals.)

9. In ΔABC, the midpoint of BC is D (Fig. 6.32). Median AD is drawn. P is any point on AD. Show that area (ΔABP) = area (ΔACP).



Fig. 6.32



Fig. 6.33

10. Given a square ABCD, let P be a point within it. Join PA, PB, PC, PD (Fig. 6.33). What is the ratio of the areas of the red region (ΔPAB and ΔPCD) and the green region (ΔPBC and ΔPDA)?
11. In ΔABC, D is the midpoint of AB. P is any point on BC, and Q is a point on AB such that CQ || PD. PQ is joined (Fig. 6.34). Prove that Area (ΔBPQ) = $\frac{1}{2}$ Area (ΔABC).



Fig. 6.34

6.10 Area of a Circle

A circle is an extremely basic shape; it is easy to draw if we have a rope and a peg to which the rope can be tied. Human beings have used the circular shape in their settlements, buildings and tools for thousands of years.

© NCERT not to be republished

Think and Reflect

Why were human beings so fond of using circular shapes? Was this only for practical reasons, or could there have been other reasons too? What kinds of uses have human beings found for the circular shape?

Early on, human beings faced the challenge of finding the area A enclosed by a circle. They may have needed, for example, to work out how much grain can be kept in a cylindrical tower (which has a circular cross section), or how much area is occupied by a circular garden or a circular building. They needed such data for planning out their cities, for tax purposes, etc.

Early societies understood very well that the area A must be proportional to the **square** of the circumference C. Let's see why this is so.

- Suppose we are given a square. Let its side be a. It has perimeter P = $4a$ and area A = a^2. So the ratio P^2 : A = $(4a^2) : a^2 = 16a^2 : a^2 = 16 : 1$. So the ratio P^2 : A is 16 : 1 for all squares; the ratio does not depend on the size of the square — it is the same for all squares.
- Consider an equilateral triangle with side a. Its perimeter is P = $3a$ and its area is $A = \frac{\sqrt{3}}{4}a^2$. So $P^2 : A = (3a)^2 : \frac{\sqrt{3}}{4}a^2 = 9a^2 : \frac{\sqrt{3}}{4}a^2 = 36 : \sqrt{3}$.

So the ratio P^2 : A is $36 : \sqrt{3}$ for all equilateral triangles; the ratio does not depend on the size of the equilateral triangle — it is the same for all equilateral triangles.

- Similarly, for various shapes, as we change the scale, the ratio P^2 : A stays fixed. The value of the ratio depends only on the shape, not on its scale.

Such reasoning suggests that for a circle too, if C = circumference and A = area, the ratio C^2 : A must be some fixed constant. But what is this constant?

Well before 1500 BCE, the Babylonians had found through actual measurement that the constant is close to 12; that is, $C^2 : A \approx 12 : 1$. So, their formula for the area of a circle was $A \approx \frac{C^2}{12}$.

Around 1500 BCE, the ancient Egyptians came up with another such formula which resembles the one described above but is much more accurate: $A \approx \left(\frac{8d}{9}\right)^2$ where d is the diameter of the circle. Since $d = 2r$,

© NCERT not to be republished

this may also be written as $A \approx \left(\frac{64}{81}\right)4r^2$, i.e., $A \approx \left(\frac{256}{81}\right)r^2$.

Amazingly, the same formula appears in the Baudhāyana Śhulbasūtra (800 BCE) via a geometric method for constructing a square with (approximately) the same area as a circle.

The Familiar Formula in Use Today

The ancient Greeks also knew that $\frac{A}{r^2}$ is some constant—but did not know what that constant was. Two different civilisations approximated it to be $\frac{256}{81}$.

Finally, in *c.* 250 BCE, Archimedes showed that the constant is exactly π (i.e., the same constant that occurs in the formula for perimeter of a circle!); so, $A = \pi r^2$. He expressed the formula this way: "The area of a circle is equal to the area of a right angle triangle with sides equal to the radius and the circumference of the circle". That is,

$$\text{Area of circle} = \frac{1}{2} \times \text{circumference} \times \text{radius} = \frac{1}{2} \times 2\pi r \times r = \pi r^2.$$

The proof given by Archimedes is very clever. It is based on a property shared by all regular polygons: The area enclosed by a regular polygon is equal to half the perimeter × the radius of the circle that fits tightly within the polygon (Fig. 6.36). (The proof of this formula is an extension of the proof of the formula of the area of a triangle in terms of the radius of its incircle.)



Fig. 6.36: Area of a regular polygon = $\frac{1}{2}$ × perimeter of the polygon × radius

© NCERT not to be republished

Archimedes did a 'thought experiment'; he asked himself what happens if the number of sides of the regular polygon gets larger and larger. Working out the details, he arrived at the result $A = \pi r^2$.

Here perhaps is the most visual and easy-to-understand explanation for why the area of a circle of radius r has area πr^2. This beautiful visual explanation for the area of the circle was first discovered by Nīlakaṇṭha Somayājī (*c.* 1500) in his commentary on the *Āryabhaṭīya*:



(A) (B)

Fig. 6.37: The slices can be rearranged to form a parallelogram-like structure

As the slices become smaller and smaller, the arcs in Fig. 6.37B become more and more closer to a line. This makes the figure more and more closer to a parallelogram with

base = half the circumference (why?) = πr,

height = radius r.

This gives a way to argue that the area of the circle is equal to the area of a parallelogram!

Area of the circle = Area of the parallelogram = base × height = πr^2.

6.10.1 Area of Sector of a Circle

A sector of a circle is the region bounded by an arc and the two radii containing the endpoints of the arc.

The area within a sector of a circle may be found the same way that we found the length of a circular arc. Examine Fig. 6.39 and Fig. 6.40.



Fig. 6.38: Sector of a circle

© NCERT not to be republished



Fig. 6.39: Area of a semi-circular disc

By symmetry, we see that the area of a semicircular disc is $\left(\frac{180}{360}\right)^{\text{th}} = \frac{1}{2}$ of the area of the circle, i.e., $\frac{1}{2}\pi r^2$.

We could use the reflection symmetry of the circle to understand this result.



Fig. 6.40: Area of a quarter circular disc

By symmetry, we see that the area of a quarter circular disc is $\left(\frac{90}{360}\right)^{\text{th}} = \frac{1}{4}$ of the area of the circle, i.e., $\frac{1}{4}\pi r^2$.

We could also use the quarter-turn symmetry of the circle to understand this result.

Examining the above, we immediately obtain the desired formula for a general sector:

Formula for the area of a sector of a disc in terms of the angle it subtends at the centre of the circle

If the arc is AB, and it subtends an angle of $\theta°$ at the centre O of the circle (see Fig. 6.38), then the area of the sector is

$$\pi r^2 \times \frac{\theta^\circ}{360^\circ}.$$

Note how we have used the rotational symmetry of a circle in deducing these formulas.

Related to a sector, there is a part of the circular region called a segment. A **segment** of a circle is the region bounded by an arc of the circle and the chord joining the endpoints of the arc.

© NCERT not to be republished

Exercise Set 6.3

Unless stated otherwise, use the approximation $\frac{22}{7}$ for π.

1. Find the area of a sector of a circle with radius 7 cm if the angle of the sector is 60°.
2. Find the area of a quadrant of a circle whose circumference is 44 cm.
3. The length of the minute hand of a clock is 7 cm. Find the area swept by the minute hand in 10 minutes.
4. A chord of a circle of radius 10 cm subtends 90° at the centre. Find the area of the corresponding: (i) minor sector (that subtends 90° at the centre), and (ii) major sector (that subtends 270° at the centre). (Use π ≈ 3.14.)
5. A chord of a circle of radius 15 cm subtends an angle of 60° at the centre of the circle. Find the areas of the corresponding minor and major segments of the circle. (Use π ≈ 3.14 and $\sqrt{3} \approx 1.73$.)
6. A car has two wipers which do not overlap. Each wiper has a blade of length 28 cm and sweeps through an angle of 120°. Find the total area cleaned at each sweep of the blades.

*7. A chord of a circle of radius r subtends an angle of 60° at the centre of the circle. Show that the area of the corresponding minor segment of the circle is equal to $\pi r^2\left(\frac{1}{6}-\frac{\sqrt{3}}{4}\right)$.

*8. An equilateral triangle is inscribed in a circle of radius r. Show that the ratio of the area of the triangle to the area of the circle is equal to $\frac{3\sqrt{3}}{4\pi} \approx 0.413$.

*9. A square is inscribed in a circle of radius r. Show that the ratio of the area of the square to the area of the circle is equal to $\frac{2}{\pi} \approx 0.637$.

*10. A hexagon is inscribed in a circle of radius r. Show that the ratio of the area of the hexagon to the area of the circle is equal to $\frac{3\sqrt{3}}{2\pi} \approx 0.827$. Can you see why the answer is exactly twice the answer to Question 8?

© NCERT not to be republished

End-of-Chapter Exercises

In the problems below, unless stated otherwise, use the approximation $\frac{22}{7}$ for π.

1. Identities in algebra can sometimes be shown as area relationships. For example:



Fig. 6.41: Area model of an identity

The figure shown corresponds to the identity

$$(a + b)^2 = a^2 + 2ab + b^2.$$

Do you see how?

Draw figures corresponding to the identities $(a + b)(a - b) = a^2 - b^2$ and $(a + b + c)^2 = a^2 + b^2 + c^2 + 2ab + 2bc + 2ca$.

2. An isosceles triangle has perimeter 40 cm; the equal sides are 15 cm each. Find the area of the triangle.
3. An isosceles triangle has base 10 cm, and its area is 60 cm^2. What are the lengths of the equal sides?
4. The area of a right-angled triangle is 54 sq. cm. One of its legs has length 12 cm. Find its perimeter.
5. The sides of a triangle are in the ratio 2: 3: 4, and its perimeter is 45 cm. Find its area.
6. The sides of a triangle have lengths 7 cm, 24 cm, 25 cm. Find the area of the triangle in two different ways.
7. If the wheel of a bicycle has a diameter of 60 cm, find how far a cyclist will have travelled after the wheel has rotated 100 times.

© NCERT not to be republished

8. Find the area of a quadrant of a circle whose circumference is 66 cm.

9. The wheel of a car has an outer radius of 28 cm. Calculate how far the car travels after one complete turn of the wheel, and how many times the wheel turns during a journey of 1 km.

*10. Two rectangles have the same area and the same perimeter. Does this mean that they are congruent to each other?

11. You know that the area of a parallelogram is base × height. Using this and the figure, show that the area of a trapezium is half the sum of the parallel sides × height, i.e., $\frac{1}{2}(a + b)h$.



Fig. 6.42: Trapezium: sides a and b, height h

12. By dividing a trapezium into two triangles show that its area is, half the sum of the parallel sides multiplied by the height (the same formula as the one given above).

13. Show how we can use two identical copies of a trapezium to make a parallelogram. How will this give us the formula for the area of a trapezium?

14. Show that the area of a kite is half the product of its diagonals. Show this: (i) using algebra, and (ii) using geometry.

15. Three problems about fitting congruent shapes together:

    (i) Rectangle ABCD has sides a, b, and rectangle PQRS has sides $2a$, $2b$. Show that PQRS has 4 times the area of ABCD. Does this mean that 4 copies of rectangle ABCD will fit into rectangle PQRS? Check and see!

© NCERT not to be republished

(ii) ΔABC has sides a, b, c, and ΔPQR has sides $2a$, $2b$, $2c$. Show that ΔPQR has 4 times the area of ΔABC. Does this mean that 4 copies of ΔABC will fit into ΔPQR? Check and see!

(iii) ΔABC has sides a, b, c, and ΔPQR has sides $3a$, $3b$, $3c$. Show that ΔPQR has 9 times the area of ΔABC. Does this mean that 9 copies of ΔABC will fit into ΔPQR? Check and see!

*16.



Fig. 6.43: What fraction of the triangle is shaded?



Fig. 6.44: What fraction of the square is shaded?

17.



Fig. 6.45: What fraction of the rectangle is covered by the circles?



Fig. 6.46: What fraction of the rectangle is covered by the circles?

18. Use the above to make a conjecture about the area occupied by circles fitted into a rectangle in the manner shown. Test your conjecture for particular cases: 10 circles; 20 circles; 50 circles. Then prove your conjecture!

*19.



Fig. 6.47: Nine identical rectangles stacked together

The figure shows nine identical rectangles fitted together to make a large rectangle whose area is 72 cm^2. Find the perimeter of each small rectangle.

© NCERT not to be republished

*20.



Fig. 6.48: Lines from a vertex to the points of trisection of the opposite side

Show that the areas of the shaded blue triangle and the shaded red triangle are equal.

Find a way of cutting up the blue triangle into some number of pieces and rearranging the pieces to cover the red triangle.

*21.



Fig. 6.49: A quarter circle and two semicircles

The figure shows a quarter circle in a square. Its centre is at one vertex, and it passes through two adjacent vertices. There are two semicircles on two adjacent sides as diameters. They create the shaded regions A and B .

Show that A and B have equal area.

*22.



Fig. 6.50

In Fig. 6.50, four semicircles have been drawn within the given square whose side is 2 units. The centres of these semicircles are the midpoints of the sides. They create a 4-petalled flower (shown in blue). Find the perimeter and the area of this flower.

*23.



Fig. 6.51

In Fig. 6.51 we see two concentric circles with a common centre O. A chord BC of the larger circle is drawn, touching the smaller circle at A. The length of BC is l. Show that the area of the green region enclosed between the two circles is $\frac{1}{4}\pi l^2$.

© NCERT not to be republished

*24. In Fig. 6.52, semicircles have been drawn on all the sides of a right-angled triangle as shown. Show that Area (A) + Area (B) = Area (C).



Fig. 6.52



Fig. 6.53: Two congruent circles, radius r

*25. Fig. 6.53 shows two circles passing through each other's centres. Find the area of the region enclosed by the two circles in terms of the common radius *r*.

*26. In Fig. 6.54, we see three triangles within a rectangle.

The areas of the triangles are *A*, *B*, *C*, as marked. Show that the area of the rectangle is

$$\frac{2(A+C)(B+C)}{C}.$$



Fig. 6.54

*27. In the figure we see two shaded regions formed by a quarter circle, a semicircle, and a triangle.



Fig. 6.55

Show that the areas of the two shaded regions are equal.

© NCERT not to be republished

Chapter Summary

- π is the constant circumference to diameter ratio for all circles, and is approximately equal to $\frac{22}{7}$ or 3.14.
- The circumference of a circle is given by C = $2\pi r$, where r is the radius of the circle.
- The arc length of a circle is given by $l = 2\pi r \times \frac{\theta^\circ}{360^\circ}$, where θ is the central angle.
- The area of a triangle is given by A = $\frac{1}{2}$ base times height.
- Heron's formula for the area of a triangle in terms of its sides a, b, c:

  area = $\sqrt{s(s-a)(s-b)(s-c)}$. where $s = s = \frac{1}{2}(a+b+c)$.
- The area of a circle is given by A = πr^2.
- Estimates for π: Archimedes: $3\frac{10}{71} < \pi < 3\frac{1}{7}$; Chongzhi: $\pi \approx \frac{355}{113}$; Āryabhaṭa: $\pi \approx 3.1416$; Mādhava's exact formula: $\pi = 4\left(1 - \frac{1}{3} + \frac{1}{5} - \frac{1}{7} + \cdots\right)$.
- π is an irrational number.
- The area of a sector of a circle is given by area = $\pi r^2 \times \frac{\theta^\circ}{360^\circ}$, where θ is the central angle.
- Brahmagupta's formula for the area of a cyclic quadrilateral in terms of its sides a, b, c, d:

  area $= \sqrt{(s-a)(s-b)(s-c)(s-d)}$. where $s = \frac{1}{2}(a+b+c+d)$.

© NCERT not to be republished

7 The Mathematics of Maybe: Introduction to Probability

0804CH07

7.1 What is Probability?

Probability is a type of measurement, similar to how we measure quantities like length, area, or volume. However, instead of measuring physical quantities, probability is used to measure the likelihood of **events**. Specifically, it helps us express how confident or certain we are that a particular event will occur. For example, you may ask your friend:

- Is it going to rain today?
- Will our school win the inter-school hockey match tomorrow?
- Will I be chosen in the monthly lucky draw to perform at the school assembly? [The names of all the students in school are written on slips of paper and one slip is randomly selected.]

These events are examples of **random** events. We know the possible outcomes (either it will rain today or it will not; our school team will either win, draw or lose the hockey match; one student will be chosen to perform at the school assembly), but we do not know in advance which one will definitely occur. That is, there is an element of **chance** or **randomness** involved every time such an event takes place.

Can we predict these outcomes with 100% certainty? One could respond to these questions with words such as **impossible** or **certain**, or using phrases such as **less likely**, **more likely** or **equally likely**. This decision is based on different kinds of **evidence** that have been gathered. For example, one friend might say, "The sun is shining brightly, so it's unlikely to rain today", while another might observe, "It's very hot, which makes me think it could rain later". In both cases, they are predicting rainfall based on how they interpret the present weather conditions. This is the **subjective probability** given to the event of today's rainfall.

© NCERT not to be republished

As you can see from the above example, probability deals with **uncertainty** or **chance**. One key feature of our increasingly complicated society is that we must deal with questions that have no fixed answer but rather one or more possibilities for the answer. Thus, understanding how to **objectively** estimate the probability of events is crucial in many aspects of life.

In this chapter, we will learn how we can measure probability more objectively, i.e., the ways of **collecting evidence** that can be used for an objective estimate of likelihood. But first, we must understand a few terms and ideas such as randomness and the probability scale.

7.1.1 What is Randomness?

Randomness refers to a situation or action (like the tossing of a coin or the rolling of a die) where you cannot predict exactly what will happen. Although you may know all the possible outcomes, you cannot say which one will definitely occur. For example,

- **Tossing a coin:** You know it could be heads or tails, but you cannot be sure which one will come up in a single toss.
- **Rolling a die:** You know the possible outcomes are 1, 2, 3, 4, 5, or 6, but you do not know which number will appear on a particular roll.

These observations (commonly called **experiments** or **trials** in probability) are called random because of their unpredictability. The lucky draw example mentioned earlier is an example of a random observation or experiment, as the outcome cannot be predicted in advance, and each student has an equal chance of being selected. All you can say is what could happen, not what will happen.

Random Observations: A random experiment is something you can repeat (like tossing a coin), where every time you do it, the result might be different and you cannot know the outcome in advance.

Think and Reflect

Such unpredictability can be useful sometimes! For example, in a cricket match, the fact that a coin is tossed to decide which team will bat first is considered to be a fair method. Can you explain why?

Probability is the area of mathematics that studies randomness and how likely a specific outcome is to happen in a random situation. For example, when you toss a coin, the probability for heads is $\frac{1}{2}$, and

© NCERT not to be republished

for tails is $\frac{1}{2}$, because each is **equally likely**. In a random experiment, every outcome has a chance to occur, but you can only determine the likelihood, not the exact result.

Have you wondered what makes an event like rain random? An event like rain is considered random because it depends on many complex factors in the atmosphere (such as temperature, humidity, wind patterns, and pressure) and is so sensitive to these factors that it is impossible to predict it with total certainty. Thus, it is impossible to know with absolute certainty whether it will rain on a specific day. Randomness in rain means that while the exact timing and location of rainfall cannot be predicted perfectly, we can estimate the likelihood or probability of rain in different locations based on patterns and probabilities derived from data.

Think and Reflect

Ask your friend to predict the outcome of a ₹1 coin you toss. Do you see that your friend could guess heads or tails but could not know for certain? That's randomness! All possible results are known, but each individual try is unpredictable.

7.1.2 The Probability Scale

Probability is measured on a scale from 0 to 1 to indicate the likelihood of the occurrence of an event. If the probability of your school winning the hockey match is 0.75, that means there is a 75% chance your school will win. This means that it is **more likely** than not that your school will win the match. If the probability of your school winning the hockey match is 0.5, that means there is a 50% chance your school will win. This means that it is **equally likely** that your school will win or lose the match. On the other hand, if the probability is 0, it would mean winning is **impossible** (for example, winning without playing), and if the probability is 1, it would mean your school is certain to win. The probabilities of most events fall somewhere strictly between 0 and 1, expressing how likely they are to happen.

Imagine a deck of six cards where the number of purple and green cards is unknown. The probability of picking a purple card from the deck (see Fig. 7.1) can range from impossible (if there are

© NCERT not to be republished

no purple cards) to certain (if all six are purple). As the number of purple cards increases, the likelihood of selecting a purple card moves smoothly along the **probability scale** from less likely, to even chance, to more likely. This scale helps us understand and compare how likely different events are, just like using a number line!



Fig. 7.1: Probabilities of picking a purple card from a deck on the probability scale

Here are a few examples of events and the probabilities of their occurrence. Look at the examples against the probability scale in Fig. 7.1 to understand how probability is measured on a scale.

Event	**What it means**
Getting a number greater than 6 on a die	**Impossible:** Dice only have numbers from 1 to 6.
Rolling a 3 on a standard die	**Less likely:** But not impossible as one face of the die is 3.
Flipping a coin and getting heads	**Even chance:** Heads or tails are equally likely.

© NCERT not to be republished

Drawing any number from 2 to 10 from a deck of 52 cards	**More likely:** There are 36 cards in a deck of 52 cards with numbers from 2 to 10.
Choosing a red sweet from a bag of all red sweets	**Certain:** All the sweets are red.

Exercise Set 7.1

1. Rank the following events on a scale from 0 (Impossible) to 1 (Certain). Label each event: Impossible, less likely, equally likely (even chance), more likely, certain. Give reasons why you gave each event its ranking.
   (i) The next Monday will come after Sunday.
   (ii) It will snow in Mumbai in July.
   (iii) An elephant will walk through your classroom today.
   (iv) You will greet at least one friend at school tomorrow.

7.2 Measuring Probability Objectively

There are two main ways of estimating the probability of an event objectively:

1. **Using evidence from experience:** This involves collecting data either by performing an experiment multiple times or by analysing statistical data from past observations. In both cases, the probability is estimated by calculating the relative frequency of the event based on the collected evidence. We call this e**xperimental probability**.
2. **Using theoretical methods:** This approach assumes that all **possible outcomes** are equally likely (when there is no reason to believe that any one outcome is more likely than another). The probability is then determined by reasoning about the number of favourable outcomes in relation to the total number of possible outcomes. We call this **theoretical probability**.

© NCERT not to be republished

7.2.1 Experimental Probability: Performing Observations or Experiments

Another way of obtaining objective estimates for probabilities is to perform an experiment. In an experiment, the event is a result of the experiment and is called an **outcome**. The set of all possible outcomes in an experiment is called the **sample space**.

The sample space may be listed within brackets, separated by commas as shown below.

Example 1: Experiment: A coin is tossed
Possible Outcomes: Heads (H) or Tails (T) (See Fig. 7.2)
Sample Space: {H, T}

Experiment: A die is rolled
Possible Outcomes: The top side of the die shows 1, 2, 3, 4, 5, or 6 dots (See Fig. 7.3)
Sample Space: {1, 2, 3, 4, 5, 6}

Fig. 7.2: Heads and tails of a coin

Fig. 7.3: A 6-sided die

$$\text{Experimental Probability} = \frac{\text{Number of times the event occurred}}{\text{Total Number of trials}}.$$

Example 2: Suppose you roll a die 50 times, and it lands on a 4 exactly 8 times.

Experimental probability of rolling a 4 is $\frac{8}{50} = 0.16$ or 16%.

We also say that the **relative frequency** of rolling a 4 is $\frac{8}{50} = 0.16$.

Relative frequency helps you understand probability based on actual data, rather than theoretical predictions. It is especially useful in statistics and data analysis when you are working with observed outcomes.

© NCERT not to be republished

Did you know? The game of Snakes and Ladders originates in ancient India. It evolved from a traditional dice game called **Jñān-Chaupaḍ**, which was used as an educational tool. Jñān-Chaupaḍ aimed to convey moral lessons, with each ladder symbolising a virtue and each snake representing a vice. Through gameplay, it illustrated the consequences of good and bad behaviour. Various versions of Jñān-Chaupaḍ have been found in different parts of India.

Fig. 7.4: A Jain Jñān-Chaupaḍ game on cloth, National Museum (India, 19th century)

7.2.2 Theoretical Probability

Theoretical probability studies the likelihood of an event happening based on all possible outcomes being **equally likely**. It is what we expect to happen in an ideal, **perfectly fair situation**. In this scenario, no experiment or data is required. Theoretical probability is usually denoted as P (Event) or P (Outcome).

Theoretical Probability (P) = $\frac{\text{Number of favourable outcomes}}{\text{Number of possible outcomes}}$.

Example 3: If you roll a standard 6-sided die, what is the theoretical probability of getting a 4?

Solution:

Number of favourable outcomes = 1 (only the number 4)

Number of all possible outcomes = 6 (the numbers 1 through 6)

P (rolling a 4) = $\frac{1}{6}$ = 0.1666... ≈ 0.167 or 16.7%.

Example 4: A letter is picked at random from the word 'PROBABILITY'. What is the probability of picking the letter B?

© NCERT not to be republished

Solution:

Number of favourable outcomes = 2 (there are 2 Bs in the word PROBABILITY)

Number of all possible outcomes = 11 (The number of letters in the word PROBABILITY)

P (Picking the letter B) = $\frac{2}{11}$ = 0.1818... ≈ 0.182 or 18.2%.

7.2.3 Analysing Statistical Data Using Probability

The way of collecting evidence through statistical data is used extensively in the world of business for marketing, forecasting sales, insurances and in science and social science research.

Example 5: Suppose you anonymously collect information regarding the favourite fruit of 50 students in your class. Let us assume that the results are: 20 students like mango, 15 students like apples, 10 students like bananas, and 5 students like grapes.

Let us play a game! Suppose we randomly pick one student from the class and try to guess their favourite fruit. What's the probability that the student's favourite fruit is mango? Statistical probability is based on collected data. So, a reasonable estimate that the student's favourite fruit is mango is

Probability of mango as the favourite fruit

$$= \frac{\text{Number of students who like mango}}{\text{Total number of students}} = \frac{20}{50} = 0.4.$$

So, there is a 0.4 or 40% chance that a randomly chosen student in the class likes mango.

Now assume that you want to buy fruits for the entire school depending on the students' favourite fruits. You would need to estimate the quantity of each type of fruit you need to purchase for the entire school of, say, 1500 students. It is usually impractical to collect data from all students or the entire **population**. The application of statistical probability in the real world is usually based on evidence collected from a **sample**. The population, i.e., the total number of students in the school, is 1500, and we collected evidence from a sample of 50 students from one class. An estimate of the probability that mango

© NCERT not to be republished

is the favourite fruit was calculated to be 0.4. So, that would mean that we need to buy approximately 600 (40% of 1500) mangoes, while the remaining would be other fruits — apples, bananas and grapes. If we want to be more confident about our estimate, we would choose a larger sample, for example, by asking 100 students, and make sure it is more representative, such as including students from different classes or grades. This process is called **sampling** in statistics.

LEARN MORE ABOUT SAMPLING

Want to learn more about sampling? What we have learned so far is just the beginning!

When collecting data through samples, there are other important things to think about — like how big your sample should be and how to make sure your sample truly represents the whole population. The size of your sample and making sure it's fair and not biased can help your results be more accurate.

If you are interested and want to explore more about why sample size and representation matter in statistics, you can read more about it in print or digital resources.

Summarising, **experimental probability** is based on actual data collected from trials, not on assumptions. **Theoretical probability** relies on the assumption of equally likely outcomes (a perfectly fair situation) and does not use experimental data. Even in perfectly fair situations, experimental probability can differ from theoretical probability, especially when the number of trials is small. As the number of trials increases, the experimental probability tends to get closer to the theoretical probability — this is known as the **Law of Large Numbers**.

Think and Reflect

If I have rolled a 4 on a die 8 times in succession, the probability of rolling a 4 again is still only ≈ 0.16 (assuming the die is fair). Probability does not tell you what will happen next but predicts what will happen in the long run.

© NCERT not to be republished

GAMBLER'S FALLACY

Many people think that if something random happens many times in a row (like flipping a coin and getting heads six times), then the opposite outcome (tails) is more likely to happen next. But actually, the coin does not keep track of what happened before. Every time you flip, the chance of heads or tails stays exactly the same — like starting afresh. The coin has no memory, so past flips do not change what happens next. This common misunderstanding is called **Gambler's Fallacy**.

For example, imagine that you are flipping a fair coin. It comes up heads six times in a row. You might feel that on the next flip you are sure to get a tail, because tails haven't come up for a while. However, the probability of getting tails on the next flip is still 50% or $\frac{1}{2}$, exactly the same as before. The coin has no memory of past flips!

Example 6: Let us say you are playing Snakes and Ladders, and you are rolling a fair 6-sided die to move.

You have just rolled the die three times in a row, and each time you got a 6.

Now, you think: 'I have already rolled three 6s — there is no way I will get a 6 again on the next roll!'

This thinking is Gambler's Fallacy — because each roll of the die is an independent event. The probability of rolling a 6 is always: $\frac{1}{6} \approx 0.166$ or 16.6%.

It does not change based on what happened in previous turns.

Key Idea: In Snakes and Ladders, as in many games of chance, each roll of dice is independent. The Gambler's Fallacy tricks people into believing there is a pattern, when in fact, such randomness has no memory.

FAIR AND UNBIASED

When we speak of a coin, we assume it to be **'fair'**, i.e., it is symmetrical so that there is no reason for it to come down more often on one side than the other. We call this property of the coin as being **'unbiased'**. By the phrase 'random toss', we mean that the coin is allowed to fall freely without any bias or interference.

© NCERT not to be republished

Exercise Set 7.2

1. A teacher mixes a large bag of sweets of different colours and randomly selects a sample of 30 sweets. She counts the number of sweets of each colour:
   10 red sweets | 8 green sweets | 7 yellow sweets | 5 blue sweets
   (i) Calculate the probability that a randomly picked sweet from the sample is green.
   (ii) If there are 600 sweets in total in the large bag, estimate how many are likely to be yellow, based on the sample results.
2. A survey is conducted at a school where a random sample of 40 students is asked about their favourite club. The responses are:
   14 students: Science Club | 11 students: Arts Club |
   9 students: Sports Club | 6 students: Debate Club
   Assume there are 800 students in the whole school.
   (i) What is the probability that a randomly chosen student from the sample prefers the Arts Club?
   (ii) Using the sample results, estimate how many students in the whole school are likely to prefer the Sports Club.
3. Toss a coin 20 times and record the result each time (heads or tails).
   (i) How many times did you get heads?
   (ii) How many times did you get tails?
   (iii) Calculate the experimental probability of getting heads.
   (iv) If you toss the coin once more, what is the probability of getting tails?
4. Toss a paper cup into the air 100 times. After each toss record whether the cup lands on its bottom, upside down on its top or on its side (See Fig. 7.5). Assign probabilities to the outcomes by using experimental probability.
5. What is the probability of getting an even number when rolling a fair 6-sided die?

Fig. 7.5: Paper cup landing positions (left to right)—bottom, top and side

© NCERT not to be republished

6. Suppose you roll a 6-sided die 12 times and get a '3' three times.
   (i) What is the experimental probability of rolling a '3'?
   (ii) What is the theoretical probability of rolling a '3'?
   (iii) Why might these probabilities be different? What would you expect to happen if you roll the die 60, 600, or 6000 times?

7.3 Elements of Probability: Sample Spaces and Events

7.3.1 Sample Space

Recall that the sample space, denoted by S, is the list of all possible outcomes. Each possible outcome is called an element of the sample space.

- The sample space S must include **every possible outcome**.
- No outcome should be **listed more than once**.
- The number of elements in the sample space is called the **sample size** and is denoted by $n(S)$.

Examples of Sample Space

1. The sample space for whether it rains tomorrow could be S = {Rain, No Rain} and the sample size $n(S) = 2$.
2. The sample space for a match, i.e., the possible outcomes for a team playing — could be S = {Win, Lose, Draw} and sample size $n(S) = 3$.
3. Tossing a Coin:
   - Experiment: Tossing a fair coin once.
   - Sample Space: S = {Heads (H), Tails (T)}
   - Sample Size = 2
4. Rolling a Die:
   - Experiment: Rolling a standard 6-sided die.
   - Sample Space: S = {1, 2, 3, 4, 5, 6}
   - Sample Size = 6
5. Tossing Two Coins:
   - Experiment: Tossing two coins simultaneously.
   - Sample Space: S = {HH, HT, TH, TT}
   - Sample Size = 4

Coin 1	Coin 2	Outcome
H	H	HH
H	T	HT
T	H	TH
T	T	TT

© NCERT not to be republished

Think and Reflect

When we used the sample space {Rain, No Rain} in Example 1, we focused only on whether it will rain or not. However, if we want to include different amounts of rainfall like drizzle, light rain or heavy rain, we need to expand the sample space to {No Rain, Drizzle, Light Rain, Heavy Rain} so that it better matches the level of detail required for the question. It is important to ensure the sample space is detailed enough to suit the specific problem being studied.

7.3.2 Events

An **event** is any single possible result or combination of results that might happen when you perform a random action. It is like choosing particular outcomes from all the things that could possibly occur. An event is a subset of a sample space.

Examples of Sample Spaces and Events

1. Tossing Two Coins
   - Sample space: All possible results like Head–Head, Head–Tail, Tail–Head, Tail–Tail. S = Sample Space = {HH, HT, TH, TT}
   - Event: 'At least one coin shows Head.' E = {HH, HT, TH}.
2. Rolling a 6-sided Die
   - Sample space: All faces numbered 1 through 6. S = {1, 2, 3, 4, 5, 6}
   - Event: 'The number rolled is greater than 4.' E = {5, 6}.
3. Picking Fruit from a Basket
   - Sample space: Types of fruit you might pick, for example, Apple, Banana and Orange. S = {Apple, Banana, Orange}
   - Event: 'Picking a fruit that is yellow.' E = {Banana}.

Exercise Set 7.3

1. When a single 6-sided die is rolled, what is the total number of possible outcomes in the sample space?
2. For the following experiments write down the sample space S.
   (i) Rolling a die and tossing a coin together.

© NCERT not to be republished

(ii) Choosing a random integer between – 5 and + 5.

(iii) A box containing 5 green and 7 red balls. One ball is drawn at random.

3. In a village fair, there are 3 popular snacks available: Samosa, Pakora, and Bhaji. For drinks, villagers can choose either Chai or Lassi.

   (i) List the sample space of all possible snack and drink combinations a person could choose at the fair.

   (ii) List the event 'Selecting Samosa as a snack.'

7.4 Tree diagrams

A tree diagram is a visual representation used to list all possible outcomes of a **multi-step experiment**. A multi-step experiment involves a series of independent trials. For example, tossing a coin two times, or rolling a dice three times are examples of multi-step experiments. Each branch of the tree represents a possible outcome, and branches split to show different paths for subsequent events.

A tree diagram is useful for

- Visualising multi-step experiments, where each path from start to end represents one complete outcome.
- Listing all outcomes of a sample space.

So far in this chapter, we have seen examples of single-step experiments. Let us look at an example of a multi-step experiment.

Example 7: Experiment: Toss a fair coin two times.

Tree Diagram (See Fig. 7.6):

From a single point draw a line to each of the possible outcomes of the first toss. From each of these outcomes draw two lines to each possible outcome. Do you see that the tree diagram shows 4 possible outcomes?

Hence the Sample Space

S = {HH, HT, TH, TT}.



Fig. 7.6: Tree diagram showing possible outcomes when we toss a fair coin twice

© NCERT not to be republished

Also, the theoretical probabilities of each outcome are mentioned on the branch representing that outcome.

$$\text{Theoretical Probability (P)} = \frac{\text{Number of favourable outcomes}}{\text{Number of possible outcomes}}.$$

Let us consider the event of getting Heads twice. This is represented by the outcome HH.

Probability of HH = $\frac{1}{4}$ = 0.25 or 25%.

Think and Reflect

Can you calculate the probability of getting one head and one tail?

Exercise Set 7.4

1. There are two fruit baskets A and B. Basket A has one apple and two oranges. Basket B has one banana and one mango. You randomly pick one fruit from each basket.
   (i) Draw a tree diagram showing all possible pairs of fruits.
   (ii) List the sample space.
   (iii) What is the probability of picking one apple and one banana?
2. Let us say that you have a box containing 3 red pens, 4 black pens and 2 green pens. You pick a pen (without looking) from the box and put it back. Then your friend does the same.
   (i) What are the possible outcomes of the pen colours? Can you draw a tree diagram representing the possible outcomes?
   (ii) Can you use the tree diagram to guess the probability that both you and your friend pick pens of the same colour?

End-of-Chapter Exercises

1. Fill in the blanks.
   (i) The probability of an impossible event is _____.

© NCERT not to be republished

(ii) The set of all possible outcomes of a random experiment is called the _____.

(iii) The probability of an event that is certain to happen is _____.

(iv) Tossing a fair coin has a probability of _____ for getting heads.

2. In a survey of 50 students, 15 students said they liked football. The number of students who like football is 15, and the _____ (frequency/relative frequency) is _____ (fill in the fraction or decimal).
3. Which of the following experiments have equally likely outcomes? Explain.

(i) A driver attempts to start a car. The car starts or does not start.

(ii) Tossing a fair coin once.

(iii) Rolling a fair 6-sided die.

(iv) Choosing a marble randomly from a bag that contains 3 red marbles and 7 blue marbles.

(v) A baby is born. It is a boy or a girl.

4. Write the sample space and calculate the probability based on the given information.

(i) Two coins are tossed at the same time. What is the probability of getting at least one head?

(ii) Ten identical cards numbered 1 to 10 are placed in a box. One card is drawn at random. What is the probability of drawing a card with an even number?

(iii) A die is rolled once. What is the probability of getting a number greater than 4?

(iv) A bag contains 3 red balls, 2 blue balls, and 1 green ball. One ball is picked at random. What is the probability that it is not red?

(v) Three coins are tossed simultaneously. What is the probability of getting exactly two heads?

5. A bag has 3 candies: strawberry, lemon, and mint. One is picked at random. What is the probability of picking a strawberry candy?

© NCERT not to be republished

6. A child has 2 shirts (one red and one blue) and 3 types of pants (jeans, khakis, and shorts). List all the possible combinations of outfits consisting of one shirt and one pair of pants. Display your answer in a table format.

7. A tyre company records distances before replacement in 1000 cases.

Distance (km)	**Less than 4000**	**4001 to 9000**	**9001 to 14000**	**More than 14000**
Number of cases	20	210	325	445

Find the probability that a randomly chosen tyre lasts:

(i) Less than 4000 km.
(ii) Between 4000 and 14000 km.
(iii) More than 14000 km.

8. The letters of the word 'PEACE' are placed on cards. Leela draws a card without looking.

(i) What is the probability that it is a P, E or C?

(ii) What is the probability that it is not an E?

*9. A game of chance consists of spinning an arrow (see Fig. 7.7.) which comes to rest pointing at one of the numbers 1, 2, 3, 4, 5, 6, 7, 8, and these are equally likely outcomes. What is the probability that it will point at

(i) 8?
(ii) An odd number?
(iii) A number greater than 2?
(iv) A number less than 9?
(v) A multiple of 3?

Fig. 7.7

*10. A basket contains 4 red balls and 5 blue balls. One ball is drawn and laid aside, and a second ball is drawn. Draw a tree diagram to represent the possible outcomes and probabilities. Use the tree diagram to answer the following questions.

© NCERT not to be republished

(i) What is the probability of drawing a red ball and then a blue ball?

(ii) What is the probability of drawing 2 blue balls?

*11. I throw a pair of 6-sided dice. Write down an event that has a probability of 0 and an outcome that has a probability of 1.

*12. Write the sample space and calculate the probability based on the given information.

(i) Two dice are rolled. What is the probability that the sum is a prime number greater than 5?

(ii) A bag contains 4 red, 3 green, and 2 blue balls. Two balls are drawn without replacement. What is the probability that both are of different colours?

(iii) Three coins are tossed. What is the probability that the first coin shows heads and exactly two heads occur in total?

(iv) A four-digit number is formed using the digits 1, 2, 3, and 4 with no repetition. What is the probability that the number is even?

(v) A student takes a multiple-choice test with 3 questions, each having 4 options (A, B, C, D), with only one correct answer. What is the probability that the student guesses and gets exactly 2 answers correct?

*13. A box contains 4 balls numbered 1 to 4. Record a sample space using a tree diagram for the following experiments:

(i) A ball is drawn, and the number is recorded. Then the ball is returned, and a second ball is drawn and recorded.

(ii) A ball is drawn and recorded. Without replacing the first ball, the experimenter draws and records a second ball.

(iii) What are the sizes of these two sample spaces?

*14. List the elements of a sample space for the simultaneous tossing of a coin and drawing of a card from a set of 6 cards numbered 1 through 6.

*15. Three coins are tossed, and the number of heads is recorded. Which of the following lists is a sample space for this experiment? Why do the other lists fail to qualify as a sample space?

© NCERT not to be republished

(i) {1, 2, 3}

(ii) {0, 1, 2}

(iii) {0, 1, 2, 3, 4}

(iv) {0, 1, 2, 3}

*16. Suppose you drop a dye at random on the rectangular region shown in Fig. 7.8. What is the probability that it will land inside the circle with a diameter of 1 m?



Fig. 7.8

Chapter Summary

- Probability is a measurement of the likelihood of an event.
- Probability is expressed on a scale from 0 (indicating impossibility) to 1 (indicating certainty), representing the likelihood of an event occurring. The probability of an event E is denoted as P(E), where $0 \leq P(E) \leq 1$.
- Experimental probability is determined by conducting an experiment and is calculated as:

  $$\text{Experimental Probability} = \frac{\text{Number of times the event occurred}}{\text{Total number of trials}}.$$

- Theoretical probability is based on all possible outcomes in a fair situation, assuming each is equally likely:

  Theoretical Probability of an event A is

  $$P(A) = \frac{\text{Number of favourable outcomes}}{\text{Number of possible outcomes}}.$$

- A sample space is the list of all possible outcomes of a random experiment. It is represented as a set S = {outcome_1, outcome_2 ..., outcome_n}.
- An event is any one or a group of possible outcomes from a random experiment. It is like picking results or outcomes from all that could happen.
- Tree diagrams help us to list and visualise all possible outcomes of a random experiment. They also help us calculate probabilities of events related to random experiments.

© NCERT not to be republished

8 Predicting What Comes Next: Exploring Sequences and Progressions

8.1 Introduction to Sequences

We see patterns around us everywhere, be it in nature, in art, in music, in finance and in many other contexts in everyday life. Patterns help us make sense of the world and predict what comes next. In mathematics, sequences are special kinds of patterns formed by numbers or other objects arranged in a particular order. By understanding sequences, we can explore fascinating ideas about how numbers grow, shrink, or repeat and even use these ideas to solve real-life problems.

In this chapter, we shall explore patterns in sequences of numbers. We will then find rules to help us predict more numbers of the sequence. Let us begin by looking at some number sequences that you have already seen in Grades 6, 7 and 8.

1, 2, 3, 4, 5, 6, ...	(Natural Numbers)
1, 3, 5, 7, 9, 11, ...	(Odd Numbers)
1, 3, 6, 10, 15, 21, ...	(Triangular Numbers)
1, 4, 9, 16, 25, 36, ...	(Square Numbers)

The three dots ... indicate that the sequence continues indefinitely.

Think and Reflect

Can you describe the pattern in each of the above sequences? Can you predict the next few numbers in these sequences?

Before we proceed, let us define a **sequence** as an ordered list of numbers where each number is a **term** of the sequence. Thus, in the sequence of square numbers, 1 is the first term, 4 is the second term, 25 is the fifth term and so on. Also, sequences may be finite or infinite. The sequences mentioned above are infinite. But the sequence 6, 12, 24, 48, 96 is a finite sequence of five terms. Can you think of other finite sequences that you see in your daily life?

© NCERT not to be republished

As you already know, in the sequence of natural numbers, every number (or term) is one more than the previous number. In the sequence consisting of all the odd numbers, there is a difference of 2 between any two consecutive terms. In the sequence of triangular numbers, the difference between consecutive terms (among the first six terms) are 2, 3, 4, 5 and 6. We may rewrite the triangular numbers in the form of sums of natural numbers as 1 = 1, 3 = 1 + 2, 6 = 1 + 2 + 3, 10 = 1 + 2 + 3 + 4, and so on. Thus, each term of the triangular number sequence is the sum of the natural numbers up to that term. For example, 15, the fifth triangular number, is equal to 1 + 2 + 3 + 4 + 5. This is represented by the diagram in Fig. 8.1, where each triangular number is represented by a triangular array of dots. Can you draw the patterns for the next two terms of the sequence?



Fig. 8.1: The first five triangular numbers

Let us now shift our attention to the sequence of square numbers, 1, 4, 9, 16, 25, 36,... Note that the differences between consecutive terms (for the first six terms) are 3, 5, 7, 9 and 11. Also 1 = 1, 4 = 1 + 3, 9 = 1 + 3 + 5, 16 = 1 + 3 + 5 + 7, and so on. Each term in the square number sequence is the sum of the odd numbers up to that term.

This interesting relationship between the odd numbers and square numbers can be represented by the diagram in Fig. 8.2. Can you explain the relationship? You may recall some of these ideas from Grade 6, Chapter 1!



Fig. 8.2: Square numbers and odd numbers

© NCERT not to be republished

Exercise: Consider the sequence 1, 4, 7, 10, 13, ... Can you predict the next four terms? Can you derive the first 10 terms of the sequence obtained by adding all the terms up to a given term of this sequence? (**Hint:** The first term is 1. The second term is 1 + 4 = 5, the third term is 1 + 4 + 7 = 12, and so on.)

In some sequences (like the ones described till now), the terms follow a certain pattern, a rule or order. To describe these rules it is helpful to have a convenient notation to describe a sequence. We can use t_1 to represent the first term of a sequence, t_2 to represent the second term, and so on. In this notation, the subscripts match the term numbers. Thus, for the sequence of odd numbers, $t_1 = 1$, $t_2 = 3$, $t_3 = 5$, $t_4 = 7$ and so on. This notation helps to connect the position of the term to the actual term. For example, $t_4 = 7$ tells us that the term in the fourth position is 7. We may need to talk about more than one sequence at a time. We can use different letters for these. Hence, we can use $t_1, t_2, t_3, \ldots$ for one sequence, $s_1, s_2, s_3, \ldots$ for another one, $u_1, u_2, u_3, \ldots$ for a third sequence, and so on.

Exercise: Can you write t_5, t_6, t_7 and t_8 for the sequence of triangular numbers?

There can be many kinds of sequences. For example, the terms could be fractions or negative integers. The ones we have discussed so far have terms that are increasing. But there could be sequences such as 1, $\frac{1}{2}$, $\frac{1}{3}$, $\frac{1}{4}$, ... where $t_1 = 1$ and the following terms are unit fractions occurring in decreasing order. We can also have sequences such as –7, –3, 1, 5, 9, ... where $s_1 = -7$, and consecutive terms have a difference of 4. Note that when we use the notation t_n for describing a term, n is always a non-negative integer but the term itself can be negative, or in fact any real number.

Think and Reflect

Can you think of any other kinds of sequences? List out five different types of sequences and discuss their properties with your friends.

8.2 Explicit Rule for a Sequence

Using the notation t_n (or s_n or u_n) we can write an explicit rule for the term in the n^{th} position of a sequence, that is, the n^{th} term. An **explicit formula** uses the term's position number, n, to calculate its value.

© NCERT not to be republished

Example 1: Consider the expression $u_n = 2n - 1$. This states that the n^{th} term of the sequence is given by the rule $2n - 1$. When we substitute 1, 2, 3, ... for n in the expression $2n - 1$, we get $u_1 = 2 \times 1 - 1 = 1$, $u_2 = 2 \times 2 - 1 = 3$, $u_3 = 2 \times 3 - 1 = 5$, etc.

Thus, $u_n = 2n - 1$ is the explicit rule for the n^{th} term of the sequence of odd numbers.

Think and Reflect

Why is it useful to have an explicit formula for the n^{th} term of a sequence?

Using an explicit formula, we can find the 20th term, the 53rd term, the 300th term or any term of the sequence directly by just substituting the appropriate value of n. If we have an explicit formula, we can find the value of a term without having to know the value of previous terms!

Exercise: Using the explicit rule $u_n = 2n - 1$, find the 53rd term, the 108th term, and the 1170th term of the odd number sequence.

The explicit rule is useful in other ways too. We can use it to check if a certain number is a term of a sequence and also find the position of the term. For example, consider the odd number 137. To find which position it occupies in the odd number sequence, we need to solve the equation $u_n = 137$. This means $2n - 1 = 137$ or $n = 69$. Thus 137 is the 69th term of the odd number sequence.

Example 2: As another example, consider the sequence that is generated by the explicit formula $s_n = 5n - 2$. Can you write the first 6 terms of this sequence? What is the 100th term? The 1000th term?

Let us check if the numbers 308 and 473 are terms of this sequence.

We solve $s_n = 308$, that is, $5n - 2 = 308$. This leads to $5n = 310$ or $n = 62$. Thus 308 is the 62nd term of the sequence. Similarly solving $5n - 2 = 471$ leads to $5n = 473$, $n = 94.6$. Since 94.6 is not a natural number, we can conclude that 471 is not a term of the sequence. Can you explain why we need n to be a natural number?

Think and Reflect

Can you find the rule describing the n^{th} term of the sequence of square numbers?

Here is the sequence of the first ten prime numbers: 2, 3, 5, 7, 11, 13, 17, 19, 23, 29. Do you see any pattern in this sequence? Can you think of

© NCERT not to be republished

a rule that can predict the next few prime numbers?

Exercise: Consider the expression $t_n = 3n - 7$.

(i) Find its first, second, third, 12th, 18th and 50th terms.

(ii) Which term of the sequence is 332?

(iii) Is 557 a term of this sequence? Why or why not?

8.3 Recursive Rule for a Sequence

So far, we have used a formula in terms of n for the n^{th} term as the explicit rule for a sequence. There is another way of writing the rule for a sequence. Consider the sequence 1, 4, 7, 10, 13, ... The n^{th} term is $t_n = 3n - 2$ (verify this for yourself). Note that each term is 3 more than its previous term. Thus, $t_2 = t_1 + 3$, $t_3 = t_2 + 3$, $t_4 = t_3 + 3$ and so on. In general, we can say $t_n = t_{n-1} + 3$ for $n \geq 2$. Or we can describe the sequence as $t_1 = 1$, $t_n = t_{n-1} + 3$, where n can take the values 2, 3, 4, ... This way of describing a sequence by relating terms to previous terms is known as a **recursive rule** or **recursive formula**. If you know earlier terms of the sequence, then you can find the next terms using the rule. Note that the earlier terms need to be known to us to use the recursive rule to find the next terms.

Example 3: Find the first four terms of the sequence given by the recursive rule

$u_1 = 1$, $u_n = 2u_{n-1} + 3$ for $n \geq 2$. Is 133 a term of this sequence?

We successively insert the values of n as 2, 3, 4, etc., and compute the values of each term.

$$u_2 = 2u_1 + 3 = 2 \times 1 + 3 = 5$$
$$u_3 = 2u_2 + 3 = 2 \times 5 + 3 = 13$$
$$u_4 = 2u_3 + 3 = 2 \times 13 + 3 = 29$$

Thus, the first four terms of the sequence are 1, 5, 13, 29. Calculating subsequent terms, we can check if 133 is a term of this sequence.

Example 4: Find the first four terms of the sequence given by the recursive rule $s_1 = 3$, $s_n = s_{n-1}(s_{n-1} - 1)$ for $n \geq 2$.

Substitute the values of n as 2, 3, 4, etc., and compute the values of each term as follows.

$$s_2 = s_1(s_1 - 1) = 3 \times (3 - 1) = 3 \times 2 = 6$$
$$s_3 = s_2(s_2 - 1) = 6 \times (6 - 1) = 6 \times 5 = 30$$
$$s_4 = s_3(s_3 - 1) = 30 \times (30 - 1) = 30 \times 29 = 870$$

© NCERT not to be republished

Thus, the first four terms of the sequence are 3, 6, 30, 870.

Virahānka–Fibonacci sequence

A recursive rule or formula does not only have to involve the previous term — it could involve the previous two or more terms.

The most famous example of such a sequence is $V_1, V_2, V_3, \ldots$ where $V_1 = 1$, $V_2 = 2$, and $V_n = V_{n-1} + V_{n-2}$ for $n \geq 3$. We compute:

$$V_3 = V_2 + V_1 = 2 + 1 = 3$$
$$V_4 = V_3 + V_2 = 3 + 2 = 5$$
$$V_5 = V_4 + V_3 = 5 + 3 = 8$$

So we get the sequence

$$1, 2, 3, 5, 8, 13, 21, 34, \ldots$$

where each term is obtained by adding the previous two.

Can you write the next two terms of this sequence?

Do you recognise this sequence from previous grades? That's right, it is the Virahānka–Fibonacci sequence! It was first written down explicitly and studied by Virahānka in his work *Vṛttajātisamuchaya* in the 7th century CE. He discovered it in the context of Prakrit meter and poetry! It was further studied by the linguist-mathematicians Gopāla (c. 1135 CE) and Hemachandra (c. 1150 CE). The sequence was later also studied by the Italian mathematician Fibonacci (c. 1200 CE).

The Virahānka sequence plays an important role throughout mathematics and science. We will encounter it again many times in later grades.

Exercise Set 8.1

1. Find the first five terms of the sequence in which the n^{th} term is given by (i) $t_n = 3n - 4$, (ii) $t_n = 2 - 5n$, and (iii) $t_n = n^2 - 2n + 3$ for $n \geq 1$.
2. Find the 10^{th} and 15^{th} terms of the sequence $t_n = 5n - 3$ for $n \geq 1$.
3. Determine whether 97 and 172 are terms of the sequence $t_n = 5n - 3$ for $n \geq 1$.
4. Which term of the sequence $t_n = 5n - 3$ for $n \geq 1$ is 607?
5. A sequence is given by the recursive rule $t_1 = -5$, $t_{n+1} = t_n + 3$ for $n \geq 1$. Find the first five terms of the sequence. Is 52 a term of this sequence? If so, which term is it?

© NCERT not to be republished

6. Let $T_1 = 1$, $T_2 = 2$, $T_3 = 4$, and $T_n = T_{n-1} + T_{n-2} + T_{n-3}$ for $n \geq 4$. Find T_4, T_5, T_6, T_7, and T_8.

8.4 Arithmetic Progressions

So far we have learnt that a sequence is an ordered list of numbers that may follow a particular rule. However, there may be sequences, such as the sequence of prime numbers, where there is no clear regularity in the rule.

In this section, we explore a special kind of sequence called an **arithmetic progression**.

Let us look at the growing pattern of squares given in Fig. 8.3. The first four stages of the pattern are shown.



Fig. 8.3: Growing pattern of squares

If we count the number of tiny squares at each stage, we get sequence 1, 5, 9, 13.

Think and Reflect

Can you predict the number of squares in Stages 5 and 6 of the sequence? In Stages 10, 11 and 12? In Stage 20? At any stage?

We observe that at each stage, 4 squares get added to the corners of the pattern in the earlier stage. The number of squares at successive stages can be written as

$$1, 1 + 4, 1 + 4 + 4, 1 + 4 + 4 + 4, \ldots$$

© NCERT not to be republished

This may be rewritten as

$$1, 1 + 1 \times 4, 1 + 2 \times 4, 1 + 3 \times 4, \ldots$$

If we treat these expressions as the terms of a sequence, we get

$$t_1 = 1, t_2 = 1 + 1 \times 4, t_3 = 1 + 2 \times 4, t_4 = 1 + 3 \times 4$$

and so on. We may therefore write the n^{th} term as $t_n = 1 + (n - 1) \times 4$, which simplifies to $t_n = 4n - 3$.

The first six terms of the sequence representing the number of squares in Fig. 8.3 are 1, 5, 9, 13, 17, 21. We note that the difference between successive terms is the constant value 4. Such sequences, in which the difference between consecutive terms is constant, are known as arithmetic progressions. We will refer to them as APs.

Think and Reflect

Consider all the sequences we have discussed so far in this chapter. Which ones are arithmetic progressions and which ones are not? Can you justify your claim?

Note that in the n^{th} term $t_n = 1 + (n - 1) \times 4$ of the sequence above, 1 is the first term of the sequence and 4 is the 'common difference'. Similarly, the n^{th} term of the sequence 1, 4, 7, 10, ... is $t_n = 1 + (n - 1) \times 3$, where 1 is the first term and 3 is the common difference. In the sequence 11, 7, 3, –1, – 5, ... the numbers decrease by 4. This is also an arithmetic progression, where the first term is 11 and the common difference is – 4.

In general, an arithmetic progression (AP) can be described as

$$a, a + d, a + 2d, a + 3d, \ldots, a + (n - 1) \times d,$$

where 'a' is the **first term** and 'd' is the **common difference**. Thus $t_n = a + (n - 1) \times d$ is an expression for the n^{th} term of any arithmetic progression, for some fixed values of a and d.

8.4.1 Visualising an AP

Let us return to the growing pattern of squares in Fig. 8.3 and prepare a table that shows the number of tiny squares at each stage.

Stage Number	1	2	3	4	5	...	n
Number of squares	1	5	9	13	17	...	$4n - 3$

© NCERT not to be republished

Let us form a pair of numbers (x, y) using the information in the table above where x represents the stage number and y the corresponding number of squares. When we plot the ordered pairs emerging from the table, that is, (1, 1), (2, 5), (3, 9), (4, 13), (5, 17), we observe that they lie on a straight line! This is shown in Fig. 8.4.



Fig. 8.4: Growing pattern of squares represented by a linear pattern

Exercise: Verify that the following sequences are arithmetic progressions and write their n^{th} terms. What do you observe when you plot the ordered pairs emerging from them?

(i) 2, 5, 8, 11, ... (ii) –5, –1, 3, 7, ...

Exercise: Using the formula $t_n = a + (n - 1) \times d$, find the n^{th} term of the following arithmetic progressions.

(i) $\frac{1}{2}, \frac{5}{2}, \frac{9}{2}, \frac{13}{2}, \ldots$ (ii) 1.5, 3.5, 5.5, 7.5, ...

Note that $t_n = a + (n - 1) \times d$ is the explicit rule for finding the n^{th}

© NCERT not to be republished

term of an AP. Can we also find the recursive rule? Yes. It is $t_1 = a$, $t_n = t_{n-1} + d$ for $n \geq 2$.

Consider once again the AP: 1, 5, 9, 13, 17, ... Since every term is 4 more than the previous term, another way of writing this sequence is $t_1 = 1$, $t_n = t_{n-1} + 4$ for $n \geq 2$. Verify for yourself that this recursive rule leads to the terms of the sequence.

Exercise: Find recursive rules for the APs in the previous exercises.

Example 5: A person books a taxi to travel in the city. The taxi company charges a fixed booking fee of ₹200 plus ₹40 per kilometre travelled. Let us write the sequence representing the total fare after travelling 1 km, 2 km, 3 km, and so on. If the person travels 10 km, what will be the total fare?

Since the fixed amount is ₹200, after 1 km the fare will be ₹200 + ₹40 = ₹240, after 2 km it will be ₹200 + ₹80 = ₹280 and after 3 km it will be ₹200 + ₹120 = ₹320. The sequence 240, 280, 320, ... is an AP with first term 240 and common difference 40. The n^{th} term of the sequence is $240 + (n - 1) \times 40 = 240 + 40n - 40 = 200 + 40n$ where n represents the distance travelled in km.

8.5 Sum of the First n Natural Numbers

In this section, we derive a simple yet important rule for the sum of the first n natural numbers. To begin with, can you find the sum of the first ten natural numbers without actually adding all of them?

Let us try a unique approach. Let S denote the sum of the first ten natural numbers. Thus S = 1 + 2 + 3 + 4 + 5 + 6 + 7 + 8 + 9 + 10. We can also write it as S = 10 + 9 + 8 + 7 + 6 + 5 + 4 + 3 + 2 + 1. If we place these two equations, one below the other, we notice something interesting.

$$S = 1 + 2 + 3 + 4 + 5 + 6 + 7 + 8 + 9 + 10$$
$$S = 10 + 9 + 8 + 7 + 6 + 5 + 4 + 3 + 2 + 1$$

Each pair of corresponding numbers, 1 + 10, 2 + 9, 3 + 8, ... , 10 + 1, in the two equations add up to 11.

Adding the two equations for S, we get

$$2S = 11 + 11 + 11 + \cdots + 11 \text{ (that is, 11 added 10 times).}$$

This leads to 2S = 110 or S = 55. The sum of the first 10 natural numbers is indeed 55.

© NCERT not to be republished

Think and Reflect

Can the same approach be used to find the sum of $1 + 2 + 3 + \cdots + 100$?

This method of writing the sum from 1 to any number, reversing the sum and then adding the two expressions can be used to arrive at the formula for the sum of the first n natural numbers for any value of n.

Let $S = 1 + 2 + \cdots + n$.

Then $S = n + (n - 1) + \cdots + 1$.

So, $2S = n(n + 1)$. We conclude $S = \frac{n(n+1)}{2}$.

We can also think of this argument pictorially.

The diagram in Fig. 8.5 represents the method to find the sum $1 + 2 + 3 + 4 + 5 + 6$. Note that the figure comprises two sets of circles that represent the sum $1 + 2 + 3 + 4 + 5 + 6$ above and below of the zigzag partition. The total number of circles forms a 7×6 rectangular array.



$2 \times (1 + 2 + 3 + 4 + 5 + 6) = 7 \times 6$

Fig. 8.5

Thus, Fig. 8.5 represents the fact $2 \times (1 + 2 + 3 + 4 + 5 + 6) = 7 \times 6$.

This can similarly be extended to find the sum

$$1 + 2 + 3 + 4 + 5 + 6 + 7 + 8 + 9 + 10.$$

Namely, $2 \times (1 + 2 + 3 + 4 + 5 + 6 + 7 + 8 + 9 + 10) = 10 \times 11$.

In general, $2 \times (1 + 2 + 3 + 4 + \cdots + n) = n \times (n + 1)$.

Therefore, $1 + 2 + 3 + 4 + \cdots + n = \frac{n(n+1)}{2}$.

If we use the notation S_n to represent the sum of the first n natural numbers, then $S_n = \frac{n(n+1)}{2}$.

© NCERT not to be republished

The first known written mention of this result can be found in Āryabhaṭa's *Āryabhaṭīya*, Chapter 2, Verse 19. The verse provides two ways to calculate the sum, with the second part describing that the sum can be calculated by taking the sum of the first and last terms, divided by two (the average), and multiplied by the number of terms.

Think and Reflect

Can you use this formula to find S_{20}, S_{50} or S_{1000}?

Also, this formula can be used to find the sum of consecutive numbers such as 25 + 26 + 27 + ⋯ + 58.

Note that 25 + 26 + 27 + ⋯ + 58 = (1 + 2 + 3 + ⋯ + 58) – (1 + 2 + 3 + ⋯ +24)

$= S_{58} - S_{24} = \frac{58 \times 59}{2} - \frac{24 \times 25}{2} = 29 \times 59 - 12 \times 25 = 1711 - 300 = 1411.$

Think and Reflect

Let us revisit the sequence t_n of triangular numbers 1, 3, 6, 10, 15, ... shown in Fig. 8.1. Note that the n^{th} term of this sequence is the sum of the first n natural numbers. Thus $t_n = \frac{n(n+1)}{2}$.

Can you use this to find the 10th, 17th and 80th triangular numbers?

Exercise Set 8.2

1. Find the 10th and 26th terms of the AP: 3, 8, 13, 18, ...
2. Which term of the AP : 21, 18, 15, ... is – 81? Also, is 0 a term of this AP? Give reasons for your answer.
3. Find the n^{th} term of the AP: 11, 8, 5, 2 ... Write the recursive rule for this AP.
4. An AP consists of 50 terms in which the 3rd term is 12 and the last term is 106. Find the 29th term.
   (**Hint:** If 'a' is the first term and 'd' the common difference, then we arrive at the equations $a + 2d = 12$ and $a + 49d = 106$. Solve this pair of linear equations for 'a' and 'd'.)

© NCERT not to be republished

5. How many 2-digit numbers are divisible by 3? What is the sum of all these 2-digit numbers?
6. Harish started work at an annual salary of ₹5,00,000 and received an increment of ₹20,000 each year. After how many years did his income reach ₹7,00,000?
7. A child arranges marbles in rows so that the first row has 1 marble, the second has 2 marbles, the third has 3, and so on up to 25 rows. How many marbles does the child use in all?

8.6 Geometric Progressions

In this section, we explore yet another special kind of sequence called a **geometric progression (GP)**. Consider the growing pattern of squares shown in Fig. 8.6. The first four stages of the pattern are shown.



Fig. 8.6: A growing pattern of squares

If we count the total number of green squares in the four stages of the pattern, we get the sequence 3, 6, 12, 24.

Think and Reflect

Can you predict the number of squares in Stages 5 and 6 of the pattern? In Stages 10, 11 and 12? In Stage 20? At any stage? How is this different from the growing pattern in Fig. 8.3?

We observe that at each stage, the number of green squares is doubled or is twice the number of squares in the previous stage. The number of squares at successive stages is 3, 3 + 3 = 6, 6 + 6 = 12, 12 + 12 = 24, ...

© NCERT not to be republished

These may be rewritten as

$$3, 3 \times 2, 3 \times 4, 3 \times 8, \ldots \text{ or as } 3, 3 \times 2, 3 \times 2^2, 3 \times 2^3, \ldots$$

If we treat these expressions as the terms of a sequence, we get

$$t_1 = 3, t_2 = 3 \times 2, t_3 = 3 \times 2^2, t_4 = 3 \times 2^3$$

and so on. We can write the n^{th} term as $t_n = 3 \times 2^{n-1}$. As a recursive formula, we can write $t_1 = 3$ and $t_n = 2t_{n-1}$ for $n \geq 2$.

The first six terms of the sequence are 3, 6, 12, 24, 48, 96. Each term of the sequence is obtained by multiplying the previous term by 2. This **constant multiplier** is also known as the **common ratio** of the sequence. We see that the ratios of consecutive pairs of terms are all the same.

$$\frac{6}{3} = \frac{12}{6} = \frac{24}{12} = \frac{48}{24} = \frac{96}{48} = 2.$$

Such a sequence with a common ratio is known as a **Geometric Progression or GP.** In general, a GP may be described in the form of a sequence as $a, ar, ar^2, ar^3, \ldots, ar^{n-1}$, where '$a$' is the **first term**, 'r' is the **common ratio** and $t_n = ar^{n-1}$ is the ***n*th term**.

Example 6: Is 1, 2, 4, 8, 16, ... a geometric progression? If so, what is the common ratio?

Example 7: Is 1, 3, 9, 27, 81, ... a geometric progression? If so, what is the common ratio?

Example 8: Is 1, –1, 1, –1, 1, ... a geometric progression? If so, what is the common ratio?

Example 9: Check whether the sequence 5, $\frac{15}{4}$, $\frac{45}{16}$, $\frac{135}{64}$, ... is a geometric progression and find its n^{th} term.

In the given sequence $t_1 = 5, t_2 = \frac{15}{4}, t_3 = \frac{45}{16}, t_4 = \frac{135}{64}$

Let us evaluate the ratios of consecutive pairs of terms.

$$\frac{t_2}{t_1} = \frac{15}{4} \div 5 = \frac{15}{4} \times \frac{1}{5} = \frac{3}{4}.$$

$$\frac{t_3}{t_2} = \frac{45}{16} \div \frac{15}{4} = \frac{45}{16} \times \frac{4}{15} = \frac{3}{4}.$$

$$\frac{t_4}{t_3} = \frac{135}{64} \div \frac{45}{16} = \frac{135}{64} \times \frac{16}{45} = \frac{3}{4}.$$

The ratio of consecutive pairs of terms is a constant $\frac{3}{4}$. Hence the

© NCERT not to be republished

given sequence is a GP with $a = 5$ and $r = \frac{3}{4}$. The n^{th} term $= a \times r^{(n-1)}$ $= 5 \times \left(\frac{3}{4}\right)^{n-1}$. Substitute $n = 1, 2, 3, \ldots$ in this expression to check if you get the terms of the given sequence.

Exercise: Check whether the following sequences are geometric progressions and find their n^{th} terms.

(i) 2, 10, 50, 250, ...

(ii) $4, \frac{8}{3}, \frac{16}{9}, \frac{32}{27}, \ldots$

(iii) $3, \frac{-3}{2}, \frac{3}{4}, \frac{-3}{8}, \ldots$

Exercise: Can you find a recursive rule for the formula $t_n = 3 \times 10^{n-1}$ that generates the geometric progression 3, 30, 300, 3000, ... ?

8.6.1 Fun with Fractals

Recall from Grade 8 another interesting pattern as shown in Fig. 8.7. Stage 0 represents a piece of paper cut in the shape of an equilateral triangle. Let us join the midpoints of the three sides of the triangle leading to four smaller equilateral triangles. Now remove the central triangle. You will get the figure in Stage 1 with a triangular hole in the centre. Repeat the process on all three black triangles in Stage 1. This will lead to the figure in Stage 2. In a similar manner, we arrive at Stage 3 from Stage 2. The process can be continued forever! This fascinating pattern is known as the **Sierpiński triangle**. This is actually a fractal. We will learn more about fractals in a later grade.



Stage 0 Stage 1 Stage 2 Stage 3

Fig. 8.7

Wacław Sierpiński (1882 – 1969) was a Polish mathematician known for his numerous contributions to mathematics, including the Sierpiński gasket, one of the earliest and most famous examples of a fractal.

© NCERT not to be republished

Think and Reflect

Observe the Sierpiński triangle and try to answer the following questions

(a) How many black triangles are there in Stages 0 to 3 of Fig. 8.7?

(b) Can you predict the number of black triangles at Stages 4 and 5?

(c) Can you find a rule for the number of black triangles at the n^{th} stage?

(d) Suppose the area of the triangle (that is, the black region) in Stage 0 is 1 square unit. What is the area of the black region in Stages 1, 2 and 3? What will be the area of the black region in Stages 4 and 5? Find a rule for the area of the black region at the n^{th} stage. What happens to this area as n, the number of stages, goes on increasing?

We observe that the number of black triangles is 1, 3, 9 and 27 in Stages 0, 1, 2 and 3 respectively. In fact, in every stage, each black triangle is replaced with three smaller triangles at the next stage. Thus, the number of black triangles at every stage is three times the number at the previous stage.

At Stages 4 and 5 the number of black triangles will be 81 and 243.

Note that the sequence 1, 3, 9, 27, 81, 243, ... is a GP since every successive term of the sequence can be obtained by multiplying the previous term by 3. Also, all the terms of this sequence are powers of 3: $1 = 3^0$, $3 = 3^1$, $9 = 3^2$ and so on. Continuing in this manner we observe that the exponent of 3 matches the stage number, as shown in Table 1. Thus, the number of black triangles at the n^{th} stage of the Sierpiński triangle is given by 3^n. The number of black triangles increases very quickly as the stage numbers increase. Can you explain why?

What about the area of the black region? In Stage 1, the equilateral triangle at Stage 0 is divided into 4 equal parts and the central part is removed. This means that, if the black region at Stage 0 is 1 square unit, then then the black region at Stage 1 is $\frac{3}{4}$ square units. This process is repeated on Stage 1 to arrive at Stage 2. Hence, the black region at Stage 2 will be $\frac{3}{4}$ of the black region of Stage 1, which is equal to $\frac{3}{4}\times\frac{3}{4}=\left(\frac{3}{4}\right)^2$. Can you explain why the area of the black region at Stage n will be $\left(\frac{3}{4}\right)^n$?

The area of the black region at each stage also leads to a geometric progression where every successive term of the sequence is obtained

© NCERT not to be republished

by multiplying the previous term by $\frac{3}{4}$. Thus, while the number of black triangles increases rapidly, the total area of the triangles decreases.

Table 1

Stage (n)	0	1	2	3	4	5	...	n
Number of black triangles (t_n)	$1 = 3^0$	$3 = 3^1$	$9 = 3^2$	$27 = 3^3$	$81 = 3^4$	$243 = 3^5$	...	3^n
Shaded area (s_n)	1	$\frac{3}{4}$	$\left(\frac{3}{4}\right)^2$	$\left(\frac{3}{4}\right)^3$	$\left(\frac{3}{4}\right)^4$	$\left(\frac{3}{4}\right)^5$	...	$\left(\frac{3}{4}\right)^n$

The explicit formula for the number of black triangles and the area of the black region at any stage is given by $t_n = 3^n$ and $s_n = \left(\frac{3}{4}\right)^n$ respectively. The recursive rules for the same are

$t_1 = 1$, $t_n = 3 \times t_{n-1}$ for $n \geq 2$ and $s_1 = 1$, $s_n = \frac{3}{4} \times s_{n-1}$ for $n \geq 2$.

Fractals are shapes or patterns that repeat themselves at different scales. This means that if you zoom in on a small part of a fractal, it looks similar to the whole! Fractals are found throughout nature—like in the branching of trees, in vegetables, such as cauliflower or broccoli, in the shape of snowflakes, or in the patterns of coastlines. They can be created using simple rules but can form very complex and beautiful designs. Fractals help us understand patterns in nature, and also lead us to important concepts in mathematics.

Fig. 8.8

8.6.2 Visualising a GP

Let us revisit the growing pattern of squares in Fig. 8.6 and prepare a table that shows the number of green squares at each stage.

© NCERT not to be republished

Stage number	1	2	3	4	5	...	n
Number of squares	3	6	12	24	48	...	$3 \times 2^{n-1}$

Let us consider the pairs of numbers (x, y) where x represents the stage number and y the corresponding number of squares. When we plot the ordered pairs emerging from the above table, that is, (1, 3), (2, 6), (3, 12), (4, 24), (5, 48), we observe that they do not lie on a straight line! This is shown in Fig. 8.9.

Similarly, when we plot the pairs of numbers (x, y) where x represents stage number and y the number of black triangles in the Sierpiński triangle we get the graph in Fig. 8.10 A. Fig. 8.10 B shows the graph where stage numbers are represented on the x-axis and the area of the black region of the stages on the y-axis. The graphs tell us that as the stage numbers increase, the number of shaded triangles increases very quickly whereas the area of black region diminishes, getting closer and closer to 0.



Fig. 8.9: Points emerging from a GP do not lie on a straight line

© NCERT not to be republished



(A) (B)

Fig. 8.10: Points emerging from a GP arising out of the stages of the Sierpiński Triangle

Here is another example in which a GP arises.

Example 10: A ball is dropped from a height of 24 feet above the ground. Each time the ball bounces up to $\left(\frac{3}{4}\right)^{\text{th}}$ of its previous height.

(a) Can you write the sequence of numbers obtained from the heights attained by the ball in five successive bounces?

(b) How many bounces are required for the ball to remain below a height of $\frac{1}{6}$ of the original height from which it was dropped?

The sequence of maximum heights attained by the ball after each bounce is:

First bounce: $24 \times 0.75 = 18$ feet

Second bounce: $18 \times 0.75 = 13.5$ feet

Third bounce: $13.5 \times 0.75 = 10.125$ feet

Fourth bounce: $10.125 \times 0.75 = 7.59375$ feet

Fifth bounce: $7.59375 \times 0.75 = 5.695$ feet

Sixth bounce: $5.695 \times 0.75 = 4.27125$ feet

Seventh bounce: $4.27125 \times 0.75 = 3.2034375$ feet

© NCERT not to be republished



Fig. 8.11

The sequence of heights forms a GP with $a = 18$ and $r = 0.75$ (or $\frac{3}{4}$), that is, 18, 13.5, 10.125, 7.594, 5.695, 4.27125, 3.2034375, ... We see that after the seventh bounce the ball remains below $\frac{1}{6}$ of the height at which it started.

Exercise Set 8.3

1. Find the 12^{th} term of a GP with common ratio 2, whose 8^{th} term is 192.
2. Find the 10^{th} and n^{th} terms of the GP: 5, 25, 125, ...

*3. A sequence is given by the recursive rule $t_1 = 2$, $t_{n+1} = 3t_n - 2$ for $n \geq 1$. Which term of the sequence is 730?

4. Which term of the GP: 2, 6, 18, ... is 4374? Write the explicit formula as well as the recursive formula for the n^{th} term.
5. A ball is dropped from a height of 80 metres. After hitting the ground, it bounces back to 60% of the height from which it fell. It continues bouncing in this way — each time rising to 60% of the previous height.
   (i) What height does the ball reach after the 5^{th} bounce?
   (ii) What is the total vertical distance the ball has travelled by the time it hits the ground for the 6^{th} time?

© NCERT not to be republished

6. Which term of the sequence $2, 2\sqrt{2}, 4, \ldots$ is 128?
7. Fig. 8.12 shows Stages 0 to 3 of the Sierpiński square carpet. Stage 0 of this fractal is a square sheet of paper. To construct Stage 1, each side of the square is trisected and the points of trisection of opposite sides are joined to obtain nine smaller squares. The centre square is then removed and the 8 smaller squares are retained, leaving a square hole in the centre. The same process is repeated on the eight smaller shaded squares to obtain Stage 2 and so on.



Fig. 8.12: Stages 0, 1, 2 and 3 of the Sierpiński square carpet

Look at Fig. 8.12 and try to answer the following questions.

(i) How many red squares are there in Stages 0 to 3?

(ii) Can you predict the number of red squares in Stages 4 and 5?

(iii) Can you find a rule for the number of red squares at the n^{th} stage? Write the explicit formula as well as the recursive formula for the number of red squares at any stage.

(iv) Suppose the area of the square in Stage 0 is 1 square unit. What is the area of the red region in Stages 1, 2 and 3? What will be the area of the red region in Stages 4 and 5? Find the explicit as well as the recursive formula for the area of the red region at the n^{th} stage. What happens to this area as n, the number of stages, goes on increasing?

End-of-Chapter Exercises

1. Find the 31^{st} term of an AP whose 11^{th} term is 38 and 16^{th} term is 73.
2. Determine the AP whose third term is 16 and whose 7^{th} term exceeds the 5^{th} term by 12.

© NCERT not to be republished

*3. How many three-digit numbers are divisible by 7? (**Hint:** All three-digit numbers divisible by 7 form an AP. Find the smallest and largest such three-digit numbers.)

*4. How many multiples of 4 lie between 10 and 250? (**Hint:** All multiples of 4 form an AP. Find the smallest and largest multiples of 4 between 10 and 250.)

*5. Find a GP for which the sum of the first two terms is –4 and the fifth term is 4 times the third term.

*6. Find all possible ways of expressing 100 as the sum of consecutive natural numbers.

*7. The number of bacteria in a certain culture doubles every hour. If there were 30 bacteria present in the culture originally, how many bacteria will be present at the end of the 2^{nd} hour, 4^{th} hour and n^{th} hour?

*8. The sum of the 4^{th} and 8^{th} terms of an AP is 24 and the sum of the 6^{th} and 10^{th} terms is 44. Find the first three terms of the AP.

*9. Find the smallest value of n such that the sum of the first n natural numbers is greater than 1,000.

*10. Which term of the GP: 2, 8, 32, ... is 131072? Write the explicit formula as well as the recursive formula for the n^{th} term.

*11. The sum of the first three terms of a GP is $\frac{13}{12}$ and their product is –1. Find the common ratio and the terms.

*12. If the 4^{th}, 10^{th} and 16^{th} terms of a GP are x, y and z respectively, prove that x, y, z are in GP.

*13. The sum of the first three terms of a geometric progression is 26, and the sum of their squares is 364. Find the terms of the GP.

*14. Suppose $P_1 = 1$, $P_2 = 2$ and for $n > 2$, $P_n = P_1 + P_2 + \cdots + P_{n-1} + 1$. Find the values of $P_1, P_2, \ldots, P_8$. Can you find a simpler recursive formula for P_n? Can you give an explicit formula?

*15. Suppose $W_1 = 1$, $W_2 = 2$ and for $n > 2$, $W_n = W_1 + W_2 + \cdots + W_{n-2} + 2$. Find the values of $W_1, W_2, \ldots, W_8$. Do you recognise this sequence?

© NCERT not to be republished

Chapter Summary

- A **sequence** is an ordered list of numbers. Each number in the list is called a term.
- A **general formula** or rule for a sequence is a rule that can be used to generate each term. An **explicit formula** is a rule that uses the term's position number, n, to calculate the term's value.
- A **recursive formula** is a rule that gives the value of a given term using the values of previous terms.
- The **triangular number sequence** is given by 1, 3, 6, 10, 15, ... Each term is the sum of the natural numbers up to the position of that term. The n^{th} term is given by $t_n = \frac{n(n+1)}{2}$ which is also the formula for the sum of the first n natural numbers.
- An **arithmetic progression** (AP) is a list of numbers in which each term after the first term is obtained by adding a fixed number d to the previous term. The fixed number d is called the **common difference**.
- The n^{th} term of an AP is given by $t_n = a + (n-1)\,d$, where a is the first term and d is the common difference. The general form of an AP is $a, a+d, a+2d, a+3d, \ldots, a+(n-1)\,d$.
- A **geometric progression** (GP) is a list of numbers in which each term after the first term is obtained by multiplying the previous term by a fixed number. This constant factor r is called the **common ratio**.
- The n^{th} term of a GP is given by $t_n = ar^{n-1}$, where 'a' is the first term and 'r' is the common ratio. The general form of a GP is $a, ar, ar^2, ar^3, \ldots, ar^{n-1}$.
- Many attributes of fractals, such as the Sierpiński triangle and the Sierpiński square carpet, lead to geometric progressions.

© NCERT not to be republished

Graph Paper



© NCERT not to be republished

Graph Paper



© NCERT not to be republished

Graph Paper



© NCERT not to be republished

Graph Paper



© NCERT not to be republished

9 Propositions and their Converses

0905CH09

Consider the following statement:

Statement 1: *If two sides of a triangle are equal, then the angles opposite the equal sides are equal.*

Such a statement that is either true or false is called a **proposition**.

Now consider the following proposition:

Statement 2: *If two angles of a triangle are equal, then the sides opposite the equal angles have equal lengths.*

The first proposition is of the form 'if X then Y'. The second is of the form 'if Y then X'. We say that the second proposition is the **converse** of the first proposition.

The statement 'if X then Y' is also written as 'X **implies** Y'. We will use both formulations interchangeably.

If a proposition is true, then is its converse always true?

Think and Reflect

We have proved the first statement in an earlier grade. Is the second statement true? Can you prove it?

(**Hint:** Draw the altitude from the vertex containing the third angle.)

Let us consider some examples of propositions and their converses,

Example 1:

- Proposition P: If it rains, then the road is wet.
- Converse Q: If the road is wet, then it has rained.

Proposition P is true but its converse, Q, may not be true. For instance, the road may be wet because a tanker spilled water on the road!

A situation that illustrates why a given proposition is not necessarily true is called a **counterexample**. It refers to an example that contradicts the stated proposition.

© NCERT not to be republished

Finding a suitable counterexample is an important ingredient of mathematics because it allows us to show in a short and convincing way that a proposition is false.

Here is a famous example. Fermat claimed that all numbers of the form $2^{2^n} + 1$ are prime ($n = 0, 1, 2, 3, \ldots$); e.g., the number $2^{2^3} + 1 = 257$. But Euler disproved this by showing that the number $2^{2^5} + 1$ is composite.

Example 2:

- Proposition P: If a number is a multiple of 6, then it is a multiple of 3.
- Converse Q: If a number is a multiple of 3, then it is a multiple of 6.

Proposition P is true. Justify why this is so.

Does this now mean that all multiples of 3 are also multiples of 6? This corresponds to the converse statement Q. Determine if it is true and if not, give a counterexample.

Example 3: In this example, n is any positive integer.

- Proposition P: If n is a perfect square, then it has an odd number of factors.
- Converse Q: If n has an odd number of factors, then it is a perfect square.

You may recall that we came across these statements in the previous grade. Which of them are true?

Discussion

Consider the following argument.

> Each factor of a number has a 'partner' factor such that their product yields the given number, e.g., 5 is a factor of 35, and $5 \times 7 = 35$. Here, 7 is the partner factor of 5, and vice-versa. Let us focus on factor-partner pairs of numbers, e.g., (1, 12), (2, 6), (3, 4) are the pairs for the number 12.
>
> If a number has an odd number of factors, there must be a factor-partner pair in which the same number repeats (e.g., the partner factor of 5 in 25). If not, the given number will have an even number of factors since each factor can be paired with its factor pair.
>
> Thus, if a number has an odd number of factors, then it is a perfect square.

What does this argument prove? Statement P or Q?

© NCERT not to be republished

To clearly understand this, let us reframe the argument as follows —

(i) n has an odd number of factors

which implies

(ii) the existence of a factor-partner pair in which the same number repeats, say (f, f)

which implies

(iii) n is a square number: $n = f \times f$

This only proves Q. It doesn't prove that every square number has an odd number of factors (Proposition P).

Is P true?

It is. The argument above can be modified to prove this.

We start with (iii). Clearly, (iii) implies (ii). Does (ii) imply (i)? Not necessarily because (ii) does not state the number of pairs with repeating factors. For example, if the number of such pairs is two — say (f, f) and (g, g) — what can we say about the number of factors? In such a case, the given number will have an even number of factors.

However, a number cannot have more than one factor pair with repeating factors. Thus, a square number necessarily has an odd number of factors. Hence Statement P is also true.

In this example, 'n is a perfect square' and 'n has an odd number of factors' imply each other.

Example 4:

- Proposition P: If two triangles have the same area, then they are congruent.
- Converse Q: If two triangles are congruent, then they have the same area.

Determine if these statements are true or not. Justify the true statements and give a counterexample for each false statement.

These examples show that a proposition can be true but not its converse. Or it can happen that both the proposition and its converse are true.

Think and Reflect

It can also happen that both the proposition and converse are false! Can you give an example?

© NCERT not to be republished

Example 5: Here is a statement of the Baudhāyana–Pythagoras theorem.

Let a, b, c be the sidelengths of a triangle. If the triangle is right-angled, then $a^2 + b^2 = c^2$.

What is its converse?

To write the converse, we keep the first sentence of the Baudhāyana–Pythagoras theorem as it is, and make the necessary change in the second.

Let a, b, c be the sidelengths of a triangle. If $a^2 + b^2 = c^2$, then the triangle is right-angled.

Is this converse true?

Let ΔABC be the triangle with sidelengths a, b, c such that $a^2 + b^2 = c^2$.



Construct another right triangle ΔXYZ whose perpendicular sides YZ and XZ have sidelengths a and b.



What can we say about the length of XY?

(**Hint:** Use the Baudhāyana–Pythagoras Theorem.)

What can we say about ΔABC and ΔXYZ?

(**Hint:** Use the SSS criterian for congruence.)

We conclude that ΔABC had to be a right triangle after all.

Hence the converse of the Baudhāyana–Pythagoras Theorem is also true!

© NCERT not to be republished

A Note

We have seen that 'If X then Y' can also be written as 'X implies Y'. These are not the only ways to express this meaning. It can be conveyed through other words and sentence structures as well. For example, 'Y when X' also gives the same meaning. The following two statements, for instance, have the same meaning.

Proposition: If a number is a perfect square, then it has an odd number of factors.

Proposition: A number has an odd number of factors when it is a perfect square.

Think and Reflect

1. Identify real-life examples in which a proposition is true but not the converse. Give nice counterexamples!
2. Give more examples from geometry as well as number theory in which a proposition is true but not its converse. Give appropriate counterexamples.

Exercise Set 9.1

Frame the converse for each of the propositions in Questions 1–12. Then, determine if each of the two statements is true or not. Justify the true statements and give a counterexample for each false statement.

1. If two lines are parallel, then the corresponding angles formed by a transversal are equal.
2. If a quadrilateral is a square, then all its angles are equal.

*3. Given any ΔABC, let us bisect the angles at B and C. The bisectors meet at the incentre I of the triangle.

Now extend the bisectors beyond I till they meet the opposite sides at E and F respectively, as shown.

Proposition: If AB = AC, then IE = IF.



Fig. 9.1

© NCERT not to be republished

4. If $x = y$, then $a + x = a + y$, where x, y and a are any three numbers.

   This proposition and its converse are routinely used while solving equations.

5. If a and b are perfect squares, then ab is a perfect square.

In Questions 6 and 7, x and y are real numbers.

6. If $x = y$, then $x^2 = y^2$.
7. If $x = y$, then $x^3 = y^3$.

In Questions 8–12, n is a positive integer.

8. If n is divisible by 24, then it is divisible by both 4 and 6.
9. If n is divisible by 60, then it is divisible by both 5 and 12.
10. If n is the square of a prime number, then it has exactly 3 factors.
11. If n is a product of two unequal prime numbers, then it has exactly 4 divisors.
12. If n and $n + 3$ have no factors in common, then n is not a multiple of 3.
13. There are no known 'neat' expressions that generate only primes! Find counterexamples to the following claims.
    (i) All numbers of the form $4n^2 + 1$ are prime.
    (ii) All numbers of the form $n^2 + n + 11$ are prime.
    (iii) All numbers of the form $4^n + 3$ are prime.
14. Find counterexamples to the following statements.
    (i) If n is a prime number, then $2^n - 1$ is a prime number.
    (ii) If n is an even number, then $2^n + 1$ is a prime number.
15. Consider the statement: 'If a number is divisible by 8, then it is divisible by both 2 and 4'.
    (i) Justify the statement.
    (ii) Recall the divisibility shortcuts that we have studied for different numbers. To check whether a given number is divisible by 8, is it enough to check whether it is divisible by 2 and 4? Why or why not?
16. Recall that a shortcut to check whether a given number is divisible by 3 is to add the digits of the number and check if the sum is a multiple of 3. Express the relationship between 'a number is divisible by 3' and 'sum of the digits is a multiple of 3' using 'If-then' sentences.

© NCERT not to be republished

17. We have identified different types of quadrilaterals — squares, rectangles, parallelograms, rhombi, kites and trapezia. One can identify more types (e.g., we could create a category of quadrilaterals that have equal-length opposite sides).

Suppose we have identified a category of quadrilaterals called Q, and we have to construct a quadrilateral of this type. For this, we are to use two thin sticks, put them together as diagonals so that the quadrilateral obtained by joining their endpoints is of type Q (see the Fig. 9.2).



Fig. 9.2

(i) Suppose Q satisfies the following property.
If a quadrilateral is of type Q, then it has equal-length diagonals.
   (a) Should the two sticks be of equal length? Why or why not?
   (b) Will it matter how the two sticks are put together?

(ii) Instead of the property mentioned above, suppose Q satisfies the following property.
If a quadrilateral has equal diagonals, then it is of type Q.
What will be your answers to (*a*) and (b) now?

Chapter Summary

- A **proposition** is a statement that is true or false.
- The **converse** of the proposition 'if P then Q' is the proposition 'if Q then P'.
- It can happen that a proposition is true while its converse is false. It can also happen that both the proposition and its converse are true, or both are false.
- **Counterexamples** are instances that demonstrate the falsity of a given proposition.

© NCERT not to be republished

10 How Quantities Combine: Understanding Data

0905CH10

10.1 Combining Things

In earlier grades, we looked at how the average conveys the 'centre' of given data. In this chapter, we shall extend the concept of average to a more general setting called 'weighted average'.

10.1.1 Average of Averages

Example 1: In a badminton academy, there is a group of 11 trainees — 8 seniors and 3 juniors. Their heights and average heights (in cm) are given in the table below. Find the average height of the whole group.

	Heights (in cm)	Average Height (in cm)
Seniors	165, 169, 164, 167, 170, 159, 164, 166	165.5
Juniors	146, 149, 153	149.33

Two students calculate the average height of the whole group in two ways:

Method 1

$$\frac{165.5 + 149.33}{2}$$

$$= \frac{314.83}{2}$$

$$= 157.415$$

Method 2

$$\frac{165 + 169 + 164 + 167 + 170 + 159 + 164 + 166 + 146 + 149 + 153}{11}$$

$$= \frac{1772}{11} = 161.09$$

Whose calculation gives the correct average height of the whole group?

The average height of the whole group is the sum of the heights of all eleven members divided by 11, as in Method 2.

Think and Reflect

Why did Method 1 not work?

© NCERT not to be republished

Method 1 does not work because it treats the average heights of seniors and of juniors equally — but there are many more seniors than juniors!

Shreyas calculated it differently as

$$\frac{(165.5 \times 8) + (149.33 \times 3)}{8 + 3}$$

$$= \frac{1324 + 448}{11} = \frac{1772}{11}$$

$$= 161.09.$$

Do you understand why this also works?

Can you see why 165.5×8 gives the sum of the heights of all the seniors and 149.33×3 gives the sum of the heights of all the juniors?

This phenomenon is explained below with a generalisation. Suppose we have two collections of data — Collection 1 and Collection 2.

Suppose the data in Collection 1, having n values, is $x_1, x_2, x_3, \ldots, x_n$.

The average of Collection 1 is

$$\frac{x_1 + x_2 + x_3 + \cdots + x_n}{n} = a.$$

Thus the sum of the data in Collection 1 is

$$x_1 + x_2 + x_3 + \cdots + x_n = an.$$

Suppose the data in Collection 2, having m values, is $y_1, y_2, y_3, \ldots, y_m$.

The average of Collection 2 is

$$\frac{y_1 + y_2 + y_3 + \cdots + y_m}{m} = b.$$

Thus the sum of the data in Collection 2 is

$$y_1 + y_2 + y_3 + \cdots + y_m = bm.$$

The average of the combined data is therefore

$$\frac{(\textit{Sum of values in Collection } 1) + (\textit{Sum of values in Collection } 2)}{(\textit{Number of values in Collection } 1) + (\textit{Number of values in Collection } 2)}$$

$$= \frac{an + bm}{n + m}.$$

Example 2: Jaspreet recently learnt cycling. She has explored different routes in her town. She tracked how much time she cycled on weekdays over the last 3 weeks. Find the mean time spent cycling per weekday over the last 3 weeks.

© NCERT not to be republished

Table 10.1: Time spent cycling, in minutes, by Jaspreet

	Day 1	Day 2	Day 3	Day 4	Day 5	Weekly Average
Week 1	10	13	10	15	16	12.8
Week 2	14	10	20	17	18	15.8
Week 3	15	18	14	20	23	18

Two ways of calculating this are given here.

Method 1

$$\frac{(12.8 + 15.8 + 18)}{3}$$
$$= \frac{46.63}{3}$$
$$= 15.53$$

Method 2

$$\frac{(12.8 \times 5) + (15.8 \times 5) + (18 \times 5)}{5 + 5 + 5}$$
$$= \frac{(64 + 79 + 90)}{15}$$
$$= 15.53$$

The average time spent cycling by Jaspreet on weekdays is 15.53 minutes.

We saw earlier how Method 1 (badminton example) did not produce the correct value. Why does Method 1 give the correct answer in this case? When does Method 1 work and when does it not work? Let us find out.

In general, the average of data in three collections is given as

$$\frac{(\textit{Sum of values in Collection } 1) + (\textit{Sum of values in Collection } 2) + (\textit{Sum of values in Collection } 3)}{(\textit{No. of values in Collection } 1) + (\textit{No. of values in Collection } 2) + (\textit{No. of values in Collection } 3)}$$
$$= \frac{ap + bq + cr}{p + q + r},$$

where a, b, c are the averages of each collection, and p, q, r are the sizes of the respective collections.

In the cycling scenario, Jaspreet cycled 5 days every week for 3 weeks. This means that all three collections are of the same size, that is 5. Thus, in the general form, the average becomes,

$$\frac{ap + bp + cp}{p + p + p} \text{ (where } p \text{ is the size of the collections)}$$
$$= \frac{(a + b + c)p}{3p} = \frac{a + b + c}{3}.$$

This is the same as adding the 3 weekly averages and dividing the sum by 3. Here, each week has 5 days, so each average comes from the same number of days; that is why treating each week's average equally works. If the weeks had different numbers of cycling days, this method would no longer be correct.

We see that when the sizes of the collections are the same, to find the average of the combined collection, we can add the averages of the collections and divide the sum by the number of collections.

© NCERT not to be republished

10.1.2 Mixtures

Let us consider what happens when things are mixed.

Example 3: Two glasses of equal quantities of lemonade are prepared. One glass has 10% jaggery and the other has 20% jaggery. If we mix the lemonade from both glasses, what is the concentration of jaggery in the mixture?

Since both the glasses contain equal amounts of lemonade, the mixture will have 15% jaggery. We can also arrive at this mathematically—

Suppose y is the quantity of lemonade in each glass.

The concentration of jaggery in the mixture is

$$\frac{\textit{quantity of jaggery in the mixture}}{\textit{quantity of the mixture}}$$

$$= \frac{\frac{10}{100}y + \frac{20}{100}y}{y + y}$$

$$= \frac{0.1y + 0.2y}{y + y} = \frac{0.3y}{2y} = 0.15.$$

Since the glasses had equal quantities of lemonade, the concentration of jaggery in the combined mixture is midway between the concentrations of jaggery in the individual glasses. This is similar to the cycling example, where all weeks had equal numbers of days.

Example 4: A bowl of 500 mL lemonade has 10% jaggery. A glass of 200 mL lemonade has 20% jaggery. If we mix the lemonade from the bowl and the glass, what is the concentration of jaggery in the mixture?

Can you estimate what part of the mixture is jaggery? Is it 15%, or is it more or less? Why do you think so?

Since the bowl has a larger quantity of lemonade, the concentration of jaggery in the mixture will be closer to 10% (less than midway).

The concentration of jaggery in the mixture is given by

$$\frac{\textit{quantity of jaggery in the mixture}}{\textit{quantity of the mixture}}$$

$$= \frac{500 \times 0.1 + 200 \times 0.2}{500 + 200}$$

$$= \frac{50 + 40}{700} = \frac{90}{700} \approx 0.13.$$

© NCERT not to be republished

Notice that the final concentration is not the simple average of 10% and 20%. It is closer to 10% because the larger quantity of lemonade comes from the 10% mixture. In general, each concentration influences the final concentration according to the quantity of mixture it contributes.

Example 5: Brass is an alloy of copper and zinc. Batch A of brass weighs 200 kg of which 70% is copper. Batch B weighs 120 kg of which 50% is copper. Batch C is 45% copper. When all three batches are combined, we get an alloy that is 55% copper. What is the weight of Batch C?

The concentration of copper in the mixture is given by

$$\frac{\textit{quantity of copper in the mixture}}{\textit{quantity of the mixture}}.$$

Suppose y is the weight (in kg) of Batch C. From the given information, we know that

$$0.55 = \frac{(\textit{Quantity of copper in Batch A + Quantity of copper in Batch B + Quantity of copper in Batch C})}{\textit{Total weight of brass in all batches}}$$

$$0.55 = \frac{200 \times 0.7 + 120 \times 0.5 + y \times 0.45}{200 + 120 + y}$$

$$0.55\,(320 + y) = 200 + 0.45y.$$

$$y = 240.$$

Batch C weighs 240 kg.

More generally, if n things with concentrations $x_1, x_2, x_3, \ldots, x_n$ and respective volumes/weights $w_1, w_2, w_3, \ldots, w_n$ are mixed, the concentration of the mixture is given by

$$x = \frac{w_1x_1 + w_2x_2 + w_3x_3 + \cdots + w_nx_n}{w_1 + w_2 + w_3 + \cdots + w_n}.$$

Such an average is called the **weighted mean** or **weighted average**. Here, the prefix 'weighted' does not refer to actual weights but abstract weights; however, in some cases, these can be actual weights. That is, the weighted mean is an average where each value is weighted (multiplied) by how important or how big it is. We shall study other contexts where the weighted average is used.

The above formula for the weighted mean was written down by Brahmagupta in his work Brāhmasphuṭasiddhānta (c. 628 CE). He used the formula to define the mean depth x of an irregularly-shaped pit. If the pit has depth measurement x_1 for length w_1, depth measurement x_2 for length w_2, ... and depth measurement x_n for length w_n, then the mean depth x is given by the above formula.

© NCERT not to be republished

The concept of weighted arithmetic mean was also used by Indian mathematicians like Śrīdharācārya (c. 750 CE) to estimate the purity of gold-alloys (essentially today's karat calculations).

The concept of the weighted mean eventually appeared in other parts of the world, e.g., Europe, where it gained prominence by the 1700s. The weighted mean now plays a crucial role across mathematics and statistics, allowing us to combine data of different sizes or importance into one number to give an overall accurate picture.

Exercise Set 10.1

1. The average score of students on a test in Section A is 72 and that of students in Section B is 76. What is the combined average of both the sections given that Section A has 30 students and Section B has 25 students?
2. A farmer mixes three equal quantities of fertilisers. The first one contains $\frac{1}{10}$ nitrogen, the second contains $\frac{9}{50}$ nitrogen, and the third contains $\frac{3}{60}$ nitrogen. What is the fraction of nitrogen in the mixture?
3. (Śrīdharācārya, Pāṭīgaṇita, c. 750 CE) In ancient India, Varṇa was the measure of gold purity. A purity of 16 varṇa meant pure gold; in general, a purity of k varṇa meant that the gold-alloy was k/16 gold and the rest impurities. (Now the term used is karat; 16 Varna = 24 karat.)

   Suppose a goldsmith melts together three pieces of gold: 9 units at 12 varṇa, 5 units at 10 varṇa, and 17 units at 11 varṇa. Find the purity in varṇa of the combined gold.
4. The average rainfall per day in the months of May, June, and July in a certain location are 3.5 mm, 10 mm and 8.7 mm respectively. Write an expression that gives their combined average.
5. Calculate the concentration of spice mix in these two scenarios.
   (i) A 100 mL *kashayam/kadha* with 5% spice mix, a 200 mL one with 10% spice mix, and a 300 mL one with 15% spice mix are combined.
   (ii) A 300 mL *kashayam/kadha* with 5% spice mix, a 200 mL one with 10% spice mix, and a 100 mL one with 15% spice mix are mixed.

10.1.3 Custom Weights

The weighted mean is also used whenever parts of data require different levels of importance or weightage. Let us look at an example.

© NCERT not to be republished

Example 6: Rehmat's marks in Maths are as follows: 60% in internal tests, 64% in the project, 73% in the final exam. The annual percentage score is calculated by combining the internals, project, and final exam in the ratio 3 : 2 : 5. What is Rehmat's annual score in Maths?

Suppose all modes of assessment had an equal weightage. Then the annual score can be obtained by calculating the arithmetic mean of 60%, 64%, and 73%, which is $\frac{60 + 64 + 73}{3} = 65.6\%$.

The given ratio 3 : 2 : 5 indicates the relative weightage and importance that each form of evaluation gets. The data with these relative weights is equivalent to 60, 60, 60, 64, 64, 73, 73, 73, 73, 73. The arithmetic mean is given by $\frac{60 \times 3 + 64 \times 2 + 73 \times 5}{10} = 67.3\%$.

This can also be expressed as a weighted mean of 60%, 64%, 73% with weights 3, 2, 5 respectively:

$$\frac{\left(\frac{60}{100}\right) \times 3 + \left(\frac{64}{100}\right) \times 2 + \left(\frac{73}{100}\right) \times 5}{3 + 2 + 5} = \frac{\left(\frac{673}{100}\right)}{10} = 67.3\%.$$

The weights assigned to the values in any data indicate the relative importance/emphasis that each value gets with respect to the others.

Exercise Set 10.2

1. Savitri's marks in Kashmiri are as follows: 35 out of 50 in internal tests, 44 out of 60 in the project, and 80 out of 100 in the final exam. The annual percentage score is calculated by combining the internals, project, and final exam in the ratio 3 : 4 : 5. Which of the following expression(s) gives her annual score (as a percentage) in Kashmiri?

   (i) $\frac{35 \times 3 + 44 \times 4 + 80 \times 5}{3 + 4 + 5}$

   (ii) $\frac{\left(\frac{35}{100}\right) \times 3 + \left(\frac{44}{100}\right) \times 4 + \left(\frac{80}{100}\right) \times 5}{3 + 4 + 5}$

   (iii) $\frac{\left(\frac{35}{50}\right) \times 3 + \left(\frac{44}{60}\right) \times 4 + \left(\frac{80}{100}\right) \times 5}{3 + 4 + 5} \times 100$

© NCERT not to be republished

(iv) $$\frac{\left(\frac{35}{50} \times 100\right) \times 3 + \left(\frac{44}{60} \times 100\right) \times 4 + \left(\frac{80}{100} \times 100\right) \times 5}{3 + 4 + 5}$$

Here are a few more situations where the concept of weighted mean is relevant:

1. **Ratings of a hotel/eatery:** The experience of eating at a restaurant is influenced not only by the taste or quality of the food but also by the ambience and the service provided. Every customer is asked to rate each of these aspects. The customer's combined rating is determined by the relative weights assigned to food, service, and ambience. Suppose one of the customers has given a rating as shown in the picture. Suppose the weights assigned to food, service, and ambience are 4 : 3 : 2 respectively. The user's rating for the restaurant is $\frac{5 \times 4 + 3 \times 3 + 4 \times 2}{4 + 3 + 2} = 4.11$.

2. **Ratings of a product:** A store makes and sells portable furniture. The store owners make changes to their products regularly. To calculate the store's average rating, it makes sense for them to give their current products more weight than older products. For example, they may choose to assign twice the weightage to customer reviews in the last 3 months compared to older reviews.

We use weighted mean whenever we want the combined result to reflect how much each part contributes to the whole — by amount, time, or importance — rather than just counting each part equally.

Exercise Set 10.3

1. A stationery shop owner made ₹8000 selling books, of which 30% is the profit amount, and ₹1000 selling book covers, of which 50% is the profit amount. What is the percentage of profit on the total sales?
2. A white stork's migration is tracked. The average daily distance travelled, calculated over 20 days, is 44.5 km. On the 21st day, it flew 55 km. What is the average daily distance travelled over these 21 days? Make a guess before you calculate.

© NCERT not to be republished

3. A 600 mL solution with 5% salt is mixed with a 300 mL solution with 8% sugar. What are the concentrations of salt and sugar in the mixture?

   (i) Salt: 5%, Sugar: 8%
   (ii) Salt: 13%, Sugar: 3%
   (iii) Salt: 6%, Sugar: 6%
   (iv) Salt: 5.55%, Sugar: 8.88%
   (v) Salt: 3.33%, Sugar: 2.67%
   (vi) Salt: 4.1%, Sugar: 7.08%

4. At a *panipuri* (*golgappa*) stall, the concentration of spice in the *pani* (spiced water) was 8%. Many customers complained that it was too spicy. What quantity of regular water should be mixed into the 10 litres of *pani* so that the spice level is reduced to $\left(\frac{3}{4}\right)^{\text{th}}$ of the original concentration?

5. A physical fitness evaluation is being undertaken. The final marks are calculated by combining the marks for strength, flexibility, and agility in the ratio 4 : 5 : 6. Rashi has scored 60, 65, and 70. Keerthi has scored 55, 65, and 75 respectively.
   (i) Find out whose total is more without calculating.
   (ii) What are their final marks?

6. A restaurant collected ratings from 10 customers on a scale of 1 to 5. The resulting data is shown in the table below.

	5★	4★	3★	2★	1★
Food	5	3	2	0	0
Ambience	0	4	5	1	0
Service	1	2	2	4	1

   What is the average rating if the metrics are combined with the weights food : ambience : service = 6 : 5 : 4?

7. The following table shows the weight data of langurs in an animal facility. Without doing any computations, can you tell

© NCERT not to be republished

whether there are more male langurs or more female langurs? Or are they equal in number?

	Male langurs	**Female langurs**	**All langurs**
Average weight	16.5 kg	13.8 kg	14.925 kg
Number of langurs			60

(i) Which of the following expression(s) describes the given scenario?

(a) $\frac{16.5x + 13.8y}{x + y} = 14.925$

(b) $\frac{16.5x + 13.8y}{60} = -14.925$

(c) $\frac{16.5x + 13.8y}{2} = -14.925$

(d) $\frac{16.5x + 13.8y}{16.5 + 13.8} = -14.925$

(ii) Find out how many male langurs are present.

(iii) A female langur weighing 15.2 kg is admitted to the facility. What is the average weight of the female langurs after this?

(iv) Two male langurs weighing 16.9 kg and 16.1 kg are released from the facility. What is the average weight of the male langurs after this?

(v) Now, suppose one of the male langurs lost 1 kg of weight. What is the average weight of all the male langurs after this?

8. Dorjee has collected 1 litre of water from the Dead Sea! Using the information in the table, answer the following questions. A calculator can be used if necessary.

© NCERT not to be republished

Water Source	Salinity
Dead Sea	≈ 34%
Other seas and oceans	≈ 3.5%
Ground water	≈ 0.01%
Purified drinking water	≈ 0.001%

(i) What is the salinity of the mixture if he mixes 1 litre of water from the Dead Sea with 2 litres of purified drinking water?

(ii) Is it possible to mix water from the Dead Sea and purified drinking water to get a mixture with the salinity of groundwater? Why/Why not? What quantity of purified drinking water should Dorjee mix with 1 litre of water from the Dead Sea to get a mixture having the salinity of groundwater?

(iii) Is it possible to mix water from the Dead Sea and groundwater to get a mixture with the salinity of purified drinking water? Why/Why not? What quantity of groundwater should he mix with 1 litre of water from the Dead Sea to get a mixture having the salinity of purified drinking water?

10.2 Visualising and Interpreting Data

10.2.1 Stacking Columns

The following table shows the average weekly expenditure, in rupees (₹), of three families across categories. What would a cluster-column chart for this data look like?

Table 10.2

	Housing	Food	Education	Transportation	Healthcare	Recreation
Family A	1940	1700	1280	1200	1770	535
Family B	1750	1546	1500	1280	1210	0
Family C	950	1700	1540	1400	1300	150

© NCERT not to be republished

There are two possibilities depending on the choice of the cluster; the clusters can be categories or families:



Fig. 10.1: Two cluster-column graphs showing different ways of visualising the data in Table 10.2

Answer the following questions based on the charts above. Try to answer each question by looking at Choice 1 first, and then Choice 2. Which was easier?

1. Which family spent the least on housing?
2. Which family spent the most on healthcare?
3. Approximately how much did Family A spend on education?
4. Which category did Family B spend most on?
5. Did Family A spend more on food or on healthcare?

You may have found Choice 1 more suitable to answer Questions 1 and 2, and Choice 2 more suitable to answer Questions 4 and 5.

The choice of the cluster-column chart depends on what the primary focus is — comparing different families' expenditures in each category (Choice 1) or comparing category-wise expenditures within each family (Choice 2).

Find the answers to the following questions.

6. Which family spent the least amount overall?
7. Approximately how much did Family C spend overall?

© NCERT not to be republished

8. Approximately what percentage of Family C's expenses were on housing?

Was it as straightforward to answer these questions as the earlier questions?

Is there a visualisation that makes it simpler to answer such questions?

Look at the following visualisation of the same data. Try to understand how the chart is organised and answer the three questions above.



Fig. 10.2: A Stacked Bar Chart of the data in Table 10.2

Such a graph/chart is called a **stacked bar or column chart**. Bars within a cluster are joined one after the other in a particular order. **Stacked bar charts are used when we want to compare the totals but also want to keep track of the components that make up the totals.** Here, the total length of a full stacked (combined) bar represents the total expenditure of a family in that month. Also, the length of a smaller bar and the full stacked bar can be compared to get an estimate of what fraction or percentage the smaller bar makes up of the full stacked bar.

Now, use the stacked bar chart to answer the Questions 1–5 shown earlier.

Is it possible? Is it easy? If not, what made it harder than before?

Except for the first small bar, the rest of the stacked small bars do not begin from 0. This makes it a little harder to estimate the quantity corresponding to a bar. Also, bars across clusters need not have a common base or a starting point. So, comparing bars within clusters and across clusters may be harder. However, seeing the totals of all the clusters is easier.

© NCERT not to be republished

Exercise Set 10.4

1. The following stacked column chart shows the number of animal species in the IUCN Red List, by class, over time.



The International Union for Conservation of Nature (IUCN) Red List is a large, regularly-updated database that tells us the extinction risk of species across the world. It classifies species into groups such as Least Concern, Vulnerable, Endangered, Critically Endangered, Extinct in the Wild and Extinct, based on scientific data about their numbers, trends and habitats.

(i) What does the number 14,234 on the top of the column 2019 represent?

(ii) Approximately how many reptile species were in the list in 2016?

(iii) Which class(es) of species have seen a relatively small increase in count between 2007 and 2019?

2.

	Test	ODI	T20
Home	62	100	32
Overseas	172	49	71

The wickets taken by a bowler in International Cricket matches till 2025 are shown in the table. Complete the given stacked bar charts (the bar lengths can be approximate),

© NCERT not to be republished

(i) comparing the total wickets taken at home vs. overseas:



(ii) The total wickets taken in each format:



10.2.2 An Alternative to Pie Chart

Try answering the following question based on the expenditure stacked bar chart you saw earlier:

Which family has the smallest share of their total expenditure towards healthcare?

Was it easy?

If not, what visualisation can help answer such questions easily?

Last year, we learnt how pie charts can capture proportions of quantities. Let us visualise this data through pie charts:



Fig. 10.3: Pie charts of data of each family in Table 10.2

Now, consider the following visualisation showing proportions for the same data:

© NCERT not to be republished



Fig. 10.4: A 100% stacked bar chart of data in Table 10.2

Here, the total expenditure of each of the three families is shown by a stacked bar of a fixed length. The lengths of the smaller bars in each stacked bar are proportional to the corresponding expenditures of that family. Such a chart is called a **100% stacked bar chart**. It is similar to a pie chart — the complete angle in a pie chart is split proportionately based on the quantities, whereas here, a fixed length is split proportionately.

In pie charts, comparing angles in different orientations may be difficult. It may be easier to compare lengths across stacked bars. However, even in 100% stacked bar charts, if the lengths of a particular bar are similar across the stacked bars but the location is different, comparison may be difficult, as in the chart above.

Powering Up!

Example 7: The average category-wise daily electricity consumption of a house, in kWh, in 2005 and 2025 is shown in the table below. The corresponding stacked bar chart is also shown.

	Lighting	Cooling	Kitchen appliances	Other appliances
2005	360	300	120	220
2025	220	800	460	520



© NCERT not to be republished

Make the corresponding 100% stacked bar chart.

In 2005, the total unit consumption was 360 + 300 + 120 + 220 = 1000 units.

The percentage share of lighting in this was $\frac{360}{1000} \times 100 = 36\%$.

Similarly, the percentage share of cooling, kitchen appliances, and other appliances was 30%, 12%, and 22% respectively.

The calculation for the year 2025 can be done in the same way.



What do you observe? What do you find interesting in the data/graphs? Discuss with others.

What Can We Infer?

Example 8: The 100% stacked bar below compares the proportion of flowers blooming in Fatima's garden and Naveen's garden across seasons.



Which of the following statements can be inferred from this chart?

(i) In Fatima's garden, there were more blooms in the summer than in the monsoon.

(ii) In summer, Fatima's garden had more blooms than Naveen's garden.

(iii) In winter, Fatima's garden had fewer blooms than Naveen's garden.

(iv) The total number of flowers, across seasons, is the same in both gardens but it varies in each season.

(**Hint:** Find out the blooms per season in each garden if both the gardens had the same total number of blooms over the year. Similarly find out what happens if the totals are very different.)

© NCERT not to be republished

What does the 100% stacked bar tell us?

In each garden, the total number of flowers for the whole year is shown as one bar and is taken as 100%. The colours show what fraction of that total bloomed in each season. So for Fatima's garden, the bar tells us: 50% of her flowers bloomed in summer, 30% in monsoon, and 20% in winter. For Naveen's garden, the bar tells us: 40% in summer, 35% in monsoon, and 25% in winter.

Statement (i): It compares seasons within the same garden (Fatima's). So, within Fatima's garden, the summer part is the largest fraction. This means she actually had more flowers in summer than in monsoon. So, (i) must be true.

Statements (ii) and (iii): These compare across gardens in the same season.

For example, in statement (ii), Fatima has a higher percentage in summer (50%) than Naveen (40%). But the chart does not tell us how many flowers they each had in total. Naveen's total could be much larger. Then even 40% of Naveen's total might still be more flowers than 50% of Fatima's total. That means we cannot be sure who has more flowers in that season. Hence, (ii) and (iii) cannot be inferred from this graph.

Statement (iv): A 100% stacked bar chart always shows each bar as '100%' of that garden's total. It does not tell us whether the totals for the two gardens are equal or not. Many different total numbers can give the same 100% bar. Therefore, we also cannot say anything about the total over the whole year from this graph.

A 100% stacked bar chart helps us compare fractions/percentages inside each garden, but it does not tell us the actual numbers of flowers.

Two possible stacked bar charts are shown below for the 100% stacked bar chart we just saw.

Number of flowers that bloomed across seasons: Case 1



$\frac{105}{210}\times 100 = 50\%$ $\frac{63}{210}\times 100 = 30\%$ $\frac{42}{210}\times 100 = 20\%$

$\frac{48}{120}\times 100 = 40\%$ $\frac{30}{120}\times 100 = 25\%$ $\frac{42}{120}\times 100 = 35\%$

Number of flowers that bloomed across seasons : Case 2



$\frac{90}{180}\times 100 = 50\%$ $\frac{54}{180}\times 100 = 30\%$ $\frac{36}{180}\times 100 = 20\%$

$\frac{96}{240}\times 100 = 40\%$ $\frac{60}{240}\times 100 = 25\%$ $\frac{84}{240}\times 100 = 35\%$

© NCERT not to be republished

Notice that the percentage of flowers that bloomed in summer is more in Fatima's garden but this doesn't say anything about the actual number — Fatima's garden has more blooms than Naveen's in summer in Case 1 but her garden has fewer blooms than his in Case 2. Also, in Case 1 both Fatima's and Naveen's garden had 42 blooms but the respective percentages are different.

Think and Reflect

1. What does this say about the scope of the stacked bars and 100% stacked bars?
2. Given a stacked bar chart can we make a corresponding 100% stacked bar chart?
3. Given a 100% stacked bar chart can we make a corresponding stacked bar chart?
4. What kind of inferences or comparisons can be made from a stacked bar chart and in a 100% stacked bar chart?

A Typical Day

Example 9: The following chart shows the time spent on different activities in a day by the average Indian. What do you notice? What do you wonder about?

You may point out that you don't do much work and that your parents don't spend any time learning. Note that this strip is representative of people across ages, genders, regions, social/family backgrounds, etc., across India.



Fig. 10.5: Time spent on different activities in a day by an average Indian (Values are rounded off)

© NCERT not to be republished

When we visualise the same data by grouping ages, we get the following stacked column chart:



Fig. 10.6: Age-wise grouping of data (Values are rounded off)

Think and Reflect

1. What do you find interesting in the chart above? What can you infer? Discuss.
2. Do you remember the sleep time over age trend that you studied last year? Does that trend align with this chart?
3. Can you explain why the learning time of people in the age group 15 – 24 has reduced significantly compared to that of the age group 6 – 14?
4. Do adults spend about an equal amount of time in paid and unpaid work? What do you think?

© NCERT not to be republished

There might be a very small fraction of people whose day is similar/close to that of the average Indian. As we saw here, looking at only the average of a diverse collection often hides the differences and nuances within the data. We observed age-specific activity trends using this chart, which gave us a better idea. We could break these down further with respect to gender to examine any gender-specific trends within age groups.

You may wonder if there are differences across regions (e.g., rural and urban), or income, etc. You may be curious to look into the details — such as, what is included under personal care for different groups, or how does time spent on travel vary across cities and towns/villages? What we spend time on also depends on the times we live in. Clearly, a few decades ago, people didn't have access to mobile phones or televisions. Only time will tell what such charts will look like after a few decades. We may also ask — how do people in other countries spend their time? How similar or different are the trends?

What type of chart is this — a stacked bar chart or a 100% stacked bar chart?

It is both! It is a stacked bar because each small bar represents the amount of time spent on a certain activity. It is also a 100% stacked bar as each stacked bar's total is the same, i.e., 24 hours, and the lengths of the smaller bars within and across the stacks also represent the relative proportions of time spent.



Think and Reflect

Do you remember the 'What Can A Strip Say?' activity from last year? In each strip, if we club the tiny strips belonging to each activity together, will we get a 100% stacked bar chart like the one in Fig. 10.6?

© NCERT not to be republished

Exercise Set 10.5

1. The smart watch data of 5 people was tracked from Monday to Friday. The recorded data tells us how many hours each person spent lying down, sitting, and standing or moving around, etc., as shown in the following table.

Table 10.3: Average number of hours spent per day (Monday – Friday) lying down, sitting, and standing or moving around, etc., of 5 people

	Lying down	Sitting	Standing or Moving around etc.
Pavani (Patient)	20	3	1
Raghu (Nurse)	7	4	13
Zakir (Teacher)	8	6	10
Sahana (Student)			
Julie (_____)	8	10	6

(i) How much time does Sahana spend per day in each of these body-states? Make a reasonable guess and fill her row in the table.

(ii) Guess what activity or work Julie could be engaged in based on the data. Find out what your classmates' guesses are.

(iii) Complete the chart below based on the tabular data.



© NCERT not to be republished

Think and Reflect

1. Will the bars look similar if a different teacher's data is considered instead of Zakir's?
2. Will the bars look different if the data for all 7 days of the week is considered?
3. Some bars in the chart may also match people doing other kinds of work/activities. Can you think of any? Discuss.

End-of-Chapter Exercises

1. In cricket, the **run rate** is the average number of runs scored per over. In a T20 match, a team scored 6 runs in the first over making the run rate 6.
   (i) In the second over they scored 12 runs. What is the run rate now?
   (ii) After Over 19, their run rate was 6. What is the run rate after 20 overs given the team made 12 runs in the last over?

2. Five friends who play badminton surveyed the city and collected the price of shuttlecocks across brands and types (Nylon and Feather). The following is the list of the prices, in rupees (₹), that each one compiled.

Nylon shuttle (N)

Feather shuttle (F)

Yusuf: 40(N), 105(N), 383(F), 108(N), 165(F), 116(F)
Srikanth: 194(N), 85(N), 93(N), 121(N)
Kashvi: 49(N), 297(F), 105(N), 275(F), 40(N)
Prasanna: 124(N), 333(F), 182(N), 258(F)
Gracy: 220(F), 458(F), 129(F), 183(N)

Can you describe a way they can work together to find the average price of a shuttlecock across types?
   (i) Each one calculated the average of the prices they had gathered. Suppose these are a_y, a_s, a_k, a_p, a_g respectively. Write an expression that gives the combined average.
   (ii) Suppose a_n, a_f are the average prices of the nylon shuttlecocks and the feather shuttlecocks, respectively. Write an expression that gives the average price of a

© NCERT not to be republished

shuttlecock. Will this be equal to the answer we got using the method in the previous part?

3. Shreyas holds 25 shares of a company at an average price of ₹150 and Vaishnavi holds 5 shares of the same company at an average price of ₹150.
   (i) Shreyas buys 10 shares of this company at a price of ₹30 each. What is the average price per share for him after the purchase?
   (ii) Vaishnavi buys some shares of this company at a price of ₹30 each and the average price per share for her after the purchase is ₹70. How many shares did she buy?

4. (Pṛthūdakasvāmī, commentary on Brahmagupta's Brāhmasphuṭasiddhānta, c. 864 CE) A "hasta" (meaning "forearm") refers to a unit of length measuring around 18 inches.
   A pool 30 hastas long is dug to different depths along its length. It is divided into 5 sections having lengths 4, 5, 6, 7, and 8 hastas, and is dug to depths of 9, 7, 7, 3, and 2 hastas, respectively. Find the mean depth of the pool.

5. Suvarna had purchased 1g gold at ₹15k (short for ₹15,000). This is shown by point O denoting the average price of gold that she possesses. Six different scenarios are given below for her next transaction. For each scenario estimate and mark the average price of gold she will have after the transaction.



   (i) Purchase 1g gold at ₹30k
   (ii) Purchase 2g gold at ₹30k
   (iii) Purchase 1g gold at ₹10k
   (iv) Purchase 10g gold at ₹10k
   (v) Purchase 0.5g gold at ₹30k
   (vi) Purchase 0.5g gold at ₹15k

6. Given some data with corresponding weights, how would the weighted average change if all the weights are doubled? If required, experiment with some data. What do you observe? Justify your answer using algebra.

7. Answer the following questions based on the graph.
   (i) In 2003, approximately how many total objects were found orbiting Earth in space? In what year did this number double?
   (ii) Find the approximate number and share of payload objects and other objects in the year 2025.
   (iii) What can you say about the number of payload objects over time, and the number of other objects over time? What can

© NCERT not to be republished

you say about the share of payload objects over time, and the share of other objects over time?



8. Observe the following infographic.



(i) Identify the correct inference(s) from the statements given.
   (a) More schools have a playground in Haryana compared to Uttarakhand.
   (b) Approximately every 2 out of 3 schools in Arunachal Pradesh have a playground.
   (c) Punjab has the highest number of schools with a playground.
   (d) Suppose it is given that Maharashtra has more schools than Telangana. Then the number of schools having a playground is more in Maharashtra.

(ii) Using the information given, can we find the nation-wide percentage of schools with a playground? If not, what additional information is needed?

9. Decision Dilemma:

(i) Which of the plays would you choose to watch based on the following chart?



(ii) The corresponding stacked bar chart is shown below. Would you change your decision after looking at this chart? Why/ Why not? Discuss.



10. A triathlon is an endurance race consisting of swimming 3.8 km, cycling 180 km, and running 42.2 km. Athletes compete for the fastest overall time, completing each segment in that order. The following table shows the finish time of 3 athletes in each segment.

© NCERT not to be republished

Table 10.4: Finish time of three athletes in each segment of a triathlon race (values in hh : mm)

	Swimming	Cycling	Running
Athlete 1	01:08	05:00	03:15
Athlete 2	01:05	05:10	03:35
Athlete 3	01:22	05:55	03:50

(i) What is a suitable representation of this data — a stacked bar chart or a 100% stacked bar chart? Why do you think so?

(ii) Suppose a 100% stacked bar chart is drawn. Which of the following question(s) can be answered by looking at just that chart?

(a) Who finished the race first?

(b) Approximately what fraction of their race time did Athlete 1 spend cycling?

(c) Which athlete took the longest for running?

11. Look at the following graph. What do you notice? What do you wonder? Write your inferences.



12. **Individual project:** Do at least one of the following.

(i) Recall the previous day and fill in the approximate time spent lying down, sitting, and standing/moving around, etc. Ask at least 2 of your family members about their day and fill it in. Alternatively, you can choose to track just your own body-state for any one of the weekdays, Saturday, and Sunday. Visualise it using a stacked bar chart. Discuss with your class how you arrived at the estimated time spent in each state.

(ii) Visualise your family's monthly expenditure using a 100% stacked bar chart.

(a) First, identify the expense categories in your family budget.

© NCERT not to be republished

(b) Discuss with your family members to decide how you will collect and organise the data.
(c) Collect expense data for at least 3 months.
(d) Represent the data in a 100% stacked bar chart, with each bar showing how the total monthly expenditure is divided across the different categories.
(e) Finally, write your observations and inferences based on the chart.

13. **Small-group project:** Make a group of 3–4 students. Choose one scenario to design a custom rating scheme by assigning appropriate weights: (a) shopping experience at a cloth store, (b) travel experience in a bus, (c) tourism experience of a nearby tourist spot, (d) clinic/hospital experience
(i) Discuss and arrive at 4–6 aspects to rate. For each aspect chosen, justify why it matters for an overall experience.
(ii) Discuss and decide the relative weights and justify.
(iii) Collect or imagine ratings from at least 10 people on a scale of 1–5 (5 being very good).
(iv) Compute each individual rating. Compute the overall average across individuals.
(v) Make a 100% stacked bar chart using your data.
(vi) Write a short note on the observations and inferences, what your rating system captures well and what it misses.

14. **Whole class project:** Each student shares the average age of their family and the number of family members. Discuss among the class and come up with a way to find out the average age of all the families of the class.

*15. Given some data with corresponding weights, what would happen to the weighted average if all the weights are increased by a constant value, say 1? If required, experiment with some data. What do you observe? Justify your answer using algebra.

*16. A farm has some cows, sheep, and chickens. Last year the cows made up 60%, the sheep 25%, and the chickens 15%. There was a decrease in the number of all three animals' population over the year. Choose the possibilities for the change in their respective shares of the population —

© NCERT not to be republished

(i) % of cows decreased, % of sheep decreased, % of chickens decreased
(ii) % of cows increased, % of sheep increased, % of chickens increased
(iii) % of cows remained the same, % of sheep remained the same, % of chickens remained the same
(iv) % of cows decreased, % of sheep increased, % of chickens remained the same
(v) % of cows increased, % of sheep increased, % of chickens decreased.

Chapter Summary

- The **weighted average** or **weighted mean** of $x_1, x_2, x_3, \ldots, x_n$ with weights $w_1, w_2, w_3, \ldots, w_n$ respectively is given by
$$x = \frac{w_1 x_1 + w_2 x_2 + w_3 x_3 + \cdots + w_n x_n}{w_1 + w_2 + w_3 + \cdots + w_n}.$$
- An average of averages can be computed using the weighted mean. The weighted mean can also be used to calculate the mean when certain values are added to or removed from data.
- The weighted average is also useful in calculating the concentration of mixtures.
- Whenever different parts of data have different number of values or levels of importance, the weighted mean can be used by assigning appropriate weights to each part of the data. Examples include rating systems and combining marks of different assessments to get a final score.
- **Stacked bar charts** may be used in place of cluster bar charts if the total of each cluster is also a matter of interest.
- **100% stacked bar charts**, like pie charts, compare proportions and not absolute values.
- Given a stacked bar chart, a corresponding 100% stacked bar chart can be made but not vice versa.

© NCERT not to be republished

11 The World of Algorithms

0905CH11

These days the word ‘algorithm’ pops up everywhere. What exactly is an algorithm? What does it have to do with mathematics?

11.1 Adding Numbers

We first learned to add numbers by counting the sum explicitly. To add 5 and 7, we would draw 5 dots to represent the number 5, then draw 7 more dots to represent the number 7, and finally count the dots, 12, to get the answer. Imagine adding large numbers this way, for instance 473 + 695!

$$\begin{array}{r} 473 \\ +\ 695 \\ \hline 8 \end{array} \qquad \begin{array}{r} {\scriptstyle 1\ \ } \\ 473 \\ +\ 695 \\ \hline 68 \end{array} \qquad \begin{array}{r} {\scriptstyle 1\ \ } \\ 473 \\ +\ 695 \\ \hline 1168 \end{array}$$

Fortunately, we discovered a much faster way to add numbers. We wrote the numbers one below the other in the Indian number system, with the rightmost digit aligned. We then added each column from right to left, remembering to add a carry to the left if the total was equal to or more than 10.

11.1.1 Adding Numbers Digit by Digit

This is an example of an **algorithm**, a step-by-step procedure to arrive at an answer. We describe an algorithm by writing down the steps as precisely as possible. For instance, here is one way to describe our addition algorithm.

Algorithm to add two numbers

1. Write the numbers one below the other in the Indian base-ten place-value system so that the digits are aligned from right to left.
2. Add the rightmost digits.
   - If the sum is less than 10, write the sum directly below the two digits. Set the value of carry to 0.
   - If the sum is more than 10, write the units digit of the sum directly below the two digits. Set the value of carry to 1.

© NCERT not to be republished

3. Move to the next column of digits on the left. Add the two digits and the current value of carry.
   - If the sum is less than 10, write the sum directly below the two digits. Set the value of carry to 0.
   - If the sum is more than 10, write the units digit of the sum directly below the two digits. Set the value of carry to 1.
4. Repeat Step 3 until there are no more digits on the left.
5. If the value of carry is 1, write 1 to the left of the bottom row.

Exercise Set 11.1

1. Add two 4-digit numbers using the steps we have written down. Make sure you follow the steps precisely; do not perform any action that is not explicitly mentioned. Are you able to obtain the correct result?
2. What happens if you add a 5-digit number to a 3-digit number. Do our steps handle this situation correctly?
3. Why is it important to align the columns from right to left?
4. In Step 3, why cannot the value of carry be more than 1?
5. What happens if we do not include the fifth step in the algorithm above? Give examples where the algorithm will work correctly and where it will fail to work.

There is also an important assumption in this algorithm, namely, that we know how to add single digit numbers without counting them out. Typically, any algorithm is built using such basic steps that we assume we can perform directly.

The main advantage of this algorithm is that it is much faster than counting explicitly. For instance, if we move from adding 3-digit numbers to adding 4-digit numbers, we have 10 times as many dots to draw and count. On the other hand, if we add the digits right to left, as in the algorithm above, we only have to add 1 more column. Likewise, 5-digit numbers would generate 100 times as many dots as 3-digit numbers, but only 2 more columns to be added.

© NCERT not to be republished

In concrete terms, suppose we can count one dot per second. To count the dots in 33 + 27 would take a minute, to count 334 + 272 would take about ten minutes, while 3347 + 2729 would take over one hour and forty minutes.

On the other hand, suppose we work slowly and carefully and take 15 seconds to add two single digit numbers with a carry. Adding 33 + 27 would take about half a minute, while 334 + 272 would take about 45 seconds, while 3347 + 2729 would take about one minute.

Whenever we provide an algorithm, we also have to justify why it works. Combining the dots and counting the sum is how addition is defined. Why does adding individual digits from right to left result in the sum of the two numbers? The key idea is that we are grouping each number into units, tens, hundreds, ... and adding each group separately. Whenever a smaller group, say units, generates a large group of ten, we carry over the newly formed ten to the tens group.

Think and Reflect

1. See if you can complete the argument about grouping by units, tens, hundreds, ... to justify why the addition algorithm works.
2. How would you modify the algorithm to add two decimal fractions?

In the rest of this chapter, we will explore the idea of an algorithm in more detail and in some other contexts.

11.2 Greatest Common Divisor

Let us look at a familiar problem: computing the **greatest common divisor (gcd) or highest common factor (hcf)** of two numbers. We have already learned different ways to solve this problem, using prime factorisation and other methods.

How can we solve the problem from the definition of gcd? How do we write down an algorithm for this?

The first step is to understand what is required and break down the problem into smaller pieces that we know how to solve.

- We want the greatest common divisor of two numbers.
- For this, we need to first compute the divisors of both numbers and note them down.
- Once we have done this, we need to compare the two collections of divisors and find the largest number that is present in both collections.

© NCERT not to be republished

11.2.1 Computing the Divisors of a Number

Suppose we want to compute gcd(375, 825).

How do we find the divisors of 375? The divisors of a number are just the factors of that number. Clearly any divisor, or factor, must lie between 1 and 375. The simplest way to find the divisors is to check each number between 1 and 375 and see if it divides 375.

We also have to keep track of the divisors of 375 so that we can compare them with the divisors of 825. We can maintain each of these in a sequence, or a **list**. How do we create the list of divisors of a number? When we start, we do not know any divisors, so the list of divisors is initially empty. Every time we find a new divisor, we add it at the end of the list.

Here is how we can write down this algorithm to find the list of divisors of any number *n*.

Algorithm to find the divisors of n

```
1. Start with an empty list-of-divisors.
2. For each number j in the sequence 1,2,3, ... ,n
   - if j divides n, add j to the list-of-divisors.
```

Notice how we use names `list-of-divisors` and `j` to identify the values that we keep track of in this algorithm. If we do not use `j` to identify the number we are checking next as a possible divisor, it would be clumsy to describe what to do each time we find a divisor.

Running through an algorithm step by step is also called **executing** the algorithm. Let us execute this algorithm for a small number, say 18. We use square brackets to denote a list of values — for instance, [1, 4, 9, 16].

Let us see how this algorithm works for a small number, say 18.

- Initially `list-of-divisors` is empty [ ].
- 1 divides 18, so we update `list-of-divisors` to [1].
- 2 divides 18, so we update `list-of-divisors` to [1, 2].
- 3 divides 18, so we update `list-of-divisors` to [1, 2, 3].
- 4 does not divide 18, so we leave `list-of-divisors` unchanged as [1, 2, 3].
- 5 does not divide 18, so we leave `list-of-divisors` unchanged as [1, 2, 3].

© NCERT not to be republished

- 6 divides 18, so we update `list-of-divisors` to [1, 2, 3, 6].
- 7 and 8 do not divide 18, so we leave `list-of-divisors` unchanged as [1, 2, 3, 6].
- 9 divides 18, so we update `list-of-divisors` to [1, 2, 3, 6, 9].
- 10, 11, 12, ..., 17 do not divide 18, so we keep `list-of-divisors` unchanged as [1, 2, 3, 6, 9].
- 18 divides 18, so we update `list-of-divisors` to [1, 2, 3, 6, 9, 18].

Thus, at the end of the algorithm we have divisors(18) = [1, 2, 3, 6, 9, 18]. Notice that the list is also in increasing order, because we checked for divisors systematically, from 1 to 18.

What is the basic step that we assumed in this algorithm? It is that we know how to compute when a smaller number divides a larger number.

If we go through the steps of the algorithm, we get the following answers.

- divisors(375) = [1, 3, 5, 15, 25, 75, 125, 375]
- divisors(825) = [1, 3, 5, 11, 15, 25, 33, 55, 75, 165, 275, 825]

Think and Reflect

Try to execute the algorithm to compute the divisors of 15, 135, and 775. How does the amount of work increase as the numbers grow?

11.2.2 Finding the Greatest Common Divisor

The second step in our procedure to find the gcd is to compare the lists of divisors of the two numbers and find the largest number that appears in both lists.

If we look through the divisiors of 375 and 825 above, we see that the answer is 75. What if the numbers were 54000 and 81000?

- divisors(54000) = [1, 2, 3, 4, 5, 6, 8, 9, 10, 12, 15, 16, 18, 20, 24, 25, 27, 30, 36, 40, 45, 48, 50, 54, 60, 72, 75, 80, 90, 100, 108, 120, 125, 135, 144, 150, 180, 200, 216, 225, 240, 250, 270, 300, 360, 375, 400, 432, 450, 500, 540, 600, 675, 720, 750, 900, 1000, 1080, 1125, 1200, 1350, 1500, 1800, 2000, 2160, 2250, 2700, 3000, 3375, 3600, 4500, 5400, 6000, 6750, 9000, 10800, 13500, 18000, 27000, 54000]

© NCERT not to be republished

- divisors(81000) = [1, 2, 3, 4, 5, 6, 8, 9, 10, 12, 15, 18, 20, 24, 25, 27, 30, 36, 40, 45, 50, 54, 60, 72, 75, 81, 90, 100, 108, 120, 125, 135, 150, 162, 180, 200, 216, 225, 250, 270, 300, 324, 360, 375, 405, 450, 500, 540, 600, 648, 675, 750, 810, 900, 1000, 1080, 1125, 1350, 1500, 1620, 1800, 2025, 2250, 2700, 3000, 3240, 3375, 4050, 4500, 5400, 6750, 8100, 9000, 10125, 13500, 16200, 20250, 27000, 40500, 81000]

It is no longer so simple to just inspect the lists to find the largest element common to both of them! We need to do this systematically.

We compute a new list, the list of common divisors. As before, when we compute the list of divisors, this list is initially empty. For each divisor in the first list, we check if it belongs to the second list. If it does, we add it to the list of common divisors. Notice that 1 divides every number, so the list of common divisors will have at least one entry, 1.

Using this, we can compute the list of common divisors of 54000 and 81000, to be [1, 2, 3, 4, 5, 6, 8, 9, 10, 12, 15, 18, 20, 24, 25, 27, 30, 36, 40, 45, 50, 54, 60, 72, 75, 90, 100, 108, 120, 125, 135, 150, 180, 200, 216, 225, 250, 270, 300, 360, 375, 450, 500, 540, 600, 675, 750, 900, 1000, 1080, 1125, 1350, 1500, 1800, 2250, 2700, 3000, 3375, 4500, 5400, 6750, 9000, 13500, 27000].

Since we know that each list of divisors is in increasing order, it must be the case that the list of common divisors is also in increasing order. Hence the largest common divisor is the rightmost element in the list. In other words the gcd of 54000 and 81000 is 27000.

11.2.3 First Algorithm for gcd

Combining the steps above, we can write out a complete algorithm to compute the gcd of two numbers m and n. This makes use of the earlier algorithm to compute the list of divisors of a number.

Algorithm to find gcd(m, n)

1. `Let divisors-of-m be the list obtained by computing divisors(m)`
2. `Let divisors-of-n be the list obtained by computing divisors(n)`
3. `Start with an empty list common-divisors`

© NCERT not to be republished

```
4. For each number x in the list of divisors-of-m
   - If x also appears in the list of divisors-of-n,add
   x to the list common-divisors
5. Report the rightmost element of the list common-
   divisors as gcd(m,n)
```

When we execute this algorithm for gcd(375, 825) we check whether each of the divisors [1, 3, 5, 15, 25, 75, 125, 375] of 375 appears in the list of divisors [1, 3, 5, 11, 15, 25, 33, 55, 75, 165, 275, 825] of 825. We see that 1, 3, 5, 15, 25 and 75 are in the second list while 125 and 375 are not. So we compute the list of common divisors to be [1, 3, 5, 15, 25, 75]. Since 75 is the rightmost element in this list, gcd(375, 825) = 75.

11.3 Data Structures

When we execute an algorithm, we compute intermediate quantities, such as the list `divisors-of-m` and the list `divisors-of-n`. To keep track of these values, we use names such as `divisors-of-m` and `divisors-of-n`, respectively, so that we can refer to them later in the algorithm. As we remarked earlier, assigning names to intermediate values is important for writing down algorithms concisely.

Also, these intermediate values are typically more complicated than just simple numbers. In this case, we maintain lists of numbers and, in fact, lists that are arranged in ascending order. A **list** is an example of a **data structure**. Data structures allow us to organise information in a manner that helps make an algorithm more efficient. We will explore this idea in higher grades.

Exercise Set 11.2

1. Suppose List 1 and List 2 are two lists of numbers in increasing order.
   (i) Write an algorithm to find elements in List 1 that are not present in List 2.
   (ii) Write an algorithm to find elements in List 2 that are not present in List 1.
2. Describe an algorithm to compute the least common multiple (lcm) of two numbers.

© NCERT not to be republished

*3. Divisors occur in pairs. For instance, the divisors of 18 are (1, 18), (2, 9) and (3, 6).

(i) If we write out divisors in pairs, how many numbers do we have to examine between 1 and n to find all the divisors of n?

(ii) If we list out the divisors in pairs, will our gcd algorithm still work in the manner we have described?

11.3.1 Improving the Algorithm

Compute both lists of divisors together

In the algorithm above, we first check all numbers between 1 and m to find the divisors of m. Then we start again with 1 and check all numbers between 1 and n to find the divisors of n. This means we have to scan $m + n$ possible divisors.

We can combine these two scans into one. Let max(m, n) be the maximum of m and n. We run through each `j` from 1 to max(m, n).

- If `j` divides m we add `j` to the list of divisors of m.
- If `j` divides n we add `j` to the list of divisors of n.

This reduces the number of possible divisors to be checked from $m + n$ to max(m, n).

Directly compute the list of common divisors

If we combine the scans, we can directly compute the list of common divisors, instead of first computing the divisors of each number and then combining the lists.

- For each number `j` from 1 to max(m, n), if `j` divides both m and n, add `j` to the list of common divisors.

In fact, a common divisor cannot be larger than the smaller of the two numbers, so we can check for common divisors up to the minimum of m and n rather than the maximum.

- For each number `j` from 1 to min(m, n), if `j` divides both m and n, add `j` to the list of common divisors.

Do away with lists

Do we need to maintain the list of all common divisors? Each time we find a larger common divisor, the ones that we have found earlier are useless!

© NCERT not to be republished

Let us keep track of a quantity called most-recent-common-divisor. We know that 1 is always a common divisor, so we can start with most-recent-common-divisor set to 1. We then scan all numbers from 2 to min(m, n).

- For each k from 2 to min(m, n), if k divides both m and n, update most-recent-common-divisor to k.

At the end of this scan, most-recent-common-divisor directly gives us the gcd.

Example: Let m = 6, n = 12.
- min(6, 12) = 6
- Initially set most-recent-common-divisor to 1
- k = 2 divides both 6 and 12.
  Update: most-recent-common-divisor to 2.
- k = 3 divides both 6 and 12.
  Update: most-recent-common-divisor to 3.
- k = 4 doesnot divide 6.
  most-recent-common-divisor remains 3.
- k = 5 doesnot divide 6.
  most-recent-common-divisor remains 3.
- k = 6 divides both 6 and 12.
  Update: most-recent-common-divisor to 6.

Scan complete. gcd(6, 12) = 6

Exercise Set 11.3

1. How would our original algorithm change if we computed the divisors of n by examining the numbers from 1 to n in reverse order, from n down to 1?
2. What about the last algorithm described above? What happens when we look at common divisors starting from min(m, n) and work backwards to 1?

11.3.2 Analysing these Algorithms

We started with a very basic algorithm. Since this was derived directly from the definition of gcd, it is easy to justify that the result it computes is actually the gcd.

Each successive refinement that we have proposed improves the efficiency but does not substantially change what is being computed. Hence, we can argue that all of the algorithms we have seen so far compute the correct value.

How efficient are these algorithms? Even in the final version, where we eliminated lists, we had to examine all numbers from 1 to min(m, n). This is similar to what we saw when adding numbers by counting. If the smaller number goes from 3 digits to 4 digits, we have to scan 10 times as many values to find the common divisors. If we go from 3 digits to 5 digits, the work grows by a factor of 100.

© NCERT not to be republished

As we did for adding, can we find an algorithm for gcd where the effort is proportional to the number of digits in the number, rather than the value of the number?

11.3.3 Euclid's Subtraction Algorithm

An elegant solution to achieve this was written down by Euclid, in his book *Elements*. Historians believe that other Greek mathematicians knew of this algorithm before Euclid, but he was the first to put it down in writing.

Reducing a problem to a simpler one

The original version of Euclid's algorithm makes use of the following observation. Let us assume that $m \geq n$. Then, gcd(m, n) is the same as gcd(n, $m - n$).

Why is this the case?

- Let d be a common divisor of m and n. Then we can write m as ad and n as bd, where a and b are natural numbers. This means that $m - n = ad - bd = (a - b)d$, so d is also a divisor of $m - n$.
- On the other hand, if d divides both n and $m - n$, then $n = xd$ and $m - n = yd$ for some natural numbers x and y. This means that $n + (m - n) = m = xd + yd = (x + y)d$, so d also divides m.

This is shown visually below. If we can 'tile' m and n using blocks of size d, we can also tile $m - n$ by blocks of the same size. In fact, Euclid used a similar pictorial proof to justify his algorithm.



Fig. 11.1: Justification for Euclid's gcd algorithm

This observation tells us that any common divisor of m and n is also a common divisor of n and $m - n$, and the converse is also true. Hence the set of common divisors are the same in both cases, which means that gcd(m, n) = gcd(n, $m - n$).

Euclid's algorithm reduces the problem of finding gcd(m, n) to that of finding gcd(n, $m - n$). The second problem involves smaller numbers, so it should be a simpler problem to solve.

© NCERT not to be republished

How do we solve it? We apply the same strategy: reduce it to gcd(x, y) where x = min(n, $m - n$) and y is the difference between n and $m - n$.

When do we stop? Suppose we compute the gcd of a number with itself, say gcd(23, 23). The answer should clearly be 23. When we reduce this we get gcd(23, 0). In other words, if we reach gcd(m, 0), the answer is m.

Euclid's algorithm for gcd*(m,n)*

```
1. If m < n, reverse the numbers and compute gcd(n,m)
2. If n = 0, report the answer as m
3. Otherwise, reduce the problem to compute gcd(n,m–n)
```

Let us apply this algorithm to gcd(375, 825), the problem that we saw before.

- Since 375 < 825, Step 1 asks us to reverse the numbers and compute gcd(825, 375).
- Since 825 – 375 = 450, Step 3 asks us to reduce the problem to computing gcd(375, 450).
- Since 375 < 450, Step 1 asks us to reverse the numbers and compute gcd(450, 375).
- Step 3 asks us to reduce the problem to computing gcd(375, 75).
- Step 3 asks us to reduce the problem to computing gcd(75, 300).
- Since 75 < 300, Step 1 asks us to reverse the numbers and compute gcd(300, 75).
- Step 3 asks us to reduce the problem to computing gcd(75, 225).
- Since 75 < 225, Step 1 asks us to reverse the numbers and compute gcd(225, 75).
- Step 3 asks us to reduce the problem to computing gcd(75, 150).
- Since 75 < 150, Step 1 asks us to reverse the numbers and compute gcd(150, 75).
- Step 3 asks us to reduce the problem to computing gcd(75, 75).
- Step 3 asks us to reduce the problem to computing gcd(75, 0).
- Since n = 0, Step 2 tells us the answer is 75.

In the example above, we reduced the problem 7 times before finding the answer. Are we close to our original goal of finding an algorithm where the effort is proportional to the number of digits? Unfortunately, no.

© NCERT not to be republished

Consider gcd(99, 2). This will reduce successively to gcd(97, 2), gcd(95, 2), gcd(93, 2), … , gcd(5, 2), gcd(3, 2), gcd(2, 1), gcd(1, 1), and gcd(1, 0) eventually giving us the answer 1. In general, if we start with an odd number $2k + 1$, gcd($2k + 1$, 2) will require about k reductions before we get the answer 1. This means the number of steps is proportional to the value we start with, rather than the number of digits used to write down the value.

11.3.4 Āryabhaṭa's Division Algorithm

In Indian treatises like Āryabhaṭa's Āryabhaṭīya (499 CE), we see the "long division" method for finding GCD using Indian place value numerals. It makes an efficient use of repeated "division by remainder" in place of repeated subtraction. For example, when one starts with 99 and subtracts 2 repeatedly, what remains, once one cannot subtract 2 anymore, is the remainder when 99 is divided by 2.

Hence, to improve the performance of Euclid's algorithm, we can change the reduction step: instead of reducing gcd(m, n) to gcd(n, $m – n$), we reduce it to gcd(n, m mod n), where m mod n stands for the remainder when m is divided by n. For example, 17 mod 5 is 2 and 33 mod 7 is 5.

We saw earlier that a divisor d 'tiles' both m and n if and only if it 'tiles' both n and $m – n$. In a similar way, we can argue that d 'tiles' m and n if and only if it tiles m and m mod n. This justifies reducing gcd(m, n) to gcd(n, m mod n).

Here is the modified algorithm. Notice that the only change is in the third statement. The stopping condition is the same as before.

```
1. If m < n, reverse the numbers and compute gcd(n,m)
2. If n = 0, report the answer as m
3. Otherwise, reduce the problem to computing gcd(n, m mod n)
```

Consider the earlier example gcd(99, 2) that took a long time to converge. Here is what happens when we execute the improved algorithm.

- Step 3 asks us to reduce the problem to computing gcd(2, 1).
- Step 3 asks us to reduce the problem to computing gcd(1, 0).
- Since $n = 0$, Step 2 tells us the answer is 1.

In other words, we needed only two reduction steps to get to the final answer. Check that this would happen for any similar problem of the form gcd($2k + 1$, 2).

© NCERT not to be republished

The above modified algorithm can be carried out concisely using the "long division" method given by Indians at least from the time of Āryabhaṭa. We illustrate the method through the following examples—

1. gcd(99, 2) = gcd(2, 1)

```
2)99(49
  98
 1)2(2
   2
   0
```

(gcd)

2. gcd(825, 375) = gcd(375, 75)

```
375)825(2
  750
 75)375(5
  375
    0
```

(gcd)

Here is another example—

3. gcd(60, 16) = gcd(16, 12) = gcd(12, 4)

```
16)60(3
  48
 12)16(1
   12
  4)12(3
   12
    0
```

(gcd)

In fact, it can be shown that the number of reductions needed in Āryabhaṭa's division algorithm is now proportional to the number of digits in m and n. Unfortunately, the justification for this fact is too involved to present here, but you will learn about it in future grades.

A Pinch of History

The influential Persian mathematician Al-Khwārizmī (780–850 CE), a scholar at the "House of Wisdom" in Baghdad, developed a great liking for Indian mathematics. He learnt Sanskrit, and around 820 CE wrote a detailed treatise expounding the Indian place value number system and the Indian procedures for the four fundamental operations — addition, subtraction, multiplication, and division. His original is lost, but its 12th-century Latin translation, *Liber Algorismi de numero Indorum* ("The Book of Al-Khwārizmī on Indian Numerals"), survives and played a major role in spreading Indian arithmetic through medieval Europe. Al-Khwārizmī's name became so closely tied to these methods that the word algorismus — from Algoritmi, the Latin form of his name — came to mean any Indian method for numerical computation; it later contracted to algorism and then algorithm. Etymologically, then, "algorithm" originally denoted an Indian method of arithmetic, before it broadened to mean any well-defined, step-by-step systematic procedure for solving a class of problems.

© NCERT not to be republished

End-of-Chapter Exercises

1. Compute the following using the improved version of Euclid's algorithm.
   (i) gcd(375, 825)
   (ii) gcd(51000, 81000)
   (iii) gcd(1789287, 237656)
   (iv) gcd(2587392, 157656)
2. Assume that $m \geq n$. Verify that d divides m and n if and only if d divides both n and m mod n.
3. Write an algorithm prime(n) to check if n is prime.
   (**Hint:** A prime number p has exactly two distinct factors, 1 and p. Can you make use of divisors(n) to write out prime(n)?)

*4. Write an algorithm primedivisors(n) to compute the list of divisors of n that are prime numbers.
   (**Hint:** Compute divisors(n) and then filter out the primes in this list.)

*5. We can also find the gcd of two numbers by computing prime factorisation of both the numbers. Try to write an algorithm to compute the prime factorisation of a number.
   (i) The prime factorisation of 180 is $2^2 \times 3^2 \times 5^1$. How would you represent this?
   (ii) How would you compare the prime factorisations of two numbers?

Chapter Summary

- An **algorithm** is a systematic procedure to solve a problem.
- Algorithms consist of basic steps that we know how to execute.
- We may execute the same step a number of times; for instance, for each `j` in 1, 2, ..., n, check if `j` is a divisor of n.
- A step in an algorithm may be conditional; for instance, add `j` to the list of divisors of n only if `j` divides n.
- When we describe an algorithm to solve a problem, we need to justify that it is correct.
- We can also analyse how many steps an algorithm takes, in terms of the size of its input, and decide how efficient it is.

© NCERT not to be republished

12 Quadrilaterals

0905CH12

Quadrilaterals, which we also call 4-gons, occur everywhere in daily life. For example, we often see flooring made of square tiles. We say that the floor has been 'tiled' using those squares.

Think and Reflect

Can we use any given quadrilateral to tile the plane? If not, which quadrilaterals can be used and which cannot?

Recall that **tiling** the plane means covering it with copies of the given shape or shapes without gaps or overlaps. Tiling the plane with a rectangle is easy, but it seems difficult with an irregular quadrilateral. We will answer the above question at the end of the chapter (can you do it now?) and understand the answer using what we learn in this chapter. However, to start with, we will discuss a simple new example of a tiling.

Imagine that tiling with rectangles is done using a grid of two sets of long wooden sticks, one set horizontal and the other set vertical. See Fig. 12.1A.



Fig. 12.1A *Fig. 12.1B*

© NCERT not to be republished

These sticks are pinned together at each intersection point such that they are free to rotate about those points. Now suppose you pick up this grid. You hold the bottom stick fixed with one hand and push the vertical side with the other. See Fig. 12.1B. Each set of parallel lines will stay parallel but the angle between the two sets will no longer be 90°. Thus we see that the plane can be tiled using copies of any fixed parallelogram.

In this chapter, we will ask and answer several questions about quadrilaterals, paying particular attention to parallelograms. We will investigate their properties, examine ways to recognise them, and see important applications in geometry. At the end, we will answer the question above about whether one can tile the plane with a given quadrilateral.

12.1 What Exactly is a Quadrilateral?

Think and Reflect

Informally, a quadrilateral is a figure with four straight sides, as in the first figure ABCD in Fig. 12.2 below. But consider the other six figures in Fig. 12.2: the five plane figures NOPE, SILY, DART, CUTS, OPENS and the non-planar BENT. Should we call all these figures quadrilaterals? If you answer 'no' for any of them, how will you define a quadrilateral so that such a figure is excluded? As you can see, some care is needed to precisely define what we think of as a quadrilateral.



Fig. 12.2

© NCERT not to be republished

To prepare, let us first consider how we can define a triangle. Let A, B and C be three points. Can we say that ΔABC consists of points on the three line segments AB, BC, CA? Yes, provided A, B, C are not collinear. Otherwise, we just get a line segment: see Fig. 12.3.



Fig. 12.3: Not a triangle

When A, B, C are non-collinear, we call them the **vertices** of ΔABC and the three segments AB, BC and CA the **sides** of ΔABC.

Think and Reflect

Can we similarly define a quadrilateral ABCD?

Take any 4 distinct non-collinear points A, B, C and D. Will segments AB, BC, CD and DA always form a quadrilateral as we visualise it? See figures NOPE, SILY, DART, CUTS, OPENS and BENT in Fig. 12.2 again. Do you see, OPENS that there are some subtle new issues to consider?

First, to rule out examples like NOPE and SILY, no three vertices should be collinear. Otherwise, the two adjacent sides formed by the three collinear vertices will be along the same line, giving a triangle like NOPE or a figure with overlapping sides like in SILY.

Second, to rule out examples like BENT, all four vertices should be in the same plane. Four-sided figures like BENT are called **non-planar** quadrilaterals. We will study only planar quadrilaterals (except in a few exercises).

Third, do we want to call CUTS a quadrilateral? The answer depends on what we decide! Ordinarily, CUTS is not considered a quadrilateral. If we want to include it, we call it a self-intersecting quadrilateral.

Can you come up with a definition that rules out self-intersecting quadrilaterals like CUTS? Answer: we should require that all the points of the quadrilateral, other than the vertices, must lie on exactly one side.

Can you see how to rule out figures like OPENS?

Putting together all three requirements, we get the following definition.

Definition 1. Suppose A, B, C, D are four distinct points in a plane. Then the points on the 4 segments AB, BC, CD and DA are said to form **quadrilateral** ABCD if every such point other than A, B, C, and D lies on exactly one of these four segments.

© NCERT not to be republished

Now that we have precisely defined a quadrilateral, let us give similarly precise definitions of familiar terms associated with a quadrilateral.

A, B, C, D are called the **vertices** of quadrilateral ABCD; segments AB, BC, CD, DA are its **sides** or **edges**; segments AC and BD are its **diagonals**. The two endpoints of a side are called **adjacent vertices**. Two sides with a common endpoint are called **adjacent sides**. A quadrilateral has 4 **internal angles**, each formed at a vertex by a pair of adjacent sides. Internal angles at adjacent vertices are called a pair of **adjacent angles**. How will you define **opposite sides**? **Opposite angles**? See Exercise Set 12.1, Q1.

Note that quadrilateral ABCD can also be denoted as BCDA, CDAB, DABC, DCBA, ADCB, BADC or CBAD but not by any other sequence of vertices. (Draw ABCD and trace the vertices in various orders to see why.)

When we refer to a quadrilateral, we always mean a planar non-self-intersecting quadrilateral, unless stated otherwise.

Convex Quadrilaterals

Should DART in Fig. 12.2 be considered a quadrilateral? It seems different from our usual mental picture of a quadrilateral because it has a dent, as if someone has taken a bite out of triangle ART! We call DART a *non-convex* quadrilateral.



Internal angles of convex and non-convex 4-gons

Fig. 12.4

A convex quadrilateral is one without a dent. How can we define this precisely? We can see in DART that at the dent at vertex D, the internal angle is more than 180°. So we call a quadrilateral convex when *all* of its internal angles are less than 180°.



Fig. 12.5

There are other ways of testing convexity. For example, visually verify that the diagonals of a convex quadrilateral intersect while those of a non-convex quadrilateral don't intersect.

© NCERT not to be republished



Venn Diagram Representation

4-gons that do not fit your mental image of a quadrilateral may look strange. Do we really need to care about, e.g., self-intersecting 4-gons? Yes, because they do occur in real life, such as in 4-bar linkages. Linkages are widely used mechanical devices with several interlinked bars. Some ends of these bars are fixed, while other interlinked ends are free to rotate around the fixed ones. Search the internet for a video showing how linkages move. Linkages can attain a range of configurations, including non-convex and self-intersecting figures, as shown below. So engineers have to take such figures into account.

© NCERT not to be republished

Exercise Set 12.1

1. Let ABCD be a quadrilateral.
   (i) List all sides of ABCD adjacent to side AB. List all sides opposite to AB.

(ii) List all angles of ABCD adjacent to ∠A. List all angles opposite to ∠A.

(iii) Define a pair of opposite sides and a pair of opposite angles without using the names of the vertices.

*2. You have used internal angles of quadrilaterals, but they too require an exact definition, just like how we gave one for a quadrilateral. Precisely define the internal angle of a quadrilateral at a given vertex. Your answer should work for a non-convex quadrilateral too. (**Hint:** use the opposite vertex as well.)

3. In a quadrilateral ABCD, suppose AB ∥ DC. Can ABCD be non-convex? What if we instead assume AB = CD? What if we instead assume ∠A = ∠C?

4. Consider three non-collinear points A, B, C and draw the lines AB, BC, CA. For every possible location of point D in the plane outside these lines, decide if ABCD is self-intersecting, non-convex, or convex. (**Hint:** the three lines divide the plane into 7 regions.)

5. Can a quadrilateral be both self-intersecting and non-planar?

12.2 Parallelograms

As we studied in Grade 8, parallelograms are quadrilaterals whose opposite sides are parallel. They include rhombuses, rectangles and squares and form a very important and widely used class of quadrilaterals.

To test if a given quadrilateral is a parallelogram, do we have to check that the opposite sides are parallel? Are there other ways to test this? To answer this, recall the following properties of a parallelogram that we proved last year.

Theorem 1:

(a) The opposite sides of a parallelogram are equal.

(b) The opposite angles of a parallelogram are equal.

(c) The diagonals of a parallelogram bisect each other.

It is usually interesting to examine if converses of known theorems are true. If the converse of any of the three properties is true, it can be used as an alternate way to show that a quadrilateral is a parallelogram. To explore this, let us write the converses. For this, we first write (a), (b) and (c) in "If … then …" form.

© NCERT not to be republished

(a) If a quadrilateral is a parallelogram, then its opposite sides are equal.

Converse: If the opposite sides of a quadrilateral are equal, then it is a parallelogram.
Is this converse statement true?

(b) If a quadrilateral is a parallelogram, then the opposite angles are equal.

Converse: If the opposite angles of a quadrilateral are equal, then it is a parallelogram.
Is this converse statement true?

(c) If a quadrilateral is a parallelogram, then its diagonals bisect each other.

Converse: If the diagonals of a quadrilateral bisect each other, then it is a parallelogram.
Is this converse statement true?

Can you experiment and guess what the answers are?

It turns out that all three converse statements are true. To demonstrate this, it is useful to recall how we had proved Theorem 1:

Proof of Theorem 1:



(a) *(b)* *(c)*

Fig. 12.6

Proof of (a): In the parallelogram ABCD, AC is a transversal for AB ∥ DC and also for AD ∥ BC. So we get $\Delta ACD \cong \Delta CAB$ by the ASA test. Therefore, AB = DC and AD = BC.

Proof of (b): BC ∥ AD with AB a transversal. Therefore $\angle A + \angle B = 180°$ as they are interior angles on the same side of this transversal. By similar reasoning, any two adjacent angles add up to 180°. By using algebra, $\angle A = \angle C$ and $\angle B = \angle D$.

© NCERT not to be republished

Proof of (c): Call the intersection point of the two diagonals E. Using property (a), $\Delta AED \cong \Delta CEB$, by ASA or AAS. So EA = EC and EB = ED, which means that E is the midpoint of both diagonals.

We will now deduce the converse statements. To prove the converse of a known theorem, we can try to run the original proof backwards. This strategy may or may not work. (For example, the reasoning "If $x = y$, then $x^2 = y^2$" cannot be reversed, because x and y may have opposite signs, e.g., we could have $x = 3$ and $y = -3$.) When the strategy does work, we should be careful to give proper justification for each step in the backward direction.

Theorem 2 (converse of (a)): *If the opposite sides of a quadrilateral are of equal length, then it is a parallelogram.*



Fig. 12.7: Converse to (a)

Proof: Let ABCD be this quadrilateral. $\Delta ACD \cong \Delta CAB$ by SSS, so corresponding angles are equal. Using transversal AC, we get AB ∥ DC and AD ∥ BC.

Pay close attention to how the above proof retraces the proof of (a) backwards. Both proofs go via the same congruence $\Delta ACD \cong \Delta CAB$, but the two proofs use different tests to justify the congruence (ASA vs SSS) and draw different conclusions. Try to use the same 'backward retracing' strategy for the remaining converses.

Theorem 3 (converse of (b)): *If the opposite angles of a quadrilateral are equal, then it is a parallelogram.*

Proof: Let ABCD be this quadrilateral. Because $\angle A = \angle C$ and $\angle B = \angle D$, we have

$$360° = \angle A + \angle B + \angle C + \angle D = 2(\angle A + \angle B) = 2(\angle B + \angle C).$$



Fig. 12.8: Converse to (b)

$2(x + y) = 360°$

© NCERT not to be republished

Therefore $\angle A + \angle B = \angle B + \angle C = 180°$. As in the proof of (b), we use the fact that AB is a transversal for the pair BC and AD. By $\angle A + \angle B = 180°$ we deduce BC ∥ AD. Similarly, we get AB ∥ DC by using $\angle B + \angle C = 180°$.

Think and Reflect

The angles of a quadrilateral add up to 360°. Therefore, if the opposite angles are equal, what can we say about adjacent angles? Is the converse of your answer true? Conclude that Theorem 3 can also be stated as follows. "If each pair of adjacent angles in a quadrilateral ABCD ... then ABCD is a parallelogram." Fill in the blank.

Theorem 4 (converse of (c)): *A quadrilateral whose diagonals bisect each other is a parallelogram.*

Proof: Let ABCD be this quadrilateral. Let E be the intersection point of the diagonals AC and BD. As EA = EC and EB = ED, we have $\Delta AED \cong \Delta CEB$ by SAS. Now using $\angle DAE = \angle ECB$ along with transversal AC, we get AD ∥ BC. Similarly, $\Delta EAB \cong \Delta ECD$ gives AB ∥ DC.



Fig. 12.9: Converse to (c)

Finally, there is one more useful test to check if a given quadrilateral ABCD is a parallelogram.

Theorem 5 (equal parallel sides test): *A quadrilateral with one pair of equal and parallel opposite sides is a parallelogram.*



Fig. 12.10

Proof: Suppose in a quadrilateral ABCD we have AB ∥ DC and AB = DC. Let E be the intersection point of the diagonals AC and BD. (Why must the diagonals intersect? See Exercise Set 12.1, Q3.) We have $\Delta EAB \cong \Delta ECD$ by ASA. So the diagonals bisect each other. By the converse of (c), ABCD is a parallelogram.

© NCERT not to be republished

Exercise Set 12.2

1. True or false?
   (i) A parallelogram with a right angle is a rectangle.
   (ii) A rhombus with perpendicular diagonals is a square.
   (iii) If the diagonals of a parallelogram are equal, then it is a rectangle.
2. The diagonal AC of a parallelogram ABCD bisects $\angle A$. Show that it also bisects $\angle C$ and that ABCD is a rhombus.
3. The following questions examine converses of true properties. Answer them with Yes or No. If your answer is No, what extra condition can you add so that the answer becomes Yes?
   (i) If the diagonals of a quadrilateral ABCD bisect its angles, must ABCD be a rhombus?
   (ii) If the diagonals of a quadrilateral ABCD bisect each other at right angles, must ABCD be a rhombus?
   (iii) If the diagonals of a quadrilateral ABCD are of equal length, must ABCD be a rectangle? (In the ancient Indian study of quadrilaterals, equality of diagonals was considered significant. Quadrilaterals were first classified according to whether their diagonals were equal or not, before considering equality of sides.)
4. Let ABCD be a parallelogram with AB ≠ BC. Show that the pairwise intersection points of the four angle bisectors form the vertices of a rectangle (see Fig. 12.11). Why did we assume AB ≠ BC?



Fig. 12.11

12.3 Applications of Parallelograms

We saw that parallelograms have several nice geometric properties. These properties make the parallelogram a versatile shape with many real-world applications. In physics, a fundamental law uses parallelograms to combine certain physical quantities like forces, as you will learn in a later year. Parallelograms are used in several mechanical linkages, such as the parallel motion linkage discovered by James Watt,

© NCERT not to be republished

which formed an important part of his steam engine. His design used the concept behind another parallelogram-based device called a pantograph, which can make exact scaled copies of a drawing: search the internet for a video showing how a pantograph works. It is ingenious!



Schematic drawing of a pantograph

Parallelograms also serve as a powerful tool within geometry. Let us illustrate this by using parallelograms in a clever way to prove an important fact about triangles. We will discover this fact through exploration.

12.3.1 An Important Property of Triangles



Fig. 12.12

On a piece of paper, draw and then cut out two copies of the same triangle. Keep one copy aside. On the other, mark the midpoint of each side. (You can do this by folding the paper to join two vertices at a time.) Draw the triangle made by the three midpoints and cut the paper along each of these lines. Now you have four smaller triangles. Compare them to each other and to the intact copy of the original triangle. What do you notice?

It appears that all four smaller triangles are congruent to each other! And each seems to be a smaller copy of the original triangle. Verify that this pattern holds for triangles of other shapes.

© NCERT not to be republished

Think and Reflect

Try to prove directly that the four smaller triangles are congruent. You will see that no congruence test applies, because many quantities are unknown.

Here is one idea. The difficulty might be because we are considering too many new things at once: three new points and three new segments. Can we try to break this down into steps?



Fig. 12.13

Let us see what happens with just one of the three new segments. Can you make a guess about this new segment, specifically about its direction and length compared with the unused third side? The triangles you cut earlier will help. It appears that the segment is parallel to the third side and has half the length! Let us try to justify this using reasoning.

Geometric reasoning: To set up, suppose that in ΔABC, P and Q are the midpoints of side AB and AC respectively. Now comes the key idea. Construct the line l through C parallel to BA. Suppose it intersects line PQ at point R.

(See the comment about this line immediately after the statement of Theorem 6.)



Fig. 12.14

In ΔAPQ and ΔCRQ, we have AQ = CQ,

$\angle AQP = \angle CQR$ (vertically opposite angles), and

$\angle APQ = \angle CRQ$ (since AP $\parallel$ RC by construction).

So $\Delta APQ \cong \Delta CRQ$ by AAS.

Therefore PQ = QR (by congruence) = $\frac{PR}{2}$ and CR = AP. Combining CR = AP with AP = BP, we get CR = BP. Hence by Theorem 5

© NCERT not to be republished

(equal parallel sides test), BCRP is a parallelogram. This gives PQ ∥ BC and also PQ = $\frac{PR}{2} = \frac{BC}{2}$. We have deduced the following important fact.

Theorem 6 (Midpoint Theorem): *The segment joining the midpoints of two sides of a triangle is parallel to the third side and has half the length.*

In the reasoning for this theorem, the idea to take a completely new line l appeared out of nowhere, and worked like magic. What is your reaction to this? Do you feel a sense of wonder? Do you perhaps feel discouraged because it seems impossible to think of such an idea on your own? This type of auxiliary construction is a classic geometric trick that one learns with experience, so no need to be disheartened! See Exercise 15 at the end of the chapter for another proof that uses a different, slightly less magical construction.

Can you now prove the original claim about cutting ΔABC into four congruent parts by using midpoints of all three sides? You are asked to do this in Exercise Set 12.3 Q1 below.

Think and Reflect

Read the statement of the Midpoint Theorem again. The following questions seem natural to ask. What can we say about (1) a segment PQ (with P on side AB and Q on side AC) that is parallel to the third side and has half the length, and (2) the line that passes through the midpoint of one side and is parallel to another side? We will address question (1) in Exercise 22 at the end of the chapter. For now, experiment and see if you can make a guess about question (2). It appears that this line must bisect the remaining side! Let us try to justify this.

Geometric reasoning: To set up, take ΔABC and suppose the line through midpoint P of AB, drawn parallel to BC, meets AC at point Q. Again draw the line parallel to BA through C, intersecting line PQ at point R. Tracing the proof of the Midpoint Theorem backwards works easily as follows.

© NCERT not to be republished



Fig. 12.15

BCRP is a parallelogram, so CR = BP. BP = PA and $\angle AQP = \angle CQR$ (vertically opposite angles).

Combining with CR ∥ BA, $\Delta APQ \cong \Delta CRQ$. (Why?)

This gives two equalities.

First, AQ = QC, so Q is the midpoint of AC.

Second, $PQ = QR$, so $PQ = \frac{PR}{2} = \frac{BC}{2}$.

We have deduced the following important fact. It can be considered a converse of the Midpoint Theorem, for reasons we will see in Exercise 22 at the end of the chapter.

Theorem 7 (Converse of the Midpoint Theorem): *The line drawn through the midpoint of one side of a triangle and parallel to another side bisects the third side (and the resulting segment has half the length of the parallel side).*

Let us see a different reasoning to justify Theorem 7. Read this short proof carefully.



Fig. 12.16

Another proof of Theorem 7. Recall our previous setup: the line parallel to BC through midpoint P of AB meets AC at point Q. Ignore this line for now and instead consider the midpoint M of AC. We want to show M = Q. We have PM ∥ BC by the Midpoint Theorem. Therefore line PM = line PQ, because there is a unique line parallel to BC through P. As lines PM and PQ coincide, they must intersect AC in the same point. Thus M = Q. This is what we wanted!

We used the Midpoint Theorem to prove its converse! This may look like cheating because, as emphasised earlier, the truth of a statement and of its converse are separate issues. But there is no mistake here. There is a key new point in this proof, namely that there is a unique line through a given point and parallel to a given line. This proof illustrates that sometimes we can use a theorem to prove its converse.

© NCERT not to be republished

In Grade 10, we will generalise Theorem 7 by dropping the condition that P is the midpoint of AB and assuming only that PQ ∥ BC. Can you guess the conclusion in this case? (**Hint:** the name of the more general theorem includes the word proportionality.)

12.3.2 A Surprising Property of Medians

The Midpoint Theorem allows us to deduce an important fact about triangles. Let us discover it experimentally. In ΔABC, suppose P, Q and R are the midpoints of side AB, AC and BC respectively. Instead of joining the midpoints with each other as we did earlier, draw segments AR, BQ and CP. These are called the **medians** of ΔABC. What do you see? Repeat this for several triangles and see that the three medians always seem to be concurrent, meaning they pass through a common point!



Fig. 12.17

There is more! Assume for the moment that the medians are always concurrent. Let M be the common point where they meet. Compare the lengths of the two parts CM and MP of the median CP, and do the same for the other two medians. Do you see a pattern? It appears that the ratio CM : MP = 2 : 1. We will now show why this is always true.

Geometric reasoning: It seems difficult to keep track of the three medians at once, so let us first examine only two medians CP and BQ. Call their intersection point M. We want to show that CM = 2MP and BM = 2MQ.



Fig. 12.18

We have not yet seen any theorem that gives a 2 : 1 division of a segment. The Midpoint Theorem only gives a 1 : 1 ratio. So to show that CM = 2MP, one idea is to bisect CM and try to show that the resulting three parts of CP are equal.

Let Y and X be the midpoints of CM and BM respectively. Now we can use the Midpoint Theorem in ΔABC and in ΔMBC! We get

© NCERT not to be republished

that PQ and XY are parallel to BC and hence to each other. Moreover PQ = XY = $\frac{BC}{2}$. So $\Delta MPQ \cong \Delta MYX$ by ASA (How?). Therefore MQ = MX = XB and MP = MY = YC. This shows CM : MP = 2 : 1 = BM : MQ.

What about the third median AR? We can repeat the argument in the previous paragraph with medians AR and BQ! Let N be the point at which the AR and BQ intersect.



Fig. 12.19

Now the same reasoning gives BN : NQ = 2 : 1 = AN : NR. (Use Fig. 12.19 if you wish to repeat the reasoning.) We already had BM : MQ = 2 : 1, so BM : MQ = 2 : 1 = BN : NQ. But this means M and N have to be the same point, because there is only one point that divides BQ in a given ratio. Thus M lies on all three medians and divides each median in the ratio 2 : 1. We have deduced the following important fact.

Theorem 8: (Centroid Theorem) *The three medians of ΔABC pass through a common point, which divides each of the medians in the ratio 2 : 1, with the longer part connecting to the vertex. This point is called the centroid of ΔABC.*

Think and Reflect

Give another proof of the Centroid Theorem using a clever construction that we will describe only partly and ask you to complete. Once again let M be the intersection point of the two medians CP and BQ. We want to show that the intersection point of line AM with side BC is the midpoint of BC. For this, extend AM up to a carefully chosen point S such that BSCM becomes a parallelogram. (**Hint:** To arrange MC ∥ BS, first note that PM and MC are along the same line. Now where should M be on segment AS? Does your placement of S also prove MB ∥ CS?)



Fig. 12.20

© NCERT not to be republished

We started this section by examining the triangle formed by midpoints of the sides of a triangle. What happens if we use midpoints of the sides of a quadrilateral to make another quadrilateral? Experiment and see what this new quadrilateral looks like. It appears to be a parallelogram! Let us try to justify this using reasoning.



Fig. 12.21

Geometric reasoning. Suppose the midpoints of sides AB, BC, CD and DA of a quadrilateral ABCD are P, Q, R and S respectively. The Midpoint Theorem applied to ΔABC and to ΔADC gives, respectively, PQ ∥ AC and SR ∥ AC. So PQ ∥ SR. Using the Midpoint Theorem in ΔBCD and in ΔBAD gives QR ∥ PS. Therefore PQRS is a parallelogram.

We have deduced the following interesting fact, also known as Varignon's theorem.

Theorem 9 (Midpoint Theorem for Quadrilaterals): *The midpoints of the four sides of a quadrilateral are the vertices of a parallelogram. This is called the Varignon parallelogram of the original quadrilateral.*

Exercise Set 12.3

1. (i) If P, Q, R are the midpoints of sides AB, AC, BC respectively of ΔABC, show that ΔPQR is congruent to ΔQPA and to two other triangles which you should identify.
   (ii) Suppose someone erases ΔABC, leaving only ΔPQR on the paper. Can you reconstruct ΔABC from ΔPQR?



Fig. 12.22

© NCERT not to be republished

2. In ΔABC, let M and N be midpoints of AB and AC respectively. Let D be any point on BC. Show that MN bisects AD.



Fig. 12.23

3. In a quadrilateral ABCD, suppose AB ∥ DC and AB ≠ CD. Suppose G and H are the midpoints of AC and BD respectively. Prove that GH ∥ AB. (Why did we assume AB ≠ CD?)



Fig. 12.24

4. Suppose the midpoints of sides AB, BC, CD and DA of a quadrilateral ABCD are P, Q, R and S respectively.
   (i) Show that PR and QS bisect each other.
   (ii) Show that if AC = BD, then PR and QS are perpendicular. Is the converse true?

5. Suppose PQRS is the Varignon parallelogram of ABCD.



Fig. 12.25

   (i) Copy only PQRS on another paper. Show how you will recreate a congruent copy A′B′C′D′ of ABCD from PQRS. This will be relevant when we return to study tilings at the end of this chapter. (**Hint:** How will you place vertex A′? How will you place B′, C′ and D′?)

© NCERT not to be republished

(ii) There are multiple ways to construct A′B′C′D′ in (i). Justify why the quadrilateral A′B′C′D′ you constructed is congruent to ABCD. You may need to show why S is collinear with the points A′ and D′ that you constructed, and similarly for P, Q and R. (**Hint:** Use congruence of triangles, for example $\Delta SDR \cong \Delta SD'R$.)

(iii) Show that if PQRS is a square, then AC and BD are perpendicular and equal. Prove the converse.

12.4 Tiling the Plane Using Any 4-gon

There are many ways to tile the plane, using a single shape or multiple shapes, leading to beautiful pictures. These occur in mosaics in several ancient civilizations to more recent artwork, such as that of M.C. Escher, in nature (for example, a honeycomb) and in decorative patterns we encounter in daily life.





Fig. 12.26

We will see how the plane can be tiled with any given 4-gon, not just a parallelogram as we saw at the beginning of the chapter.

Before you see the answer in Fig. 12.28, see the hints below and try to find a tiling using the given irregular 4-gon SOME. First, trace SOME on paper with its four angles labelled 1, 2, 3, 4. Remember that they add up to 360°. Cut out 15 identical copies.

© NCERT not to be republished

Throughout this section, we will focus on experimental verification of our methods. However, you are encouraged to try to prove, on your own, that they work.

Think and Reflect

Suppose we have a tiling of the plane. Consider any vertex. As we go around this vertex and consider the angles made by consecutive lines, the total of these angles must be 360°. This suggests an idea. What if we take 4 copies of SOME and fit them together around a common point so that each angle is used once as we go around?

There are multiple ways of doing this, as shown in Fig. 12.27. Can you use any of these ways to continue fitting further copies of SOME to tile the plane? Try it with the 15 copies you made!



Fig. 12.27

Here is how one can tile! Recreate it with your pieces.



Fig. 12.28

How can we understand the figure? There seems to be a repeating pattern. (1) Can you precisely describe a procedure to draw the pattern

© NCERT not to be republished

so that someone can draw the tiling on their own, based only on your description? (2) Can you justify why your procedure works?

We will sketch two methods and ask you to complete the details.

Method 1: We start with two copies of SOME, one exactly above the other. Rotate the top copy by 180° around the midpoint of OM. The rotated copy aligns with the original copy perfectly along the shared edge OM.



Fig. 12.29

Now repeat this procedure at each edge of every copy of SOME that you add. Verify that this will result in a tiling! Two steps of a possible continuation are shown in Fig. 12.30. The first step (Fig. 12.30 A) adds 4 copies around the starting copy and the second step (Fig. 12.30 B) adds 4 more copies. Note two interesting things about the second step: (1) each new copy can be obtained by rotating any one of its neighbours, and both ways give the same result. (2) The new copies fit perfectly. Can you explain these facts by reasoning? This is needed to prove that the method works!

Do you see which of the three possibilities shown in Fig. 12.27 occurs in the tiling?



Fig. 12.30 A *Fig. 12.30 B*

© NCERT not to be republished

Method 2. Before we explain Method 2, let us conduct a thought experiment. Remember the Varignon parallelogram for 4-gons (Theorem 9). Imagine that we have drawn this parallelogram in each copy of SOME in the tiling shown earlier in Fig. 12.28. Visualise what the picture looks like. Fig. 12.31 shows the result: It appears that the Varignon parallelograms form a grid, giving the same parallelogram tiling we saw in the introduction!

This suggests an idea. What if we start by drawing just the simple grid tiling made by the Varignon parallelogram of SOME? Can we use this grid to construct the new tiling by SOME?



Fig. 12.31

A grid of Varignon parallelograms of SOME is given in Fig. 12.32. To begin with, focus only on the 9 green coloured copies of SOME in Fig. 12.31. We will first place only these 9 copies in Fig. 12.32. The corresponding parallelograms are shaded in Fig. 12.32. Place 9 copies of SOME so as to match the way the green coloured copies of SOME are placed in Fig. 12.31 (You were asked to give a precise description of how to do this in Exercise Set 12.3, Q5.) If done carefully, you will observe that each

4-gon you placed meets other placed copies exactly at vertices. Now see how 4 copies of SOME are made automatically in the gaps! Carefully place four more copies of SOME in these gaps. Continuing this process with more copies of SOME will give us the desired tiling.



Fig. 12.32

It should be emphasised that our procedure needs to be justified to assure us that it will always work. We will not do this here, but invite you to try it on your own!

Mathematicians have found many interesting ways to tile the plane using a small set of shapes. Some of these, called aperiodic tilings, turned out to be useful to describe atomic arrangements of quasicrystals—new physical structures that were discovered some time later. The discovery of quasicrystals, made by Dan Shechtman, was very surprising because the atomic arrangement was outside what was then considered physically possible. It led to a broader scientific understanding of the nature of order in solids. Dan Shechtman won the chemistry Nobel prize in 2011 for his discovery.

© NCERT not to be republished

A Cutting-edge Discovery

The following shape—the first of its kind!—that leads to aperiodic tilings was discovered only recently in 2023 by a team of four mathematicians (Smith, Myers, Kaplan and Goodman-Strauss).

Cut out 15 identical copies of the following shape (known as the 'hat') and start to tile with it. Do you see any pattern? You will find that the hat shape will tile the plane endlessly, but without ever quite repeating the same pattern. That is why it is called an 'aperiodic' tiling.



Exercise Set 12.4

1. Justify why the plane cannot be tiled with a regular pentagon. (**Hint:** Read the first 3 sentences of 'Think and Reflect' in the section on tiling.) (There are many ways to tile the plane using a suitable irregular pentagon. The most recent method was found in 2015.)



A = 60°
B = 135°
C = 105°
D = 90°
E = 150°

$a = 1$

$b = \frac{1}{2}$

$c = \frac{1}{\sqrt{2}(\sqrt{3}-1)}$

$d = \frac{1}{2}$

$e = \frac{1}{2}$



© NCERT not to be republished

2. Draw a non-convex 4-gon DART. Show how we can tile the plane with copies of DART. Both methods that we discussed earlier will work. Which do you prefer?

End-of-Chapter Exercises

1. Using a fact about parallelograms, show how to tile the plane using any given triangle. (**Hint:** Can you use the parallelogram tiling in the introduction?)
2. Mark the midpoint of the line drawn on the paper (see Fig. 12.33), given that the horizontal lines are equally spaced. Justify your answer.



Fig. 12.33

3. You know that the sum of angles of a quadrilateral is 360°, even for a non-convex quadrilateral. (Recall the proof.) Now consider a self-intersecting quadrilateral ABCD, where AB and CD intersect at point E. Show that $\angle A + \angle B + \angle C + \angle D < 360°$. Can you construct ABCD such that $\angle A + \angle B + \angle C + \angle D = 2°$?
4. In a parallelogram ABCD, two points P and Q are taken on diagonal BD such that DP = BQ (see Fig. 12.34). Show that APCQ is a parallelogram.



Fig. 12.34

© NCERT not to be republished

5. A right-triangle shaped cutout of a paper is folded such that point A touches point B (Fig. 12.35). Show that the crease line can be used to find the midpoint of not only AB but also that of AC.



Fig. 12.35

6. You saw how to use the Midpoint Theorem to divide a given triangle into 4 congruent triangles. Can we divide a triangle into 3 congruent triangles? This exercise shows us how to do that and more, provided we are allowed to cut and reassemble.

   (i) Draw medians AP, BQ and CR of ΔABC, meeting in a common point M. Cut along each median to get 6 triangles. Show with justification how to assemble the 6 pieces into 3 congruent triangles! (**Hint:** Align ΔMPB and ΔMPC along equal sides PB and PC, matching P with itself and B with C.) Prove that you get a triangle. What are its side lengths?

   *(ii) Repeat the procedure with each of the 3 assembled triangles you got in (i). Show that each of the resulting 9 triangles has sides $\frac{AB}{3}$, $\frac{BC}{3}$ and $\frac{AC}{3}$.

   The procedure and the result above were unnoticed till 2014, when they were discovered by Lee Sallows, an amateur mathematician!

   (iii) Naturally, we can next ask about the possibility of cutting a triangle and reassembling it into 2 congruent triangles. You were asked this question in the chapter *Measuring Space: Perimeter and Area*. Can you solve this now? (**Hint:** Use median AP in ΔABC and then a median of ΔAPB.)

   For any two given figures with straight sides, we can ask whether one figure can be cut (using only straight cuts) into pieces and reassembled to make the other. This notion is

© NCERT not to be republished

called scissors congruence. The figures need not be in the plane. Research on such questions at a higher level is ongoing.

7. **A more general midpoint theorem and its converse.** In a quadrilateral ABCD, suppose AB ∥ DC. Recall that such ABCD is called a trapezium. Let E be the midpoint of AD. A line drawn through E intersects side BC at F.



Fig. 12.36

(i) If EF ∥ AB, then show that F is the midpoint of BC. Conclude that EF = $\frac{(AB + CD)}{2}$.

(ii) If F is the midpoint of BC, then show that EF ∥ AB.

There are at least two ways to solve (ii). Do it directly by using the midpoint M of BD and showing that EM and FM are the same lines. Or use (i) along with the same idea used in the second proof of the converse of the Midpoint Theorem. Which way do you think is simpler?

8. The diagonals AC and BD of a parallelogram ABCD intersect at O. A line through O meets AB and CD at points P and Q respectively. Show that O is the midpoint of PQ. (Multiple proofs are possible. Which is the simplest?)



Fig. 12.37

*9. ABCD is a trapezium with parallel sides AD = 3 cm and BC = 5 cm. E and F are the midpoints of the non-parallel sides. Find the ratio of the areas of the 4-gons AEFD and EBCF.

© NCERT not to be republished



Fig. 12.38

10. Consider 4 points A, B, C, D in the plane with no three collinear. Answer the following questions. Some answers may require you to consider different cases, depending on how the points are positioned in the plane.
    (i) How many different quadrilaterals do they form if the quadrilateral is allowed to be self-intersecting or non-convex?
    (ii) How many of these quadrilaterals are self-intersecting? How many are convex?

11. Suppose P is a point on side AB of ΔABC and the line through P parallel to BC meets AC in point Q. For parts (i) to (iii), assume AP = 1, AQ = $\sqrt{5}$, and see Fig. 12.39.



Fig. 12.39

(i) If PB = 2 find QC. (**Hint:** See the dotted line)

*(ii) If PB = $\frac{1}{3}$ find QC. (**Hint:** See the dotted lines)

*(iii) If PB = $\frac{2}{3}$ find QC.
(**Hint:** Divide both PB and AP suitably.)

*(iv) Show that if $\frac{AP}{PB}$ is a rational number, then $\frac{AP}{PB} = \frac{AQ}{QC}$. In Grade 10, you will prove this equality without assuming $\frac{AP}{PB}$ is rational. That will require a new idea.

© NCERT not to be republished

12. (i) Suppose ABCD is a parallelogram and M, N are midpoints of AB and CD respectively. Show that segments DM and BN trisect segment AC.
    (ii) Use part (i) to find a procedure to trisect any given segment PQ. Find two other ways to trisect PQ, one using Exercise 11 above and a third using the Centroid Theorem.



Fig. 12.40

13. Is the Midpoint Theorem for Quadrilaterals (Theorem 9) true when the quadrilateral is non-convex? How about when it is self-intersecting? Experiment and check. The pictures may look strange, but the theorem appears to be true.
    (i) Can you explain why this is so? See the geometric reasoning in the text.
    (ii) There is one exception: In a very special case the Varignon parallelogram becomes a single segment. When will this happen?
    *(iii) Does your reasoning apply even when ABCD is non-planar?

14. Let P, Q, R, S be four points on sides AB, BC, CD and DA respectively of a quadrilateral ABCD. Suppose PQRS is a parallelogram. Must P, Q, R and S be midpoints of the respective sides? This can be considered a possible converse question to Theorem 9.

15. (i) Complete the following proof of the Midpoint Theorem. Extend segment PQ beyond Q until point S. By how much should we extend PQ?



Fig. 12.41

© NCERT not to be republished

It would be good to be able to prove that $\Delta APQ \cong \Delta CSQ$. (Why?) Use this as a guide to specify the location of S and then complete this proof.

(ii) Give a similar proof of the converse of the Midpoint Theorem (Theorem 7). Start by extending PQ up to a suitable point S.

*16. Review all the properties of a rhombus/rectangle/square that you proved in Grade 8. Formulate a converse of each. Decide if the converse is true. There are many possibilities here!

*17. Show that the sum of angles of a non-planar quadrilateral is always less than 360°. Can you find a non-planar quadrilateral ABCD for which $\angle A + \angle B + \angle C + \angle D = 2°$?
(**Hint:** Think of a diagonal, say AC, as a hinge around which triangles ABC and ADC can rotate.) What happens to each angle of ABCD as you do this rotation?

*18. Let us see a third method to tile the plane using a 4-gon.

Focus on only two *coloured copies* of SOME sharing a vertex. What do you see? It appears that each 4-gon is just a shifted copy of the other. Let us see exactly how. Draw two copies of SOME as shown in Fig. 12.42 so that the diagonals EO and E′O′ are collinear with O = E′. Now place a cutout of one copy on top of SOME with diagonal EO drawn on it. Slide this cutout so that segment EO moves along EO′ until EO matches E′O′. Verify that your cutout exactly matches S′O′M′E′.



Fig. 12.42

(i) Prove the exact match of SOME with S′O′M′E′ using four parallelograms.

(ii) Follow the described procedure along each diagonal of the starting coloured 4-gon in both directions to get 4 new 4-gons. Using these 4 copies, repeat the procedure 4 more

© NCERT not to be republished

times to place 4 new copies, resulting in a 3 by 3 grid of 9 copies exactly like the 9 coloured copies in Fig. 12.42. These 9 copies meet each other only at vertices and once again the blank spaces among them also form 4-gons congruent to SOME!

*19. **Is there a 4-gon with given side lengths?**

(i) Recall the following fact about triangles and check it by construction. For given positive numbers a, b, c, is there a triangle whose sides have these lengths? The answer is Yes exactly when the sum of any two numbers is greater than the third. If we arrange the numbers in increasing order (suppose $a \le b \le c$), then this amounts to requiring $a + b > c$. (**Hint:** Start by drawing a segment of length c.)

(ii) Suppose a 4-gon has 2, 5, 11 as three side lengths. Can the length of the fourth side be 100? Can it be 10? Can it be 1? What are the possible lengths of the fourth side?

(iii) For given positive numbers a, b, c, d, how will you decide if there is a 4-gon whose sides have these lengths?

*20. **Counting diagonals of a polygon.**

(i) How should we define a diagonal of an n-gon? How many diagonals does an n-gon have? Make a table for small values of n. A 3-gon has no diagonals. A 4-gon has 2. How many diagonals does a 5-gon have? A 6-gon? Try to find a pattern and guess the answers for $n = 7$ and $n = 8$. Check your guesses by systematic counting.

(ii) Can you guess a formula for the number of diagonals? How many diagonals get added when we increase the number of sides by 1? Can you now justify why the formula you guessed is true for all n?

*21. **Sum of angles of a polygon.** What is the sum of angles of a (planar non-self-intersecting) n-gon? We know that the answer is 180° for $n = 3$ and 360° for $n = 4$. Find the next few values. Then find a formula in terms of n and prove it.

*22. **Multiple converses to a theorem.** Let us see how multiple statements can be considered converses to the Midpoint Theorem and how Theorem 7 is one of them.

To formulate a converse we should express the original statement in "If ... then ..." form. For a complex statement, there may be multiple ways to do that. The Midpoint Theorem starts with ΔABC and points P and Q on sides AB and AC respectively.

© NCERT not to be republished

The theorem has two assumptions and two conclusions, which we have named for further discussion.

Assumptions:	(P MID) P is the midpoint of AB, and	(Q MID) Q is the midpoint of AC.
Conclusions:	(PRLL) PQ ∥ BC, and	(HALF) PQ = $\frac{BC}{2}$.

Let us use these four named conditions to discuss various possible statements.

(i) A natural converse of the Midpoint Theorem would be: "If (PRLL) and (HALF) are true, then (P MID) and (Q MID) are true." Write out this statement fully. Experiment and see that it seems to be true! Prove the statement. (**Hint:** Try to run a proof of the Midpoint Theorem backwards.)

(ii) To see Theorem 7 as a converse of the Midpoint Theorem, we first write the Midpoint Theorem as follows: "Suppose P is the midpoint of side AB of ∆ABC and Q is a point on side AC. If Q is the midpoint of AC then PQ ∥ BC." (Also PQ = $\frac{BC}{2}$, but let us set that aside for now.) Write the converse of the second sentence in quotes by keeping the first sentence the same. Verify that Theorem 7 is what you get! (And PQ = $\frac{BC}{2}$ also follows.) Now write Theorem 7 in terms of the four named conditions.

(iii) The discussion so far suggests that it is reasonable to take two of the four listed statements as assumptions and ask if the other two are true. Verify that only one such combination remains to be examined. "If (P MID) and (HALF) are true, then can we conclude (Q MID) and/or (PRLL)?" Write this out in words. This is a precise version of question (1) stated before Theorem 7. Can you answer it?

In the text, why did we focus only on Theorem 7 among the multiple possibilities? Because Theorem 7 turns out to be particularly useful. It is still important to pursue various avenues while exploring a subject: often it is only after examining multiple possibilities that we can judge what is most valuable.

*23. **Validity of tiling methods.** Show using reasoning that each of the three tiling methods we saw produces a tiling of the plane

© NCERT not to be republished

using the given 4-gon. You have to prove that when we place new copies using any of the three procedures, the entire plane is covered with no gaps and no overlaps. First, think carefully about what it means to prove this. Then find a proof for each procedure.

*24. What fraction of the square is shaded?



Fig. 12.43

Chapter Summary

- **Quadrilateral:** For four distinct points A, B, C, D in a plane with no three collinear, the **quadrilateral** ABCD is a collection of all points on segments AB, BC, CD, DA provided every point other than A, B, C, and D lies on exactly one of these four segments.
- A quadrilateral is **convex** when all of its internal angles are less than 180°, or equivalently, when its diagonals intersect.
- The following converse statements about parallelograms are true:
  - If the opposite sides of a 4-gon are equal, then it is a parallelogram.
  - If the opposite angles of a 4-gon are equal, then it is a parallelogram.
  - If the diagonals of a 4-gon bisect each other, then it is a parallelogram.
  - If a pair of opposite sides of a 4-gon are equal and parallel, then it is a parallelogram.

© NCERT not to be republished

- **The Midpoint Theorem:** the line joining the two midpoints of any two sides of a triangle is parallel to the third side and has half the length of the third side.
- **A Converse to the Midpoint Theorem:** the line passing through the midpoint of a side of a triangle and parallel to a second side bisects the third side.
- Medians of a triangle are concurrent and the point of concurrence, called the **centroid**, divides each median in a 2 : 1 ratio.
- The 4-gon formed by joining the midpoints of a given 4-gon is always a parallelogram.
- The plane can be tiled with any given 4-gon.

© NCERT not to be republished

13 Two Variables, One Line

0905CH13

In Chapter 2 of *Ganita Manjari*, Part I, we explored linear patterns and learnt about linear polynomials. In this chapter, we will go a step further in exploring linear equations in two variables, by learning how to solve a **pair** of linear equations.

13.1 Linear Equations in Two Variables

Radha stops at a fruit cart. The price tags say that mangoes cost ₹60 per kg and bananas cost ₹50 per kg. She buys some kilograms of mangoes and some kilograms of bananas. Altogether, she pays ₹280. Can we express this situation as an equation?

Since we do not know how many kilograms of mangoes or bananas she bought, let us assume that

x = number of kilograms of mangoes

y = number of kilograms of bananas

The cost of the mangoes is ₹60x and the cost of the bananas is ₹50y.

The total cost is ₹280. Hence, we can express this using the linear equation

$$60x + 50y = 280.$$

Notice that the left-hand side (LHS) and the right-hand side (RHS) of the equation both represent the same quantity, that is, the total cost (in ₹).

The equation $60x + 50y = 280$ is a **linear equation in two variables**.

© NCERT not to be republished

13.1.1 Standard Form of Linear Equations in Two Variables

Any equation that can be expressed in the form $ax + by + c = 0$, where a, b and c are real numbers, and a and b are not both zero, is called a **linear equation** in two variables.

$ax + by + c = 0$ is referred to as the **standard form** of the linear equation. Here a and b are the coefficients of the variables x and y respectively and c is a constant.

It is useful to note the following:

(i) The coefficients a and b and the constant c can also be rational numbers. For example, $\frac{1}{4}x + \frac{3}{5}y - \frac{1}{2} = 0$ is also a linear equation in two variables in standard form. However, for convenience, in such cases we often multiply the equation by a suitable number to remove the fractions and write the equation with integer coefficients. Here we can multiply by 20 to get the equation $5x + 12y - 10 = 0$.

(ii) Equations of the type $ax + c = 0$ are special cases of linear equations in two variables as they can be expressed as $ax + 0 \times y + c = 0$. For example, $7 + 4x = 0$ can be written as $4x + 0 \times y + 7 = 0$, with $a = 4$, $b = 0$ and $c = 7$.

Example 1: Write each of the following equations in standard form, $ax + by + c = 0$, and indicate the values of a, b and c in each case:

(i) $5x + 2y = 2.7$ (ii) $\frac{x}{2} - 4 = \frac{3}{2}y$ (iii) $4 = 1.5x - 1.3y$

(iv) $3y = 5$

Solution:

(i) $5x + 2y = 2.7$ can be written as $5x + 2y - 2.7 = 0$. Here $a = 5$, $b = 2$ and $c = -2.7$. The equation can also be rewritten as $-5x - 2y + 2.7 = 0$. In this case $a = -5$, $b = -2$, $c = 2.7$.

(ii) $\frac{x}{2} - 4 = \frac{3}{2}y$ can be written as $\frac{x}{2} - \frac{3}{2}y - 4 = 0$.
Here $a = \frac{1}{2}$, $b = -\frac{3}{2}$ and $c = -4$.

(iii) $4 = 1.5x - 1.3y$ can be written as $1.5x - 1.3y - 4 = 0$.
Here $a = 1.5$, $b = -1.3$ and $c = -4$. It can also be written as $-1.5x + 1.3y + 4 = 0$. In this case $a = -1.5$, $b = 1.3$ and $c = 4$.

(iv) $3y = 5$ can be written as $0 \times x + 3y - 5 = 0$. Here $a = 0$, $b = 3$ and $c = -5$.

© NCERT not to be republished

EXERCISE SET 13.1

1. Write a linear equation in two variables in which $a = 3$, $b = 0$ and $c = -\frac{1}{5}$.

2. Complete the following table after expressing the given linear equations in standard form.

Linear equation in two variables	Standard Form	Coefficient of x	Coefficient of y	Constant term
$y - 15 = \sqrt{2}x$				
$3y - 2x = 0$				
$5x = 3y$				
$x = 8$				
$3y = 1$				

3. (i) The cost of a notebook is twice the cost of a pen. Consider the cost of a notebook to be ₹t and that of a pen to be ₹p. Charlie wrote $t = 2p$, whereas Meera wrote $p = 2t$. Which of these two representations is correct?

   (ii) In a one-day International Cricket match between India and Sri Lanka played in Nagpur, two Indian batsmen together scored 176 runs. Manisha expressed this situation as $x + y = 176$, where the number of runs scored by one batsman is x, and the number of runs scored by the other is y. Is this a correct representation?

© NCERT not to be republished

13.2 Solution of Linear Equation in Two Variables

In earlier grades, we have seen how to solve linear equations in one variable. What can we say about the solution of a linear equation involving two variables?

13.2.1 Algebraic Meaning of Solution

A **solution** of a linear equation in two variables is a pair of values of x and y which satisfy the given equation.

Let us consider the equation $3x + 2y = 12$.

Here, $x = 2$ and $y = 3$ is a solution because substituting the values of x and y into the given equation satisfies the equation.

Note that, $3x + 2y = (3 \times 2) + (2 \times 3) = 12$.

A solution can be written compactly as a pair of numbers. For example, the solution $x = 2$ and $y = 3$ can be written as (2, 3). The order of the numbers in this pair matters: the first number is the x-value, and the second number is the y-value. Hence we call this an **ordered pair**.

Similarly, (4, 0) is also a solution of the equation $3x + 2y = 12$ since substituting $x = 4$ and $y = 0$ leads to $3x + 2y = (3 \times 4) + (2 \times 0) = 12$.

What about the ordered pair (1, 3)?

We see that $3x + 2y = 3 \times 1 + 2 \times 3 = 9 \neq 12$. So, (1, 3) is not a solution.

Think and Reflect

Are $\left(1, \frac{9}{2}\right)$, (0, 6), (4, 1) and $\left(\frac{1}{2}, \frac{21}{4}\right)$ solutions of the equation $3x + 2y = 12$?

Can you find any other solution? How many solutions can you find?

Suppose we are given a linear equation in two variables. For any value u that we assign to x, we can find a value v for y such that (u, v) is a solution. We first substitute u for x in the equation. This gives us a new linear equation in y that can be solved to find v. This allows us to generate an infinite number of solutions to the original equation.

13.2.2 Geometric Visualisation of Solutions

Consider all the solutions of a linear equation in two variables, expressed as ordered pairs. What do we get when we plot the points corresponding to these ordered pairs?

The equation $3x + 2y = 12$ can be rewritten as

$2y = -3x + 12$ or $y = -\frac{3}{2}x + \frac{12}{2}$ which is the same as $y = -\frac{3}{2}x + 6$

© NCERT not to be republished



Fig. 13.1

We have already seen in the chapter on Linear Polynomials that plotting the solutions of an equation of the form $y = mx + d$ leads to a straight line joining them. Every solution (x, y) of the equation is a point on the line.

Clearly the solutions of $y = -\frac{3}{2}x + 6$ are the same as those of $3x + 2y = 12$. Hence the graph of $3x + 2y = 12$ is the same as that of $y = -\frac{3}{2}x + 6$.

Example 2: Find any two solutions of $2x + y = 7$. Draw the graph of this equation. Use the graph to find 4 more solutions.

When we substitute $x = 0$ in the equation, we get $(2 \times 0) + y = 7$, that is, $y = 7$. Hence one solution is (0, 7). By substituting $y = 0$, we get $2x + 0 = 7$, that is, $x = \frac{7}{2}$. Thus, $\left(\frac{7}{2}, 0\right)$ is also a solution.

© NCERT not to be republished

We can represent these solutions or ordered pairs in the form of a table.

x	0	$\frac{7}{2}$
y	7	0

Using these two points, we can draw the graph of the equation.



Fig. 13.2: Graph of the linear equation $2x + y = 7$

From the graph, we see that (1, 5), (2, 3), (3, 1), $\left(\frac{3}{2}, 4\right)$ are also solutions of $2x + y = 7$.

Note that an easy way of identifying two points on a line is to substitute $x = 0$ in the linear equation and obtain the corresponding value of y. This will give us the point where the line intersects the y-axis. Similarly, we can substitute $y = 0$ and obtain the corresponding value of x. This will give us the point where the line intersects the x-axis.

Example 3: Find any two solutions for each of the following equations and draw their graphs:

(i) $4x + 3y = 12$ (ii) $2x + 5y = 0$

Solution:

(i) Substituting $x = 0$ in the equation, we get $3y = 12$, that is, $y = 4$. So (0, 4) is a solution of the given equation. Similarly, by substituting $y = 0$, we get $x = 3$. Thus, (3, 0) is also a solution.

© NCERT not to be republished



Fig. 13.3: Graph of the linear equation 4x + 3y = 12

(ii) Substituting $x = 0$, we get $5y = 0$, that is, $y = 0$. So (0, 0) is a solution of the given equation. To get another solution, substitute $x = 1$. The corresponding value of y is $-\frac{2}{5}$. So, $(1, -\frac{2}{5})$ is also a solution. In fact, we can substitute any value for x and obtain a corresponding value of y. For example, substituting $x = 5$ we obtain $y = -2$. Let us represent these solutions or ordered pairs in the form of a table.

x	0	1	5
y	0	$-\frac{2}{5}$	–2

When we plot the ordered pairs A (0, 0), B $\left(1, \frac{-2}{5}\right)$ and C (5, –2) we see that they lie on a line.



Fig. 13.4: Graph of the linear equation 2x + 5y = 0

© NCERT not to be republished

Example 4: In the equations shown below, a and b are unknown numbers.

$$3ax + 4y = -2$$
$$2x + by = 14.$$

If (–3, 4) is the solution of both equations, find the values of a and b.

Solution:

Step 1: Substitute (–3, 4) into the first equation, (that is, $x = -3$ and $y = 4$).

$$3a(-3) + 4(4) = -2$$
or $$-9a + 16 = -2$$
or $$-9a = -18$$
or $$a = 2$$

Step 2: Substitute (–3, 4) into the second equation.

$$2(-3) + b(4) = 14$$
or $$-6 + 4b = 14$$
or $$4b = 20$$
or $$b = 5$$

Think and Reflect

Four friends — Ranju, Meena, Farhan, and Toshi — are solving problems.

Ranju: I noticed something! If $c = 0$ in the standard form of a line $ax + by + c = 0$, then the line must pass through the origin. Look, if I substitute $x = 0$ and $y = 0$, in equation $ax + by = 0$, the equation is satisfied. So, the origin lies on the line! We can also say that the line passes through the origin.

Farhan: Let us try for the equation $2x + 3y = 0$. Here $a = 2$, $b = 3$ but $c = 0$. If we substitute $x = 0$, then we get $3y = 0$ or $y = 0$. This means (0, 0) lies on the line. So yes, this line passes through the origin.

Toshi: Suppose our equation has $b = c = 0$, say, $5x = 0$. This becomes $x = 0$ which is the equation of the y-axis. And the y-axis passes through the origin.

Meena: And if we take $a = c = 0$, say, $7y = 0$, that means $y = 0$, which is the equation of the x-axis that also passes through the origin.

So, they conclude: Whenever $c = 0$, the line $ax + by + c = 0$ will always pass through the origin, irrespective of the values of a or b. Do you agree with them?

© NCERT not to be republished

EXERCISE SET 13.2

1. Verify if the ordered pair (4, 3) is a solution of $5x - 6y = 2$. Explain your reasoning.
2. Find any two solutions for each of the following equations:

   (i) $7x - 3y = 21$ (ii) $2x + 3y = 5$
3. In the equations given below, m and n are unknown constants: $2mx + 3y = 7$; $4x + ny = -10$. If (2, –1) is the solution of both equations, find the values of m and n.
4. Find two solutions which lie in different quadrants for each of the following linear equations. Identify the quadrants in which the points lie.

   (i) $5x + 3y = 7$ (ii) $5x - 3y = 7$

   (iii) $-5x + 3y = 7$ (iv) $-5x - 3y = 7$

   Verify your solutions by representing the linear equations on a graph paper.
5. Consider the graph of the equation $3x - 7y = 21$ shown below. Does the point C (2, 3) lie on the line? Does it satisfy the equation? Can points that do not lie on the line satisfy the equation?



© NCERT not to be republished

6. State whether the following sentences are True or False. Justify your answer.
   (i) A linear equation in two variables has only one solution.
   (ii) The graph of a linear equation in two variables always passes through the origin.
   (iii) A linear equation in two variables can never have rational solutions.
   (iv) $x = 3$ is a valid linear equation in two variables.
   (v) The equation $2x + 3y = 7$ has infinitely many solutions.
   (vi) The point (1, 2) is a solution of the equation $2x + 3y = 7$.

7. (i) Compare the solutions of the equations $3x + 4y = 7$ and $6x + 8y = 14$. Argue that they have the same set of solutions, that is, every solution of one is also a solution of the other.
   (ii) Show that the equations $ax + by = c$ and $kax + kby = kc$, with $k \neq 0$, have the same set of solutions.

13.3 Slope-intercept form of a Linear Equation in Two Variables

13.3.1 Understanding Slope

Have you ever walked or cycled up a steep hill? How did it feel compared to walking on a flat road? On a flat road, you can move without much effort. But as the road becomes steeper, you have to work harder to climb.

The steeper it is, the more effort is needed to cycle.

In mathematics, the idea of 'steepness' of a line is called its **slope** or **gradient**.

1. A **positive slope** means going 'upward' as we move from left to right.
2. A **negative slope** means going 'downward' as we move from left to right.

© NCERT not to be republished

Fig. 13.5: (i) represents the case of a positive slope, whereas (ii) represents that of a negative slope.



Fig. 13.5

Let us consider a line passing through two points A (x_1, y_1) and B (x_2, y_2).



Fig. 13.6

The horizontal distance between the two points is $(x_2 - x_1)$ and is often referred to as the **Run**. It tells you how far the line goes to the left or right. Moving to the right means a positive run while moving to the left means a negative run.

The vertical distance between the two points is $(y_2 - y_1)$ and is often referred to as the **Rise**. It tells you how much the line goes up or down when moving from one point to another. If the line goes up, the rise is positive. If the line goes down, the rise is negative.

$$\text{The slope of a line} = \frac{\text{Rise}}{\text{Run}} = \frac{y_2 - y_1}{x_2 - x_1}.$$

Consider the graph of the equation shown in Fig. 13.7 which passes through the points A (2, 0) and B (4, 3).

© NCERT not to be republished



Fig. 13.7

Point B can be reached from point A by moving 2 units along the positive x-direction (the run), and 3 units along the positive y-direction (the rise). Hence slope of the line = $\frac{\text{Rise}}{\text{Run}} = \frac{3}{2}$.

Now consider the same line AB further extended beyond B as shown in Fig. 13.8.



Fig. 13.8

© NCERT not to be republished

The slope of the line using points A and B is $\frac{3}{2}$ and using B and D we get $\frac{6}{4} = \frac{3}{2}$. We may therefore conclude that the slope of the line remains the same and is independent of where we measure it on the line.

Think and Reflect

1. Consider the point on the line AB whose x-coordinate is 8. What is the y-coordinate of this point? Express this as an ordered pair.
2. What is the x-coordinate of the point on the line AB whose y-coordinate is 6? Express this as an ordered pair.

Example 5: Consider the straight line that passes through A (–1, 0), B (1, 2), and C (4, 5). Plot the points and find the slope of the line.



Fig. 13.9

Take any two points, say B and C, and find the ratio of vertical step (rise) to the horizontal step (run).

Hence, slope = $\frac{CP}{BP} = \frac{5-2}{4-1} = 1$.

It may be verified that we will get the same slope by considering any two points.

Example 6: Consider the line in Fig. 13.10 which passes through A (–4, 5) and B (–1, 2). Find the slope of the line.

© NCERT not to be republished



Fig. 13.10

If we denote the points A(–4, 5) and B(–1, 2) as (x_1, y_1) and (x_2, y_2) respectively, then

$$\text{Slope} = \frac{AP}{BP} = \frac{2-5}{-1-(-4)} = \frac{-3}{3} = -1.$$

If we do the reverse, taking B(–1, 2) as (x_1, y_1) and A(–4, 5) as (x_2, y_2), then

$$\text{Slope} = \frac{PA}{PB} = \frac{5-2}{-4-(-1)} = \frac{3}{-3} = -1.$$

Hence the slope remains the same irrespective of the order in which we choose the points.

In general, if (x_1, y_1) and (x_2, y_2) are two points on a line, the slope is given by the expression $\frac{y_2 - y_1}{x_2 - x_1}$, and it remains the same for any two points on the line. There is a simple and elegant proof of this result which you will see below.

13.3.2 Slope-Intercept Form

In the chapter on linear polynomials, we were introduced to the fact that in the linear equation $y = mx + d$, 'm' represents the slope or steepness of the line while 'd' represents the y-intercept, that is, the length cut off by the line on the y-axis from the origin. Thus, $y = mx + d$ is also referred to as the **slope-intercept form of a line**.

© NCERT not to be republished

But why does 'm' represent the slope? To understand this let us consider two points A(x_1, y_1) and B(x_2, y_2) which lie on the line $y = mx + d$. Since they satisfy the equation we get, $y_1 = mx_1 + d$ and $y_2 = mx_2 + d$.

Now, the slope of the line passing through the points A and B is

$$\frac{y_2 - y_1}{x_2 - x_1} = \frac{(mx_2 + d) - (mx_1 + d)}{x_2 - x_1} = \frac{mx_2 - mx_1}{x_2 - x_1} = \frac{m(x_2 - x_1)}{x_2 - x_1} = m$$

This is the reason why we can just read off the slope of a line if its equation is in the form $y = mx + d$. This also shows that the slope m of a line with equation $y = mx + d$ is given by $\frac{y_2 - y_1}{x_2 - x_1}$ for any two points (x_1, y_1) and (x_2, y_2) on the line, regardless of which points they are.

Note that the standard form of the equation of a line $ax + by + c = 0$ can be rewritten as

$$by = -ax - c \text{ or } y = -\frac{a}{b}x - \frac{c}{b}, (b \neq 0),$$

which is of the form $y = mx + d$. Here $m = -\frac{a}{b}$ and $d = -\frac{c}{b}$.

Hence $y = mx + d$ is another form of expressing the linear equation $ax + by + c = 0$, provided $b \neq 0$.

Consider the line $5x + y = 3$. Rewrite it as $y = -5x + 3$. Can you now find its slope? What does it mean?

In $y = -5x + 3$, $m = -5$ is the slope, which means for every increase of 1 unit in x, y decreases by 5 units. $d = 3$ is the y-intercept which means the line crosses the y-axis at (0, 3).

Let us make a table of values to draw its graph.

x	0	1	–1
y	3	–2	8

Plotting the ordered pairs A(0, 3), B(1, –2), C(–1, 8) and drawing the line through them we get the graph of $y = -5x + 3$.

Think and Reflect

Can you use the points A, B and C to verify that the slope of this line is indeed –5?

© NCERT not to be republished



Fig. 13.11: Graph of the linear equation $y = -5x + 3$

Let us further explore the geometrical meaning of the slope of a line $y = mx + d$. To do this we will consider the following cases:

1. Positive Slope ($m > 0$). The line goes upward from left to right. As x increases, y increases. In $y = 2x + 1$, the slope is $m = 2$. It means for every unit you move to the right, you also go up 2 units.
2. Negative Slope ($m < 0$). The line goes downward from left to right. As x increases, y decreases. In $y = -3x + 4$, the slope is $m = -3$. It means for every unit you move to the right, you go down by 3 units.
3. Zero Slope ($m = 0$). In this case the line is horizontal and parallel to the x-axis. That is, y remains constant as x changes. For example, in $y = 5$, the slope = $m = 0$.

© NCERT not to be republished



Fig. 13.12: Graph of y = 5

4. Undefined Slope. Here the line is vertical and parallel to the y-axis. x is constant as y changes. The line $x = 2$ is an example. But it is not of the form $y = mx + d$. While calculating the slope of this line we get 0 in the denominator. Since division by 0 is undefined, we take the slope also to be undefined.



Fig. 13.13: Graph of x = 2

© NCERT not to be republished

Exercise Set 13.3

1. The following diagrams represent ski hills. Rank the hills in order of their steepness, from least to greatest.

A

B

C

2. The ramp at a loading dock rises 2.5 metres over a run of 4 metres. Find the slope of the ramp.



3. Find the slope of the line l in each of the following diagrams.

(i)



(ii)



© NCERT not to be republished

(iii)



(iv)



4. An accessibility ramp for wheelchairs is to be made alongside the staircase. The guidelines given for the slope of the ramp is 1 cm vertical rise to 12 cm horizontal length. What should be the horizontal length of the ramp if the total height of the stairs is 18 cm?

13.4. Pair of Linear Equations in Two Variables

Think and Reflect

The cost of one paratha and 2 bowls of *dahi* is ₹90. Also, the cost of 2 parathas and 7 bowls of *dahi* is ₹260. Can you figure out the cost of one paratha and one bowl of *dahi* and explain your reasoning?

Do you remember Rakesh's puzzle from Grade 7? "I have thought of two numbers", he said. "Their sum is 25 and their difference is 11". We solved the problem by making a table and listing possible combinations. We can also solve this using a pair of linear equations.

First Number	Second Number	Sum	Difference
10	15	25	–5
20	5	25	15
18	7	25	11

If the two numbers are x and y, we get the equations

$$x + y = 25 \text{ and } x - y = 11.$$

Such problems lead to a **pair of linear equations in two variables**. A solution to such a pair of equations is an ordered pair (a, b) that satisfies both equations. How do we find a solution? We shall soon see.

Consider another situation. A science exhibition charges an entry fee that is different for adults and children. Here are the amount paid by two different groups.

Group A: 2 adult tickets and 3 child tickets for ₹600

Group B: 3 adult tickets and 2 child tickets for ₹700

How much do individual adult and child tickets cost?

If the cost of one adult ticket is ₹x and one child ticket is ₹y, then:

$$2x + 3y = 600,\ 3x + 2y = 700.$$

This gives us another pair of linear equations in two variables.

A solution to these equations will give us the answer that we seek. Can you see why?

© NCERT not to be republished

In general, a pair of linear equations in two variables x and y can be written as:

$a_1 x + b_1 y + c_1 = 0$ and $a_2 x + b_2 y + c_2 = 0$, where a_1, b_1, c_1, a_2, b_2, c_2 are all real numbers, a_1 and b_1 are not both zero, and a_2 and b_2 are not both zero.

Exercise Set 13.4

Given below are some everyday situations. Construct a pair of linear equations in two variables for each situation:

1. On two different days a family buys movie tickets and snack boxes. Let the cost of one movie ticket be ₹x and the cost of one snack box be ₹y. Frame a pair of linear equations in x and y to represent the following situations:
   (i) On the first day, the family buys 2 movie tickets and 3 snack boxes for ₹850.
   (ii) On the second day, the family buys 4 movie tickets and 1 snack box for ₹1100.
2. Two friends, Sahil and Meena, travelled by taxi. Let the fixed charge for one taxi trip be ₹x and the additional charge per kilometre be ₹y. Frame a pair of linear equations in x and y to represent the following situation:
   (i) Sahil travelled 6 km and paid a total fare of ₹122.
   (ii) Meena travelled 8 km and paid a total fare of ₹160.
3. In a sports meet, tickets for adults cost ₹150 each and tickets for children cost ₹100 each. A total of 200 people attended the meet, and the total amount collected from ticket sales was ₹25,000. (Let the number of adult tickets sold be x and the number of children's tickets sold be y.) Frame a pair of linear equations in x and y to represent this situation.

13.5 Finding Solutions to a Pair of Linear Equations

We have already seen how to solve a linear equation in a single variable. In order to find the solution of a pair of linear equations, we need to think of methods by which we can reduce the pair to a linear equation in one variable. In this section we shall study two methods.

© NCERT not to be republished

13.5.1 Algebraic Methods for Solving a Pair of Linear Equations

Think and Reflect

Solve the puzzle and discuss your strategy with your friends. Can you determine the value represented by each shape?



We note from the first row that the values of 2 triangles and 2 rectangles add up to 28. We may express this as 2T + 2R = 28 or as T + R = 14. Similarly, the last column may be written as 2C + T + R = 22. Here T, S and C represent the values assigned to a triangle, a rectangle and a circle respectively.

Since we know that T + R = 14, we can rewrite the second equation as 2C + 14 = 22, solving which, we get C = 4. Once you have the value of C, you can find the values of the other shapes. Try it for yourself.

We will now learn two methods for solving a pair of linear equations. One is called the **method of substitution** while the other is referred to as the **method of elimination**.

Substitution Method: We will demonstrate the method of substitution by solving a pair of linear equations in two variables.

Example 7: Solve the following pair of equations by substitution method:

$$7x - 15y = 2 \quad (1)$$

$$x + 2y = 3 \quad (2)$$

Solution:

Step 1: We select either of the equations and express one variable in terms of the other.

Let us consider Equation (2), that is, $x + 2y = 3$ and write it as

$$x = 3 - 2y \quad (3)$$

Step 2: Clearly, all (x, y) that satisfy both the given equations must also satisfy $x = 3 - 2y$. Since this relation must hold true in Equation (1), substituting $x = 3 - 2y$ in it we get

$$7(3 - 2y) - 15y = 2$$

© NCERT not to be republished

or $21 - 14y - 15y = 2$

or $-29y = -19$

Therefore, $y = \frac{19}{29}$.

Step 3: We can find the value of x by substituting the value of y in any of the equations. Let us use Equation (3).

$$x = 3 - 2\left(\frac{19}{29}\right) = \frac{49}{29}.$$

Therefore, the solution of the Equations (1) and (2) is $x = \frac{49}{29}, y = \frac{19}{29}$.

To verify if the solution is correct, we substitute $x = \frac{49}{29}, y = \frac{19}{29}$, in Equations (1) and (2) and check if they are satisfied. Try it for yourself.

Think and Reflect

What if we had expressed y in terms of x, i.e., take Equation (2) and write $y = \frac{1}{2}(3 - x)$. Would we still get the same solution?

Example 8: If two angles of a triangle are $x°$ and $y°$ with $y = 4x$, and the third angle is 50°, what are the angles?

The three angles of the triangle are $x°$, $y°$, and 50°.

Using the angle sum property of triangles,

$$x° + y° + 50° = 180° \quad (1)$$

Also, $$y = 4x. \quad (2)$$

Substituting the value of y in Equation (1),

we get $x + 4x + 50 = 180$

or $5x = 130$

or $x = 26°$.

Therefore, $y = 4x = 104°$.

Elimination Method

Now let us consider the method of elimination for solving a pair of linear equations. This requires us to eliminate one of the variables x or y. Sometimes it is more convenient than the substitution method. Let us see how this method works.

© NCERT not to be republished

Example 9: The ratio of incomes of two persons is 9 : 7 and the ratio of their expenditures is 4 : 3. If each of them manages to save ₹2000 per month, find their monthly incomes.

Since the ratio of the incomes of the two persons is 9 : 7, it means that for every 9 equal parts of income of the first person, the second person has 7 equal parts. If the equal part is x, the incomes of the two persons will be $9x$ and $7x$.

In a similar manner, we may consider their expenditures to be $4y$ and $3y$, respectively.

Then the equations formed by subtracting the expenditure from the income leading to a saving of ₹ 2000 are as follows:

$$9x - 4y = 2000 \quad (1)$$
$$7x - 3y = 2000 \quad (2)$$

To solve these by the method of elimination, we proceed as follows:

Step 1: We first decide which variable to eliminate. Suppose we wish to eliminate y from both equations. We multiply each side of Equation (1) by 3 [the coefficient of y in Equation (2)], and multiply Equation (2) by 4 [the coefficient of y in (1)]. By doing this the coefficients of y in both equations become equal. We get the equations:

$$27x - 12y = 6000 \quad (3)$$
$$28x - 12y = 8000 \quad (4)$$

Step 2: Subtract the LHS and RHS of Equation 3 from the LHS and RHS of Equation 4 respectively. Since we are subtracting equal quantities from equal quantities, we get

$$(28x - 27x) - (12y - 12y) = 2000.$$

This step eliminates the variable y, leaving us with $(28x - 27x) = 2000$ or $x = 2000$.

Step 3: Substituting this value of x in (1), we get

$$9(2000) - 4y = 2000 \text{ i.e., } y = 4000.$$

Hence, the solution of the equations is $x = 2000$, $y = 4000$.

Therefore, the monthly incomes of the two persons are ₹18,000 and ₹14,000, respectively.

Let us verify our solution. The ratio of the incomes is 18000 : 14000 = 9 : 7. Also, the ratio of their expenditures = (18000 – 2000) : (14000 – 2000) = 16000 : 12000 = 4 : 3. Hence, the conditions of the problem are satisfied.

© NCERT not to be republished

Think and Reflect

The method used in solving this problem is called the Elimination Method because we eliminate one of the variables to obtain a linear equation in the other variable. In the example above, we eliminated y. Try the same problem by eliminating x instead of y. Also try to solve the two equations using the Substitution Method. Assess the pros and cons of each method.

Example 10: The sum of a two-digit number and the number obtained by reversing its digits is 66. If the digits of the number differ by 2, find the number. How many such numbers are there?

Let the ten's and the unit's digits in the first number be x and y, respectively. Also let us assume that x is the larger digit and y is the smaller one. So, the first number may be written as $10x + y$ in the expanded form (for example, $73 = 10 \times 7 + 3$).

When the digits are reversed, x becomes the unit's digit and y becomes the ten's digit. This number, in the expanded notation, is $10y + x$ (for example, when 73 is reversed, we get $37 = 10 \times 3 + 7$).

According to the given condition, we have $(10x + y) + (10y + x) = 66$. Thus

$$11(x + y) = 66, \text{ i.e., } x + y = 6 \quad (1)$$

We are also given that the digits differ by 2, i.e.,

$$x - y = 2 \quad (2)$$

Solving (1) and (2) by elimination, we get $x = 4$ and $y = 2$, so, the two-digit number is 42.

The number 42 and its reverse 24 when added gives 66, and this is the unique solution.

Think and Reflect

Does a pair of linear equations always have a unique solution? Can you analyse this using the Elimination Method? While subtracting the equations to eliminate a particular variable, if the other variable remains, then clearly there is a unique solution. But what if the second variable gets eliminated too while eliminating the first variable? Can you think of a situation where this happens?

© NCERT not to be republished

Consider the linear equations

$$x - y = 10 \quad (1)$$
$$10x - 10y = 100 \quad (2)$$

To eliminate x, we multiply the first equation by 10. But by doing this, both equations become $10x - 10y = 100$. Since both equations are the same, every solution of $10x - 10y = 100$ is a solution of both equations. We know that $10x - 10y = 100$ has infinitely many solutions. Hence, the given pair of equations has infinitely many solutions.

Think and Reflect

How many solutions are there to the equations

$$10x - 5y = 20 \text{ and } 4x - 2y = 8?$$

Give 3 more examples of pairs of equations that lead to $0 = 0$ after subtraction, and therefore have infinitely many solutions. Can you find a simple rule to check when this happens?

Consider a general pair of equations

$$a_1x + b_1y + c_1 = 0$$
$$a_2x + b_2y + c_2 = 0$$

with a_2, b_2 and c_2 each not equal to 0.

From the discussion above, it can be seen that whenever one of the equations is a constant multiple of another, the equations are the same and so have an infinite number of solutions. Suppose this constant multiple is k, where k is not necessarily an integer but may be any number. Then

$$a_1 = ka_2,\ b_1 = kb_2,\ c_1 = kc_2, \text{ where } k \neq 0.$$

Thus, when $\frac{a_1}{a_2} = \frac{b_1}{b_2} = \frac{c_1}{c_2} = k$, the pair of equations has infinitely many solutions.

Think and Reflect

What if one of a_2, b_2, c_2 is zero?

Think and Reflect

Does a pair of linear equations always have either a unique solution or infinitely many solutions?

© NCERT not to be republished

Consider the linear equations

$$x - y = 10 \quad (1)$$
$$10x - 10y = 101 \quad (2)$$

Multiplying both sides of (1) by 10 gives

$$10x - 10y = 100 \quad (3)$$

The left hand side in (2) and (3) are equal expressions, but the right hand side are not. Hence we cannot find values of x and y that satisfy both (2) and (3). Thus, this pair of equations has no solution!

Think and Reflect

Give 3 more examples of pairs of equations that have no solution. Can you find a simple rule to check when this will happen?

When a pair of equations

$$a_1x + b_1y + c_1 = 0$$
$$a_2x + b_2y + c_2 = 0$$

(with a_2, b_2 and c_2 all not equal to 0) is such that after suitable multiplications, we can make

(i) the coefficients of x of both equations equal, and
(ii) the coefficients of y of both equations equal

while the constants c_1 and c_2 remain unequal, the pair has no solution.

These conditions mean $a_1 = ka_2$, $b_1 = kb_2$, $c_1 \neq kc_2$, where $k \neq 0$.

Hence, when $\frac{a_1}{a_2} = \frac{b_1}{b_2} \neq \frac{c_1}{c_2}$, the pair has no solution.

When $\frac{a_1}{a_2} = \frac{b_1}{b_2}$, both the variables get eliminated during the Elimination Method. Based on what happens to the constants, the pair can either have an infinite number of solutions or no solution.

We have already seen that when one of the variables remains during the Elimination Method, there exists a unique solution. This can happen only when $\frac{a_1}{a_2} \neq \frac{b_1}{b_2}$.

Summarising, we have the following cases:

1. when $\frac{a_1}{a_2} \neq \frac{b_1}{b_2}$, the pair has a unique solution,

© NCERT not to be republished

2. when $\frac{a_1}{a_2} = \frac{b_1}{b_2} = \frac{c_1}{c_2}$, the pair has an infinite number of solutions, and

3. when $\frac{a_1}{a_2} = \frac{b_1}{b_2} \neq \frac{c_1}{c_2}$, the pair has no solution.

Think and Reflect

Are the converses of the above statements true?

Thus, (1), (2) and (3) can be used as simple rules to check for the nature of solutions.

Think and Reflect

Can there be methods other than elimination and substitution to reduce a pair of linear equations in two variables to a linear equation in one variable? If so, describe them.

A Pinch of History

Solving systems of linear equations is one of the oldest problems in mathematics, going back thousands of years. The earliest traces appear in Babylonian cuneiform tablets (c. 2000 BCE). They were studied systematically in ancient China; the Nine Chapters on the Mathematical Art (compiled roughly two thousand years ago) devotes an entire chapter, fangcheng, to systems of linear equations, solved by arranging coefficients in columns of counting rods and then combining columns to cancel out variables — a procedure essentially identical to modern elimination, fully eighteen centuries before Gauss's name became attached to it in Europe. Many Indian mathematicians, including Āryabhaṭa (499 CE) and Brahmagupta (628 CE), also studied general systems of equations in several unknowns using their own systematic reduction techniques including elimination.

13.6 Graphical Method for Solving a Pair of Linear Equations in Two Variables

In this section, we learn how to solve a pair of linear equations graphically, that is by plotting the lines represented by the two equations.

© NCERT not to be republished

Consider the following pairs of linear equations in two variables.

Pair 1: $2x + y = 6$ and $x - y = 2$

Pair 2: $x + y = 4$ and $2x + 2y = 8$

Pair 3: $3x - 2y = 6$ and $6x - 4y = 12$

Pair 4: $x - 2y = 4$ and $2x - 4y = 6$

For each pair, prepare a table of values (with at least two ordered pairs). Plot the points on the Cartesian plane. Draw the straight lines.

Think and Reflect

How do we find solutions from the graph? What can we say about the number of solutions when the two lines (i) intersect at a point, (ii) are parallel, (iii) are coincident?

Solutions to the pair of equations are points that lie on both lines. Thus

(i) when the lines intersect in a single point, there is a unique solution;

(ii) when the lines are parallel, there are no solutions; and

(iii) when the lines are coincident, there are infinitely many solutions.

Example 11: Solve the pair of linear equations $x + 3y = 6$ and $2x - 3y = 12$ graphically. Comment on the nature of the solution.

Consider the equation $x + 3y = 6$. Expressing y in terms of x, we get $y = \frac{6 - x}{3}$.

Considering x to be first 0 and then 6 we obtain the corresponding values of y as 2 and 0 respectively. Hence (0, 2) and (6, 0) are points on the line.

x	0	6
y	2	0

Now consider the equation $2x - 3y = 12$. Expressing y in terms of x, we get $y = \frac{2x - 12}{3}$. Considering x to be 0 and then 3, we obtain the values of y as -4, and -2 respectively. Hence $(0, -4)$ and $(3, -2)$ are points on the line.

x	0	3
y	-4	-2

© NCERT not to be republished

Now plot the points A(0, 2), B(6, 0), P(0, –4) and Q(3, –2) on a graph paper, and join the points to form the lines AB and PQ as shown in Fig. 13.14. We observe that the point B(6, 0) is common to both the lines. In fact the lines AB and PQ intersect at B. So, the solution of the pair of linear equations is $x = 6$ and $y = 0$. Also, we can say that the given pair of equations has a **unique solution**.



Fig. 13.14: Graph of the pair of linear equations $x + 3y = 6$ and $2x – 3y = 12$. They have the unique solution (6, 0) or $x = 6, y = 0$

If we consider the ratios of the corresponding coefficients and constants in the equations $x + 3y = 6$ and $2x – 3y = 12$, we get $\frac{a_1}{a_2} = \frac{1}{2}$, $\frac{b_1}{b_2} = \frac{3}{-3} = -1$. Here $\frac{a_1}{a_2} \neq \frac{b_1}{b_2}$. We have also seen graphically that the lines intersect.

Example 12: Determine if the lines $x + 2y – 4 = 0$ and $2x + 4y – 12 = 0$ intersect, coincide or are parallel to each other. Then verify your answer by graphing the equations.

On comparing the coefficients of these two equations we get $\frac{a_1}{a_2} = \frac{1}{2}$, $\frac{b_1}{b_2} = \frac{2}{4} = \frac{1}{2}$, $\frac{c_1}{c_2} = \frac{-4}{-12} = \frac{1}{3}$. We observe that $\frac{a_1}{a_2} = \frac{b_1}{b_2}$ but is not equal to $\frac{c_1}{c_2}$. Thus, the equations have no solution and hence the lines are parallel.

As before, we identify the points (0, 2) and (4, 0) on the line $x + 2y – 4 = 0$

x	0	4
y	2	0

© NCERT not to be republished

Similarly we find two points on the line $2x + 4y - 12 = 0$, say, (0, 3) and (6, 0).

x	0	6
y	3	0

To represent the equations graphically, we plot the points R(0, 2) and S(4, 0), to get the line RS and the points P(0, 3) and Q(6, 0) to get the line PQ.



Fig. 13.15: Graph of the pair of linear equations $2x + 4y - 12 = 0$ and $x + 2y - 4 = 0$

We observe in Fig. 13.15 that the lines do not intersect anywhere and are parallel.

Think and Reflect

Can you prove that two lines of equal slope are parallel?

(**Hint:** Consider the equations of the two lines to be $y = mx + d_1$ and $y = mx + d_2$)

Example 13: Romila went to a stationery shop and purchased 2 erasers and 3 A4 sheets for ₹9. Her friend Sonali saw the new variety of erasers and A4 sheets Romila bought, and she also bought 4 erasers and 6 A4 sheets of the same kind for ₹18. Represent this situation graphically.

Let us denote the cost of a erasers by ₹x and one A4 sheets by ₹y. Then the algebraic representation is given by the equations $2x + 3y = 9$ and $4x + 6y = 18$. Writing these equations in standard form we get $2x + 3y - 9 = 0$ and $4x + 6y - 18 = 0$.

© NCERT not to be republished



Fig. 13.16: Graphs of the pair of linear equations 2x + 3y = 9 and 4x + 6y = 18. The two lines coincide.

We find that both equations are represented by the same straight line. On comparing the coefficients of the two equations we find that $\frac{a_1}{a_2} = \frac{2}{4} = \frac{1}{2}, \frac{b_1}{b_2} = \frac{3}{6} = \frac{1}{2}, \frac{c_1}{c_2} = \frac{-9}{-18} = \frac{1}{2}$ which represents the fact that the pair of lines has infinitely many solutions.

Exercise Set 13.5

1. Form a pair of linear equations for each of the following problems and find their solutions.
   (i) The sum of two integers is +5 and their difference is –21. Find the two numbers.
   (ii) The difference between two numbers is 26 and one number is three times the other. Find the numbers.
   (iii) The coach of a cricket team buys 7 bats and 6 balls for ₹8880. Later, she buys 3 bats and 5 balls for ₹4000. Find the cost of each bat and each ball.
   (iv) The taxi charges in a city consist of a fixed charge together with the charge for the distance covered for every km. For a distance of 10 km, the total amount paid is ₹155 and for

© NCERT not to be republished

a journey of 15 km, the total amount paid is ₹220. What is the fixed charge and the charge per km? How much does a person have to pay for travelling a distance of 25 km?

(v) A fraction becomes equal to $\frac{9}{11}$ if 2 is added to both the numerator and the denominator. If 3 is added to both the numerator and the denominator, it becomes equal to $\frac{5}{6}$. Find the fraction.

(vi) If we add 1 to the numerator and subtract 1 from the denominator, a fraction reduces to 1. It becomes equal to $\frac{1}{2}$ if we add 1 only to the denominator. What is the fraction?

(vii) Five years ago, Nuri was thrice as old as Sonu. Ten years later, Nuri will be twice as old as Sonu. How old are Nuri and Sonu?

(viii) The sum of the digits of a two-digit number is 9. Also, nine times this number is twice the number obtained by reversing the order of the digits. Find the number.

(ix) Meena went to a bank to withdraw ₹2000. She asked the cashier to give her ₹50 and ₹100 notes only. Meena got 25 notes in all. Find how many notes of ₹50 and ₹100 did she receive?

(x) A lending library has a fixed charge for the first three days and an additional charge for each day thereafter. Saritha paid ₹27 for a book kept for seven days, while Susy paid ₹21 for the book she kept for five days. Find the fixed charge and the charge for each extra day.

2. Form a pair of linear equations and find their common solutions graphically.

   10 students of Grade 9 took part in a Mathematics quiz. If the number of girls is 4 more than the number of boys, find the number of boys and girls who took part in the quiz.

3. Use the ratios $\frac{a_1}{a_2}$, $\frac{b_1}{b_2}$, $\frac{c_1}{c_2}$, to determine whether the lines representing the following pairs of linear equations intersect at a point, are parallel or are coincident.

   (i) $5x - 4y + 8 = 0$; $7x + 6y - 9 = 0$

   (ii) $9x + 3y + 12 = 0$; $18x + 6y + 24 = 0$

   (iii) $6x - 3y + 10 = 0$; $2x - y + 9 = 0$

© NCERT not to be republished

4. Which of the following pairs of linear equations have solutions? If they have solutions, find them graphically.
   (i) $x + y = 5, 2x + 2y = 10$
   (ii) $x – y = 8, 3x – 3y = 16$
   (iii) $2x + y – 6 = 0, 4x – 2y – 4 = 0$
   (iv) $2x – 2y – 2 = 0, 4x – 4y – 5 = 0$
5. Half the perimeter of a rectangular garden, whose length is 4 m more than its width, is 36 m. Find the dimensions of the garden.
6. Given the linear equation $2x + 3y – 8 = 0$, write another linear equation in two variables so that the graphs of the pair formed represent (i) intersecting lines (ii) parallel lines (iii) coincident lines.
7. Here is a problem that was posed by Mahāvīrāchārya in *Gaṇita sāra saṅgraha* (c. 850 CE).

   The price of 9 citrons and 7 fragrant wood-apples taken together is 107; and the price of 7 citrons and 9 fragrant wood-apples taken together is 101.

   O mathematician, tell me quickly the price of each citron and of each fragrant wood-apple.

   (**Hint:** The given problem can be modelled as

   $$9x + 7y = 107$$
   $$7x + 9y = 101$$

   Can you figure out a way of solving these equations without directly using elimination or the substitution method? What is special in this pair of equations? The x and y coefficients are interchanged in the 2 equations.

   What will happen if we add the pair of equations? What will happen if we subtract the pair of equations? Can the resulting equations be solved to find the values of x and y?)
8. 5 pencils and 7 pens together cost ₹50, whereas 7 pencils and 5 pens together cost ₹46. Find the cost of each pencil and pen.
9. Find the height of the stool.



© NCERT not to be republished

End-of-Chapter Exercises

1. The graph of the line $y = 3x$, passing through (0, 0) and (2, 6) is given below.

   (i) Identify the slope of the line from the graph and explain how you calculated it using the two points on the line.

   (ii) What is the y-intercept of the line? Explain its significance.

   (iii) A water tank is being filled so that the water level y (in cm) after x minutes follows this graph.



   (a) How high is the water after 5 minutes?

   (b) How many minutes will it take for the water to reach a height of 21 cm?

   (iv) Without drawing a new graph, determine whether the point (4, 10) lies on this line. Justify your answer.

   (v) Plot the point where this line intersects the line $x = 3$. Explain how you found the coordinates.

© NCERT not to be republished

2. In countries like the USA, temperature is measured in Fahrenheit, whereas in countries like India, it is measured in Celsius. Here is a linear equation that converts Celsius to Fahrenheit:

$$F = \frac{9}{5}C + 32$$

   (i) Draw the graph of the linear equation above using Celsius on the x-axis and Fahrenheit on the y-axis.
   (ii) If the temperature is 30 °C, what is the temperature in Fahrenheit?
   (iii) If the temperature is 95 °F, what is the temperature in Celsius?
   (iv) If the temperature is 0 °C, what is the temperature in Fahrenheit and if the temperature is 0 °F, what is the temperature in Celsius?
   (v) Is there a temperature which is numerically the same in both Fahrenheit and Celsius? If yes, find it.

3. Solve the following system of equations graphically:

$$2x + y = 6,\ 2x - y - 2 = 0.$$

4. Find the point of intersection of the lines shown on the cover page.

5. Give a formula to find the x-intercept of the line $y = mx + c$.

6. A person is choosing between two mobile plans.
   Plan A: ₹50 monthly fee + ₹0.20 per minute of call time.
   Plan B: ₹30 monthly fee + ₹0.30 per minute of call time.
   For how many minutes of calling per month is Plan A cheaper than Plan B? For how many minutes is Plan B cheaper? Also find the number of minutes at which both plans cost the same.

7. How many lines exist that
   (i) have a given slope?
   (ii) have a given slope and pass through a given point?

8. For what values of p does the pair of equations given below have a unique solution?

$$4x + py + 8 = 0; \quad 2x + 2y + 2 = 0.$$

© NCERT not to be republished

9. Find the values of a and b for which the following system of equations has infinitely many solutions:

$$(a + b)x - 2by = 5a + 2b + 1;\ 3x - y = 14.$$

10. Find the value of 'k' for which the following system of equations represents a pair of coincident lines:

$$x + 2y = 3;\ (k - 1)x + (k + 1)y = k + 3.$$

11. (i) Robot 1 starts from the origin and traces a path by repeatedly moving 3 units to the right and then 4 units upward. Robot 2 starts from the point (10, 0) and repeatedly moves 1 unit to the right and then 2 units upward. Will the paths traced by these two robots intersect and if so, where?

(ii) Robot 1 starts from (3, 0) and traces a path by repeatedly moving 5 units to the right and then 5 units upward. Robot 2 starts from the point (7, 0) and repeatedly moves 5 units to the right and then 3 units downwards. Will the paths traced by these two robots intersect and if so, where?

*12. At a certain time, Jacob notices that his digital watch reads 'a' minutes after two o'clock. Fifteen minutes later, it reads 'b' minutes after three o' clock. He noticed that a is six times greater than b. What time was it when he looked at his watch for the second time?

*13. The sum of the digits of a two-digit number is 15. The number obtained by interchanging the digits exceeds the given number by 9. Find the number.

*14. In a cyclic quadrilateral ABCD, $\angle A = (x + 7)°$, $\angle B = (y + 8)°$, $\angle C = (3y + 23)°$ and $\angle D = (4x + 12)°$. Find all four angles of the cyclic quadrilateral.

*15. A train moving with uniform speed for a certain distance takes 6 hours less if its speed is increased by 6 km/hour. It would have taken 6 hours more had its speed been decreased by 4 km/hour. Find the distance travelled and the speed of the train.

*16. The age of a father is equal to the sum of the ages of his four children. After 20 years, the sum of the ages of the children will be twice the age of the father. Find the age of the father.

© NCERT not to be republished

Chapter Summary

- An equation of the form $ax + by + c = 0$, where a, b and c are real numbers, such that a and b are not both zero, is called a **linear equation in two variables**.
- A linear equation in two variables has infinitely many solutions.
- An equation $y = mx + d$ is the **slope-intercept form** of a linear equation in two variables. Here 'm' represents the slope and 'd' the y-intercept. The line cuts the y-axis in the point $(0, d)$.
- Every point on the graph of a linear equation in two variables is a solution of the linear equation. Moreover, every solution of the linear equation is a point on the graph of the linear equation.
- A pair of linear equations in two variables can be represented, and solved, both algebraically and graphically.
- A pair of linear equations can be solved algebraically using the Method of Substitution or the Method of Elimination.
- If a pair of linear equations is given by $a_1x + b_1y + c_1 = 0$ and $a_2x + b_2y + c_2 = 0$, then the following cases may arise:
  - $\frac{a_1}{a_2} \neq \frac{b_1}{b_2}$: In this case, the pair of linear equations **has a unique solution**.
  - $\frac{a_1}{a_2} = \frac{b_1}{b_2} \neq \frac{c_1}{c_2}$: In this case, the pair of linear equations **does not have a solution**.
  - $\frac{a_1}{a_2} = \frac{b_1}{b_2} = \frac{c_1}{c_2}$: In this case, the pair of linear equations **has infinitely many solutions**.
- The graph of a pair of linear equations in two variables is represented by two lines.
  - If the lines intersect at a point, then that point is the **unique solution** of the two equations.
  - If the lines coincide, then there are **infinitely many solutions**, each point on the line being a solution.
  - If the lines are parallel, then the pair of equations has **no solution**.

© NCERT not to be republished

14 Math of Space: Surface Area and Volume

0905CH14

In the previous grade we explored nets of some solids including cubes, cylinders, and cones. We saw that solids have a surface and occupy some space or volume. In this chapter, we will learn how to determine surface areas and volumes of cuboids, cylinders, cones, pyramids, and spheres, and how we can use these to solve some interesting problems.

14.1 Cuboids and Cubes

Fig. 14.1A: Cuboid bricks

Fig. 14.1B: Rubik's Cube



Fig. 14.1C: Cuboid

A *cuboid* has the shape shown in these pictures. A useful way of thinking about a cuboid is that it is a 'three-dimensional (3D) version' of a rectangle.

It has six faces, all rectangles. It is characterised by three quantities: length, width, and height — these are denoted by l, w, h respectively. You can cut out the net of a cuboid given at the end of the textbook, make appropriate folds and join the edges to form the cuboid.

What is the total surface area of a cuboid? You may refer to the net of the cuboid given in Fig. 14.2.

Considering the faces individually, we see that the total surface area (TSA) of the cuboid is

$$\text{TSA} = 2(wl + hl + hw).$$



Fig. 14.2

© NCERT not to be republished

Volume measures the amount of three-dimensional space an object or a container occupies. It is measured in cubic units, e.g., cubic meters (m^3) or cubic centimeters (cm^3). We set the volume of a *unit cube* (i.e., a cuboid measuring one unit in each direction) to be one cubic unit (e.g., 1 m^3 or 1 cm^3, as the case may be). The volume of a general cuboid is the number of unit cubes that fit into it. Accordingly, the formula for the volume V of a cuboid is length × width × height or

$$V = lwh.$$

Compare the formula for the volume of a cuboid with the formula for the area of a rectangle (length × width).

Here is a way of understanding why the formula $V = lwh$ is true: think of a cuboid as a large number of thin rectangular pieces (length l, width w) stacked on top of each other, like a pack of playing cards. (Fig. 14.3).

Fig. 14.3

Think and Reflect

Try to work out for yourself why this model explains the formula for the volume of a cuboid, i.e.,

volume = area of base × height.

Write the formula for the surface area and the volume of a cube.

A particular and important case of a cuboid is a *cube*, whose length, width, and height are the same. This length is the 'side' of the cube.

Let the side be a. Then:

- Total surface area of the cube is $6a^2$.
- Volume of the cube is a^3.



Fig. 14.4

Observe how these two formulas are special cases of the formulas $2(wl + hl + hw)$ and whl, when $w = h = l$.

© NCERT not to be republished

Do you remember cube numbers? Cube numbers are the numbers in the sequence 1, 8, 27, 64, …. These numbers represent the number of unit cubes that can fit inside cubes of side lengths 1, 2, 3, 4, … respectively — in other words, they represent the volumes of these cubes. We know that $1^3 = 1$, $2^3 = 8$, $3^3 = 27$, $4^3 = 64$, …; and $\sqrt[3]{1} = 1$, $\sqrt[3]{8} = 2$, $\sqrt[3]{27} = 3$, $\sqrt[3]{64} = 4$, and so on.

Example 1: Two solid objects are made from the same material: Cube A has side 6 cm and Cuboid B has dimensions 9 cm × 6 cm × 4 cm. Compare their volumes and surface areas and determine which object has a greater surface area. How is this useful in a real-life situation?

For Cube A, side (a) = 6 cm.

Hence its volume is $a^3 = (6\text{ cm})^3 = 216\text{ cm}^3$ and surface area (SA) is $6a^2 = 6 \times (6\text{ cm})^2 = 216\text{ cm}^2$.

For Cuboid B, length (l) = 9 cm; width (w) = 6 cm; height (h) = 4 cm.

Hence its volume is $l \times w \times h = 9 \times 6 \times 4 = 216\text{ cm}^3$

and surface area (SA) is $2(lw + wh + lh) = 2[(9 \times 6) + (6 \times 4) + (4 \times 9)] = 228\text{ cm}^2$.

Thus, the two objects have the same volume but different surface areas. The cuboid has greater surface area than the cube.

Conclusion: For the same storage capacity: a cube requires less covering material; a cuboid exposes more area to its surroundings.

This concept is important in packaging, heat transfer and engineering.

Exercise Set 14.1

1. The volume of a cube is 64 cm^3. What is its total surface area?
2. How many small cubes with side 20 cm can be packed tight in a cubical box with side 2 m?
3. The dimensions of a godown are 40 m × 25 m × 10 m. If it is filled with cuboidal boxes, each of dimensions 2 m × 1.25 m × 1 m, then find the number of boxes.
4. Two cubes each of volume 125 cm^3 are joined end to end. Find the surface area of the resulting cuboid.

© NCERT not to be republished

5. A cube of side 4 cm is cut into cubes of side 1 cm. What is the ratio of the surface areas of the original cube and all the cut-out cubes? (Note that there is no change in volume but a big change in the surface area. This property has major consequences in the biological world.)

6. The surface areas of the three faces of a cuboid that meet at one of the corners of the cuboid are 6 cm^2, 15 cm^2, and 10 cm^2 respectively. What is the volume of the cuboid?

*7. A cube of side 5 cm is painted on all its faces. If it is sliced into 1 cm^3 cubes, how many of these 1 cm^3 cubes have



(i) exactly three faces painted?
(ii) exactly two faces painted?
(iii) exactly one face painted?
(iv) no face painted?

*8. Find a cuboid with edges whose lengths are integers (in cm), given that it has a total surface area of exactly 100 cm^2.
(i) Is there more than one such cuboid?
(ii) Can you find them all?
(iii) Show that you have found them all.

Think and Reflect

Suppose a swimming pool is being built in your school. Two choices are available for the dimensions of the pool: (A) 8 ft (depth) × 50 ft × 20 ft and (B) 6 ft (depth) × 100 ft × 15 ft. Which option would be suitable/appropriate for your school? Why? What parameters/aspects did you consider to make the choice? [1 cubic foot ≈ 28.3 litres]

© NCERT not to be republished

14.2 Right Circular Cylinder

The following figures show different types of cylinders. What is different in each of these cylinders?



Right circular cylinder



Oblique circular cylinder

The first one is a **right circular cylinder**. The term *circular* indicates that the cross-section of the cylinder is a circle, while the term *right* signifies that the axis of the cylinder is perpendicular to its circular base. Many pipes have this shape. It is worth noting that not all cylinders are of this type. Some cylinders may have axes that are inclined rather than perpendicular to the base. The second one is an **oblique circular cylinder**. We restrict ourselves to the study of the right circular cylinder only. You can cut out the net of a cylinder given at the end of the textbook, make appropriate folds and join the circles to form the cylinder.

We used the word **cross-section** above. Given a three-dimensional object, suppose we take an extremely thin slice of it. The shape we get is called a 'cross-section' of the object. In the case of a cylinder, if the slice is parallel to its base, we get a circular cross-section. But if the slice is parallel to the axis of the cylinder, we get a rectangular cross-section. Generally, we are interested in the cross-section that is parallel to the base.

Examples of cross-sections are shown in the following figure.

Cylinder

Papaya

Apple

© NCERT not to be republished

When doctors take an MRI scan of some part of your body, it is like taking a cross-section because it allows them to look at the inside of your body in slices.

What is the area of the curved surface of a cylinder?

Let the radius of the circular base of the cylinder be r; let its height be h. Suppose the cylinder is cut as shown in the figure below. We get a rectangle.



Fig. 14.5A

Therefore, the curved surface area of the cylinder is the area of the rectangle.

- The curved surface area (CSA) of the cylinder is

$$\text{CSA} = \text{circumference} \times \text{height} = 2\pi rh.$$

If the cylinder is closed at both ends (top and bottom) like a biscuit tin (see Fig. 14.5B), then the flat circular surfaces at the ends also contribute to the area. Since there are two ends,

$$\text{total surface area (TSA)} = 2\pi rh + 2\pi r^2 = 2\pi r(h + r).$$

Fig. 14.5B

- If the cylinder is closed at one end and open at the other end, like a tumbler, then

$$\text{surface area} = 2\pi rh + \pi r^2 = \pi r(2h + r).$$

- The volume V of the cylinder is

$$V = \text{cross-sectional area} \times \text{height} = \pi r^2 h.$$

14.2.1 Another Way of Understanding Why the Above Formulas Are True

To understand why the formulas for the surface area (curved part) and the volume of a cylinder hold, it helps to think of the cylinder as a large number of thin circular khakhras stacked on one another.

© NCERT not to be republished

Example 2: Savitri had to make a model of a cylindrical kaleidoscope for her science project. She wanted to use chart paper to make the curved surface of the kaleidoscope (see Fig. 14.6). What would be the area of chart paper required by her, if she wanted to make a kaleidoscope of length 25 cm with a 3.5 cm radius? You may take $\pi = \frac{22}{7}$.



Fig. 14.6

Radius of the base of the cylindrical kaleidoscope (r) = 3.5 cm.
Height (length) of kaleidoscope (h) = 25 cm.

Area of chart paper required = curved surface area of the kaleidoscope

$$= 2\pi rh$$
$$= 2 \times \frac{22}{7} \times 3.5 \times 25 \text{ cm}^2$$
$$= 550 \text{ cm}^2$$

Exercise Set 14.2

1. Two cylinders, A and B, are given. The radius of cylinder B is twice that of cylinder A, and the height of cylinder B is half that of cylinder A. Find the ratio of the curved surface area of A to the curved surface area of B. Also find the ratio of the volume of A to the volume of B.
2. The radii of two cylinders are in the ratio 2:3, and their heights are in the ratio 3:2. Find (a) the ratio of their volumes, and (b) the ratio of their curved surface areas.
3. The edge of a cube measures r cm. The largest possible right circular cylinder is cut out of the cube. What do you think is the volume of the cylinder (in cm^3)?

*4. The radius of the base of a cylinder is increased by 10%. At the same time, the height of the cylinder is decreased by x%. Given that the volume of the cylinder remains unchanged, find the value of x.

5. A solid metallic cube of side 12 cm is melted and recast into solid cylindrical rods, each having radius 2 cm and height 12 cm. Find:
   (i) the volume of the cube,

© NCERT not to be republished

(ii) the volume of one cylindrical rod,
(iii) the approximate number of complete cylindrical rods that can be formed. $\left(\pi \approx \frac{22}{7}\right)$

14.3 Cones

Fig. 14.7A

Fig. 14.7B



Fig: 14.7C

A right circular cone is generated when a right triangle is rotated about one of its legs. The relationship among the slant length l, the height h, the radius r of the base is

$l^2 = h^2 + r^2$ (using the Baudhāyana–Pythagoras theorem)



Right circular cone Unrolled cone

Fig. 14.8

Imagine cutting the cone along a slant edge and 'opening up' or unrolling the surface. The unrolled surface has the shape of a sector of a circle. To create the cone again, bring the two straight edges together. You can use the cutout of the net of a cone given at the end of the textbook to make a cone.

What is the curved surface area of a cone?

The formula for surface area becomes clear if we imagine cutting the cone along a slant edge, unrolling the surface, and cutting it up into

© NCERT not to be republished

a large number of very thin sectors, each of which can be regarded as a narrow isosceles triangle of height l (Fig. 14.9).



(a) (b) (c)

Fig. 14.9

From Fig. 14.9, it follows that the curved surface area (CSA) of the cone is equal to

$$\text{CSA} = \frac{1}{2}b_1 l + \frac{1}{2}b_2 l + \cdots + \frac{1}{2}b_n l = \frac{1}{2}(b_1 + b_2 + \cdots + b_n)l$$

$$= \frac{1}{2} \times \text{circumference of the base} \times l$$

$$= \frac{1}{2}(2\pi r)l = \pi r l$$

Here is another way of working out the formula for the curved surface area. We have, from the formula for area of a sector of a circle,

$$\text{CSA} = \pi l^2 \times \frac{\theta°}{360°} = \pi l \times l \times \frac{\theta°}{360°}.$$

Let us try to express this formula in terms of r and l. For this, note that from the cone, we have,

$$\text{arc length} = s = 2\pi r,$$

and from the sector, we have

$$\text{arc length} = s = \frac{\theta°}{360°} \times 2\pi l.$$

Equating these two, we get

$$\frac{\theta°}{360°} = \frac{r}{l}.$$

From this, we see that the curved surface area is

$$\text{CSA} = \pi r l,$$

the same formula as earlier. The formula for the total surface area (TSA) (curved portion plus the flat base) is TSA = $\pi r l + \pi r^2$.

© NCERT not to be republished

What is the volume of a cone? It turns out that

$$V = \frac{1}{3}\pi r^2 h.$$

The volume formula tells us that the volume of a cone is exactly $\frac{1}{3}$ the volume of a cylinder formed on the same circular base and with the same height as the cone. The formula may be expressed in different ways, e.g.,

$$V = \frac{1}{3} \times \text{area of base} \times \text{height}.$$

Students often wonder about the factor of $\frac{1}{3}$ in this formula. Why $\frac{1}{3}$? To explain the reason for this factor requires more advanced methods, e.g., calculus, which you will study when you are in Grade 12.

But it is possible to *experimentally* verify this relationship. Let us start with a right circular cylindrical tin. Using paper, we make a right circular cone with the same base radius and the same height as the cylinder (see Fig. 14.10).



Fig. 14.10

We are now going to perform an experiment to find the volume of the cone. We need some clean fine-grained salt for this purpose.

Fill the cone to the brim with salt. Empty it into the cylinder. We find that it fills up only part of the cylinder. Fill the cone with salt to the brim again and empty it into the cylinder. We find that the cylinder is still not full. When we fill the cone with salt for the third time and empty it yet again into the cylinder, we find that the cylinder is full to the brim.

We can therefore conclude that the volume of the cylinder is three times the volume of the cone. That is, given a right circular cylinder and

© NCERT not to be republished

a right circular cone of the same base radius and the same height, the cone has one third the volume of the cylinder. This gives an experimental verification of the formula given above.

Here is another hands-on activity that uses modelling clay (earlier this used to be called 'plasticine'). Carefully mold the clay into a solid cylinder and measure its radius and height. Then reshape the same portion of clay into identical cones, each having the same radius and the same height as the cylinder. You will find that you are able to make exactly three such cones. This brings out the relationship between the volume of the cylinder and cone quite visibly

$$V = \frac{1}{3} \times \text{area of base} \times \text{height}.$$

The formula for the volume of a cone was first found by the Greek mathematician Archimedes (c. 225 BCE). He also derived formulas for the surface area and volume of a sphere (i.e., ball), which we will study in later sections.

Example 3: A right triangle ABC with sides 5 cm, 12 cm and 13 cm is rotated through 360° about the side with length 12 cm. Find the volume of the solid so obtained.

The triangle has sides 5 cm, 12 cm, 13 cm.

Since $5^2 + 12^2 = 25 + 144 = 169 = 13^2$, the triangle is a right-angled triangle with perpendicular sides 5 cm and 12 cm and hypotenuse 13 cm.

The triangle is rotated about the side with length 12 cm. When a right-angled triangle rotates about one of its perpendicular sides, it forms a right circular cone. Here, height of cone h = 12 cm, radius of cone r = 5 cm.

Hence, volume of the cone (V) = $\frac{1}{3}\pi r^2 h = \frac{1}{3}\pi \times 5^2 \times 12 = 100\,\pi \text{cm}^3$.

Exercise Set 14.3

For π, use one of the following approximations: $\pi \approx \frac{22}{7}$ or $\pi \approx 3.14$

1. Find the total surface area of a cone, if its slant height is 21 m and diameter of its base is 24 m.
2. Find the curved surface area of a right circular cone whose slant height is 10 cm and base radius is 7 cm.

© NCERT not to be republished

3. The height of a cone is 16 cm, and its base radius is 12 cm. Find the curved surface area and the total surface area of the cone.
4. A cone has a height of 15 cm. If its volume is 1570 cm^3, find the radius of the base.
5. The curved surface area of a cone is 308 cm^2 and its slant height is 14 cm. Find (i) the radius of the base, (ii) the total surface area of the cone.
6. A joker's cap is in the form of a right circular cone of base radius 7 cm and height 24 cm. Find the area of the sheet required to make 10 such caps.

*7. What length of tarpaulin 3 m wide is required to make a conical tent of height 8 m and base radius 6 m? Assume that the extra length of material that is required for stitching margins and wastage in cutting is 20 cm.

8. A right triangle with sides 6 cm, 8 cm and 10 cm is rotated through 360° about the side of 8 cm. Find the volume and the curved surface area of the solid so formed.

*9. Suppose you have a cup in the shape of a right circular cone. Fill it with water to half the depth of the cone. What fraction of the volume of the cup is occupied by the water?

14.4 Pyramidal Shapes

A pyramidal shape is of the type shown in the following figures.

Fig. 14.11A



Fig. 14.11B

Its base may be a triangle, a square or indeed any closed shape. All points in the base are connected to a single point (the *apex*) which lies in a different plane. You can make the pyramids by using the cutouts of nets given at the end of the textbook.

© NCERT not to be republished

The famous pyramids in Egypt have square bases. The puzzle in Fig. 14.11B (made by the Hungarian architect Erno Rubik) has a triangular base.

Some mountains have pyramidal peaks (formed by glacier erosion over many millennia). In India, there is the Shivling Peak in the state of Uttarakhand. An example from the Alps is the Matterhorn.

Shivling Peak (Uttarakhand)

The Matterhorn (Switzerland)

The volume V of a pyramidal shape is found by using the formula

$$V = \frac{1}{3} \times \text{area of base} \times \text{height}.$$

The same formula is applicable whether the base is triangular, square or any other shaped flat surface.

Note that the formula is the same as the one used for the volume of a cone. Indeed, we may think of a cone as a pyramid with a circular base.

The surface area of a pyramidal shape is found by adding up the areas of all the polygonal faces. So, we do not need a separate formula for the surface area.

14.5 Spheres and Hemispheres

Volleyball

Football (Soccer)



Sphere

Lastly, we consider a familiar object in daily life: a ball or a sphere.

© NCERT not to be republished

This is the three-dimensional (3D) equivalent of a circle. Whereas a circle is the collection of all points **in a plane** that are at some given distance from some given point, a sphere is the collection of all points in 3D space that are at some given distance r (the radius of the sphere) from a given point O, the centre of the sphere. If we rotate the circle about any diameter, we obtain a hollow sphere.

Archimedes showed that the surface area A of a sphere with radius r is equal to $4\pi r^2$. He did this by showing that the surface area of a sphere is exactly equal to the curved surface area of a cylinder with radius r and height $h = 2r$ that fits tightly over the sphere, Fig. 14.12.



Fig. 14.12

The curved surface area of such a cylinder is equal to

$$2\pi rh = 2\pi r \times 2r = 4\pi r^2,$$

This is the formula obtained by Archimedes.

© NCERT not to be republished



Fig. 14.13: Rectangular map projection
Source: https://en.wikipedia.org/wiki/Equirectangular_projection#/media/File:Equirectangular_projection_SW.jpg

In passing, we note that this result is used in cartography (map-making), when making a rectangular map projection of the earth. Imagine a cylinder tightly wrapped around the earth, touching it at the equator, as described above. By drawing radial lines from the central north pole–south pole axis, we project horizontally from the earth's surface to the surface of the cylinder. Then, we unwrap the cylinder and obtain the desired map. The resulting world map is rectangular in shape which is easy and convenient to use. But it suffers from an important defect: there is great distortion in shapes at high latitudes (close to the poles). For locations close to the equator, the distortion is negligible.

Archimedes also found the formula for the volume V of a sphere:

$$V = \frac{4}{3}\pi r^3.$$

You will study the derivations of these formulas in later grades, using calculus.

But you may be able to find your own derivation of the formula by connecting it with the formula for volume of a cone; namely, by writing it as

$$V = \frac{1}{3} \times (4\pi r^2) \times \mathrm{r}\,,$$

i.e., Volume of sphere = $\frac{1}{3}$ × surface area of sphere × radius of sphere.

Try to work out the connecting links on your own.

© NCERT not to be republished

*Visualising Volume Formula

Here is a way to see the link between the formulas for volume of a cone, surface area of a sphere and volume of a sphere. Recall that

$$\text{Volume of cone} = \frac{1}{3}\text{ area of base} \times \text{height of cone.}$$

Imagine that the entire surface of the sphere is divided into tiny regions. The shapes of these regions do not matter; what matters is that they are very tiny. Now connect all these regions to the centre of the sphere. This creates a large number of thin cones. They all have the same height, namely r. The volume of the sphere is equal to the sum of the volumes of all the cones. Using the fact that the cones all have the same height, we may write:

$$\text{Volume of sphere} = \frac{r}{3} \times \text{sum of base areas of all the thin cones}$$

$$= \frac{r}{3} \times \text{surface area of sphere} = \frac{r}{3} \times 4\pi r^2 = \frac{4}{3}\pi r^3.$$



14.5.1 Hands-on Activity to Verify the Formula for Surface Area of a Sphere

Have you ever played with a top? You must know how a string is wound around it. Take a rubber ball and drive a nail into it. Using the nail for support, wind a string tightly around the ball. When you have reached the 'fullest' part of the ball, use pins to keep the string in place, and continue to wind the string around the remaining part of the ball, till you have completely

© NCERT not to be republished

covered it; see Fig. 14.14. Mark the starting and finishing points on the string, and unwind the string from the surface of the ball. Now, measure the diameter of the ball and get its radius. On a sheet of paper, draw four circles with a radius equal to the radius of the ball. Fill the circles with the string you had wound around the ball (as shown in the figure).



Fig. 14.14

The string, which had completely covered the surface of the sphere, has now been used to fill the four circles, all with the same radius as the sphere. So, the surface area of a sphere of radius r is equal to 4 times the area of a circle of radius r, i.e., equal to $4\pi r^2$. Hence, surface area of a sphere = $4\pi r^2$ where r is the radius of the sphere. This experimentally verifies the stated formula.

14.5.2 Hemisphere

A hemisphere is a three-dimensional solid formed when a sphere is cut into two equal halves by a plane passing through its centre. The flat circular region formed after cutting the sphere is called the *base* of the hemisphere. A hemisphere has one curved surface and one circular base. See Fig. 14.15.

Fig. 14.15: Hemispheres

You may also recall encountering the term hemisphere in the context of the Northern Hemispheres and the Southern Hemispheres in Geography.

Examples: Bowls, serving dishes, dome-shaped covers, planetariums and igloos.

© NCERT not to be republished

Let the radius of the sphere be r. The surface area of the complete sphere is $4\pi r^2$. Therefore, the curved surface area of a hemisphere, which is half of the sphere, is $2\pi r^2$.

The total surface area (TSA) includes the curved surface and circular base. The area of the circular base = πr^2.

Hence TSA = $2\pi r^2 + \pi r^2 = 3\pi r^2$.

Volume of the hemisphere = $\frac{2}{3}\pi r^3$.

Example 4: A hemispherical bowl has a radius of 3.5 cm. What would be the volume of water it would contain?

The volume of water the bowl can contain

$$= \frac{2}{3}\pi r^3$$

$$= \frac{2}{3} \times \frac{22}{7} \times 3.5 \times 3.5 \times 3.5 \text{cm}^3 = 89.8 \text{cm}^3.$$

Exercise Set 14.4

1. A ball bearing has a radius of 0.7 cm. Find its surface area.

*2. Two solid spheres made of the same metal have weights 5920 g and 740 g. Determine the radius of the larger sphere, if the diameter of the smaller one is 5 cm.

3. The diameter of the moon is approximately one fourth the diameter of the earth. Given that the moon and earth are both roughly spherical, find the ratio of their surface areas.

4. Find (i) the curved surface area and (ii) the total surface area of a hemisphere of radius 21 cm.

5. Metal spheres, each of radius 2 cm, are packed into a rectangular box of internal dimensions 16 cm × 8 cm × 8 cm. When 16 spheres are packed, the box is filled with preservative liquid. Find the volume of this liquid. Round your answer to the nearest integer.

6. The radius of a sphere is increased by 10%. Show that the volume increases by approximately 33.1%.

© NCERT not to be republished

*7. The radius of a sphere is increased by x%. The volume of the sphere increases by 72.8%. Find the value of x.

8. The hemispherical dome of a building needs to be painted (see Fig. 14.16). If the circumference of the base of the dome is 35.2 m, find the cost of painting it, given the cost of painting is ₹ 10 per 100 cm^2.



Fig. 14.16

14.6 Areas and Volumes Around Us

We learned about different 3D solids. Identify and list objects or structures around you that are cubical, cuboidal, cylindrical, conical, spherical, or pyramidal in shape, or closely resemble these shapes.

Activity: Find the approximate volumes of a gas cylinder, a bucket, any cylindrical vessel, a cupboard, a water tank that you can find near you (use 1000 cm^3 = 1 litre).

14.6.1 Guesstimates: Did You Ever Wonder?

Guesstimate questions are problems in which you make a reasonable estimate for a quantity when exact data are not available. Instead of finding a perfectly accurate answer, you use assumptions, approximations, logic, and everyday knowledge to model a given situation and arrive at a sensible estimate. Do you remember solving such questions in earlier grades?

Example 5: Lallan's *golgappa* (a small hollow ball made of wheat) stall has a cylindrical vessel with *pani* (spiced water) in it. The vessel is of radius 10 cm and it has *pani* up to a height of 50 cm. Estimate the number of *golgappas* he can serve assuming all *golgappas* are spheres. Before calculating, make a guess.

Can you guess what number this could be — is it in the hundreds, thousands, or more?

The number of *golgappas* that can be served is

$$\frac{\text{Total } \textit{pani} \text{ in the vessel}}{\text{Volume of } \textit{pani} \text{ in each } \textit{golgappa}}.$$

© NCERT not to be republished

The amount of *paani* in the cylindrical vessel is given by V = area of base × height.

$$V = \pi (10)(10) \times 50 = 5000\pi \text{ cm}^3.$$

To estimate the number of *golgappas*, two students went about in different ways:

Student 1's calculation	**Student 2's calculation**
Estimated radius of an average *golgappa* is 1.5 cm.	Estimated radius of an average *golgappa* is 1.75 cm.
Volume of a *golgappa* $= \frac{4}{3} \times \pi (1.5)^3$ $\approx 14.14 \text{ cm}^3$. (neglecting the thickness of the *golgappa*)	Volume of a *golgappa* $= \frac{4}{3} \times \pi (1.75)^3$ $\approx 22.43 \text{ cm}^3$. (neglecting the thickness of the *golgappa*)
Assuming each *golgappa* is filled with 60% *pani* on an average, the volume of *pani* in a *golgappa* $= 14.14 \times 0.6 \approx 8.5 \text{ cm}^3$.	Assuming each *golgappa* is filled with 80% *pani* on an average, the volume of *pani* in a *golgappa* $= 22.43 \times 0.8 \approx 18 \text{ cm}^3$.
The number of *golgappas* that can be served is $= \frac{5000\pi}{8.5} \approx 1848$.	The number of *golgappas* that can be served is $= \frac{5000\pi}{18} \approx 873$.
Lallan can serve about 1850 *golgappas* with the *pani* he has.	Lallan can serve about 870 *golgappas* with the *pani* he has.

We see that the final answer depends upon the assumptions, estimations, and approximations done in the process.

Example 6: Anirban saw a few tennis balls lying around. He wondered, "How many tennis balls can fit in an empty classroom?". The classroom is of dimensions 30 ft × 30 ft × 15 ft. Estimate how many tennis balls of radius 3 cm fit in this classroom. Before calculating, make a guess.

The volume of the tennis ball is $\frac{4}{3} \times \pi \times 3^3 \approx 113 \text{ cm}^3$.

© NCERT not to be republished

The volume of the classroom is

$$30 \times 30 \times 15 = 13{,}500 \text{ ft}^3 \approx 37{,}80{,}00{,}000 \text{ cm}^3.$$

Can we find the number of tennis balls that can fit in the classroom by dividing the volume of the classroom by the volume of a tennis ball?

$$\frac{37{,}80{,}00{,}000}{113} \approx 33{,}45{,}132.$$

1 ft = 30.48 cm
1 ft³ ≈ 28317 cm³

1 ft ≈ 30 cm
1 ft³ ≈ 28000 cm³

No, the balls cannot fit in the room without leaving gaps in between. Hence this operation will only give an upper bound value, i.e., we can say for sure that we cannot fit more balls than this.

Accounting for these gaps can give a better estimate.



Fig. 14.17: These are some of the ordered ways of packing spheres in a cuboidal structure

Using the first configuration: Along each side of the room, the number of balls that can be placed side-by-side along the length is $\frac{\text{dimension of the room}}{\text{diameter of the ball}} \approx \frac{900}{6} = 150$. The same number can be placed along the width. Along the height, it is 75 balls.

Therefore, 150 × 150 × 75 = 16,87,500 denotes the approximate number of balls that can fill the room.

Using the other configurations, we might be able to fit more balls because of higher packing efficiency.

Make an estimate based on the second and third configurations.

Note: This is why spheres are not used as basic units to measure volumes as they leave gaps unlike cubes.

© NCERT not to be republished

As we have seen in guesstimate problems, different people may get different answers, but the reasoning they use matters the most. For these problems, you can start with a quick intuitive guess, model the situation by identifying the relationships among the quantities, make reasonable assumptions, and then calculate an answer by making suitable approximations. Look back to see how close your intuitive guess is to your estimate.

End-of-Chapter Exercises

For guesstimate problems, make a guess first before solving.

1. Estimate how many scoops of ice cream can be obtained from a cuboidal container of dimensions 10 cm × 15 cm × 20 cm.
2. A cube of integer side length a is made of unit cubes. Write an expression giving the number of unit cubes to be added to make a cube of side length $a + 1$.

*3. Solve the following:
   (i) Could a person drink enough water in a lifetime to fill an entire room the size of your classroom?
   (ii) Estimate the number of bricks used to build the walls of your classroom.
4. You are given two options: (A) one chocolate cube of side 50 mm, (B) hundred chocolate cubes of side 10 mm. Which option gives you more chocolate?

5. If all the people in the world are crowded together in one location, how much area would it cover?
6. A school provides milk to its students in cylindrical glasses, each with a diameter of 7 cm. If each glass is filled with milk to a height of 12 cm, how many litres of milk are needed to serve 1600 students? Use 1000 cm^3 = 1 litre.
7. The surface area of a sphere of radius 5 cm is five times the area of the curved surface of a cone of radius 4 cm. Find the height and the volume of the cone.

© NCERT not to be republished

8. Take Earth to be a perfect sphere with radius 6370 km. Take Jupiter to be a perfect sphere with radius 69,900 km. Take the Sun to be a perfect sphere with radius 6,95,700 km. Compute approximately:
   (i) the ratio of the volume of Jupiter to the volume of the Earth;
   (ii) the ratio of the volume of the Sun to the volume of the Earth.

   (Calculator can be used.)

9. Show that the volume of a sphere is equal to $\frac{2}{3}$ of the volume of the smallest cylinder which encloses it.

*10. Suppose the Earth is perfectly spherical. A string is wrapped tightly around the equator of the Earth. Another string, 1 metre longer, is placed around the Earth so that it forms a larger circle, staying the same distance above the ground everywhere.

How high above the ground is the second string?
Repeat this for: (i) the Moon (ii) Jupiter (iii) a volleyball. Are you surprised by the three answers? Why or why not?

*11. We have a cylinder with a base radius of r cm and height h cm. A square pyramid is fitted inside it. The square base of the pyramid lies on the base of the cylinder, its corners on the boundary of the cylinder. The apex of the pyramid lies on the top of the cylinder. Find the ratio of the volume of this pyramid to the volume of the cylinder.

12. What is the change in volume when:
   (i) the length of a cuboid with dimensions l, w, h is increased by 1 unit?
      (a) 1 cubic unit
      (b) $(lwh + 1)$ cubic unit
      (c) wh cubic units
      (d) lw cubic units
      (e) lh cubic units
   (ii) the radius of a cylinder with dimensions r, h is increased by 1 unit?
      (a) 1 cubic unit
      (b) $\pi r^2 h$ cubic units
      (c) πr^2 cubic units
      (d) $2\pi rh + 2\pi h$ cubic units
      (e) $2\pi rh + \pi h$ cubic units

   *(iii) the radius of a sphere is decreased by 1 unit?

*13. Given a cube with volume V, express its total surface area S in terms of V.

© NCERT not to be republished

*14. Given a cube with total surface area S, express its volume V in terms of S.

15. A cylindrical glass of height 25 cm and radius 4 cm has water up to a height of 16 cm. A crow wants to drink water from this glass. The water must be at a height of 20 cm for the crow to reach it. There are some marbles lying around. How many marbles of radius 1 cm should the crow drop into the glass to make the water reach the required height?

16. Find the volume of ink in a new ball point pen. Take the necessary measurements and make approximations, as needed.

17. Solve:
    (i) A ball of chapati dough of radius 6 cm is prepared. Estimate how many chapatis can be made from it?
    *(ii) Cut a coconut/muskmelon in half and find out the approximate volume of edible coconut flesh/fruit by taking the necessary measurements.

18. Looking at the *Ganita Manjari*, Grade 9, Part 2 textbook, Sheela wonders:
    (i) If all the pages of this textbook were laid out side-by-side on the floor would they cover the entire classroom floor?
    (ii) What is the maximum number of textbooks that can fit in an empty storeroom of dimensions 15 ft × 20 ft × 30 ft?

*19. If the entire human population decided to climb into one giant cube, how long would the side have to be?



*20. The Earth's surface has an estimated volume of 1.38 billion km^3 of water. Suppose the Earth is a perfect sphere and all this water forms a uniform layer completely covering the Earth's surface, like a thin water bubble. Estimate the thickness of this water layer. The Earth's radius is ~6371 km.

© NCERT not to be republished

(i) Write an expression that gives the thickness of this water layer.

(ii) Simplify the expression in (i) using a calculator.

*21. Give the dimension of a cuboid whose volume is halved when its surface area is doubled.

22. **Project:** Find the volume of your house making necessary approximations. Present how you solved it.

Chapter Summary

In this chapter, we have studied the following formulas for the surface areas and volumes of various fundamental shapes.

3D Shape	Surface Area	Volume
1. Cuboid 	$2(wl + hw + lh)$	whl
2. Right Circular Cylinder 	Curved surface area: $2\pi rh$ Total Surface Area of a cylinder covered at one end: $2\pi rh + \pi r^2 = \pi r(2h + r)$ Total Surface Area of a cylinder covered at both ends: $2\pi rh + 2\pi r^2 = 2\pi r(h + r)$	$\pi r^2 h$
3. Right Circular Cone 	Curved surface area: πrl Total surface area: $\pi r(l + r)$	$\frac{1}{3}\pi r^2 h$

© NCERT not to be republished

4. Sphere 	$4\pi r^2$	$\frac{4}{3}\pi r^3$
5. Hemisphere 	Curved surface area: $2\pi r^2$ Total surface area: $2\pi r^2 + \pi r^2$ $= 3\pi r^2$	$\frac{2}{3}\pi r^3$

© NCERT not to be republished

Learning Material

Graph Paper



© NCERT not to be republished

Graph Paper



© NCERT not to be republished

Graph Paper



© NCERT not to be republished

Graph Paper



© NCERT not to be republished

Net of a Cuboid



© NCERT not to be republished

© NCERT
not to be republished

Net of a Cube



© NCERT not to be republished

© NCERT
not to be republished

Nets of a Cylinder





© NCERT not to be republished

© NCERT
not to be republished

Nets of a Cone



© NCERT not to be republished

© NCERT
not to be republished

Net of a Triangular Pyramid



© NCERT not to be republished

© NCERT
not to be republished

Net of a Square Pyramid



© NCERT not to be republished

© NCERT
not to be republished

Chapter 3

Atmosphere and Climate

The Big Questions

1. *What is the composition of the atmosphere?*
2. *How do the different layers of the atmosphere affect the planet Earth?*
3. *What is the mechanism of monsoon?*
4. *How can we reduce our carbon footprint?*

0908CH03

What do you see when you look up in the sky? You might see the floating clouds, the sunshine, and feel a breeze as well. All of these are a result of a blanket of air surrounding the Earth, called the atmosphere. It is pulled down around the Earth by **gravity**, and is a mixture of gases in various proportions, vital for the survival of all living beings on the Earth. The atmosphere shields us from the harmful radiation coming from the Sun, including ultraviolet radiation. It regulates the Earth's temperature by trapping some of the Sun's energy and prevents it from escaping back into space. The atmosphere is a key component of the Earth's weather and climate systems, influencing factors such as temperature, humidity, and air pressure.

Gravity: Gravity is a fundamental physical force of attraction between objects that have mass or energy such as the Sun and the Earth. The force of attraction that the Earth's mass exerts on the objects that are on or close to its surface is referred to as Earth's gravity.

THINK ABOUT IT

Fig. 3.1

Can you imagine what would happen if there were no atmosphere? Discuss your thoughts with your friends and teachers.

© NCERT not to be republished

Composition and Structure of the Atmosphere

Composition of the Atmosphere

The Earth's atmosphere is composed of a mixture of various gases. Nitrogen and oxygen are the two primary and most abundant gases that are essential to life on the Earth. Carbon dioxide, argon, helium, neon, krypton, xenon, ozone, and hydrogen are some other gases present in the atmosphere, but are found in lesser quantities. Besides these, the atmosphere also consists of water vapour and tiny dust particles. The amount of water vapour in the atmosphere varies, but it generally ranges from 0.1 per cent to 0.4 per cent. It plays a significant role in cloud formation and precipitation. The composition of the atmosphere also varies with altitude.



Fig. 3.2. Composition of the atmosphere

LET'S RECALL

How is nitrogen useful for plants? Remember that you learnt this in the chapter 'The Invisible Living World: Beyond Our Naked Eyes', in your Grade 8 Science textbook.

Structure of the Atmosphere

The atmosphere has a layered structure. These layers are defined on the basis of changes in temperature and density with increasing altitude. The density of air is highest near the Earth's surface and

© NCERT not to be republished

decreases with **altitude**. The major layers extending from the Earth's surface to outer space are illustrated below.

Altitude: The height of a location above mean sea level is called altitude, usually measured in metres or feet. The mean sea level is considered zero.



Fig. 3.3. Layers of the atmosphere

- **Troposphere:** The troposphere is the most important layer of the atmosphere, with an average height of about 12 kilometres. In this layer, temperature decreases with increasing altitude. The air we breathe exists here, along with most of the water vapour and clouds. Nearly all the weather phenomena, such as rainfall, fog, and hail, occur in this layer. The troposphere is separated from the stratosphere by a transition zone known as the tropopause.

© NCERT not to be republished

- **Stratosphere:** Above the troposphere lies the stratosphere, extending up to 50 kilometres. This layer is ideal for flying aeroplanes because it is free of clouds and other weather disturbances. A notable feature of the stratosphere is that it contains a layer of ozone gas, which shields us by filtering the Sun's harmful radiation, including ultraviolet radiation. The stratopause marks the boundary between the stratosphere and the mesosphere.
- **Mesosphere:** Above the stratosphere lies the third layer of the atmosphere, the mesosphere. It extends up to a height of 80 kilometres. In this layer, temperature decreases with increasing altitude. Most meteorites entering from space burn up in the mesosphere.

DON'T MISS OUT

Temperature decreases with altitude only in the troposphere and mesosphere.

- **Thermosphere:** In the thermosphere, temperature rises very rapidly with increasing altitude, as the gas molecules in this layer absorb the X-rays and short-wave ultraviolet radiation of the Sun. The thermosphere extends from 80 to 700 km. It also helps with radio transmission by reflecting radio waves transmitted from the Earth back towards it. Ionosphere is a part of the thermosphere. Additionally, the northern and southern lights (**auroras**) also occur in the thermosphere.

Fig. 3.4: Aurora

The word 'aurora' originates from Latin, meaning 'dawn' or 'morning light.' It is named after the Roman goddess Aurora, the goddess of dawn , and refers to the colourful display of light seen in the sky near the poles. The 'solar wind' (charged particles emitted by the Sun), upon reaching the Earth's atmosphere, is directed towards the magnetic poles. As these particles interact with different atmospheric gases, each gas glows with a particular colour. This phenomenon is known as the Aurora Borealis in the Northern Hemisphere and the Aurora Australis in the Southern Hemisphere.

© NCERT not to be republished

- **Exosphere:** The uppermost layer of the atmosphere is known as the exosphere, characterised by very thin air. Light gases like helium and hydrogen float into space from this layer due to weak gravity. All of these layers play a vital role in the Earth's atmospheric processes and also affect its weather and climate.

DON'T MISS OUT

The air above us exerts a significant force on our bodies, and yet we do not feel it. This is because air presses on us from all sides, and our bodies exert a counter-pressure in response.



Fig. 3.5. The pressure inside our bodies is also equal to the atmospheric pressure and cancels the pressure from outside.

Weather and Climate

'Is it going to rain today?' 'Will it be bright and sunny today?' How often do you find yourself wondering about these questions when you want to go out and play?

The term **weather** refers to the hour-to-hour and day-to-day conditions of the atmosphere. Hot or humid weather may make one irritable, while pleasant or breezy weather may make one cheerful, or even plan for an outing. Weather can vary significantly from day-to-day. The average weather conditions of a place over a longer period of time refer to the **climate** of the place. Climate refers to the sum total of weather conditions and variations over a large area for an extended period of time, usually thirty years or more.

Elements of Weather and Climate

Various elements influence weather and climate. The major elements of atmosphere that impact human life on the Earth are temperature, precipitation, humidity, wind, and atmospheric pressure. These elements can change under varying conditions.

- **Temperature:** The temperature of the atmosphere varies not only between day and night but also across seasons, just as summers tend to be hotter than winters. An important factor affecting temperature distribution is **insolation**. The amount of

Insolation: The incoming solar energy from the Sun that is intercepted by the Earth.

© NCERT not to be republished

insolation decreases from the equator towards the poles. Hence, the temperature decreases from the equator towards the poles.



Fig. 3.6. Temperature zones of the Earth

- **Humidity:** When water evaporates from land and different water bodies, it becomes water vapour. When the levels of water vapour in the air are high, it leads to humidity. Therefore, humidity refers to the presence of water vapour in the air, creating moisture. As the air gets warmer, its capacity to hold water vapour increases, leading to higher humidity levels. On such a day, clothes take longer to dry, and sweat evaporates more slowly, leaving us feeling very uncomfortable.
- **Precipitation:** It occurs when a part of the atmosphere becomes saturated with water vapour, which condenses and 'precipitates', or falls on the Earth due to gravity. This includes drizzle, rain, snow, sleet, and hail. The main factors that affect precipitation include prevailing winds, mountains, and seasons. When precipitation falls on the the Earth in liquid form, it is called rain. Rain is the most common form of precipitation and lowers the temperature of a place. A long absence of rainfall results in a dry climate. Most of the groundwater is collected from rainwater.

© NCERT not to be republished

- **Atmospheric pressure:** The pressure exerted by the weight of air on the the Earth's surface is called air pressure. As we go higher in the atmosphere, pressure falls rapidly. It is highest at sea level and decreases with altitude. Horizontally, the distribution of air pressure is influenced by the air's temperature at a given place. In areas with high temperatures, air heats up and rises. This creates a low-pressure area. Low pressure is associated with cloudy skies and wet weather. In areas with lower temperatures, air is cold. It is therefore heavy and sinks, creating a high-pressure area. High pressure is associated with clear and sunny skies. Air always moves from high-pressure areas to low-pressure areas. You can refer to Chapter 8 of the Grade 8 Science textbook *Curiosity* to learn more about this.



Fig. 3.7. Wind is caused by air flowing from high-pressure to low-pressure areas. Its direction is influenced by the Earth's rotation.

- **Wind:** The movement of air from a high-pressure area to a low-pressure area is called wind. It can be gentle or strong. You can observe the flow of wind as it blows dry leaves down the pavement, gently blows away dust particles, or uproots trees during a storm.

THINK ABOUT IT

You might have noticed that sometimes the wind is so strong that it is difficult to walk against it. Can you think of some other times when strong winds have caused problems for you?

DON'T MISS OUT

Winds are named after the direction they blow from, for example, the wind blowing from the west is called westerly.

© NCERT not to be republished

Table 3.1. Wind speeds and their common effects

Wind	Speed (km/hr)	Common Effects
Calm	0–1	Calm, smoke rises vertically.
Light breeze	6–11	Wind can be felt on the face. Leaves rustle. An ordinary vane moves by winds.
Strong breeze	39–49	Large branches sway in the wind. Umbrellas are difficult to use.
Storm	103–117	It is very rarely experienced. Usually accompanied by widespread damage.

LET'S EXPLORE

Find out other categories of wind based on speed and their common effects, and share your findings in class.

Local winds such as the land breeze and the sea breeze, also affect the weather and climate of a place. They are essential in creating moderate climatic conditions in the coastal region.



Land is warmer than the water *Water is warmer than the land*

Fig. 3.8. Land and sea breeze

Sea breeze

It is a local wind that blows from sea to land during the day, especially in the afternoon, when the land becomes relatively warmer than the sea. This results in the formation of a low-pressure region over land, and so the wind starts blowing from the sea.

Land breeze

It is a local wind that blows from land to sea during the night, resulting from differential surface cooling between the land and the sea. Land cools faster than sea at night. Since the difference in temperatures and air pressure between the sea and the land is low, the wind speed is low.

© NCERT not to be republished

You may have observed that weather conditions often fluctuate, sometimes even within a single day. However, based on generalised monthly atmospheric conditions, or a common pattern over a few weeks or months—such as the days being cool or hot, windy or calm, cloudy or bright, and wet or dry—the year is divided into seasons.

LET'S ANALYSE

Note down the weather report from a local newspaper for two weeks and observe the changes occurring in the weather.

Seasons in India

The climate of India can be broadly classified as tropical monsoon. The Indian Meteorological Department (IMD) has recognised four distinct seasons in India:

- **Winter:** The winter season generally lasts from December to early April. The coldest months of the year are December and January, when the average temperature in the north-west is around 10–15°C. Temperatures increase towards the equator, reaching around 20–25°C in mainland India's south-east.
- **Summer or pre-monsoon:** The summer or pre-monsoon season spans from April to June, or up to July in north-western India. In western and southern regions, the hottest month is April; in northern regions, it is May. The average temperature across most of inland India ranges from 32–40°C.
- **Monsoon or rainy (Advancing monsoon):** The monsoon season generally spans from June to September. This season is dominated by the humid south-west summer monsoon, which slowly sweeps across the country in late May or early June. Monsoon rain begins to recede from north India at the beginning of October, and South India typically receives more rainfall during this time.
- **Post-monsoon (Retreating monsoon):** The post-monsoon season lasts from October to December. In north-western India, October and November are usually cloudless.

The Himalayan states, being more temperate, experience two additional seasons, autumn and spring.

© NCERT not to be republished

DON'T MISS OUT

Traditionally, India experiences six seasons, each about two months long—spring, summer, monsoon, early autumn, late autumn, and winter. These seasons are based on the astronomical division of the 12 months into six parts. The traditional Indian calendar also reflects these seasons through its arrangement of months.

Table 3.2. Traditional Indian seasons. These seasons and their duration may vary across different parts of the country.

Seasons (*Ṛtu*)	Months (According to the Indian Calendar)	Months (According to the Gregorian Calendar)
Vasanta	*Chaitra–Vaiśhākha*	March–April
Grīṣhma	*Jyeṣhṭha–Āṣhāḍha*	May–June
Varṣhā	*Śhrāvaṇa–Bhādrapada*	July–August
Śharad	*Āśhvina–Kārtika*	September–October
Hemanta	*Mārgaśhīrṣha–Pauṣha*	November–December
Śhiśhira	*Māgha–Phālguna*	January–February

THINK ABOUT IT

Hindustani Classical music associates certain *rāgas* with specific seasons. Find out which *rāgas* are connected to each season with the help of your elders and teachers.

DON'T MISS OUT

Kauṭilya's *Arthaśhāstra* contains records of scientific measurements of rainfall and their practical application in managing the country's revenue and relief efforts.

© NCERT not to be republished

Monsoon

The climate of India is strongly influenced by **monsoon** winds. The sailors who came to India during ancient times were among the first to notice the phenomenon of monsoon. They benefited from the reversal of the wind system as they travelled by sailing ships at the mercy of the winds. The Arabs, who had also come to India as traders, named this seasonal reversal of the wind system 'monsoon', derived from the Arabic word *mausim*, which literally means season.

Monsoon: It refers to the seasonal reversal in the wind direction during a year.

DON'T MISS OUT

Since crop production often depended on seasonal monsoon rains, Indians worked out methods to predict rainfall. *Kṛiṣhiparāśhara* and the *Bṛihatsaṁhitā* describe such methods in every season. *Kṛiṣhiparāśhara's* main technique was based on the positions of the Moon and the Sun in the sky. Varāhamihira in his *Bṛihatsaṁhitā* considered **lunar mansions (*nakṣhatras*)** in predicting seasonal rainfall. Even today, a large number of farming practices in India are based on these ancient methods.

Lunar Mansions (*nakṣhatras*): *Nakṣhatras* are a way of dividing the sky into 27 equal parts along the path the Moon travels. Each part is linked to a star or group of stars, but really it is just a fixed section of the sky. The Moon takes about 27 days to go around the Earth relative to the stars, so it moves through one *nakṣhatra* each day. That's why they are called "lunar mansions"—it's like the Moon stays in a different "house" in the sky every night.

Fig. 3.9. Arrival of monsoon in the Mountains

Monsoon winds are seasonal winds. They can be categorised into the south-west and the north-east monsoon. The south-west monsoon, also known as the summer monsoon, is characterised by winds blowing from sea to land across the Indian Ocean, the Arabian Sea, and the Bay of Bengal between June and September. It is mainly caused by the unequal heating of land and the sea. During summer, the landmass of India heats up faster than the surrounding oceans. This creates a low-pressure area over the Indian subcontinent, while the Indian Ocean remains relatively cooler and has high pressure. Winds move from high-pressure areas to low-pressure areas, so moist winds blow from the ocean towards the land, bringing rainfall. It accounts for most of the rainfall in the country throughout the year.

The winter monsoon, also known as the north-east monsoon, occurs in India from October to February. During this season, the Indian landmass cools faster than the surrounding oceans, creating a high-pressure area over the land and low pressure over the seas.

© NCERT not to be republished



Fig. 3.10. Normal dates of advancing of south-west monsoon

© NCERT not to be republished



Fig. 3.11. Normal dates of retreating monsoon

© NCERT not to be republished

As a result, cold and dry winds blow from land to sea. These winds generally do not bring rainfall to most parts of India. However, when the north-east monsoon winds pass over the Bay of Bengal, they pick up moisture and cause rainfall in the eastern coast of India, especially in Tamil Nadu, Andhra Pradesh, and parts of Karnataka. Thus, the winter monsoon is important for the rainfall of the south-eastern regions of India.

Monsoon plays a vital role in the lives of people in India. Most of India's agriculture depends on monsoon rainfall, as farmers rely on rain for sowing and growing crops. A good monsoon ensures sufficient food production and water supply in rivers, reservoirs, and wells. Monsoon also affects daily life, transport, festivals, and employment, especially in rural areas. However, excessive rainfall can cause floods, while weak monsoons can lead to droughts. Thus, monsoon greatly influences the economy, lifestyle, and livelihoods of people in India.

DON'T MISS OUT

Kālidāsa, in *Meghadūtam* written around the 5th century CE, mentions the date of the onset of the monsoon over central India and also traces the path of monsoon clouds.

LET'S EXPLORE

Describe in your own words how monsoon affects the lives of the people around you.

DON'T MISS OUT

Under the National Monsoon Mission (NMM), Ministry of Earth Sciences (Government of India) has developed state-of-the-art weather and climate prediction models. The overall objective of the NMM is to enhance monsoon predictions for India over all time frames.

'Mission Mausam' is designed to position India as a global leader in weather and climate sciences. The mission aims to make the nation 'Weather Ready' and 'Climate Smart', meeting the global standards. It aims to improve weather and climate services, ensuring timely and precise observation, modelling, and forecasting information for multiple sectors, including agriculture, disaster management, and rural development.

© NCERT not to be republished

Climate Change

One of the most urgent challenges that the Earth is facing today is climate change. It refers to long-term changes in weather patterns, such as temperature, rainfall, and wind, caused mainly by human activities, including the burning of fossil fuels, deforestation, and industrial pollution that releases gases like carbon dioxide into the atmosphere. These actions increase greenhouse gases such as carbon dioxide, methane, nitrous oxide, water vapour in the atmosphere, trapping heat and raising global temperatures. As a result, we are witnessing more frequent floods, droughts, melting of glaciers, rising sea levels, and loss of biodiversity. Climate change not only threatens ecosystems but also impacts human health, agriculture, and livelihoods. You may recall that you have read about 'climate change' in your grade 8 Science textbook. What actions can be taken to reduce such changes? It also has great impact on almost all sections of the population including women and children. Tackling this issue requires collective efforts—reducing **carbon footprints**, using renewable energy, protecting forests, and adopting sustainable lifestyles. Every small step counts, and every human being plays a vital role in shaping a healthier and greener future.

© NCERT not to be republished

LET'S EXPLORE

My Carbon Footprint

Step 1: My Daily Habits

Tick the options that best describe you.

A. Transport

- I usually walk/use a cycle. (Low impact)
- I use public transport/carpool. (Medium impact)
- I travel by private cars even for short distances. (High impact).
- I take flights more than twice a year. (Very high impact)

B. Electricity Use

- I always switch off electrical appliances (lights, fans, etc.) when not in use. (Low impact)
- I sometimes forget to switch off electrical appliances (lights, fans, etc.). (Medium impact)
- I leave electrical appliances (lights, fans, etc.) on frequently. (High impact)

C. Water Use

- I use water judiciously, for example, just one bucket of water for bathing. (Low impact)

Carbon footprint: The total amount of greenhouse gases released into the atmosphere as a result of human activities, such as energy use, transportation, or the production of goods and services.

- I sometimes waste water (leaving the tap running/ more buckets of water for a bath/long showers). (Medium impact)
- I rarely think about saving water. (High impact)

D. Waste and Plastics

- I reuse, recycle, and avoid single-use plastics. (Low impact)
- I sometimes use disposable plastics (bottles/bags/ straws). (Medium impact)
- I often throw away plastic and do not recycle. (High impact)

Step 2: Score Yourself

- **Low impact choices = 1 point**
- **Medium impact choices = 2 points**
- **High impact choices = 3 points**
- **Very high impact choices = 4 points**

Now add up your total score: _____ points

Step 3: My Climate Action Pledge

Think about **two simple changes** you can make to reduce your score, and write them down below.

1. ----------
2. ----------

Punjab Floods 2025: A Case Study

Fig. 3.12. Floods in Punjab

In 2025, Punjab experienced severe floods due to heavy monsoon rains and the consecutive swelling of the rivers Satluj, Beas, and Ravi. The floods damaged large parts of the state, including villages, agricultural fields, houses, and important infrastructure such as roads and bridges. While the water started to recede in some

© NCERT not to be republished

places and relief operations were carried out, the overall impact was devastating. The state suffered heavy economic losses, social disruption, and environmental damage, underscoring the urgent need for improved flood management and preparedness.

Causes

The floods in Punjab resulted from both natural and human-made factors.

- **Natural Causes:** In 2025, Punjab faced very heavy monsoon rains, which were intensified by the western disturbances that brought even more moisture and rain. It rained not only in Punjab but also in Himachal Pradesh and Jammu & Kashmir. The major rivers of Punjab—the Satluj, the Beas, the Ravi, and the Ghaggar—were already flowing high before the heavy rains began. When additional rain fell, water from the hills and local rainfall caused rivers to overflow, leading to severe flooding in many parts of Punjab.
- **Human-made Causes:** The floods were further aggravated by weak and old river embankments, or *dhūsī bāndh*, which could not stop the rising water during heavy monsoon rains. People had also built houses and farms too close to the rivers, reducing the natural space where floodwater could spread safely. Over time, silt and mud had collected in rivers and dams, reducing their capacity to hold and carry water. In some areas, flood warnings came late or were not clearly communicated, leaving people unprepared. All these factors together increased the damage caused by the floods.

Fig. 3.13. Relief operations during the floods

© NCERT not to be republished

Effects of the Floods in Punjab

- Many people lost their lives in the floods.
- Thousands of people had to leave their homes and move to relief camps for safety.
- Large areas of farmland were covered with water, and crops like paddy were severely damaged.
- Poultry and dairy farms were damaged and destroyed. Many animals, including cows, buffaloes, and chickens, got sick or died.
- Roads, bridges, border fences, and some public buildings were also damaged.
- Murky standing water caused health problems, including the spread of waterborne diseases and sanitation concerns.

Classroom Discussion

- To what extent did natural factors cause these floods compared to human activities?
- Do you think better planning could have reduced the damage? How?
- What are the guidelines for the management of floods according to the National Disaster Management Authority (NDMA)?
- What role can students/youth play in helping with disaster preparedness?

Before we move on...

- The Earth's atmosphere is made up of different gases, mainly nitrogen and oxygen, along with small amounts of other gases like water vapour and dust, support life and help in forming clouds and causing rainfall.
- The atmosphere is made up of different layers, namely the Troposphere, Stratosphere, Mesosphere, Thermosphere, and Exosphere, which are divided based on changes in temperature and air density as we go higher above the Earth's surface.
- Weather refers to the daily atmospheric conditions, while climate is the average weather of a place over a long period of time.
- India has a tropical monsoon climate, and the Indian Meteorological Department (IMD) divides the year into four main seasons, namely—Winter, Summer, Monsoon, and Post-monsoon.

© NCERT not to be republished

- Climate change is the long-term change in weather caused mainly by human activities like burning fuels and cutting trees, which leads to global warming and extreme weather conditions.
- We can reduce our carbon footprint by saving energy, using renewable sources, planting trees, and living in more eco-friendly ways.

Questions and activities

1. What is atmosphere? Explain its composition with the help of a pie diagram.
2. Draw a labelled diagram of the structure of atmosphere.
3. Which are the four main seasons of India?
4. Why do you not feel the pressure of the atmosphere?
5. In which layer of the atmosphere do aeroplanes fly and why?
6. Distinguish between the following:
   a. The troposphere and stratosphere
   b. The south-west monsoon and north-east monsoon
7. Do it yourself: Table 3.3 shows the average monthly temperatures and rainfall amounts for 10 representative stations. Study these figures on your own and convert them into 'temperature and rainfall' graphs. The visual representations will help you grasp their similarities and differences at a glance. One such graph (Fig. 3.14) is already prepared for you. See if you can arrive at some broad generalisations about our diverse climatic conditions.
   7.1. Now look at Table 3.3 again. Re-arrange the 10 stations according to their distance from the equator.
   7.2 Find out:
      a. Two stations with the most extreme climate.
      b. Two stations influenced by retreating monsoons.
      c. The two hottest stations in the months of
         (i) February (ii) June
   7.3. Now find out:
      a. Why does Shillong experience more rainfall than Kolkata?
      b. Why does Delhi receive more rainfall than Jodhpur?

© NCERT not to be republished

Table 3.3. Average monthly temperatures and rainfall for 10 representative stations (temperature and rainfall data are representational)

Stations	Latitude	Altitude (Metres)	Jan.	Feb.	Mar.	Apr.	May	Jun.	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.	Annual Rainfall
Temperature (°C) **Bengaluru**	12°58'N	909	20.5	22.7	25.2	27.1	26.7	24.2	23.0	23.0	23.1	22.9	18.9	20.2	
Rainfall (cm)			0.7	0.9	1.1	4.5	10.7	7.1	11.1	13.7	16.4	15.3	6.1	1.3	88.9
Temperature (°C) **Mumbai**	19°N	11	24.4	24.4	26.7	28.3	30.0	28.9	27.2	27.2	27.2	27.8	27.2	25.0	
Rainfall (cm)			0.2	0.2	–	–	1.8	50.6	61.0	36.9	26.9	4.8	1.0	–	183.4
Temperature (°C) **Kolkata**	22°34'N	6	19.6	22.0	27.1	30.1	30.4	29.9	28.9	28.7	28.9	27.6	23.4	19.7	
Rainfall (cm)			1.2	2.8	3.4	5.1	13.4	29.0	33.1	33.4	25.3	12.7	2.7	0.4	162.5
Temperature (°C) **Delhi**	29°N	219	14.4	16.7	23.3	30.0	33.3	33.3	30.0	29.4	28.9	25.6	19.4	15.6	
Rainfall (cm)			2.5	1.5	1.3	1.0	1.8	7.4	19.3	17.8	11.9	1.3	0.2	1.0	67.0
Temperature (°C) **Jodhpur**	26°18'N	224	16.8	19.2	26.6	29.8	33.3	33.9	31.3	29.0	20.1	27.0	20.1	14.9	
Rainfall			0.5	0.6	0.3	0.3	1.0	3.1	10.8	13.1	5.7	0.8	0.2	0.2	36.6
Temperature (°C) **Chennai**	13°4'N	7	24.5	25.7	27.7	30.4	33.0	32.5	31.0	30.2	29.8	28.0	25.9	24.7	
Rainfall (cm)			4.6	1.3	1.3	1.8	3.8	4.5	8.7	11.3	11.9	30.6	35.0	13.9	128.6
Temperature (°C) **Nagpur**	21°9'N	312	21.5	23.9	28.3	32.7	35.5	32.0	27.7	27.3	27.9	26.7	23.1	20.7	
Rainfall (cm)			1.1	2.3	1.7	1.6	2.1	22.2	37.6	28.6	18.5	5.5	2.0	1.0	124.2
Temperature (°C) **Shillong**	24°34'N	1461	9.8	11.3	15.9	18.5	19.2	20.5	21.1	20.9	20.0	17.2	13.3	10.4	
Rainfall (cm)			1.4	2.9	5.6	14.6	29.5	47.6	35.9	34.3	30.2	18.8	3.8	0.6	225.3
Temperature (°C) **Thiruvananthapuram**	8°29'N	61	26.7	27.3	28.3	28.7	28.6	26.6	26.2	26.2	26.5	26.7	26.6	26.5	
Rainfall (cm)			2.3	2.1	3.7	10.6	20.8	35.6	22.3	14.6	13.8	27.3	20.6	7.5	181.2
Temperature (°C) **Leh**	34°N	3506	–8.5	–7.2	–0.6	6.1	10.0	14.4	17.2	16.1	12.2	6.1	0.0	–5.6	
Rainfall (cm)			1.0	0.8	0.8	0.5	0.5	0.5	1.3	1.3	0.8	0.5	–	0.5	8.5

7.4. Now think why

a. Thiruvananthapuram has an equable climate?

b. Chennai has more rainfall only after the fury of the monsoon is over in most parts of the country?

c. Leh has moderate precipitation almost throughout the year?

© NCERT not to be republished



Fig. 3.14. Temperature and Rainfall of Delhi

7.5. Despite these differences across regions, can you observe any substantial evidence to conclude that the monsoons provide a very strong framework, lending overall climatic unity to the whole country?

8. Collect pictures of houses and clothing of people from different regions of India. Examine whether they reflect any relationship with the climatic conditions or the relief of those regions.

© NCERT not to be republished

Notes

© NCERT not to be republished

Chapter 8

Building Blocks in Economics: The Problem of Choice

The Big Questions

1. *What does economics deal with?*
2. *What are the key questions in economics?*
3. *How do different economic systems address these questions?*

0908CH08

If you had to choose, would you spend your pocket money on snacks or save it for a new pair of shoes? If your school library had only five copies of a new storybook but 20 students wanted to read it, who should get the book first? Can the students share them or should the school buy more copies? Which type of crop should a farmer grow based on the condition of the soil, rainfall, and **market** demand? Should an enterprise employ more labour or capital in the production process? Should the government spend more on building highways or hospitals?

Market: A place where buying and selling of products and services takes place. It could be a physical market or a virtual one on the internet.

These are not random questions; rather, these are examples of economic choices that individuals, enterprises, and governments have to make.

Some of our preferences are *needs*, such as essentials like food, water, and shelter, while others are *wants*, like gadgets, vacations, or luxury items. Human wants are unlimited and keep changing; for instance, people may want to upgrade from a bicycle to a motorbike and then to a car.

Needs

Wants

Fig. 8.1. Needs vs wants

© NCERT not to be republished

LET'S EXPLORE

→ List three things your parents bought this month. Can you classify them into needs or wants?

→ Do you think having too many wants may create problems? Why or why not?

Choices and Limited Resources

Resources: Factors used for the production of goods and services. These can be natural, like water and coal, or human-made, like capital and technology.

Medical equipment



Aircraft manufacturing

Refrigerator manufacturing

Fig. 8.2. Alternative uses of steel

Resources are required to satisfy human needs and wants. In Grade 8, you have learnt about factors of production—land, labour, capital, and technology—which are used for the production of goods and services. However, both natural and human-made resources are limited in quantity. They can be put to many alternative uses such as allocating money to buy fruit or a pair of shoes. Not just households, economies also have to decide how to use their scarce resources in the best possible way to meet unlimited wants and improve people's quality of life. For example, pictures in Fig. 8.2 show the alternative uses of steel.

When one alternative is chosen, the other options are given up. The value of what is given up is known as the **opportunity cost**. Let us understand this through an example. Imagine that a farmer has a piece of land and can choose to grow either barley or wheat on it. With limited land, water, and labour, the farmer must decide how much of each crop to produce. Consider the following table, which

© NCERT not to be republished

shows various combinations of quantities of barley and wheat that can be grown by the farmer.

Combination	Barley (in kg)	Wheat (in kg)
A	0	100
B	25	90
C	50	70
D	75	40
E	100	0

When these combinations are plotted on a graph (Fig. 8.3), where the x-axis represents the quantity (in kg) of barley grown, and the y-axis represents the quantity (in kg) of wheat grown, a downward sloping curve is derived.



Fig. 8.3. Production Possibility Curve

This is called the **Production Possibility Curve (PPC)**, which shows the trade-off between barley and wheat produced. As the farmer moves from point A to E, they produce more barley and lesser wheat. However, to grow more barley, some wheat must be sacrificed—this is the opportunity cost of growing barley. All the points on the PPC show the maximum output that can be produced through efficient use of resources by avoiding wastage. This helps in better planning and decision-making by enterprises and the governments.

Production Possibility Curve (PPC): The curve showing different combinations of goods that can be produced using all available resources.

© NCERT not to be republished

LET'S EXPLORE

- → Ask your parents about how they make choices for everyday purchase. What is the opportunity cost of making a particular decision?
- → How do you decide to spend your time? Is time a scarce resource?

What does Economics Deal with?

The word **Economics** comes from the Greek word *oikonomia*, which in turn is composed of two words: *oikos*, which is usually translated as 'household'; and *nemein*, which is best translated as 'management'. So, economics refers to household management. In the case of limited resources and unlimited wants, not just families but also nations must plan how to use their resources efficiently.

Since resources have competing uses, individuals, enterprises, and governments must decide how to best allocate them, as these decisions affect the well-being of people and society as a whole. The discipline of Economics deals with how choices are made by optimising the use of limited resources to satisfy the needs and wants. It explains how different **economic entities**—consumers, producers, governments, and financial institutions—interact in an economy. For example, how people work and earn wages, how wealth and resources are distributed, how prices are determined in the market, how education and technology drive investment, and how government policies and trade influence prices in the market, employment, and so on.

However, good decisions rely on **data** and analysis, not guesswork. For example, families allocate their money for essential items (such as food, medicines, and school supplies), non-essential items (such as jewellery, entertainment, and restaurant meals) and savings. Governments use revenue from taxation to plan expenditure on infrastructure and welfare programmes. Enterprises study market trends and new innovations to better serve customers and maximise profits. Economists study the available alternatives, associated opportunity costs, and potential outcomes to help individuals, enterprises, and institutions make decisions. They use data from government reports such as economic **surveys** and financial statements of companies, and their analysis helps to understand the potential risks and opportunities. The scope of their work includes:

Economy: The state of a country or region in terms of the production and consumption of goods and services, and the flow of money.

Economic entities: One who participates in an economic activity, for example, producers, consumers, government, and enterprises.

Data: Facts and statistics collected together for reference or analysis.

Surveys: A systematic method for collecting and analysing data related to the economic conditions and behaviours of populations.

© NCERT not to be republished



Fig. 8.4. Scope of work of Economists

Economic Survey: A Report on Indian Economy



The *Economic Survey of India* is an important annual document prepared by the Ministry of Finance and presented in Parliament before the Union Budget. It reviews the country's economic performance during the past year and analyses various sectors of the economy such as agriculture, industry, services, and other areas like employment, inflation, education, health, infrastructure, etc. It discusses future challenges and opportunities for the economy. This helps people understand how the Indian economy is performing and what steps the government may take to improve growth and development. It also acts as a blueprint for the upcoming Union Budget by providing crucial insights for policymakers while making **policy**-related decisions. It is also useful for citizens as it explains economic data in a clear manner.

You can have a look at the latest economic survey at:

https://www.indiabudget.gov.in/economicsurvey/

Policy: A course or principle of action adopted or proposed by organisations or individuals.

© NCERT not to be republished

Key Questions in Economics

Any mismatch between unlimited wants and limited resources gives rise to three key questions that the discipline of economics seeks to address.



Fig. 8.5. Key questions that economics seeks to address

What to Produce and for Whom?

Economy: System of production, distribution, trade, and consumption of goods and services within a specific area such as a country.

This fundamental question concerns which goods and services, and in what quantities, should be produced to meet the needs of the **economy** over a given period. For instance, should farmers produce water-intensive crops such as sugarcane and paddy, or drought-resistant crops such as millets and pulses? Producing sugarcane yields high profits and supports industries such as sugar, whereas producing millets and pulses saves water, improves soil health, and promotes sustainable agriculture. Here, the opportunity cost of producing sugarcane is the forgone gains from saved water and improved soil health. This type of decision reflects the trade-off between short-term economic gains and long-term sustainability by accounting for the opportunity costs of various alternatives. Similar trade-offs have to be made by companies, governments, and consumers.

The question of 'for whom to produce' delves into the purpose of goods and services produced, how they are produced and distributed, and who benefits from their production. Since resources are limited

© NCERT not to be republished

and people have different needs, income levels, tastes, and lifestyles, producers decide which group of consumers they want to serve. For example, shoes are a common product, but different types of shoes are produced for different groups of people depending on their needs and purchasing power.

- School shoes are produced for students. They are usually simple in design, durable, and affordable.
- Office-wear shoes are made for working professionals. These shoes focus on comfort, formal appearance, and quality, often using leather or polished materials.
- Sports shoes are produced for athletes and fitness enthusiasts. They are designed using special rubber soles and lightweight materials to provide grip, flexibility, and support.
- Casual shoes or slippers are produced for daily use by people and need to be comfortable yet affordable.

The decision of 'for whom to produce' also affects the materials used. For instance, leather shoes are generally targeted at office-goers and high-income customers, whereas rubber or synthetic shoes are aimed at sports players, factory workers, or people who need affordable and durable footwear. Producers analyse what consumers like, how much money they have, and how much demand there is, before deciding what to make. This makes sure that limited resources are used well and not wasted.

THINK ABOUT IT

Should the government allocate more funds to healthcare and education or to defence and space exploration? Why or why not?

How to Produce?

After deciding what to produce, the next question is how to produce it—which methods, resources, and technologies should be used. For example, whether a manufacturer should automate processes or employ more labour for producing goods.

To answer this question, producers must select the right mix of factors of production—land, labour, capital, and technology. Production can be labour-intensive (using more workers and less machinery) or capital-intensive (using more machines and technology and less workers). Usually, economic activities related to agriculture and handicrafts rely more on labour, whereas industries such as steel and automobile manufacturing depend more on machinery.

© NCERT not to be republished



Fig. 8.6. Factors of production

However, the choice of the production technique employed depends on the cost of capital, choice of technology, and the nature of the product. The availability of various factors of production and their relative cost, and the laws as well as regulations in the country determine the decision by enterprises to address this key question. A garment manufacturer must choose between labour-intensive and capital-intensive methods of production. If machines are expensive, the firm will rely more on labour, but if machines become affordable, it may shift to automation. The choice also depends on the level of technology available—advanced technology encourages machine use, while limited technology leads to manual production. The nature of the product is important too, as customised or designer clothes require skilled labour, whereas mass-produced garments are better suited for machines. Additionally, if labour is cheap and easily available, labour-intensive methods are preferred, but if labour is costly or scarce, machines become more efficient. Government laws and regulations, such as labour laws or incentives for machinery, also influence this decision.

Economic Systems and How Choices are Made

In an economy, the answers to these three key questions depend on how the resources used to produce goods and services are organised and who controls the decision-making regarding them. The system that defines the mechanisms for the production, consumption, and distribution of goods, services, and resources is known as the economic system of a country.

The three kinds of economic systems are explained in the following pages.

© NCERT not to be republished

Planned Economy

In a **planned economy**, a central planning authority of the government, such as the planning commission, makes all major economic decisions in the market, that is, what and how much will be produced, how they will be produced, and who will get to use them and at what prices. The government has ownership in most resources and sectors like land, factories, banks, and transport. With limited private ownership, enterprises usually follow the central authority's targets rather than market demand, and are heavily regulated by the government through strict permits and licenses to produce goods and services. However, this prevents a large number of enterprises to operate in the market and thus restricts competition among private enterprises. As a result, there is little motivation among enterprises to improve quality or innovate. Some examples of planned economies are the former Soviet Union, North Korea, and Cuba.

Planned economy: An economic system in which the allocation of resources, and prices of goods and services are determined by the government.

Market Economy

In a **market economy**, the questions of what, how, and how much to produce are addressed mainly by the forces of demand and supply with little government intervention. Often, the government acts like a referee in a football match. It ensures safety and law and order, and it does not control prices or production. The ownership of factories, shops, land, and other resources, largely rests with individuals and private companies. Many producers offer similar products, which encourages better quality, lower prices, and innovation in production of goods and services. Some of the prominent examples include the United States of America, Japan, and Hong Kong. However, governments play an important role even in these economies.

Market economy: An economic system in which the allocation of resources, and the prices of goods and services are determined primarily by market forces. The role of the government is to provide public goods and physical infrastructure.

LET'S EXPLORE

- In your opinion, should the government completely stay out of enterprise decisions?
- Can you think of an example where government action helped or harmed an industry or sector?



Fig. 8.7. Role of government and private ownership in a market economy

© NCERT not to be republished

Mixed Economy

Mixed economy: The market system of resource allocation in which the government and private sector coexist and compete with each other in the market. The private players are regulated by the government. Almost all economies are mixed.

A **mixed economy** combines features of both market and planned economies. In this system, private individuals, enterprises, and the government play important roles in making economic choices and decisions. We also find large public sector companies that play a very improtant role in the market. In reality, most economies have features of mixed economic systems that allow the existence of private ownership, with some degree of government regulation.

A few examples of mixed economies include India (post-1991), China (post-1978), Germany, and Sweden. Even market economies like the United States of America and Singapore have significant government involvement in the market.

Public goods: Goods and services that are available to all individuals without anyone being excluded. The use of public goods by some people does not prevent others from using them—for example, parks, roads, police services, street lights, and basic education.



Fig. 8.8. The role of government and market in a mixed economy

© NCERT not to be republished

DON'T MISS OUT

India's economic system has also evolved over time in response to changing needs and challenges. In the decades after Independence, India followed a more state-led approach similar to a planned economy. The government played a major role in controlling industries, allocating resources, and regulating production through licenses and permits, while many key sectors, such as banking, transport, and heavy industries were dominated by the public sector. However, by 1991 the country faced serious economic difficulties. As a result, the government introduced major economic reforms that reduced excessive regulations, encouraged private enterprise, opened the economy to global

trade and investment, and increased competition. These reforms gradually shifted India towards a more market-oriented system while still retaining an important role for the government. You will study more about these changes in your higher grades.

This chapter has shown that economics is essentially about making choices in a world of scarce resources and unlimited wants. Individuals, enterprises, and governments must constantly decide how to best use available resources, keeping in mind the opportunity cost of each decision. These choices are reflected in the three key economic questions—what to produce, how to produce, and for whom to produce. Different economic systems provide different ways of answering these questions, but most modern economies combine elements of both market and planned economic systems. Understanding these ideas helps us appreciate how everyday decisions, public policies, and economic systems together shape the production, distribution, and use of resources in an economy.

Before we move on...

- Economics deals with how individuals and societies make choices to use limited resources to satisfy unlimited wants. Every choice involves an opportunity cost—giving up one option for another.
- Every economy faces three central questions—what to produce, how to produce, and for whom to produce—to decide how best to use scarce resources.
- Different systems answer these questions differently: market economies rely on private decisions and demand and supply whereas, planned economies depend on government control, and mixed economies combine both.

Questions and activities

1. Why do you think people's wants keep changing over time? How does this affect production in an economy? Why cannot all our wants be satisfied?
2. 'Human wants are unlimited and keep changing'. How do you think this constant desire for more creates pressure on the environment? Can the fulfilment of wants and the extraction of resources be balanced?

© NCERT not to be republished

3. Can you think of a resource in your region that is scarce but used wastefully? How could it be managed better?
4. Which economic system—market, planned, or mixed—do you think gives people the most freedom? Which economic system is best suited for promoting innovation? Why?
5. Critically examine why pure economic systems rarely exist in reality. Assess the limitations of such systems and justify why a mixed economy is often considered a more practical and effective approach in real-world contexts.
6. A student has ₹100 and must choose between buying a notebook or saving the money for buying a tennis racket later. Which economic concept best explains this situation?

   a. Demand
   b. Opportunity cost
   c. Production
   d. Inflation

7. How does understanding opportunity cost improve the quality of economic decision-making?
8. Can effective economic decisions be made without reliable data? Support your answer with an example.
9. Analyse how a country's present economic choices can shape its long-term future. Why is it important to consider future consequences while making economic decisions today?
10. Identify a news article from any newspaper of your choice about a product or commodity (such as vegetables, fruits, fuel, or electronics) where producers or companies are deciding how much to produce or supply. Write 2–3 sentences explaining the example you found and why the production decision was made.

Notes

© NCERT not to be republished

Chapter 9

The Price Puzzle: What Drives the Market

The Big Questions

1. *What are the factors that influence the demand for and supply of goods and services in a market?*
2. *How are prices of goods and services determined through demand and supply interactions?*
3. *What is market equilibrium, and does it exist in the real world?*
4. *How and why does the government intervene in the market?*

0908CH09

What happens if the mangoes your parents bought last week are now half the price? Why are vegetables expensive in the morning but are cheaper in the evening? Or why does the price of onions seem to change every few months? Why does the same flight seat cost ₹3,000 on one day but ₹9,000 on another day? Why do shops and malls announce discounts at certain times of the year? Have you ever wondered about the reasons behind these situations in a market?

In the Grade 7 chapter 'Understanding Markets', you learnt about the interaction among buyers and sellers and how prices adjust when the seller sets them too high or too low. Prices do not change randomly; they react to what people want, how much is available, the seasons, festivals, trends, and sometimes even rumours. Whether it is snacks, movie tickets, mobile phones, or vegetables, the prices of all goods and services are determined by two powerful forces constantly at work, that is, demand and supply.

This chapter explores the concepts of demand, supply, and price determination and provides a glimpse of the outcomes of their interplay in real-world situations.

© NCERT not to be republished

Demand

Purchasing power: It is a measure of how much one unit of a particular currency can buy at a particular time.

As the mango season approaches, the prices of mangoes are generally high, so people tend to buy them in smaller quantities. But when prices start falling, people prefer to buy larger quantities. *The quantity of a product that people are willing and able to buy at a particular price, depending on their needs, preferences, season, trend, and income, is called the demand for the product.* Demand is not just the desire to buy something; it is the willingness complemented by the ability or **purchasing power** to buy it.

Fig. 9.1. P= Price, Q= Quantity

As with mangoes, when the price of any product rises, the quantity demanded decreases, and when the price falls, the quantity demanded increases. This phenomenon is called the **Law of Demand**, which highlights the inverse relationship between the price of a product or service and its quantity demanded.

Let us understand this with an example. At the beginning of the mango season, the price of mangoes was very high (₹150 per kg). Srivalli, a consumer, bought only 1 kg. As more mangoes became available in the market, over time, the price fell to ₹100, so she bought 2 kg, and later, when the price dropped to ₹50 per kg, she bought 3 kg. The quantity of a good or service that an individual consumer wants to buy at different prices, keeping other factors constant, is known as **individual demand**. For Srivalli, the individual demand is shown in the table below, which is also known as the 'demand schedule'. This demand schedule, when represented graphically, is called the 'demand curve'.

Demand Schedule

Price of mango per kg	Quantity demanded by Srivalli
₹ 150	1 kg
₹ 100	2 kg
₹ 50	3 kg

(a)



(b)

Fig. 9.2. Individual demand schedule (a) and Individual demand curve (b)

© NCERT not to be republished

The y-axis in the Fig. 9.2 (b) represents the price of mangoes (in ₹), and the x-axis shows the quantity demanded of mangoes (in kg). Srivalli bought 1 kg of mangoes at ₹150 (represented at point A). As the price fell to ₹100 per kg, she bought 2 kg (at point B). But as the price fell to ₹50, she bought 3 kg (at point C). When the points of intersection, such as A, B, and C, are connected, the downward sloping line DD' is called the demand curve. The downward-sloping individual demand curve represents the inverse relationship between price and the quantity of a product demanded by the buyer, assuming other factors like income, taste, etc., to be constant.

What happens when others want to buy mangoes too? The total quantity of mangoes demanded by all potential buyers at different prices is known as **market demand**, that is, the sum of all individual demand. Let us consider two more consumers, Alex and Israt, whose individual demand is given in the schedule below:

Table 9.1. Individual and market demand schedule

Price	Q1 (Srivalli)	Q2 (Alex)	Q3 (Israt)	Market Demand (Q_D)
₹150	1 kg	2 kg	3 kg	6 kg
₹100	2 kg	4 kg	6 kg	12 kg
₹50	3 kg	6 kg	9 kg	18 kg

By summing the demand of all three consumers, Q1+Q2+Q3, the market demand Q_D is derived. When the market demand is plotted at



Fig. 9.3. Individual demand curve (a) and market demand curve (b)

© NCERT not to be republished

different prices, we get the market demand curve DmDm' as shown in Fig. 9.3 (b).

DON'T MISS OUT

Did you notice that the market demand curve is flatter than Srivalli's individual demand curve? Why is that? Market demand aggregates many consumers, so the same price change creates a larger total quantity response. When the price falls from ₹150 to ₹50, Srivalli's demand increases by 2 kg, but market demand increases by 12 kg, making the market curve flatter and more responsive.

Other Determinants of Demand

When a new model of a popular smartphone is launched, long queues and pre-bookings indicate the rush to buy it, even if it is more expensive. So, the demand for a product does not necessarily change only because of price. Many other factors influence how much people want to buy, even when the price of the good or service remains the same. Let us see some of these factors at play.

Related goods: Products whose demand is interconnected, meaning a change in the price or availability of one directly affects the demand for the other.

Price of related goods

The demand for a good can be affected by changes in the prices of **related goods**. There are two types of related goods:

a) **Substitute goods** – These goods can replace each other, like tea and coffee. If tea's price remains the same while coffee becomes more expensive, people who consume coffee may switch to tea, thereby increasing its demand. If Srivalli cannot afford to buy mangoes at the market price, she may buy bananas. When the price of a good rises, people tend to replace it with another relatively cheaper alternative. Hence, if the price of the substitute good increases, the demand for the other related good will increase.

b) **Complementary goods** – These goods are generally used together to provide utility to the consumer, for instance, smartphones and earphones, or cars and petrol. If the demand for printers increases, the demand for printer cartridges may also rise, even though the price of cartridges remains unchanged. Similarly, if movie tickets become more expensive, people may refrain from going to the cinema, so demand for popcorn sold in cinema halls may also fall.

© NCERT not to be republished

Income of the consumer

When household income rises, consumers can afford to buy more or choose higher-quality products. A rise in income generally makes people feel more confident about their ability to spend, so the quantity demanded for several goods rises, even if prices remain the same.

Taste and preference of the buyer

Every consumer has specific tastes and preferences for certain products, which determine their demand. For example, Srivalli likes mangoes and cannot substitute them by oranges, even if oranges are cheaper than mangoes.

The demand also depends on the size and composition of the nation's population. For example, being the most populous nation, India's domestic consumer demand contributes to its economic growth. In addition, the population's composition shapes the demand for types of products and services. More children indicate increased demand for sports shoes, more working adults means a higher demand for formal shoes, and more elderly people imply a higher demand for comfortable or orthopaedic shoes.

THINK ABOUT IT

What happens when you consume the first mango? It tastes delicious, right? The second one is good? The third one and so on? You are barely interested in eating mangoes by this point. Why do you think this happens?

This is because the additional utility or usefulness derived from a product declines as more of it is consumed. This is known as the **diminishing marginal utility** principle in economics. As the utility derived from a successive quantity of products falls, the willingness to pay for the products also decreases, so demand falls.

Seasonality

Have you seen crowded bookshops at the beginning of the new academic session? Or customers flocking to sweet shops during the festive season? Or sweaters and jackets being demanded during the winter season? This is because individuals may demand different products at different times of the year, and these changes often depend on weather, festivals, and cultural habits rather than the price of the good.

© NCERT not to be republished

Future price expectations

Future price expectations influence current demand even when current prices have not changed. If consumers expect prices to fall, they postpone purchases, decreasing present demand. If they expect prices to rise, they buy immediately, increasing present demand. For example, people delay buying durables before Diwali or the New Year, expecting festival discounts.

LET'S EXPLORE

- → Create your own demand schedule for buying notebooks at different prices. At what price would you buy the most? At what price would you stop buying altogether? What could be the reason behind your choices?
- → Ask your family members if they postponed or advanced buying any product because of future expectations of changes in price?

Supply

Supply is the quantity of a product that sellers are willing and able to offer at a particular price. As price increases, quantity supplied increases, and as price decreases, quantity supplied falls. This is because higher prices increase profitability, incentivising producers to increase output, and also attract new firms to the market. This is known as the law of supply. **Individual supply** is the quantity a particular seller offers at different prices.

Supply Schedule

Price of mango per kg	Qs by seller A
₹ 50	1 kg
₹ 100	2 kg
₹ 150	3 kg

(a)



(b)

Fig. 9.4. Individual supply schedule (a) and Individual supply curve (b)

© NCERT not to be republished

At the start of mango season, supply is low, making mangoes costly. Mid-season, the supply increases and prices fall. This shows how prices depend on the interaction between demand and supply. When supply is less than demand, prices rise; when supply exceeds demand, prices fall.

Market supply is the sum of all individual supplies. For example, when mango prices are ₹50/kg, a seller supplies 1 kg; at ₹100/kg, he supplies 2 kg; at ₹150/kg, the seller supplies 3 kg. This pattern of higher prices leads to greater quantity supplied, which gives an upward-sloping supply curve as shown in Fig. 9.4.

Now consider three sellers, A, B, and C, in the market, who offer mangoes for sale in different quantities at different prices. So, their supply schedule is as follows:

Table 9.2. Supply schedule of sellers

Price	Seller A	Seller B	Seller C	Market supply (kg) ($A+B+C=Q_S$)
₹ 50	1	3	2	6
₹ 100	2	4	6	12
₹ 150	3	7	8	18

By combining the quantity supplied by all three sellers (A+B+C), the market supply Q_S is derived. By plotting the market supply with corresponding prices, the market supply curve is obtained.



Fig. 9.5. Individual supply curve (a) and market supply curve (b)

© NCERT not to be republished



Fig. 9.6. Prices affecting supply decisions

Other Determinants of Supply

Price of related goods

Suppose a farmer faces two choices. If wheat prices are low but chickpea prices are high, he will grow more chickpeas in the next season. Therefore, the supply of one good depends on the profitability of other alternatives for the supplier.

Number of sellers in the market

If there are more sellers in a market due to higher competition and increased production, the market supply of the product would exceed the demand. As a result, prices would fall. Likewise, if there are fewer sellers in the market, supply would be lower than demand, and prices would rise.

Technology

Improvement in technology reduces the cost of production, allowing producers to produce more and supply more and vice versa. For example, with improved techniques such as drip irrigation and weather sensors, crop production may rise, leading to a higher supply. Similarly, the adoption of cold storage facilities in the transportation of mangoes to distant markets, thereby increasing market supply.

© NCERT not to be republished

Future expectations

If producers or suppliers expect a boom in the demand for goods in the near future, they will produce more, and supply will rise. Similarly, if the producer is expecting lower demand, they will reduce production, leading to a fall in supply. For instance, if potato wholesalers expect prices to rise during the peak season, they might hold back supply now to sell later at higher prices.

LET'S EXPLORE

What happens to the supply of a product in case of a change in the cost of inputs, discovery of an alternate input, depletion of resources, change in weather, disaster, etc.? Discuss in class using examples of diverse goods and services.

Market Equilibrium

Every market involves negotiation between what buyers are willing to pay and what sellers are willing to accept. Thus, prices are determined by the interaction between demand and supply.

The table below shows the quantities of mangoes demanded and supplied at the selected prices. At a lower price, there is excess demand, whereas at a higher price, there is excess supply.

Table 9.3

Price (₹)	Quantity demanded (Qd) of Mangoes (in kg)	Quantity supplied (Qs) of Mangoes (in kg)	Quantity Supplied and Quantity Demanded	Outcome
40	38	6	Qs<Qd	Excess Demand
100	12	12	Qs= Qd	Market Equilibrium
150	8	43	Qs > Qd	Excess Supply
Equilibrium Price = ₹ 100		Equilibrium Quantity = 12 kg		

At a price of ₹100, the quantity demanded equals the quantity supplied. This point is known as the **market equilibrium.** At this point, there is no pressure for prices to change, and the market is 'cleared', which means that there is neither a shortage (excess demand) nor a surplus (excess supply).

Market equilibrium: Market equilibrium is the point where supply of goods and services equals demand, meaning there is no excess supply (surplus) or excess demand (shortage) in the market, and prices tend to remain stable unless external factors change.

© NCERT not to be republished



Fig. 9.7

On the graph in Fig. 9.7, equilibrium is where the demand curve DMDM' intersects the supply curve SMSM', that is, at point E, where the equilibrium price = ₹100 and the equilibrium quantity = 12 kg.

LET'S ANALYSE

Using data from Table 9.3, plot the demand and supply curve at the three prices, i.e., ₹40, ₹100, and ₹150. Identify and mark excess demand and supply on the graph. Think about how equilibrium could be reached in these scenarios.

Does Market Equilibrium Exist in the Real World?

In theory, equilibrium is an intersection point between demand and supply. But in the real world, markets are dynamic with constantly changing conditions. For example, changes in technology, wages, interest rates, as well as wars, political events, pandemics, weather, and natural disasters alter demand and supply. Therefore, 'equilibrium' in the real world is never stable and moves all the time, i.e., the market is always in a process of adjusting to a new equilibrium, never fully settling at the previous one. For example, during the COVID-19 pandemic in 2020, the demand for face masks surged rapidly. As a result, the supply could not catch up immediately, and the price of masks rose significantly. Over time, suppliers adjusted to the increased demand and prices fell. Once the pandemic was over, demand reduced further, and the prices reduced to pre-pandemic levels.

© NCERT not to be republished

Tariffs by hotels: An example of dynamic markets

Hotels do not charge the same price (also called tariff) for rooms all the time. Their prices change according to demand, season, and special situations. This shows how markets are dynamic, meaning prices keep changing based on varying conditions.

Suppose a hotel in Goa has 100 rooms. The room tariff changes as follows:

- Off-season weekday (Monday in July): ₹1,500 per night
- Weekend during tourist season (Saturday in December): ₹8,000 per night
- New Year's Eve (very high demand): ₹25,000 per night

If a group tour cancels its booking, the hotel may reduce tariff by 40 per cent overnight to quickly fill empty rooms. Hotels may also change tariff several times in a day to earn maximum **revenue**. These tariff changes depend on other factors such as:

- How fast rooms are getting booked
- Tariff charged by nearby hotels
- Festivals, conferences, or events in the area
- Weather forecasts
- Number of days left before arrival
- Past booking trends

This example shows how prices in a market change with changes in demand and supply in real-world markets.

Revenue: Total amount of money a business earns from the sale of goods or services, or other operating activities, before any expenses are deducted.

THINK ABOUT IT

Can you think of another real-life example (other than hotels) where prices change frequently? Explain why the prices keep changing.

Our choices today affect future resources. For example, high demand for fast fashion, overfishing and overuse of groundwater can harm future supply. So, should we focus only on short-term gains, or also think about long-term sustainability? How could this affect the market equilibrium?

© NCERT not to be republished

Price ceiling: An imposed price control that sets the maximum amount a seller can charge for a product or service.

Price floor: An imposed limit on how low a price can be charged for a product, good, or service. For a price floor to be effective, it must be set above the market equilibrium price.

Monopoly: A market structure with a single seller or producer controlling the entire supply of a unique product or service, facing no close substitutes, allowing them significant power to set prices and output.

Role of Government in the Economy

Today, India is the fourth-largest economy in the world. It is a market-based, regulated economy in which prices depend on demand and supply. However, markets do not always work fairly. Markets allocate goods and services based on willingness and ability to pay. Suppose essential goods like medicines become very expensive, will they be accessible to all? In such cases, fairness and equity in allocation are required, particularly to ensure the welfare of vulnerable and low-income groups.

So, the government plays an important role in the economy in the following key aspects.

Regulation of Unfair Practices

The government regulates unfair practices to protect consumers, workers, and producers from exploitation and injustice. For example, the government sets maximum prices (**price ceiling**) for essential goods like medicines to prevent overcharging. Similarly, the government sets a minimum wage to ensure workers earn enough for their hard work. This lower limit is known as the **price floor**.

Sometimes a single or a few sellers dominate the market; they can charge higher prices and supply less than a competitive market would. This form of **monopoly** would be detrimental to consumer welfare as it may charge higher prices, provide poorer quality of goods and services, restrict supply, and so on. The government regulates such practices by keeping the prices and quantity supplied in check.

THINK ABOUT IT

Have you ever seen or heard of the government fixing prices or wages (for example, bus fares, medicines, or minimum wages)? Share an example and why you think it was done.

Many regulators such as the Reserve Bank of India (RBI) for banking, the Central Consumer Protection Authority for violation of consumer rights and unfair trade practices, the Telecom Regulatory Authority of India (TRAI) for the telecommunications sector, the Securities and Exchange Board of India (SEBI) for the securities market, and so on, ensure transparency in the market. Do you remember some regulators from the Grade 7 Social Science textbook chapter 'Understanding Markets'?

© NCERT not to be republished

During COVID-19, the demand for sanitisers surged, leading to stockouts and sharp price increases. Some shopkeepers began **hoarding** and **black-marketing**. The government intervened by declaring sanitisers essential commodities under the Essential Commodities Act, 1955, capping the maximum retail price at ₹100 for 200 ml bottles. Meanwhile, many companies started production, and sanitisers soon became widely available at fair prices. How do such price controls affect suppliers and consumers? While in this case the price control was for an emergency, do you think such controls should be in practice forever?

Hoarding: Accumulation of goods, commodities, or money by individuals, or firms beyond what is immediately necessary, typically driven by fear of future shortages, anticipated price increases, or speculative motives.

Black marketing: The illegal trade of goods and services that are banned or regulated.

Provision of Public Goods

Public goods are goods and services that are provided by the government for the benefit of all citizens, for example, roads, bridges, public parks, and streetlighting are provided for public use; national defence protects the country from external threats; sanitation, and drainage systems improve living conditions, and so on. These goods are usually not provided by private companies because they do not generate direct profit.

Suppose your neighbourhood needs a park. Building it is expensive, but many families would benefit from it. If each family contributed ₹5,000, the park could be built. However, many families may think, "If others pay, the park will be built anyway, and I can use it without paying." Because of this thinking, not enough money is collected, and the park is never built even though everyone needs it. This explains why goods that benefit everyone often require government provision or funding to ensure social welfare, economic development, and equal access to essential services.

LET'S EXPLORE

From your surroundings, list two goods or services that are provided by the government (for example: roads, streetlights, parks, police, and so on.). Choose one of the goods you listed and answer:

- → Who does benefit from it?
- → Why would it be difficult for a private company to provide this service on its own?
- → Imagine the government stops providing this good or service, what problems might people in your area face?

© NCERT not to be republished

Limitations of Government Intervention

Although government regulations are required when markets are inefficient, they must be implemented carefully, as excessive government intervention can have adverse effects.

a) Price distortions and reduced producer incentives

When the government fixes prices below market levels, producers may lose motivation to supply goods or services. For instance, if the government sets a maximum price for wheat at ₹20 per kg while the market forces set it at ₹30 per kg, farmers receive less than what they would in a free market. This may lead to reduced production and shortages.

b) Compliance burdens

Government intervention often requires extensive regulations, licenses, permits, and compliance procedures. This can hurt businesses, especially small enterprises and hamper **ease of doing business**. For instance, a small restaurant may need multiple permissions related to food safety, fire safety, pollution control, and local clearances. The time and cost involved can discourage small entrepreneurs from starting or expanding businesses.

Ease of doing business: How simple it is to start, run, and close a business in a country, measured by regulations, bureaucratic efficiency, and legal frameworks.

c) Discourages innovation and entrepreneurship

Heavy regulation and price controls reduce incentives to invest in new ideas or better technology. For example, in the case of price distortions, farmers won't invest in better seeds, irrigation, or technology, if they cannot earn adequate returns. This reduces long-term productivity and output.

LET'S RECALL

In the chapter 'Democracy', you have read that a democratic government is accountable to the people and is expected to act in their interest.

→ According to you, how should a democratic government decide when and how much it should intervene in markets to protect people's welfare?

→ Whose voices should a democratic government consider while making such decisions—consumers, producers, workers, or others? Why?

© NCERT not to be republished

Understanding how these economic systems work and the general principles of economics help to see the logic behind the choices people make, whether it is the price they pay, the jobs they do, or the policies governments implement. It provides the tools to think critically, use resources wisely, and make informed decisions in a world where every choice affects individuals, society, and the economy.

Markets are not machines with fixed equilibria but dynamic systems that constantly adapt, evolve, and respond to changing conditions. The next time you notice a price change—whether it is books, vegetables, or sports equipment—pause and ask, what is really happening here? Is supply changing? Is demand shifting? Is the market moving toward equilibrium or being pushed away from it? Is government intervention helping or hurting? While understanding these forces, you are not merely learning key principles in economics; instead, you are decoding how market dynamics work in real life.

Before we move on...

- Demand is the quantity consumers are willing and able to buy at different prices. The Law of Demand shows an inverse relationship, that is, as price falls, quantity demanded rises. Demand is influenced by income, prices of substitutes and complements, tastes, seasonality, future expectations, and population.
- Supply is the quantity sellers are willing and able to offer at different prices. The Law of Supply shows a direct relationship—as price rises, quantity supplied increases. Supply depends on prices, related goods' prices, the number of sellers, technology, input costs, and other factors such as weather.
- Market equilibrium occurs when the quantity demanded equals quantity supplied. Fundamental markets constantly adjust toward a new equilibrium as conditions change—weather, trends, technology, income, and so on, create dynamic pricing conditions.
- Government intervenes when markets fail and produce unfair outcomes (unaffordable essentials), under-provide public goods, and enable monopolies. However, excessive government regulations may also have adverse effects.

© NCERT not to be republished

Questions and activities

1. An increase in income always leads to a rise in demand for goods. Defend or refute, giving reasons for the same.
2. If petrol prices double, what happens to
   a. Demand for diesel cars
   b. Demand for electric cars
   c. Demand for car accessories
   d. Demand for public transport
3. A farmer traditionally irrigates fields manually (labour-intensive). He installs drip irrigation (a technology upgrade) that reduces water use by 40 per cent and increases yield by 30 per cent. How does this affect
   a. His cost of production
   b. His willingness to supply at different prices
   c. The overall market supply if many farmers adopt this technology
4. During online festival sales, the prices of many products are very low. Use the concept of demand and supply to explain why the sellers sell at such a low price. What happens to the equilibrium when the price is lowered? Does this benefit only consumers or sellers as well? Explain.
5. Suppose the government sets a maximum sale price for an essential vaccine below the market-driven price. What is likely to happen? Choose from the options below and elucidate your point.
   a. Surplus
   b. Shortage
   c. No effect
   d. Fall in demand
6. The government levies higher taxes on products such as tobacco and alcohol to promote healthier choices among citizens. Can you find out other goods where price controls have been set in place? What are the reasons for the same?
7. Can excessive government regulation hurt markets? Explain with suitable examples.

© NCERT not to be republished

8. In the table below, different prices of guava are given.

   a. Think and write how much guava you will buy at each price.

   b. Ask the same question to three of your friends and fill in the table.

   c. Also make a graph for each one of you and one final graph for the total quantity.

Price	You	Friend 1	Friend 2	Friend 3	Total
₹100/kg					
₹80/kg					
₹50/kg					
₹20/kg					

9. Visit the nearby vegetable market and try to find answers to the following questions.

   a. Who decides the prices of different vegetables in the vegetable market?

   b. Sometimes the prices of a few vegetables is too high, and sometimes too low. Why is this?

   c. The price of tomatoes is high in the morning and eventually gets lower by the evening. Have you ever noticed this? Comment.

10. Categorise the following combination of goods into substitute goods and complementary goods.

   a. Movie ticket in the cinema hall and popcorn

   b. Eraser and pencil

   c. Laptop and computer

   d. Air Conditioner and cooler

   e. Notebook and pen

   f. Apple and banana

   g. Mobile and earphones

© NCERT not to be republished

11. Fig. 9.8 shows the demand curve DD' and Supply curve SS'. Based on the figure, answer the following questions:

    a. What does point E represent in this market?

    b. What is the equilibrium price and equilibrium quantity at point E?

    c. Point A lies on DD'. Point B lies on SS'. What do the points A and B indicate about demand and supply? What does the gap between A and B (both on the upper dashed price line) represent?

    d. Point F lies on DD'. Point C lies on SS'. What do the points F and C indicate about demand and supply? What does the gap between C and F (both on the lower dashed price line) represent?

    e. If the price stays at the lower dashed line, what could happen next in a free market?



Fig. 9.8

© NCERT not to be republished

12. Draw a market equilibrium graph using the following demand schedule.

Price (₹)	10	20	30	40	50
Q.D. (kg)	5	10	15	20	25
Q.S. (kg)	25	20	15	10	5

a. Plot the demand and supply curve using the above data.

b. Identify the equilibrium price and quantity.

c. Observe the above data and analyse what happens if the price is set at ₹20 or ₹40.

© NCERT not to be republished

Political Map of India

© NCERT not to be republished

Map and Image Credits.indd 214 18-Jun-26 11:34:12 AM



Physical Map of India

Map and Image Credits.indd 215 18-Jun-26 11:34:13 AM

Map and Image Credits.indd 216



Political map of the world, with names of a few countries

© NCERT not to be republished

18-Jun-26 11:34:14 AM

Map and Image Credits.indd 217



Physical map of the world

18-Jun-26 11:34:15 AM

Images and maps from external sources

NCERT thanks the following organisations and individuals for permission to use their images

1. Organisations and individuals

- Fig. 1.1. https://bhuvan-app1.nrsc.gov.in/mhrd_ncert/help/Map_Your_Own_City_Varanasi.pdf
- Fig. 1.2. Courtesy: National Museum
- Fig. 1.3. https://commons.wikimedia.org/wiki/File:Tirukkural_manuscript.jpg
- Fig. 1.4. Courtesy: National Museum
- Fig. 1.5. Courtesy: National Museum
- Fig. 1.6. https://commons.wikimedia.org/wiki/File:Kannada_inscription_of_Krishnadeva_Raya_(1509_AD)_at_the_underground_Shiva_(Prasanna_Virupaksha)_temple_in_Hampi.jpg
- Fig. 1.7. Courtesy: National Museum
- Fig. 1.8. Courtesy: National Museum
- Fig. 1.9. Courtesy: National Museum
- Fig. 2.5. Courtesy: Indian Express
- Fig. 2.7. https://fr.wikipedia.org/wiki/Baratang#/media/Fichier:Baratang_mud_volcano.jpg
- Fig. 2.9.(a) https://commons.wikimedia.org/wiki/File:CSIRO_ScienceImage_4434_Gully_erosion_in_the_Warren_Catchment_east_of_Adelaide_in_the_Mount_Lofty_Ranges_South_Australia_1992.jpg
- Fig. 2.13. https://commons.wikimedia.org/wiki/File:Sundarbans_web_ESA362980.jpg
- Fig. 2.16. https://upload.wikimedia.org/wikipedia/commons/3/38/Bedrock_Weathering_Pits_%288409974927%29.jpg
- Fig. 2.20. Courtesy: Hindustan Times
- Fig. 2.28. Courtesy: ANI
- Fig. 2.29. https://artsandculture.google.com/asset/naidu-and-gandhi-hulton-archive/YgHPdHPkD5VJMA?hl=en
- Fig. 2.30. https://en.wikipedia.org/wiki/Abdul_Ghaffar_Khan
- Fig. 2.31. https://en.wikipedia.org/wiki/Muhammad_Iqbal#/media/File:Muhammad_Iqbal_in_1931.jpg
- Fig. 2.32. Public domain
- Fig. 2.33. Courtesy: Indian Express
- Fig. 2.34. https://en.wikipedia.org/wiki/Aruna_Asaf_Ali#/media/File:Aruna_Asaf_Ali_1998_stamp_of_India.jpg
- Fig. 2.35. https://upload.wikimedia.org/wikipedia/commons/f/f2/Sardar_patel_%28cropped%29.jpg
- Fig. 2.36. https://upload.wikimedia.org/wikipedia/commons/c/cb/A_refugee_special_train_at_Ambala_Station_during_partition_of_India.jpg
- Fig. 3.13. Courtesy: Hindustan Times
- Fig. 4.1. Seal from Mohenjodaro M375A; p.93 and p.386, Corpus of Indus Seals and Inscriptions 1. Collections in India JP Joshi and Asko Parpola (Eds.) Memoirs of the Archaeological Survey of India No. 86; Annales Academiae Scientiarum Fennicae, Series B 239. Helsinki 1987
- Fig. 4.2. Courtesy: Ravi Korisettar
- Fig. 4.6.(a,b,c,d) Courtesy: Ravi Korisettar

© NCERT not to be republished

Map and Image Credits.indd 218 19-Jun-26 12:16:00 PM

- Fig. 4.7.
  - → https://commons.wikimedia.org/wiki/File:Bronze_Age_hoard_and_Post-Medieval_material_found_in_the_vicinity_(FindID_401114).jpg
  - → https://commons.wikimedia.org/wiki/File:Mesolithic_tranchet_axehead,_Tranchet_adze_or_pick_(FindID_762762).jpg
  - → https://commons.wikimedia.org/wiki/File:Big_Chalcolithic_churn.JPG
  - → https://commons.wikimedia.org/wiki/File:Early_Iron_Age_Bronze_Knives,_700-400_BC.jpg
- Fig. 4.9. Courtesy: Ajithprasad, Department of Archaeology and Ancient History, The Maharaja Sayajirao University of Baroda)
- Fig. 4.10. Courtesy: Ajithprasad, Department of Archaeology and Ancient History, The Maharaja Sayajirao University of Baroda)
- Fig. 4.11.(a) Courtesy: Ravi Korisettar, Robert Bruce Foote Sanganakallu Museum, Ballari, Karnataka
- Fig. 4.11.(b) Courtesy: Ajithprasad, Department of Archaeology and Ancient History, The Maharaja Sayajirao University of Baroda
- Fig. 4.12. Courtesy: Ravi Korisettar, Robert Bruce Foote Sanganakallu Museum, Ballari, Karnataka
- Fig. 4.13. Courtesy: Ajithprasad, Department of Archaeology and Ancient History, The Maharaja Sayajirao University of Baroda
- Fig. 4.15. Courtesy: Ravi Korisettar, Robert Bruce Foote Sanganakallu Museum, Ballari, Karnataka
- Fig. 4.16. https://commons.wikimedia.org/wiki/File:Mehrgarh_ruins.jpg
- Fig. 4.18. https://images.metmuseum.org/CRDImages/as/original/DP702288.jpg
- Fig. 4.19. Courtesy: Archaeological Survey of India, Govt. of India
- Fig. 4.20. Courtesy: Dr RS Bisht & ASI
- Fig. 4.25. Wikimedia Commons: Louvre Museum, Cuneiform tablet 2800BCE. Los Angeles County Museum of Arts (LACMA) Gallery: http://collections.lacma.org/node/228141
- Fig. 4.28.
  - → https://www.metmuseum.org/art/collection/search/544184
  - → https://www.metmuseum.org/art/collection/search/549719
  - → https://upload.wikimedia.org/wikipedia/commons/5/5f/Shabti_of_Siptah_MET_DP160300.jpg?utm_source=commons.wikimedia.org&utm_campaign=index&utm_content=thumbnail_unscaled
- Fig. 4.29. https://en.wikipedia.org/wiki/Papyrus_of_Ani#/media/File:BD_Weighing_of_the_Heart.jpg
- Fig. 4.33.
  - → https://www.metmuseum.org/art/collection/search/544822
  - → https://www.metmuseum.org/art/collection/search/545130
  - → https://www.metmuseum.org/art/collection/search/548981
- Fig. 4.35. https://www.metmuseum.org/art/collection/search/44781
- Fig. 4.37.
  - → https://www.metmuseum.org/art/collection/search/74524
  - → https://www.metmuseum.org/art/collection/search/39637
  - → https://www.metmuseum.org/art/collection/search/44781

© NCERT not to be republished

Map and Image Credits.indd 219 18-Jun-26 11:34:15 AM

- Fig. 5.1. https://commons.wikimedia.org/wiki/File:City_of_Kushinagar_in_the_5th_century_BCE_according_to_a_1st_century_BCE_frieze_in_Sanchi_Stupa_1_Southern_Gate.jpg
- Fig. 5.2. https://en.wikipedia.org/wiki/Rigveda#/media/File:1500-1200_BCE_Rigveda,_manuscript_page_sample_i,_Mandala_1,_Hymn_1_(Sukta_1),_Adhyaya_1,_lines_1.1.1_to_1.1.9,_Sanskrit,_Devanagari.jpg#
- Fig. 5.5. Courtesy: ASI
- Fig. 5.7. https://commons.wikimedia.org/wiki/File:494_CE_Karitalai_copper_plate_inscription,_Hinduism,_king_Jayanatha,_Sanskrit.jpg
- Fig. 5.13. https://en.wikipedia.org/wiki/Nasik_Caves#/media/File:Nasik_cave_17.jpg
- Chapter 6 Title: https://commons.wikimedia.org/wiki/File:View_of_Lok_Sabha_chamber_in_the_New_Parliament_building,_New_Delhi.jpg
- Fig. 6.2. https://commons.wikimedia.org/wiki/File:Group_Photograph_of_the_Constituent_Assembly_Members_1950.jpg
- Fig. 6.3. https://en.wikipedia.org/wiki/B._R._Ambedkar
- Fig. 6.6
  - → Courtesy: PIB
  - → Courtesy: ECI
- Fig. 6.8. https://commons.wikimedia.org/wiki/File:A_Polling_Officer_affixes_indelible_ink_mark_on_the_fore-finger_of_a_voter_before_allowing_her_to_cast_the_vote_at_a_polling_station_in_Delhi_on_14_January_1952.jpg
- Fig. 7.5. https://ecisveep.nic.in/pledge/englishpledge.php
- Fig. 7.8. Courtesy: ECI

2. Royalty free stock from dreamstime.com

- Fig. 2.9.(b), 2.10, 2.11, 2.12, 2.14, 2.15, 2.17, 2.18, 2.19, 2.21, 2.22, 2.23 (a), 2.23 (b), 2.23 (c), 2.24, 2.25, 2.26, 2.27, 2.28, 2.29, 2.30
- Chapter 3 Title, Fig. 3.1, 3.4, 3.6, 3.9, 3.12, 3.20, 3.23, 3.24, 3.26, 3.31, 3.32, 3.33, 3.37, 3.38, 3.41, 3.42, 3.43, 3.45, 3.46, 3.47, 3.48, 3.53, 3.54
- Fig. 4.5, 4.7, 4.18, 4.22, 4.23, 4.24, 4.27, 4.31, 4.34, 4.35, 4.36, 4.38
- Chapter 5 Title, Fig. 5.1, 5.11
- Chapter 7 Title, Fig. 7.2, 7.4
- Fig. 8.1, 8.2, 8.5

3. AI generated images

- Chapter 1 Title
- Chapter 2 Title, Fig. 2.6
- Chapter 4 Title
- Fig. 6.7
- Chapter 8 Title
- Chapter 9 Title

© NCERT not to be republished

Map and Image Credits.indd 220 19-Jun-26 12:16:20 PM

Chapter 1
Oceans and Life

The Big Questions

1. *What is the importance of ocean relief?*
2. *How does ocean water movement impact life and environment?*
3. *Why are maritime zones important for a country?*
4. *How can we use ocean resources in a sustainable way?*
5. *How do early warning systems help protect people from tsunamis and cyclones?*

0909CH01



1. Ocean water is always in motion.

Waves, tides, and currents shape our climate, support marine life, and impact travel.

2. The gravitational pull creates tides.

The daily rise and fall of sea level is crucial for navigation and generating tidal energy.

3. The ocean floor is a hidden landscape.

Like land, it has features like mountains, plains, mid-oceanic ridges, trenches, etc.

4. The 'Blue Economy': sustaining ocean resources.

Oceans provide food, energy, and jobs, which must be used sustainably.

5. Early warning systems protect coastal life.

Seismic sensors and satellites detect tsunamis and cyclones, allowing for timely evacuations.

6. Maritime zones create 'rules of the sea'.

International laws like UNCLOS define a country's rights from its coast to the high seas.

Fig. 1.1. The dynamic ocean system

In earlier grades, you learnt about continents and oceans. In Indian culture, the ocean—commonly called *Samudra*—is considered powerful and sacred, and features prominently in stories and rituals.

© NCERT not to be republished

Oceans cover most of our planet and conceal many secrets beneath their waters. Have you ever wondered what the land under the oceans looks like, why ocean water is always moving, or what wealth and resources lie beneath the sea? How do areas like maritime zones help countries use the oceans, and how can we protect ourselves from ocean hazards, such as cyclones and tsunamis?

In this chapter, we will explore these human–ocean connections and discover how oceans shape both our daily lives and the world around us.

Ocean Relief

As we explore human–ocean connections, let us begin with the ocean floor and its features. Just as land has mountains, valleys, and plains, the ocean floor, too, has several landforms, together known as **submarine relief** or **ocean relief.** These include underwater mountains, valleys, plateaus, and trenches. The Mariana Trench in the Pacific Ocean is the deepest place on Earth, while the Mid-Ocean Ridge is the world's longest mountain range, hidden beneath the ocean. Some underwater mountains like Mauna Kea (Hawai'i) are even taller than Mount Everest.



Fig. 1.2. Submarine relief

© NCERT not to be republished



LET'S EXPLORE

Looking at Fig. 1.2

→ How do you think these oceanic features would have been formed?

→ Which part of the ocean floor appears deep and shallow?

→ How do you think these underwater features would have an effect on marine life and ocean movements?

Important submarine relief features

Continental Shelf

The submerged, shallow edge of a continent; extends under the ocean. Rich in marine life and resources like oil and gas.

Continental Slope

The steep slope marking the true edge of a continent.

Abyssal Plain

The vast, flat, and deep ocean floor.

Mid-Ocean Ridge

An immense underwater mountain range formed by volcanic activity.

Ocean Trenches

The deepest parts of the ocean.

Seamounts and Guyots

Seamounts are often volcanic, with some flattened by wave action over millennia to form **guyots**.

Seamount:
An underwater mountain, usually of volcanic origin, that rises from the ocean floor but does not reach the sea surface.

Guyot:
A flat-topped underwater mountain, usually a former seamount whose summit was eroded and later submerged.

© NCERT not to be republished

Movement of Ocean Water—Waves, Tides, and Currents

The water in the oceans is constantly in motion. Waves, tides, and currents are not merely movements of ocean water; they help shape the Earth's surface, support marine life, aid fishing and travel, and even influence climate. Let us learn more about these oceanic movements.

Waves

When the surface of the ocean rises and falls alternately, it is called a **wave**. Waves are primarily caused by winds blowing across the water. They carry energy across the oceans over long distances. Observe Fig. 1.3 and note the crests (high peaks) and troughs (lower valleys).

Wavelength: The horizontal distance between two consecutive wave crests or troughs.

Waves are often called coastal architects as they shape the shoreline through erosion and sediment transport. Observe the various landforms formed by waves in Fig. 1.4 and note how wave action creates erosional features, such as sea cracks, caves, arches, sea stacks, and stumps. Also notice the original headland shown in the figure.



Fig. 1.3. Anatomy of waves

In addition to erosional landforms, waves also form depositional features such as beaches.

© NCERT not to be republished



Fig. 1.4. Landform features formed by waves

LET'S EXPLORE

Find out the names of some famous sea beaches in our country and locate them on the map of India.

During storms, strong winds can generate huge waves that may cause significant damage along coastlines. The giant waves majorly caused by underwater earthquakes are called **tsunamis**, which can be extremely destructive. On reaching the shore, tsunamis may attain a maximum vertical height above sea level, known as the run-up height, of up to 30 metres, or even more in extreme cases.

Hydraulic action: The erosion of rock and soil caused by the force of moving water, which loosens and removes material.

Tides

Tides are the rhythmic rise and fall of ocean water that occur twice a day in most parts of the world. When the water rises to its highest level and covers much of the shore, it is called high tide (flood tide). When the water falls to its lowest level and moves away from the shore, it is called low tide (ebb tide). Observe Fig. 1.5 and note the change in water level during high and low tides. Do you notice the oval layer around the Earth indicating water level? Can you also see how the water level rises during high tide and falls during low tide?

© NCERT not to be republished



(a) *(b)*

Fig. 1.5 (a) Spring tide (b) Neap tide (Schematic diagram of tidal forcing showing idealised bulges)

Spring Tides and Neap Tides

You may wonder what causes this regular rise and fall of ocean water. To understand this, let us explore how tides are formed.

- **Spring tides:** Observe Fig. 1.5(a), where the Sun, the Earth, and the Moon are aligned in a straight line. Spring tides occur during this alignment, which happens on full moon and new moon days. At this time, the combined gravitational pull of the Sun and the Moon causes high tides of unusual heights and low tides that are unusually lower. The figure also shows the bulging of water on opposite sides of the Earth due to this strong gravitational pull, leading to the formation of spring tides.
- **Neap tides:** When the Moon is in its first- and third-quarter phases, as shown in Fig. 1.5(b), the gravitational pull of the



Fig. 1.6. Levels of spring and neap tides

© NCERT not to be republished

Sun and the Moon acts in different directions. As a result, the difference between high tide and low tide becomes smaller, producing neap tides. Fig. 1.6 shows the levels of high and low water during both spring and neap tides, along with the average low-water levels for each.

High tides are important for navigation because they raise the water level near the shore, allowing ships to enter harbours more easily. In ports and coastal areas, tidal information is essential, as tidal ranges in some ports can reach 4–5 metres. The Gulf of Khambhat has one of the highest tidal ranges, at about 12 metres. Before a ship berths at a port, it must check both the water depth and the tidal range to ensure safe docking, especially during low tide.

Some sea channels, such as the Singapore Strait, contain shallow areas. Hence, ships such as Very Large Crude Carriers (VLCCs) passing through these regions often wait for hours to transit only during high tide to ensure sufficient water depth and avoid running aground.

Tidal changes also generate strong currents because large volumes of water flow in and out of coastal areas. These tidal currents can reach speeds of 5–6 knots (about 9–11 km/h).

Fig. 1.7. Observe how high and low tides help in fishing activities

High tides also support fishing activities (Fig. 1.7). During high tide, many fish move closer to the shore in search of food and shelter, enabling fishing communities to obtain a better catch.

The rise and fall of tidal water are also used to generate electricity in some places (Fig. 1.8). India has a vast coastline of 11,098.81 kilometres, and although tidal energy is not yet widely used on a large scale, certain areas have been identified as suitable for its development. The Gulf of Kutch, the Gulf of Khambhat, and the Sundarbans are among the major tidal energy sites in India.

© NCERT not to be republished

DON'T MISS OUT

Fig. 1.8. Tides at the Bhadkeshwar Mahadev Temple, Dwarka, Gujarat

The Bhadkeshwar Mahadev Temple in Dwarka is situated on a small hillock in the Arabian Sea. Visitors can reach the temple only during low tide, as the stone pathway leading to it is completely submerged during high tide.

Ocean Currents

Coriolis force: A force caused by Earth's rotation that deflects any free moving object from its straight path to the right in the Northern Hemisphere and to the left in the Southern Hemisphere.

Ocean currents are continuous streams of water that flow across the ocean surface in definite directions (Fig. 1.9). They are caused by factors, such as winds, the Earth's rotation (**Coriolis force**), differences in temperature and salinity, and the shape of continents and ocean basins. Ocean currents may be warm or cold depending on the direction from which the water flows. Currents flowing from warmer regions are called warm currents, while those flowing from colder regions are called cold currents. On maps, warm currents are usually shown in red and cold currents in blue.

THINK ABOUT IT

Observe the map carefully and note the movement patterns of cold and warm currents. Do you think these currents affect the temperature of nearby coastal regions?

The Gulf Stream, a warm current originating in the Gulf of Mexico in the Atlantic Ocean, flows towards Norway and keeps its waters relatively warm. As a result, sea ice does not form easily in the Norwegian region despite its high latitude (60°–70°). In contrast, the Labrador Current, a cold current flowing along the east coast of Canada, carries freezing water and supports the formation of sea ice and icebergs even at lower latitudes.

LET'S EXPLORE

Observe Fig. 1.9 and take a note on ocean currents along the coastline of India. What is the nature of ocean currents?

© NCERT not to be republished



Fig. 1.9. Major ocean currents

DON'T MISS OUT

The regions where warm and cold currents meet are known as fishing grounds. These waters are rich in nutrients, supporting a large variety of fish and making them important fishing grounds.

Cyclones and Tsunamis—Early Warning Systems

Oceans and seas can give rise to sudden natural hazards such as cyclones, which are large rotating storms, and tsunamis, which are giant waves caused by earthquakes. To protect people from such dangers, scientists have developed Early Warning Systems that work like giant alarm systems for coastal areas. To reduce risks, people, communities, and governments must act in advance. Early Warning Systems help detect cyclones and tsunamis, predict disasters, and issue timely warnings so that people can evacuate and stay safe.

LET'S EXPLORE

Most deaths during the 2004 Indian Ocean tsunami occurred in Indonesia. However, the Island of Simeulue was largely spared from the disaster. Researchers suggest that this was partly because

© NCERT not to be republished

of local folklore, passed down through generations, that helped residents recognise the warning signs of a tsunami and respond quickly. Talk to your elders and find out whether similar folk traditions or stories related to natural disasters exist in your culture. Share these with your classmates and discuss how traditional knowledge can help communities stay safe.

India has several Cyclone Warning Services and Marine Weather Services that monitor storms along both the eastern and western coasts. For early warning systems to be effective, they must function continuously. India uses advanced technologies to predict cyclones at an early stage, which has significantly reduced the loss of human and animal lives.

The Government of India has launched the National Cyclone Risk Mitigation Project (NCRMP) to build cyclone shelters, strengthen warning systems, and improve emergency response mechanisms. The project focuses on cyclone-prone States and Union Territories and includes a Decision Support System (DSS) for disaster management authorities. The Indian National Centre for Ocean Information Services (INCOIS), in collaboration with the India Meteorological Department (IMD), has also established the Storm Surge Early Warning System (SSEWS) for the Indian coasts. Its main objective is to protect coastal communities by forecasting cyclone-induced storm surges and the extent of coastal inundation.

DON'T MISS OUT

The **GAGAN-Enabled Mariner's Instrument for Navigation and Information (GEMINI)** is a handheld device designed for fishermen that plays an important role in ensuring the safety of fishing communities at sea (Fig. 1.10). The device receives satellite information and transmits it to mobile phones through Bluetooth. Using its dedicated mobile application, fishermen can access

Fig. 1.10. Local fishermen at work in the Arabian Sea; Alappuzha, Keralam

© NCERT not to be republished

important information in their local language, including alerts about high waves and strong winds, cyclone and tsunami warnings, potential fishing zone advisories, current speeds, **bathymetry** data, mapping, and risk management information.

Under the Pradhan Mantri Matsya Sampada Yojana (PMMSY), the government provides financial support for GEMINI devices to improve the safety of coastal communities while they are at sea (Fig. 1.11).

Bathymetry: The study and mapping of the underwater topography of water bodies, such as oceans, rivers, lakes, and streams.

How GEMINI Works

- The GEMINI device receives data from the GAGAN satellite and transfers it to fishermen's mobile phones through Bluetooth.
- The INCOIS mobile application decodes and displays this information in nine regional languages.
- At present, the communication channel can transmit information only up to 50 nautical miles into the sea.
- An upgraded version is expected to provide a two-way communication system on a pilot basis, allowing fishermen to send feedback as well.

Fig. 1.11. GEMINI

- This upgraded system will benefit fishermen travelling up to 300 nautical miles in search of better fishing opportunities.

Focus on Cyclones

Cyclones are caused by atmospheric disturbances over warm ocean waters.

Naming the cyclone: Cyclones in the North Indian Ocean are named sequentially from a list of 169 names submitted by 13 member countries, including India. This system aids clear communication and public awareness. Recent examples include Biparjoy (2023) and Remal (2024). Note: You may track cyclones and their affected areas in India on the School Bhuvan–NCERT Geoportal (Fig. 1.12).

Fig. 1.12. Satellite image of a cyclone

© NCERT not to be republished

DON'T MISS OUT

On 26 December 2004, the world witnessed unprecedented devastation caused by the Indian Ocean Tsunami. The disaster claimed around 2,30,000 lives and caused severe environmental damage across many countries bordering the Indian Ocean. India was among the worst-affected countries, as massive waves swept away people and structures along the coasts. Tamil Nadu, Puducherry, Andhra Pradesh, Keralam, and the Andaman & Nicobar Islands especially suffered extensive damage. The scale of the disaster led many countries to establish effective tsunami early warning systems and stronger disaster-management mechanisms. Under an initiative of the Indian Tsunami Early Warning Centre (ITEWC), the Government of India set up a real-time network of tsunami detection buoys (Fig. 1.14) designed to detect, measure, and monitor tsunamis.

The photograph in Fig. 1.13 shows some areas of Chennai affected by the Indian Ocean tsunami (2004).

Fig. 1.13. Some of the tsunami-affected areas in Chennai (2004)

Fig. 1.14. Tsunami detection buoy

© NCERT not to be republished



Detection
A network of seismic stations detects undersea earthquakes in real time.

Confirmation
Ocean Bottom Pressure Recorders (OBPRs) placed on the seafloor detect the passage of tsunami waves, confirming the threat.

Tracking
Coastal tide gauges and radars monitor changes in sea level to track the arrival and movement of tsunami waves.

Warning Dissemination
Alerts are transmitted via satellite to government agencies and are also sent directly to officials and the public through SMS and other communication channels.

Fig. 1.15. Functioning of the tsunami early warning system



1 Warning centre	2 Modelling/ simulation	3 Capacity development	4 Communication satellite	5 GPS satellite
6 Tide gauges station	7 GPS station	8 Seismometer station	9 Seismic waves	10 Earthquake

Fig. 1.16. The different elements of the tsunami early warning system

© NCERT not to be republished

For an early warning system to save lives, information must reach the public quickly and effectively. The Indian Tsunami Early Warning Centre (ITEWC) is tasked with sending alerts to the Government of India, which then informs state governments and emergency response teams. Reliable communication is ensured through satellite-based communication networks, SMS, emails, and coastal display boards.

Besides technology, public awareness and training programmes are equally important for an effective early warning system. Educating officials and coastal communities on how to interpret warnings helps ensure that when disasters such as cyclones are predicted, people know how to respond appropriately.

THINK ABOUT IT

If you receive a tsunami or cyclone alert on your phone right now, do you know the five steps your family should take to stay safe?

Marine Resources and Their Significance

Do you recall learning about natural resources in the Grade 8 Social Science Part 1 textbook? These resources are obtained from land, water, forests and animals, and other natural sources. Oceans, too, are vast storehouses of resources, and the materials and features found in oceans that have intrinsic or economic value are called marine resources. Marine resources can be broadly classified into two categories—Marine Living Resources and Marine Non-living Resources. They include fish and seafood, biodiversity, oil and natural gas, minerals, sand and gravel, renewable blue energy sources such as tidal and wave energy, tourism potential, and unique ecosystems such as coral reefs. Fig. 1.17 presents a detailed classification of marine resources.

Significance of Marine Resources

Marine resources are vital for food security, economic activities, and maintaining a healthy environment (Fig. 1.17). Countries with long coastlines, such as India, benefit greatly from the sea. Fishing, trade, and tourism provide livelihoods to millions of people, while oceans also support biodiversity and sustain numerous plant and animal species. However, marine resources must be used responsibly without disturbing marine ecosystems.

© NCERT not to be republished



Fig. 1.17. Classification of marine resources

The Ocean is a Vast Storehouse of Resources Vital for Life, Livelihoods, and Culture

Marine resources hold immense value for humanity and for coastal nations like India, they are the bedrock of local economies and traditions.

Food and Livelihood: Fish are a major source of protein, while fishing and aquaculture support important industries and livelihoods.

Minerals and Materials: Sand, gravel, and deep-sea minerals.

Energy: Offshore oil and gas reserves; immense potential for renewable 'blue energy' from tides and waves.

Trade and Tourism: 90% of global trade by volume is carried by sea; coastal tourism is a multi-billion dollar industry.

Cultural Significance:
The sacred *śhaṅkha* (conch) and *kapardikā* (cowrie shells), once used as currency, are regarded as divine treasures from the mythological *Samudra Manthana*, reflecting the close connection among the sea, prosperity, and culture.

Fig. 1.18. Significance of marine resources

© NCERT not to be republished

DON'T MISS OUT

Blue Economy is the Future: Sustainable Growth Powered by Healthy Oceans

The World Bank defines **Blue Economy** as "the sustainable use of ocean resources to promote economic growth, improved livelihoods, and jobs, while preserving the health of the marine ecosystem".

Connecting to Global Goals: This concept is enshrined in the UN's Sustainable Development Goal (SDG) 14: Life Below Water. Its key aims are to:



Fig. 1.19. The role of Blue Economy

Maritime Zones

Have you ever wondered who owns the oceans and how countries decide where they can fish or travel? To understand this, we need to learn about maritime zones—different areas of the ocean defined by international law.

The sea area closest to a country is called its territorial waters, over which the country has near-complete control, subject to the right of innocent passage for foreign ships. Just as on land, the government can make laws relating to customs, immigration, and pollution control in this zone.

Observe Fig. 1.20 and note the extent of the territorial sea in **nautical miles**. Beyond this lies the contiguous zone, extending from the baseline up to 24 nautical miles, where the country has limited control over customs, fiscal matters, and illegal immigration.

Nautical mile: A unit of measurement used in maritime and air navigation. It is defined as exactly 1,852 metres (about 6,076 feet). Based on the Earth's circumference, one nautical mile corresponds to one minute of latitude making it a convenient unit for charting and navigation across the world's seas.

© NCERT not to be republished



Fig. 1.20. Maritime zones (Indicative only)

DON'T MISS OUT

Innocent Passage is a principle that allows foreign ships to pass through the territorial waters of a country as long as they do not threaten its peace, good order, or security. Ships must move continuously without stopping, except in emergencies or cases of breakdowns. This right does not permit activities such as fishing, military operations, or other non-peaceful actions.

Beyond the contiguous zone, lie the Exclusive Economic Zones (EEZs), which extend from the baseline up to 200 nautical miles from the coast, and are defined under the United Nations Convention on the Law of the Sea (UNCLOS) by global agreement. In these zones, a country has special rights to use ocean resources, such as fish, oil, and gas, although ships from other countries may still pass through peacefully. It is important to note, however, that the country does not fully own or control the waters of the EEZ.

Beyond the EEZs of all countries lie the high seas, also known as international waters. Covering about 64 per cent of the world's oceans, these waters do not belong to any single country and are therefore considered part of the global commons. All countries enjoy equal rights on the high seas, including navigation, fishing, flying over them, laying undersea cables, building lawful structures such as artificial lands, and exploring for minerals.

© NCERT not to be republished

Although the high seas are essential, they also present many challenges. Since no single country controls them, issues, such as overfishing, illegal fishing, and conflicts over resources often arise. These problems affect millions of people who depend on the sea for food and livelihoods. Ensuring navigation and safety is also more difficult without clear enforcement mechanisms. On the high seas, the laws of the flag state—the country in which a ship is registered—apply.

International Maritime Rules and Regulations

In the earlier sections of this chapter, you learnt that oceans are vital for trade, travel, and communication. To ensure that activities at sea remain safe, fair, and peaceful, countries follow a set of international rules and agreements known as maritime law or maritime regulations. These laws regulate how ships operate and move; protect the marine environment; address issues such as piracy, terrorism, natural disasters, and accidents; safeguard trade routes; and help settle disputes between countries.

LET'S EXPLORE

Maritime disputes are conflicts or disagreements between countries over territory, resources, or rights in naval areas such as oceans, seas, or coastal regions. Can you find out some countries that have conflicts over their territorial sea waters?

Important Maritime Rules and Regulations

Just as there are traffic rules on land, ships must follow "rules of the road at sea" to avoid accidents. These rules, known as COLREGs (Convention on the International Regulations for Preventing Collisions at Sea), include maintaining a proper lookout, deciding which side to pass on, identifying the give-way and stand-on vessels, proceeding at a safe speed, and using lights, sound signals, shapes (for different types of vessels such as fishing boats), along with appropriate actions to prevent collisions. In addition, ships use international signals and radio communication to share information and prevent accidents, especially in crowded or hazardous waters.

© NCERT not to be republished

Ships must also meet safety standards and are prohibited from polluting the seas. The MARPOL (International Convention for the Prevention of Pollution from Ships) Convention is an important international agreement aimed at reducing pollution from ships.

Why are Maritime Rules Important?

International maritime rules, regulations, and agreements help keep the oceans safe and ensure the fair and sustainable use of ocean resources. These rules enable countries to cooperate in using marine resources without conflict while protecting marine life, ships, sailors, and coastal communities. Without such regulations, the oceans could become dangerous and chaotic, with increased pollution, accidents, collisions, and disputes over resources. By establishing common standards for all ships, regardless of the country they belong to, maritime rules help keep the oceans safe, clean, and open for trade and travel.

Before we move on...

- Oceans are vital for global trade, travel, communication, and climate regulation.
- Submarine relief refers to the physical features of the ocean, such as the continental shelf, ridges, trenches, and seamounts, which influence marine life, resource availability, and undersea exploration.
- Movements of ocean water—waves, tides, and currents—affect marine ecosystems, global climate, and human activities like fishing and navigation.
- Maritime zones include territorial waters, EEZs (Exclusive Economic Zones), and the high seas.
- Sustainable use of marine resources through cooperation, regulation, and conservation is essential to protect aquatic life and support future generations.
- Maritime rules and regulations exist to resolve disputes over marine boundaries.
- International laws, such as UNCLOS (United Nations Convention on the Law of the Sea), help define maritime zones and settle disputes among countries.

© NCERT not to be republished

Questions and activities

1. How do different features of the ocean floor affect human activities such as fishing, transport, and underwater exploration?
2. How do waves, tides, and ocean currents influence climate, marine life, and human activities around the world?
3. Describe the importance of marine resources.
4. Draw a poster that encourages people to protect marine resources. Include a slogan (like Save Our Seas or Fish for the Future) and explain your message in 2–3 sentences.
5. Using a map of India, mark at least five coastal states that might need tsunami warnings.
6. Work in a group and act out what would happen when a cyclone warning is issued. Highlight what role different people, like scientists, officials, and coastal villagers, would play.
7. Suppose a foreign ship is sailing through India's territorial sea. What principle allows the ship to pass through these waters, subject to certain conditions?
8. A country has an Exclusive Economic Zone (EEZ) extending up to 200 nautical miles from its baseline. What rights does the country have over the natural resources in this zone?
9. Create a model of an ocean with ship routes, protected zones, and safety measures. Based on the model, explain how it follows maritime laws and protects the ocean.

Notes

© NCERT not to be republished

Chapter 2

Life on Earth

The Big Questions

1. *How do physiography and climate shape life on Earth?*
2. *How are humans and other life forms interconnected?*
3. *What is the importance of preserving various life forms, and how can we contribute to their conservation?*

0909CH02

Geography helps us understand how climate, landforms, and water shape life on Earth—and how humans adapt their lives to these conditions. From forests and grasslands to deserts and coastal regions, different environments support different forms of life. At the same time, human activities influence these natural systems in significant ways. This chapter explores the close relationships among physical features, climate, and living organisms, and encourages us to reflect on our responsibility towards preserving the diversity of life on Earth.

Imagine our planet as a giant patchwork quilt, where each patch has its own colours, weather, and living beings. These huge patches are called **biomes**. The word 'biome' is made up of the word *bio*, derived from the Greek word *bios*, meaning 'life', and *-ome*, a suffix used in biology to denote a group of a specific type of biological constituents. Biomes are large natural regions of the world where certain types of plants and animals live under similar climatic conditions. For example, icy tundras, hot deserts, green forests, and vast grasslands are all different types of biomes. In simple terms, a biome is like a broad environmental region, while an **ecosystem** is like a neighbourhood within it, where plants, animals, and non-living things interact closely. Each biome is unique, but together they form the living world of our planet, supporting diverse forms of life and helping maintain the balance of nature.

Fig. 2.1. Earth as a giant patchwork quilt

© NCERT not to be republished



Fig. 2.2. World map showing distribution of biomes (map not to scale)

Temperate deciduous biome: This biome is characterised by forests of broad-leaved trees that shed their leaves seasonally, with moderate temperatures and distinct seasons.

Taiga biome: This biome is characterised by coniferous forests consisting mainly of pines, spruces, and larches.

LET'S MAP

Look at the world map in Fig. 2.2 and answer the following questions.

→ Which type of biome is found in smaller, separate regions, and why?

→ Which continent has the least number of biomes? What could be the reason for this?

→ Why are there areas that do not have any specific biomes?

Types of Biomes

Now that you have understood the meaning and uniqueness of biomes, let us identify the different types of biomes. Different **biomes** support diverse plant and animal life and can be categorised into **terrestrial** (land-based) and **aquatic biomes** (water-based).

There are several factors that determine which types of plants and animals can survive and thrive in a biome. These include temperature, precipitation patterns, dominant plant species, growth forms of vegetation, etc.

© NCERT not to be republished

Terrestrial Biomes

Terrestrial biomes are classified into forests, grasslands, deserts, and tundra, based on their climate.

Forest Biome

A forest biome is like nature's giant green umbrella—warm, wet, and bursting with life at every level, from the tallest trees to the damp forest floor. **Tropical rainforests** are mainly found near the Equator, between the Tropic of Cancer and the Tropic of Capricorn (23.5° N to 23.5° S). These regions remain hot and wet throughout the year, which supports the growth of dense forests. The largest tropical rainforests are located in the Amazon Basin in South America, the Congo Basin in Africa, and parts of Southeast Asia, such as Indonesia and Malaysia. Smaller rainforest regions are also found in Central America, as well as in India's Andaman & Nicobar Islands, and the Northeastern states. Together, these areas form the world's richest

Fig. 2.3. (Left to right, top to bottom) A beach, Andaman Islands; Dzukou Valley, Nagaland; Nohkalikai Falls, Sohra; Gurudongmar Lake, Sikkim

storehouse of biodiversity with rich genetic resources. They preserve unique genetic material, supporting conservation and scientific research, and are hence also known as a 'gene bank'. Forests also play an important role in maintaining oxygen levels and balancing the Earth's climate.

LET'S EXPLORE

Look at the layers of vegetation in a rainforest. What do the yellow shapes in the figure indicate?



Fig. 2.4. Ideal structure of a rainforest biome

Grassland Biome

Grasslands are large open areas covered mainly with grass and very few trees. These develop in regions that receive moderate rainfall, which is not enough to support dense forests. Temperate grasslands (such as the prairies in North America and the steppes in Asia) have

Fig. 2.5. Typical grassland landscape

© NCERT not to be republished

fertile soil and are often used for farming. Tropical grasslands, also known as Savannas (as in Africa), have scattered trees and are home to large animals such as lions, elephants, and giraffes. Grasslands support grazing animals and are important for human activities like agriculture and livestock rearing.

LET'S EXPLORE

Observe Fig. 2.5 and explore which of these animals you will find in the grasslands of India.

Desert Biome

Deserts are the driest biomes, receiving very little rainfall. They can be hot, like the Sahara in Africa, or cold, like the Gobi in Asia. The Rann of Kutch in Gujarat is one of the world's largest salt deserts, turning into a marshy wetland during the monsoon and a vast white salt desert during the dry season. The extreme conditions of a desert make it difficult for life to survive; however, plants like cacti and animals such as camels, lizards, and snakes are specially adapted to these conditions. They can store water and withstand heat and dryness. Deserts often have sandy soil and sparse vegetation. Despite their harshness, they are home to unique ecosystems, and many of them also provide valuable resources such as minerals and oil.



Fig. 2.6. Life in the Thar Desert

© NCERT not to be republished

LET'S EXPLORE

- What types of activities do you think people in desert regions generally undertake to sustain their households and livelihood?
- With the help of your teacher, explore how do people address issues related to the availability of water.

(a) (b)

Fig. 2.7. Camels in deserts

- Compare the physical features of the Rajasthan camel (Fig. 2.7a) and the Nubra Valley (Ladakh) camel (Fig. 2.7b).
- Considering the climatic conditions, why do you think the Nubra Valley camel might have a different fur density than the Rajasthan camel?

Tundra Biome

The tundra biome is the coldest of all and is found near the Arctic and Antarctic regions. It has very long, harsh winters and short summers. The soil is frozen almost year-round—a condition called permafrost—which makes it difficult for trees to grow. The vegetation is limited to mosses, lichens, and small shrubs. And animals, such as reindeer, arctic foxes, and polar bears, which are well adapted to survive freezing temperatures, are often found here. The tundra is fragile, and even small temperature changes can affect its ecosystem.

© NCERT not to be republished

Fig. 2.8. Tundra (left) and the Himalaya (right)

THINK ABOUT IT

Tundra in polar regions has mosses, lichens, shrubs, etc., while the Himalaya, in the subtropics, is dominated by conifers. What could be the reason for this? What difference do you find in the animals found in these two regions? Which species are found only in the Himalaya? Discuss in class.

Aquatic Biomes

Aquatic biomes cover about three-fourths of the Earth's surface and are divided into freshwater and marine biomes (Fig.2.9). **Freshwater biomes** include rivers, lakes, ponds, and wetlands. These are crucial for agriculture, getting access to drinking water, and supporting species, such as fish, frogs, and insects. **Marine biomes** include oceans, seas, and coral reefs, which are rich in biodiversity and influence the Earth's climate by storing and distributing heat. They are also home to countless species, including whales, dolphins, fish, and plankton, and provide food and livelihood for millions of people.

Fig. 2.9. The diversity of the aquatic biome

© NCERT not to be republished

LET'S EXPLORE

Explore your local environment. This could be your village, city, town, or residential area. Observe how people, plants, and animals build structures and interact. Complete the table with your findings.

Component type	Examples observed	Interaction with humans
Trees/Vegetation/Plants		
Insects		
Animals		
Non-living things		

Biome Pyramid

A **biome pyramid** is a graphical representation that illustrates the relationship between different organisms within a biome, usually in terms of energy, number, or biomass. At the base of the pyramid



1 Tundra	6 Desert
2 Coniferous Forest (Boreal Forest)	7 Rainforest
3 Deciduous Forest	8 Scrubland
4 Chaparral	9 Tropical Seasonal Forest
5 Grassland	10 Savanna
11 Desert	

Fig. 2.10. Biome pyramid

are the producers, such as plants and algae, which capture solar energy through photosynthesis. The next levels consist of herbivores (primary consumers), carnivores (secondary consumers), and top predators (tertiary consumers). As we move up the pyramid, the

© NCERT not to be republished

number of organisms, biomass, and available energy decrease as energy is lost at each trophic level as heat during metabolic processes. Thus, a biome pyramid helps in understanding the structure of ecosystems, the flow of energy, and the balance between different living organisms in a biome.

LET'S MAP

Mark the following regions at appropriate levels on the Fig. 2.10: Andaman & Nicobar Islands, Keralam, Ladakh, Chhattisgarh, Odisha, Meghalaya, and Lakshadweep. Where will you place your home?

There is no arrow on the third side of the triangle. What would happen if we drew an arrow? Would it point upwards or downwards?

Interconnectedness between Biomes and Living Beings

Biomes are closely connected to living beings because they provide a natural environment where plants, animals, and humans can survive and interact. At the same time, living beings also influence biomes—animals help in pollination and seed dispersal, humans modify landscapes for farming or cities, and microorganisms recycle nutrients. In this way, biomes and living beings are interconnected systems that depend on one another to maintain ecological balance and biodiversity. We will discuss some of the aspects of this interconnectedness in the following section.

Maintaining Ecological Balance and Biodiversity

Biodiversity

Biodiversity is the variety of life on Earth, including plants, animals, microorganisms, and the ecosystems they inhabit (Fig. 2.11). It refers not only to the number of different species but also to the genetic differences within species and the variety of habitats and ecological processes that sustain life. In simple terms, biodiversity means the richness of life forms and the natural balance they create, which is essential for maintaining healthy ecosystems and supporting human survival.

Fig. 2.11. Biodiversity in wild animals

© NCERT not to be republished

The **geographical aspects of biodiversity conservation** focus on how location, climate, landforms, and ecosystems influence the protection and management of living organisms. Since biodiversity is unevenly distributed across the Earth, geography plays a vital role in conservation. Some key aspects of conservation are—

Hotspots of Biodiversity: Certain regions, such as the Himalaya, the Western Ghats, the North–East India, and the Andaman & Nicobar Islands, are rich in unique species found nowhere else. Identifying and protecting these hotspots is a priority in conservation.

Fig. 2.12. (Left to right, top to bottom) Endangered Nilgiri Tahr Wild Goat; Himalayan Snowcock Bird; Indian Spider, Western Ghats; Big Himalayan Yak; Mangrove Forest, Andaman Islands

Ecosystem-Based Conservation: Different biomes (forests, wetlands, deserts, coasts, and mountains) support distinct life forms. Conservation strategies must suit the geographical setting; for example, mangrove protection along coasts or afforestation in mountains.

Protected Areas: National parks, wildlife sanctuaries, biosphere reserves, and World Heritage Sites are chosen based on geography to preserve critical habitats and prevent habitat fragmentation.

Geographical Barriers and Corridors: Natural features like rivers, mountains, and valleys serve as barriers or corridors that influence animal movement and gene flow. Conservation planning uses this knowledge to create wildlife corridors.

Human–Environment Interaction: Geography also considers how local communities use land, water, and forests. Sustainable practices vary with geography, such as terrace farming in the hills or agroforestry in the plains.

In short, biodiversity conservation is an intrinsic part of geography because the survival of species depends on their location, habitat conditions, and human activity within those regions.

© NCERT not to be republished

LET'S MAP



Fig. 2.13. Political Map of India

Mark and name the following regions on the map in Fig. 2.13. Also gather more information about these biodiversity regions from your teacher or other sources and discuss their features with your peers.

1. Namdapha National Park
2. Rann of Kutch
3. Gahirmatha beach
4. Gulf of Mannar
5. Pachmarhi
6. Achanakmar–Amarkantak

© NCERT not to be republished

Forest Ecotourism

Ecotourism: Travelling to nature-friendly places without harming the environment, and supporting local people.

Ecotourism in forests refers to responsible travel to forested areas where tourists enjoy nature while contributing to its conservation. Forests are home to a wide variety of plants, animals, rivers, and waterfalls, which attract people who want to experience natural beauty, wildlife, etc. Unlike mass tourism, ecotourism emphasises minimal environmental impact, respect for local communities, and learning about ecosystems. For example, visiting national parks, wildlife sanctuaries, or trekking through rainforests allows visitors to observe biodiversity while supporting conservation programmes and generating income for the local people. Thus, ecotourism in forests helps balance tourism, environmental protection, and sustainable development.

DON'T MISS OUT

The Swadesh Darshan 2.0 Scheme, launched by the Ministry of Tourism, Government of India, aims to develop sustainable tourism destinations with a tourist- and destination-centric approach, and a focus on factors such as sustainable development, conservation, and local community involvement.

LET'S EXPLORE

Thenmala Ecotourism in Keralam

→ Thenmala, located in the Kollam district of Keralam, is India's first planned ecotourism destination, developed jointly by the Tourism Department, the Forest Department, and the Irrigation Department of Keralam. The name *Thenmala* means 'Honey Hill', reflecting the area's natural richness and biodiversity within the Western Ghats—a UNESCO World Heritage Site. The project was launched to promote sustainable tourism while conserving forests and supporting local communities, by employing the inhabitants as guides, eco-guards, and service providers, ensuring that the tourism benefits are shared within the community. Thenmala's success lies in its balanced approach—combining recreation, environmental education, and conservation—making it a model for responsible forest-based ecotourism in India (Fig. 2.14).

→ Is there any such ecotourism site in your State/UT? Collect some information and discuss with your friends.

© NCERT not to be republished

→ What should be a tourist's behaviour while visiting any tourist site? What should one be mindful of?

Fig. 2.14. Exploring forest canopy in Thenmala

Forests and Livelihoods

Fig. 2.15. Rituals to honour the forest deities

People, particularly rural and tribal communities, rely heavily on forests for their livelihoods. Forests provide essential resources such as food, fuel, fodder, medicine, shelter, timber, bamboo, and firewood. Non-timber forest products, such as honey, fruits, nuts, resins, and medicinal plants, help families meet daily needs and earn income. Several communities including the Gonds and Bhils perform rituals to honour the forest deities before collecting resources, reflecting sustainable cultural practices and a deep respect for nature (Fig. 2.15). Forests also support livestock grazing, small forest-based industries, ecotourism, and employment, making them vital for the livelihood, culture, and survival of many.

THINK ABOUT IT

Sacred groves are small forest patches protected by local communities for religious and cultural purposes. Across India, there are over 1,00,000 sacred groves, though many are not officially recorded. They are known by different names, such as *Devrai*, *Devarakadu*, *Kavu*, and *Sarna*.

Why are these groves so special? Despite being small, they are rich biodiversity hotspots, often preserving rare plants, medicinal species, and wildlife that may not survive elsewhere. Some groves are even linked to water sources and help to maintain streams and groundwater.

© NCERT not to be republished

Timber and bamboo (Assam, Tripura, Keralam)	Wild fruits, honey, mushrooms, and roots (Jharkhand, Odisha)
Tendu leaves, mahua flowers, sal seeds, gums (Madhya Pradesh, Chhattisgarh)	Ecotourism (Uttarakhand, Assam, Keralam)
Herbs like ashwagandha, neem, and tulsi (Himalayan region, Western Ghats)	Handicrafts and cottage industries (Rajasthan, Keralam)
	You may add some examples of forest produces from your own state/UT in the map above.

Fig. 2.16. Forest produces from different Indian states (map not to scale)

© NCERT not to be republished

Forest Dwellers

Forest dwellers have a deep and multifaceted connection to forests as they rely on them for household needs, cultural practices, and livelihood activities. Through their roles and responsibilities, they are often deeply involved in caring for and using forest resources. Women, in particular, play a vital role in collecting and managing forest resources for household needs, sustaining traditional knowledge and practices, and contributing to the livelihoods. Some of these connections are:

Knowledge Holders: They possess rich traditional knowledge of using herbs, plants, and forest resources for food, medicine, and cultural practices. This knowledge is passed down through generations and helps in biodiversity conservation.

Livelihood and Income: They are actively engaged in gathering and processing non-timber forest products (NTFPs) such as tendu leaves, mahua flowers, honey, lac, and bamboo, which provide income for households.

Forest Protection: They have been at the forefront of forest protection movements, such as the Bishnoi Movement in Rajasthan led by Amrita Devi. This also influenced the Chipko Movement in Uttarakhand, where village women hugged trees to prevent deforestation. Hence, they often play a key role in community forest management and eco-restoration.

Household Needs: In many rural and tribal areas, forest dwellers collect firewood, fodder for cattle, wild fruits, roots, tubers, and medicinal plants from forests to sustain their families.

Cultural and Social Role: In many communities, forests are linked to several rituals, festivals, and beliefs making them guardians of ecological and cultural traditions.

Fig. 2.17. Connections between forest dwellers and forests (Central image shows women carrying bundles of leaves and wood from a mountain forest in Sohra, Meghalaya)

© NCERT not to be republished

LET'S EXPLORE

Fig. 2.18. Traditional tribal livelihoods

Try to identify and classify the items for sale in the images given in Fig. 2.18.

Also, make a list of the food and medicinal varieties available in your local market.

Geographical Indication (GI)

Did you know that some forest products are unique to specific regions and are recognised as Geographical Indications (GI)? A **Geographical Indication (GI)** tag is a type of intellectual property right that identifies a product as originating from a specific place, where a given quality, reputation, or other characteristics of the product are essentially linked to its geographic origin.

In simple terms, it is a label that indicates that a product comes from a particular region and derives its uniqueness from that place. Thus, GI tagging helps protect region-specific products, promote cultural heritage, and generate economic benefits for local communities through exclusive market recognition.

GI-tagged Forest Products in India

India has several forest-based products that have been granted Geographical Indication (GI) tags because they are unique to their region, linked to traditional knowledge, and depend on the forest ecosystem (Fig. 2.19).

© NCERT not to be republished

Fig. 2.19. Some GI-tagged forest products of India (map not to scale)

1. **Ramban Sulai Honey (Jammu and Kashmir):**
   It is highly nutritional with strong antioxidant and immuno-modulatory potential and has a distinct flavour, aroma, and taste.
2. **Tezpur Litchi (Assam):**
   - Grown in the forest-influenced soil and climate of Assam's Tezpur region.
   - It has a distinctive bright colour and high pulp content.
3. **Channapatna Toys (Karnataka):**
   The notable aspect of this forest-based craft is that they are made from *Wrightia tinctoria*, a forest tree locally known as 'Aale mara'.
4. **Kandhamal Haldi (Odisha):**
   - A variety of turmeric grown by tribal communities in the forest regions of Kandhamal.
   - It is known for its high curcumin content and medicinal value.
5. **Erode Manjal/Erode Turmeric (Tamil Nadu):**
   Cultivated in **forest-influenced soils**, it is used for cooking and ayurvedic medicine.
6. **Nilgiri Tea (Tamil Nadu, Keralam, Karnataka):**
   Though plantation-based, its quality depends on the forest ecosystem conditions of the Western Ghats.
7. **Tripura Queen Pineapple (Tripura):**
   With a forest-dependent cultivation, it is famous for its sweetness and aroma.
8. **Khasi Mandarin (Meghalaya):**
   A citrus fruit from the forest-rich hills of Meghalaya.

You may explore more GI-tagged forest products from other states through the School Bhuvan-NCERT Geoportal.

Forest-influenced soils: Soil profiles shaped over long periods by forest vegetation, root systems, and organic litter accumulation.

© NCERT not to be republished

LET'S EXPLORE

- → Can you explain how GI tagging of the forest products mentioned above connects geography, cultural traditions, local governance, and rural economy?
- → Can you name some GI-tagged forest products from your state or union territory?

Challenges Faced by People Living in Forests

People living in forests often struggle to access essential facilities such as healthcare, education, and clean water. Women are exposed to fuelwood fumes and face, many health issues, making their daily lives difficult. Forest dwellers depend heavily on forest produce such as firewood, honey, bamboo, and medicinal plants for their livelihood. Restrictions on forest use, deforestation, and the commercial exploitation of resources often limit their access to these resources. This creates a conflict between conservation laws and their survival needs, leading to economic insecurity.

Forested hilly regions are prone to natural disasters such as floods and landslides. Floods can wash away homes, crops, and roads, while landslides can bury villages and cut off access to essential services. Forest fires can quickly spread through dense vegetation, destroying homes and resources. Human care and preventive measures can help prevent many forest fires.

Crops are often damaged by elephants, monkeys, or wild boars, and sometimes people face direct attacks. Such conflicts not only cause economic losses but also create fear and insecurity among forest communities.

Many forest dwellers also face discrimination and neglect from mainstream society. They are often engaged in selling forest products at relatively low prices. Therefore, creating opportunities for processing and marketing these products is essential to enhance their income. Forest communities also require assistance in accessing government schemes and programmes, as well as greater awareness of their legal rights.

THINK ABOUT IT

You may already be aware that incidents of forest fires have been reported from different parts of India and are a matter of serious concern. According to the Forest Survey of India (FSI), about 36

© NCERT not to be republished

per cent of the country's forest cover is estimated to be prone to forest fires, of which nearly 4 per cent is extremely prone. Climate change as well as human-induced factors are the main reasons for such occurrences, some of which are quite severe and cause extensive damage to human life and the environment (Fig. 2.20). *Note: You may explore various fire locations on the School Bhuvan–NCERT Geoportal.*

Fig. 2.20. A forest fire

LET'S EXPLORE

You may have heard about the Pradhan Mantri Ujjwala Yojana (PMUY). How are the benefits of this scheme impacting the health of women?

THINK ABOUT IT

- Which wild animals (like monkeys or deer) have you seen in your residential area?
- Identify the causes behind these animals' presence in human settlements.

Fig. 2.21. Forest bridge to avoid roadkill

Government Efforts to Support Forest Dwellers

To reduce the hardships of people living in forests, the Government of India has taken several steps. One of the most important measures is the Scheduled Tribes and Other Traditional Forest Dwellers (Recognition of Forest Rights) Act, 2006, commonly called the Forest Rights Act (FRA). The Act recognises the rights of eligible communities over the forest land and forest resources that they have traditionally depended upon. It allows them to collect minor forest produce such as bamboo, honey, and medicinal plants, and grants ownership of small patches of land cultivated by them.

© NCERT not to be republished

Along with the FRA, the Government runs schemes for tribal welfare, including education scholarships, healthcare programmes, and skill development initiatives. The Joint Forest Management (JFM) programme encourages local communities to participate in protecting forests while benefiting from forest produce. Other initiatives, such as the Panchayats (Extension to Scheduled Areas) Act (PESA), the Dharti Aaba Janjatiya Gram Utkarsh Abhiyan (DAJGUA), and the Pradhan Mantri Janjati Adivasi Nyaya Maha Abhiyan (PM JANMAN), aim to promote the welfare of such communities.

Mendha Lekha: A Case Study in Community Forest Management

Mendha Lekha is a small tribal village located in the Gadchiroli district of Maharashtra, known for its effective community-based forest management and self-governance. The village, inhabited mainly by the Gond tribe, became the first in India to gain rights over its forest resources under the Forest Rights Act (2006). The people of Mendha Lekha follow the principle of *Mawa Nate Mawa Raj* (our village, our rule), ensuring that all decisions are made collectively through the Gram Sabha. They protect and sustainably utilise their 1,800 hectares of forest by regulating tree cutting, preventing forest fires, and promoting bamboo harvesting as a renewable resource. The revenue from the forest produce is used for community welfare activities such as education and infrastructure. This also upholds the fundamental rights of the people to participate in governance and control resources that sustain their livelihoods. Simultaneously, the villagers fulfil their fundamental duties by protecting biodiversity and preventing illegal exploitation. This model has not only strengthened local livelihoods but also demonstrates how traditional knowledge, rights, and duties, as well as democratic participation, can coexist to achieve sustainable forest conservation (Fig. 2.22).

Fig. 2.22. Community-led protection of forests through self-governance, traditional livelihood, and controlled grazing in Mendha Lekha

© NCERT not to be republished

Ecological Commons—Shared Resources

The term **ecological commons** refer to natural resources like forests, rivers, lakes, grazing lands, air, and biodiversity that are shared by a community and used collectively for its survival and well-being. Unlike private property, these resources are not owned by any single individual but belong to the community as a whole, and are often managed through traditional rules and practices. For centuries, people have depended on the ecological commons for food, water, fuel, fodder, and medicinal plants. However, with population growth, industrial use, and privatisation, many of these commons are shrinking or degrading. Protecting ecological commons is important not only for the livelihoods of rural and tribal communities but also for maintaining ecological balance, regulating climate, and conserving biodiversity.

A Case Study of Commons-based Fisheries Management in Bihar

After independence, The Indian Fisheries Act, 1897, remained the basis for the governance of inland fisheries. Historically, control over perennial water bodies and *diara* waterfronts in Bihar was held by large landowners who marginalised the fishing community, rendering them the most vulnerable group in an environment abundant with aquatic resources.

Fig. 2.23. Fishermen at work in a maun (lake) at dawn

The historical insights from Bihar's 19th century case study suggest that a commons-based management model is best suited to riverine regions. To promote community-led management, legal safeguards for public access, and cooperative resource stewardship as

© NCERT not to be republished

sustainable alternatives—along with the preservation of cultural heritage associated with riverine waterscapes—the Bihar Fish Jalkar Management Act, 2006, and its subsequent amendments, were introduced. Under this model, local communities develop context-specific solutions to balance the productivity of local resources with sustainable rates of exploitation. The success of this model is reflected in the persistent growth of fish production in the region.

Case Study of Water Tanks Built by the Gond Kings

In India, for centuries, regions with seasonal rainfall have tackled the issue of water demand and management as a collective concern and used common public resources for the same. In fact, between 800 and 1200 CE, the Chandella and Bundela kings built around 8,000 tanks in the Bundelkhand region. Similarly, *keres* were built in Karnataka, *eri* tanks in Tamil Nadu, and *chevuru* tanks in Andhra Pradesh and Odisha. Bihar had the famous *ahar pynes* to store water and the Gond kings funded huge *katas*—three-sided reservoirs—in the Gondwana region. According to official estimates, there are more than 15 lakh functional tanks in India at present.

LET'S EXPLORE

Below is Fig. 2.24 from the School Bhuvan–NCERT Geoportal. Observe the image carefully and see if you can identify some of the tanks and mark the agricultural fields irrigated by them.

Fig. 2.24. Water tanks in Bhandara district, Maharashtra

© NCERT not to be republished

Before we move on...

- Biomes are large areas on Earth with specific vegetation and animal life. Biomes are classified based on temperature, precipitation, flora, fauna, etc.
- Humans interact closely with different biomes and adapt their lifestyles to the conditions and resources available.
- Traditionally, different human cultures have developed various practices for conserving nature. Today, there is a legal framework to support conservation efforts.
- Occupations have been closely associated with forests, right from primitive hunting to modern ecotourism. The variety of human interactions with forests highlights their significance for various communities.
- With growing population, there is increasing pressure on forests, which leads to problems like human–wildlife conflict, depletion of resources, etc.

Questions and Activities

1. Why does India have diverse biomes? How does the local geography connect to the diversity?
2. Make a list of economically valuable native plants in your region and comment on their abundance.
3. Prepare a map of your state or Union Territory showing national parks and sanctuaries.
4. Study the impact of forest fires on people dependent on forests. Try to include the causes, losses, and preventive measures.
5. Why are forests often called the 'lungs of the Earth'?
6. If large forest areas continue to be destroyed, what do you think would be its long-term effect on the global climate?
7. Discuss some traditional forest conservation methods with your grandparents or an elderly person.
8. How do forest dwellers contribute to the protection and conservation of forests?
9. What is a forest fire? Prepare a plan for prevention and mitigation of forest fires.

© NCERT not to be republished

Notes

© NCERT not to be republished

Chapter 3
Resistance and Resilience (1000–1700 CE)

0909CH03

The Big Questions

1. *How did Indian rulers use resistance and alliances to safeguard their lands?*
2. *What factors contributed to the resilience of different kingdoms and communities during this period?*
3. *How did the Bhakti tradition foster a sense of solidarity?*
4. *How did the expansion of agriculture, trade, and commerce keep the economy sound?*

The period between 1000 CE and 1700 CE witnessed profound political, social, and cultural changes. The Indian subcontinent experienced repeated invasions and wars accompanied by religious discrimination and social distress. Regional powers frequently resisted invaders who were making inroads into their territories. This resistance took both military and cultural forms. Nonetheless, this period manifested the resilience of the Indian civilisation, which safeguarded its core ideas and values. Indian society not only defended itself from external threats but also preserved its traditions. In this chapter, we will see how resistance and resilience shaped this period of Indian history.

Let us begin by understanding the meaning of resistance and resilience in the context of the period under study and how they are interconnected.

Resilience refers to the capacity to, survive and adapt in challenging situations, including times of political unrest and instability. It is also about how communities and groups across diverse regions respond to challenges and opportunities. This capacity to absorb and adapt to hardship while preserving inherited socio-cultural and spiritual traditions can also be understood as resilience. The idea of India's resilient spirit extends beyond political and military spheres.

© NCERT not to be republished

For instance, rulers and communities restored places of worship, modified customs to suit changing circumstances and, in many regions, established lasting patterns of coexistence across religious and cultural lines.

Resistance means actively opposing or challenging a force, authority, or threat in order to protect political power, territory, interests, or cultural and spiritual identity. Resistance may take the form of warfare, alliances, diplomacy, negotiation, or other political actions.

Resistance and resilience are, in fact, closely linked. Resilience is the backbone of resistance. While a political cause or leadership provides the condition for resistance, the ability to endure comes from resilience. Together, resistance and resilience help explain how Indian society sustained itself through different ages, particularly the period under study. This period is characterised by both conflict and cooperation, rather than being merely a story of invasion and resistance.

Safeguarding Sovereignty: Resistance, Alliances, and Confederacies

From the 7th century onwards, the Indian subcontinent witnessed successive phases of invasions driven by territorial expansion and religious motives. It may also be noted that the surplus agrarian produce of the fertile plains fed by perennial river systems contributed to the people's economic well-being and also became a major reason for the invasions. Against this backdrop, let us examine instances of resistance, as well as the strategic alliances and confederacies that emerged in these centuries at both the regional and pan-Indian level.



© NCERT not to be republished

From the mid-7th century, Arab forces launched invasions by sea and land. These early invaders were confronted and repulsed by Indian rulers across the Deccan, Malwa, Kashmir, and Rajasthan. Mahmūd, the Sultan of Ghaznī (in present-day Afghanistan and northeastern Iran), launched his first invasion in 1001 against Jayapāla of the Hindu Shāhi dynasty. During the 11th and 12th centuries, rulers of the Hindu Shāhi kingdom, and the Chandellas, Solankīs, and Chauhāns opposed and fought against the Turkish invaders. In 1178, Queen Nāikī Devi of the Chaulukya kingdom defeated Muhammad Ghurī at Kasahrada, near Mount Abu. In northern India, some powers, such as the Chauhāns, Gahaḍavālas, and Senas, however came under Turkic control towards the end of the 12th century, even as Gujarat, Malwa, and Bundelkhand under the Chandellas put up stiff resistance for about a hundred years thereafter. The Turks failed to conquer present-day Odisha, and parts of present-day Assam. Several states of Rajputana, in particular, remained centres of sustained resistance throughout the period under study. Thus, during the 11th and 12th centuries, northern and western India bore the brunt of Turkish invasions, while peninsular India remained free from Turkic control.

LET'S RECALL

You may recall learning about the invasions of Mahmūd of Ghaznī and Muhammad Ghūrī in the 11th and 12th centuries, covered in Grade 7 Social Science textbook. These invasions had seriously disrupted the political, social, and religious fabric of the Indian subcontinent.



© NCERT not to be republished



Fig. 3.1. Some political kingdoms of Indian subcontinent in the 11th and 12th centuries

© NCERT not to be republished

Rajput Dynasties: Confederacies and Resistance (1200–1500 CE)

The establishment of the Delhi Sultanate in 1206 was a turning point in Indian history. The new state introduced administrative practices that led to greater centralisation of authority. For example, the *iqta* system, under which territories were assigned to military commanders in lieu of salaries, became a mechanism for land revenue collection and a system that increased the burden on the peasantry. Furthermore, during their military campaigns for territorial expansion, the forces of the Sultanate demolished sites sacred to the local communities. This led to stiff resistance from several kingdoms and chieftains. Therefore, resistance throughout the Delhi Sultanate was fuelled by both political factors and the determination to preserve socio-cultural continuity. For instance, the Yādava dynasty of western Deccan (Devagiri), several Rajput dynasties of present-day Rajasthan, the Kākatīya rulers of eastern Deccan (Warangal), and the Hoysālas of present-day Karnataka repeatedly resisted the Sultans of Delhi. These states played an important role in checking the expansion of the Sultanate.

Over the years and under different Sultans, the Delhi Sultanate faced opposition and defiance from several states and regions including Mewar, Gwalior, Malwa, Awadh, Etawah, Ajmer, Jalore, Kalinjar, and Kannauj.



© NCERT not to be republished

Rajput–Mughal Dynamics: Politics and Complexities of Rule (1500–1700 CE)

In the early 1500s, the weakening and subsequent decline of the Delhi Sultanate under its last ruler, Ibrāhim Lodī, opened the door to two parallel developments. First, Zahiruddin Muhammad, also known as Bābur, from Central Asia launched an invasion on India. Second, Indian rulers began to assert their own authority. In 1526, Bābur defeated the Lodi forces in the First Battle of Panipat, bringing the Sultanate to an end. In 1527, Rāṇā Sangrām Singh I, popularly known as Rāṇā Sāngā, of Mewar led a Rajput confederacy against Bābur in the Battle of Khanua. The battle ended in favour of Bābur and is seen as an important turning point in Indian history.

Mansab: It means 'rank' or 'office', and its holders were known as mansabdars. Akbar introduced the mansabdari system, which combined military organisation with civil administration. It established a clear hierarchy among the nobility and helped strengthen imperial control.

As Mughal rule consolidated its power, relations between the Rajputs and the Mughals evolved over time, shaped by strategic considerations. Some Rajput kingdoms such as Mewar, maintained stiff resistance to Mughal authority, while others like the Kachhwāha Rajputs of Amber, negotiated cooperative relationships. The Mughals, for their part, had a strong incentive to collaborate with the Rajputs—they needed the Rajputs' military might, their loyalty as well as their administrative strength to consolidate and stabilise the Mughal Empire. Towards this end, the Mughals integrated some of the Rajputs into the empire through the grant of **mansabs** and other understandings.

Mewar's Resistance against Mughals

Akbar attacked the kingdom of Mewar and laid siege to the fort at Chittor in 1567–1568. The Mughal army paid a heavy price in the campaign. Under Rāṇā Udai Singh, the Rajputs put up a stiff resistance for more than five months before the fort was captured



© NCERT not to be republished

Fig. 3.2. A painting depicting the Battle of Haldighati

by the Mughals. By this time, Akbar had already concluded several successful campaigns and the empire was at the peak of its power. In a strategic move, Rāṇā Udai Singh retreated to the Aravalli Hills along with a large number of his subjects.

In 1576, Akbar launched another attack on Mewar. This time, Mahārāṇā Pratāp, the son and successor of Rāṇā Udai Singh, fought against Mughal forces in the Battle of Haldighati. Continuing his fierce resistance, Mahārāṇā Pratāp modified his military strategy and adopted guerrilla warfare. He used the rugged Aravalli terrain to his advantage and conducted surprise attacks, raids, and ambushes on the Mughal forces and their networks. He continued to resist and eventually reclaimed most of his ancestral territories in the 1580s.



© NCERT not to be republished

The Battle of Dewair fought near Udaipur in 1582 was significant as it resulted in the collapse of key Mughal military outposts in Mewar and helped Mahārāṇā Pratāp reclaim control over Mewar.

Mahārāṇā Pratāp's son and successor, Mahārāṇā Amar Singh, continued Mewar's tradition of military resistance against the Mughals. Jahāngīr made military advances towards Mewar in 1605, 1608, and 1609. But each attempt was countered by a strong and organised resistance from the Rajputs. Eventually, the Mughals were compelled to acknowledge Mewar's distinct political position.

Fig. 3.3. Victory memorial in Dewair, Rajasthan

Fig. 3.4. A 19th century miniature painting of Mahārāṇā Pratāp



© NCERT not to be republished

On one hand Mewar continued its defiance in the form of a strong, organised, and determined resistance, and on the other hand, the Mughal state began to recognise and appreciate Mewar's unique geo-political position with trade routes leading to the major port of Surat. Needing peace with the rulers of Mewar more than ever, the Mughals were eventually compelled to negotiate a treaty. Under the terms of the treaty, Mewar leadership was exempted from personal attendance at the Mughal court, thus clearly acknowledging Mewar's continued autonomy.

LET'S RECALL

Do you remember reading about the Battle of Haldighati in your Grade 8 textbook? You may recall that the Bhil community provided crucial, tactical, and logistical support to Mahārāṇā Pratāp in his resistance against the Mughals. Their extensive knowledge of the Aravalli terrain, expertise in guerrilla warfare, skills in archery, role as guides, and above all, their bravery strengthened Mewar's resistance. This enduring alliance was later commemorated in Mewar's state emblem (Coat of Arms), which depicts a Rajput warrior and a Bhil warrior with the local deity Eklingji (Shiva) shown at the centre.

Fig. 3.5. Mewar's Coat of Arms

1658–1707: Reign of Aurangzeb

© NCERT not to be republished

LET'S EXPLORE

After the death of Mahārāṇā Pratāp, renowned poet Dursā Arhā gave a vivid account of Mahārāṇā Pratāp in the following lines:

> *O Pratap, you kept your horses unbranded, your head unbowed, your fame untarnished. You were strong enough to carry on your work against heavy odds. You never participated in the Nauroz festival, nor did you mount guard for the imperial presence during Jharokha Darshan. You attained a very high place in this world.*

Fig. 3.6. Source: Rawat Saraswat, Dursā Arhā (New Delhi: Sahitya Akademi, 1983)

Identify any two specific actions mentioned in the text which show that Mahārāṇā Pratāp maintained his independence from the Mughal court.

DON'T MISS OUT

Other Rajput rulers like Kānhaḍa Deva Chauhān (Jalore), Rāṇā Hammīra Deva (Ranthambore), Rāṇā Kumbhā (Mewar), and Rāo Surjan Hāḍā (Bundi) put up a strong resistance at different points of time.

The Ahom Kingdom: Centuries of Endurance

The Ahom kingdom of Assam maintained its political independence for almost six centuries (1228–1826) and successfully resisted several invasions and attempts at annexation. The military strategy of the Ahoms relied on exploiting the local terrain rather than engaging in direct confrontation. Ahom commanders possessed detailed knowledge of Assam's forests, river systems, and monsoon cycles, which invading forces generally lacked. Despite repeated attempts by the Mughals to annex the Brahmaputra valley, the Ahoms successfully defended their territories against Mughal invasion.

© NCERT not to be republished

Fig. 3.7. A monument at Guwahati, Assam commemorating the Battle of Saraighat

The first Ahom–Mughal clash took place in 1615 near Samdhara. Mughal forces under Abu Bakr made early gains but were soon compelled to retreat. By 1616, the Ahoms had recovered the lost territory, setting a pattern that would recur over the next sixty years. In 1662, Mīr Jumlā captured the Ahom capital, Garhgaon. Subsequently, a treaty was imposed on King Jayadhvaj Singha. However, the king defied the Mughals and renounced the treaty within a year of the Mughal withdrawal, and the Ahoms retained their independence.

A decisive check on Mughal ambitions in the region came in 1671, when the Ahom commander Lachit Borphukan defeated a Mughal fleet at the Battle of Saraighat, securing the Brahmaputra as an effective territorial boundary. The Ahoms' successful resistance against the might of the Mughal empire is a remarkable story of bravery, pride, and endurance.

Ahom endurance rested on a combination of strategic alliance-building, guerrilla tactics, Assam's challenging geography, and the *Paik* system (about which you have read in Grade 8) of military-administrative organisation. The Ahom navy also played a key role, using light, fast boats, called *bāchārī*, built specifically for river warfare, which gave them an advantage over Mughal fleets.

Fig. 3.8. Model of a bāchārī boat

© NCERT not to be republished

Fig. 3.9. An aerial view of Hampi, the capital of the Vijayanagara Empire

Vijayanagara Empire: Resilience against Expansion

Resistance to foreign invasions was not confined to northern India. In the Deccan and beyond, the expanding campaigns of the Delhi Sultanate steadily weakened the older kingdoms of the south. Malik Kāfūr, Alauddin Khiljī's general, attacked major cities and temples, including those at Warangal, Belur, and Madurai. Later, Muhammad bin Tughlaq's rise to power extended the Sultanate's influence even farther south, ultimately contributing to the decline of the Pandya Kingdom and the eventual emergence of a new sultanate territory known as the Madurai Sultanate.

It was against this backdrop that the Vijayanagara Empire rose in 1336 to check the expansion of the Sultanate into peninsular India. Harihara and Bukkā established the independent kingdom of Vijayanagara—meaning 'City of Victory'—located near present-day Hampi, Karnataka. The region's geography, including a formidable river and rugged, rocky terrain, provided Vijayanagara with a strong natural defence and a secure base for military operations. They made determined efforts to defend and expand their state's frontiers. The empire gradually expanded by annexing territory south of the Krishna and Tungabhadra rivers and became one of the richest and most influential states, encouraging the flourishing of literature in Kannada, Telugu, Tamil, and Sanskrit. Vijayanagara's capital city became a centre of trade, culture, and political power in southern India.

During Bukkā's reign, Vijayanagara made major territorial gains, including the subjugation of the Madurai Sultanate and the annexation of Arcot. In 1342, the ageing Hoysāla king Vīra Ballāla III

© NCERT not to be republished

fought the Madurai Sultanate, resulting in the Battle of Kannanur, which was a pivotal episode in this struggle. However, the Sultan launched a surprise counter-attack and executed the Hoysāla ruler. For almost four decades, Vijayanagara wrestled with the Sultans of Madurai. Later, the campaign against Madurai Sultanate was led by Kumāra Kampana, the son of Bukkā. He killed the Sultan and brought the Sultanate of Madurai to an end. Kumāra Kampana also reinstated the divine images in the Rajasimheshwara Temple at Kanchipuram and the Sri Ranganathaswamy Temple at Srirangam.

LET'S RECALL

In Grade 8, Part I, you have read about how the Vijayanagara Empire reached its peak in the 16th century, under its celebrated ruler, Kṛiṣhṇadevarāya, who expanded and secured the empire's dominance over the Deccan. Under his rule, the empire achieved both military power and cultural glory. Kṛiṣhṇadevarāya provided grants to many temples, including Tirupati in Andhra Pradesh and the Vitthala temple in his own capital Vijayanagara, which had many grand temples, palaces and other buildings. After winning many wars against his neighbours, Kṛiṣhṇadevarāya died of illness in 1529.

Decades later, the Vijayanagara army was defeated at the Battle of Talikota in 1565 by an alliance of the Deccan sultanates. In the aftermath, the city of Vijayanagara was sacked and largely abandoned, while the empire gradually fragmented. Several of its territories came under the rule of smaller Nāyaka kingdoms.

DON'T MISS OUT

By the end of the 16th century, the Vijayanagara Empire had split into smaller kingdoms ruled by the Nāyakas. They also continued the tradition of resistance—not always through military action, but sometimes through bold acts of defiance aimed at Mughal authority. An interesting account is of Muthu Vīrappa Nāyak III of Madurai. Local tradition holds that the Mughal emperor would dispatch a royal slipper to rulers as a symbol of imperial supremacy and domination. Recipient rulers were expected to receive the slipper ceremonially at the borders of their territories and pay tribute. When the slipper arrived at the borders of Madurai, Muthu Vīrappa Nāyak refused to observe this protocol. In an act of defiance against

© NCERT not to be republished

this ritual of subordination, he refused to meet the procession at the border, compelling the Mughal emissary to carry the token right up to the palace hall. Even then, Muthu Vīrappa Nāyak refused to bow before the slipper. Instead, he forced the Mughal representatives to place it on the floor, put his own foot inside it, and mockingly asked why the Badshah had not sent a matching pair. He then had the messengers expelled from his kingdom.

Fig. 3.10. A painting of Chhatrapati Śhivājī with his personal guards

Marathas: The Quest for Swarājya

The Marathas were a formidable force in the Deccan particularly during the 17th and 18th centuries. The establishment of an independent Maratha state in 1674 is closely associated with the rise of Chhatrapati Śhivājī. The Marathas had been involved in the region's political affairs for centuries. Their knowledge of the Deccan's complex geography and landscape, along with their bravery and martial abilities, made them a formidable force in both administrative and military affairs.

LET'S RECALL

You have already learnt about the foundation of Maratha power and the rise of Chhatrapati Śhivājī in your Grade 8 textbook, Part I. Think back to his struggle and the ways in which he built and strengthened his kingdom. What do you remember about the strategies and institutions that helped the Marathas establish their power?

Over time, the Marathas emerged as a prominent political and military force in India. In the Maratha state, territorial control and sovereignty were closely linked to the idea of *swarājya*, or self-rule. Chhatrapati Śhivājī is regarded as one of the earliest proponents of

© NCERT not to be republished

the spirit of *Swarājya*—the idea of an independent, self-governing territory free from external control.

As you have read in your Grade 8 textbook, the Marathas fought many battles against the Mughals and other powers. The prolonged warfare exhausted the Mughal Empire economically and politically, to the point that Aurangzeb spent more than two decades in the Deccan in an attempt to control the region and subdue Maratha resistance. As political boundaries shifted constantly, the Marathas relied on strategic alliances to extend their control over diverse territories. Through these alliances, they built a vast network of tributary relationships that extended their influence far beyond the areas under their direct rule. The key to the success of the Marathas was their bravery and military skills.



Fig. 3.11. Raigad fort

Fig. 3.12. Sinhagad fort

The Marathas strategically built forts such as Raigad and Sinhagad which played a crucial role in resistance against the Mughals. The Maratha territories were characterised by hills and deep valleys. Maratha forts, therefore, functioned as strategic nuclei for guerrilla warfare. This network of forts enabled the Marathas to launch swift attacks from different directions and provided safe retreats. Different types of forts were constructed to serve distinct purposes, and while some functioned as advanced outposts, those on the frontiers served

as fallback capitals to avoid total defeat. Many formed part of the wider defensive network, and most were designed to withstand prolonged sieges. Forts also served as centres of administration and judicial authority. Strong defences, water sources, and armouries provided resilience and self-sufficiency, enabling the Marathas to sustain prolonged resistance during sieges.

DON'T MISS OUT



Fig. 3.13. Gingee Fort or Senji Fort in Tamil Nadu

The Fort of Senji, or Gingee, is situated in the Villupuram district of Tamil Nadu. It is considered a marvel of military and civil engineering and military architecture. One of its gateways is said to have been designed so that a small contingent of soldiers could defend it against an army of ten thousand. The fort came under the control of several powers, including the Vijayanagara Nayakas, Bijapuri Sultans, Mughals, Marathas, French, and English. Its changing control also highlights the fort's strategic importance and centrality to the political affairs of the region.

In 2025, the Fort was declared a UNESCO World Heritage Site during the 47th session of the World Heritage Committee in Paris.

not to be republished



Fig. 3.14. Some political dynasties in the Indian subcontinent in the 17th century

The Sikhs: A Story of Spiritual and Political Resilience

A major spiritual movement was founded by Guru Nānak in the late 15th century which later came to be known as Sikhism. It emphasised devotion to one God, social equality, and the rejection of rituals. Under Guru Nānak and his successors, the Sikh community expanded and flourished across the subcontinent, particularly in the Punjab, Sindh, and Gangetic plains. During this period, Punjab was largely under the Lodī Sultans and later under the Mughals. It was a fertile, densely populated region, with a large peasant population.

© NCERT not to be republished

Fig. 3.15. A 19th century image of Sri Harmandir Sahib (Golden Temple), Amritsar

Due to the growing socio-cultural influence of the Sikh Gurus, the Mughal state increasingly intervened in their affairs from the beginning of the 17th century. As the Guru's influence was increasing, Jahāngīr ordered the execution of Guru Arjan Dev (the fifth Sikh guru) on the pretext of the Guru's alleged support to Jahāngīr's rebellious son, Khusrau Mirza. The martyrdom of Guru Arjan Dev marked a significant turning point in the history of the Sikhs and contributed to a gradual shift in their organisational and political orientation. Later, Guru Hargobind (the sixth Sikh Guru) was detained by Jahāngīr in Gwalior Fort. During this period, the Sikhs visited Gwalior in large numbers and paid their respects to the Guru from outside the fortress. In 1675, Aurangzeb ordered the execution of Guru Tegh Bahādur, the ninth Sikh Guru. The martyrdom proved a turning point in Indian history. The brutality of the Mughal state against the Sikh Gurus particularly Guru Arjan Dev, Guru Tegh Bahādur, and the tenth Guru, Guru Gobind Singh has few comparisons in history. The valour and sacrifice of the Gurus for the cause of the faith became the defining features of Sikhism. Beyond political motivations, the act was also deeply rooted in the rigid religious and discriminatory practices of the Mughals. The martyrdom of the Sikh Gurus to uphold their faith and principles firmed the conviction of the Sikhs that persecution had to be met with firm resistance and resilience. Such persecution and political pressure could only be countered through collective organisation, and armed resistance as and when required. Many armed conflicts took place between the Sikhs and the Mughals. Guru Hargobind established the *Akāl Takht*, a seat of temporal authority, to administer justice and address matters of governance. Scholars suggest that the establishment of the *Akāl Takht* was intended, in part, to counter Mughal political dominance.

The concept of *mīrī-pīrī* became vital in this context, representing the Guru's authority over both spiritual (*pīrī*) and worldly (*mīrī*) affairs. In Amritsar, the Harmandir Sahib (Golden Temple) represented spiritual authority (*pīrī*), while temporal power (*mīrī*) was represented by the *Akāl Takht*. In 1699, Guru Gobind Singh established and developed a

© NCERT not to be republished

Sikh order known as the Khalsa. The Khalsa adopted a distinct martial code in response to the changing socio-political environment. Through this process, spiritual identity became closely intertwined with the pursuit of political identity.

Due to sustained Mughal hostility, including the execution of Guru Gobind Singh's sons, the Sikhs organised themselves into armed groups known as *misals* to defend themselves and the territories through military and administrative structures (Eventually, these *misals* became a network of confederacies that united the Sikhs against the Mughals.). In this process, many people from peasant communities became soldiers and fought against Mughals in Punjab.

Jat Resistance

During the 17th century, the Jats, a farming community from Ganga–Yamuna Doab were burdened with heavy taxes and exploitation by Mughals. These economic hardships combined with Aurangzeb's religious policies led to growing resentment amongst the Jats. In 1669, under the leadership of Gokul Jat, they rebelled against the Mughal Empire. Mughal forces struggled for many months to suppress the uprising.

However, the Jats continued their resistance. In 1686, they took advantage of Aurangzeb's prolonged military campaigns in the Deccan and rebelled once again under the leadership of the *zamindars* of Sinsani and Sogar. The Mughals sent several armies to suppress the rebellion, leading to a long and fierce struggle in which both sides suffered heavy losses. By 1691, the Mughals had gained the upper hand. Yet, the Jat resistance continued.

DON'T MISS OUT

Niccolao Manucci, an Italian traveller, wrote an extensive account about India during his journey (17th century) including descriptions of Jat resistance against the Mughals.

Bhakti Tradition: Affirmation of the Spirit of Resilience

India underwent a profound transformation in its religious and spiritual landscape between the 11th and 17th centuries. Bhakti—a tradition of personal devotion to the divine—was expressed through devotional

© NCERT not to be republished



Fig. 3.16. Saint Kabīr with Nāmdeva, Rāidās, and Pipājī, Jaipur, early 19th century

hymns composed in local languages. From the 7th century onwards, the rise and expansion of Bhakti in peninsular India shaped social, religious, and political life. Bhakti tradition emphasised inclusivity, socio-religious equality, simplicity, and connecting with people's everyday life. For instance, Eknāth composed in Marathi and propagated a devotional path that was accessible to all without dependence on institutions.

LET'S EXPLORE

Explore the contributions of the Nayanar saints (devotees of Śhiva) like Karaikal Ammaiyar and the Alvar saints (devotees of Viṣhṇu) like Andal to the spread of the Bhakti tradition in peninsular India. Discuss their teachings and devotional practices and the ways in which they connected with people through their hymns.

DON'T MISS OUT

Bhakti saints sang divine lores in different languages, but the unifying factor was devotion to the ultimate reality.

From the 14th century onwards, a strong wave of Bhakti spread across northern India. Rāmānanda, a prominent saint of this period, helped bridge the Bhakti traditions of southern and northern India. The tradition developed into two broad streams—*Nirguṇa bhakti*, devoted to a formless divine, and *Saguṇa bhakti*, centred on a divine with attributes. One of the remarkable features of the Bhakti tradition was the diverse social and cultural background of its saints.

The Bhakti tradition not only provided a spiritual refuge, but also played a role in preserving and transmitting core cultural traditions. When the construction of temples faced restrictions or existing temples were being destroyed, devotees could turn to non-material forms of worship, such as *nām kīrtan* (the recitation of the divine Name). This made devotional practice less dependent on

© NCERT not to be republished

physical structures that could be destroyed. Bhakti flourished through local songs and community participation (*satsang*), making it accessible to wider sections of society and more difficult to suppress. For instance, Sankardev composed the *Kīrtana Ghosha,* a highly respected work that remains central to present-day Vaishnava traditions.



Fig. 3.17. King Pratap Rudra of Odisha bowing to Chaitanya Mahāprabhu

Bhakti saints such as Chaitanya Mahāprabhu and Guru Nānak used community singing to bridge social divides. Community singing, or *sankīrtan*, drew large gatherings and fostered a shared sense of community and collective emotion among devotees. In some instances, it also became an act of defiance. For example, Chaitanya Mahāprabhu led public *sankīrtan* in Bengal to protest against restrictions imposed by a Qazi on devotional practices. In Rajasthan, religious orders such as the Dādu Panth and Niranjani Sampradāya provided a form of stability. Some of them even maintained standing armies of warrior ascetics to protect trade routes, facilitate the movement of saints, and provide educational and medical services.

DON'T MISS OUT

The widespread popularity of Indian literature also strengthened social resilience over time. The two great epics, *Rāmāyaṇa* and *Mahābhārata*, were translated into many regional languages. Tulsidas, a well-known Bhakti saint from northern India, composed the *Rāmcharitmānas* in Awadhi, a widely spoken variety of Hindi in the Awadh region of present-day Uttar Pradesh. By doing so, he brought the story of Rāma into households across the region. The work played a transformative role in the Bhakti tradition by making the spiritual knowledge and teachings of the *Rāmāyaṇa* accessible to wider sections of society.

The Bhakti tradition's emphasis on equality and inclusion gradually encouraged greater participation of women. Many rose to prominence as saints, coming from diverse socio-economic backgrounds. They expressed their spirituality through devotional hymns composed in their own languages. The use of local languages strengthened shared identities and fostered a sense of solidarity.

© NCERT not to be republished

DON'T MISS OUT

Fig. 3.18. A stamp commemorating Atukuri Molla

Atukuri Molla, a Telugu poet, composed the *Rāmāyaṇa* in Telugu, now known as the *Molla Rāmāyaṇam.* Her father was a potter in Gopavaram, a village in Badvel Mandal, Andhra Pradesh. She also recited the *Rāmāyaṇa* at the court of Kṛiṣhṇadevarāya.

Some Bhakti saints left their homes and devoted themselves entirely to the divine. Akkā Mahādevi (from present-day Karnataka) and Lāl Ded (from present-day Kashmir), both Shaivites, renounced worldly comforts and attachments, living as ascetics. In contrast, Bahināībāi, a saint from Maharashtra, fulfilled her familial duties while following the path of devotion to the deity Vithoba.

Northern and Central Region

- Lāl Ded
- Guru Nānak
- Rāmānanda
- Kabīr
- Mīrābāī
- Rāidāsa
- Vallabhāchārya
- Sūrdās
- Tulsīdās

Eastern Region

- Jayadeva
- Chaitanya Mahāprabhu
- Krittibāsa
- Mādhava Kandalī
- Sankardev

Southern Region

- Basavannā
- Mādhavāchārya
- Annamāchārya
- Pothanā
- Poonthanam Namboothiri

Western Region

- Ekanātha
- Jñānadeva
- Muktābāī
- Nāmadeva
- Janābāī
- Chokhamelā
- Narasimha Mehtā
- Bhalana
- Pīpājī
- Tukārām

Fig. 3.19. Some prominent Bhakti Saints from 12th–17th centuries

© NCERT not to be republished

LET'S MAP

On a map of India, locate and label the present-day states associated with the saints mentioned in the above infographic. Also, find and mark a saint from your own state who is not on the list. Are you familiar with any songs, poems, or verses composed by these saints? Share with the class and explain what it means or what you like about it.

THINK ABOUT IT

***Vakh* (*vachan* or saying) of Lāl Ded**

To learn the scriptures is easy, to live them, hard.
The search for the Real is no simple matter.
Deep in my looking, the last words vanished.
Joyous and silent, the waking that met me there.

Fig. 3.20. Translation of a vakh composed by Lāl Ded

Lāl Ded says that it is 'easy' to learn scriptures but 'hard' to live them. What is the difference between knowing a rule and actually following it? Can you give an example from your daily life?

During this period, many devotees from diverse backgrounds contributed to the Bhakti traditions. Syed Ibrāhim Khān, popularly known as Raskhān, from present-day Uttar Pradesh, wrote in Braj and is known for his compositions like *Prem Vāṭikā* and *Sujān Raskhān*. Abdul Rahīm Khān-i-Khāna, popularly known as Rahīm, a Mughal military commander, wrote poetry in Braj to express his devotion to Kṛiṣhṇa. Bibi Lachimar (of Turkish origin) devoted herself to the Bhakti of Viṣhṇu.

DON'T MISS OUT

Worship of goddesses was a long-standing tradition in India, and during the period under study, kings continued to invoke goddesses such as Kālī, Durgā, Bhavānī, and other forms of Shakti as protectors in times of conflict. Annamarājā, ruler of Bastar kingdom, is believed to have received his sword from Mānikyadevī (Danteśhvarī), while Kumāra Kampana was believed to have used a goddess-given sword against the Sultanate forces at Madurai. Similarly, Śhivājī is also believed to have received a sword from the goddess Tuljā Bhavānī to resist the Mughals.

© NCERT not to be republished

Fig. 3.21. A Mughal painting depicting Akbar worshipping the Sun

Sulh-i-Kul

During the later part of Akbar's reign, the philosophy of *Sulh-i-kul* was adopted as a state policy. It represented 'peace with all', 'universal toleration', or 'absolute peace'. This policy had political implications, as it appears to have been intended to secure the support of political powers other than Muslims. Over time, Akbar also began to distance himself from certain orthodox elements and adopted practices that included reverence for the Sun. The Mughal state adopted a relatively inclusive approach during the later part of his reign.

Within the Indian religious, spiritual, and philosophical landscape, the Bhakti tradition emerged as a transformative force. It spread across the Indian subcontinent, taking distinct forms in different regions and social contexts. It played a crucial role in shaping and preserving India's spiritual landscape and social fabric.

DON'T MISS OUT

Sufism began to expand in the subcontinent with the arrival of the Turks. It was a mystical dimension of Islam that generally adopted a comparatively liberal outlook towards the world. It emerged in West Asia as a form of spiritual response to the worldly orientation of some *Ulema* (Islamic theologians and jurists) and the orthodoxy of *Shariat* (Muslim jurisprudence and law). Sufism spread through various orders, or *silsilahs*. During the Delhi Sultanate, the Chishti and Suhrawardi orders became prominent, while under the Mughals, the Qaddiriyya and Naqshbandiya orders gained importance. Sufi *khanqahs* (hospices) and shrines developed as centres of popular religious life and also played a role in social and political affairs. Sufis also contributed to the spread of Islam. In India, Sufis adopted many local practices to connect with the wider population, including using Indian languages such as Hindavi and Bengali. Some Sufis also incorporated yogic practices, such as *prāṇāyāma*, known in Persian as *habs-i-dam*.

© NCERT not to be republished

Temples: The Resilience of Sacred Sites

Temples functioned as central pillars of the region's socio-economic and political life. These religious institutions evolved into major economic hubs that managed extensive land grants, provided employment to hundreds of specialised workers, and served as financial institutions for local traders. Rulers used temple patronage to strengthen their political legitimacy. Beyond their spiritual and religious functions, temples facilitated social integration and served as centres of education and culture, where artistic traditions such as Bharatanatyam and many other art forms were preserved. They also exercised quasi-judicial authority, collecting local taxes and administering legal penalties.

Temples also served as sources of legitimacy for political authority. The deities of these temples were regarded as protectors of the state and its people. In some cases, the deity was regarded as the ruler, while the actual ruler governed as the deity's deputy. For example, the Gajapati rulers of Odisha called themselves the *Rauta* (deputy) of Jagannath. Similarly, the Kachhwāhā rulers of Jaipur governed on behalf of Govindadevajī, while the Rajput rulers of Kota regarded themselves as representatives of Rāma.

Temples in India also functioned as significant economic institutions. They provided employment to a wide range of groups, including architects, artisans, sculptors, priests, musicians, and administrative staff. As substantial landholders, temples received donations, endowments, and land grants, often given as acts of

Fig. 3.22. Sri Ranganathaswamy Temple, Srirangam

© NCERT not to be republished

Fig. 3.23. Brihadeeswara Temple, Thanjavur

religious merit. The Brihadeeswara (Rajarajeshvara) temple at Thanjavur exemplifies this, having received extensive donations of gold, ornaments, and vessels. This wealth enabled temples to support irrigation works and agrarian development, reinforcing their role in economy and the society. Temples also extended credit to cultivators, village assemblies, and merchant groups. This convergence of economic and religious activity contributed to the emergence of temple towns such as Thanjavur, Kanchipuram, and Puri, as prominent urban centres.

Between the 7th and 13th centuries, temple construction proliferated across the subcontinent under the patronage of various dynasties. However, from the 11th century onwards, we begin to see many instances of temple destruction, particularly during the Ghaznavid and Ghurid invasions. From the 12th century onwards, many temples and *maṭhs* were not only plundered or destroyed, but mosques were also sometimes constructed on the same sites.

While there were instances of the destruction of sacred sites, local rulers, merchant guilds, and religious communities actively maintained and restored temples during this period, allowing sacred centres to continue functioning. Local rulers who negotiated alliances with the central authority were generally allowed to build major structures. A royal temple built by Vīra Someśhvara at Kannanur, an earlier Hoysāla regional capital, was converted into a

© NCERT not to be republished

Fig. 3.24. Kashi Vishwanath Temple, Varanasi

mosque under the Sultanate rule before being restored as a temple by Kumāra Kampana. Further examples of temple construction and restoration include the reconstruction of the Kashi Vishwanath Temple by Toḍar Mal, revenue officer of Akbar, and Rājā Mān Singh, chief of the Rajput Kachhwāha family (the temple was later demolished during the reign of Aurangzeb. The present temple was built by Ahilyābāī Holkar adjacent to the original site in 1780). The latter also patronised the construction of the Govind Devji Temple at Vrindavan, one of the largest temples built in northern India during this period. The Bundela king, Vīr Singh, patronised the construction of the new Keshav Dev Temple at Mathura.

From the 16th century onwards, a shift can also be seen in the design and location of Indian temples. Temples built during this period were often situated in less visible locations, along narrow lanes, with entrances that did not open onto main streets. Many lacked the conventional appearance of temples, and instead, resembled ordinary houses. Detailed exteriors became less common, and tall *shikharas* were frequently avoided. This pattern is captured in the term 'havelī temple', used by some historians to describe temples constructed in the style of *havelī* residences.

It reflects how communities adapted temple architecture to avoid destruction. Such examples can be found in Delhi, Varanasi, and Rajasthan, including the Jagat Shiromani Temple.

© NCERT not to be republished

The Jagat Shiromani Temple, also known as Mīrābāī Temple, was built by Queen Kanakwati, wife of Mān Singh I, in Amer. The temple is dedicated to Kṛiṣhṇa and Mīrābāī.

Fig. 3.25. Jagat Shiromani Temple, Amer

DON'T MISS OUT

Jagat Singh challenged the Mughal authorities through his architectural projects. In addition to fortifying Chittor, he built a large Jagdish temple near his palace in Udaipur. Scholars suggest that the temple was a religious and political response to the Jama Masjid constructed by Shah Jahan in Delhi.

Fig. 3.26. Jama Masjid, Delhi

Fig. 3.27. Jagdish temple, Udaipur

Indian Economy: Agriculture, Trading Networks, and Merchant Communities

The expansion of the agrarian economy and the gradual proliferation of centres of artisanal and craft production were significant developments of the early second millennium CE.

© NCERT not to be republished

The main source of state income was land revenue, and the expanding frontiers of empires resulted in an increase in the area under cultivation. Over time, the collection of land revenue became increasingly strict and exploitative at various levels of administration. For example, during the reigns of Alauddin Khiljī and Mohammad bin Tughlaq, the land tax was raised to as much as 50 per cent of total agricultural production, in addition to other taxes. Moreover, the Sultans of Delhi, and later the Mughals had limited role in maritime trade. Their concerns regarding coastal areas and port cities were largely confined to political and military matters and, to some extent, the collection of customs duties. As a result, coastal areas and their commerce remained largely in the hands of regional power holders and local communities.

Irrigation technologies such as rope pulleys, spinning wheel, and Persian wheel were widely used by local populations, resulting in enhanced agricultural and economic output. In the Vijayanagara Empire, agricultural production varied greatly in both form and scale. Consequently, irrigation systems ranged from extensive canal networks to small rain-fed patches of land. A defining feature of the Vijayanagara economy was its investment in small-scale irrigation.

DON'T MISS OUT

During this era *hunḍī* was widely used as a financial instrument and can be compared in some respects to modern bank cheques. It functioned as a bill of exchange, facilitating large-scale commercial transactions without the need to carry large amounts of currency. It was also a trusted means of secured long-distance remittance. *Hunḍīs* were operated through networks of money-changers known as *sarrāfs* and their agents, called *gumasthas*.

Fig. 3.28. A hunḍī stamped by the Bank of Bengal, Agra, with a denomination of one rupee and eight annas

© NCERT not to be republished

THINK ABOUT IT

What do you think made *hunḍī* a safer and more convenient choice than physically transporting money across long distances?

Fig. 3.29. A painting of a sarrāf or money changer

In addition to agricultural expansion, the period witnessed significant growth in trade and commerce. India's inland regions were connected to trade routes in Central Asia, facilitating a substantial flow of goods and artisanal knowledge, much of it carried by large groups of traders known as caravans. Inland trade networks expanded alongside the growth of urban centres. Local trading communities such as the *banjārās*, along with revenue-collecting officials, played a crucial role in connecting rural regions with urban centres.

From the 13th century onwards, seaborne trade grew significantly, with trading networks linking western India to the Persian Gulf and the Arabian Sea. Gradually, India became a major centre of the Indian Ocean trading network, with the eastern Mediterranean and China forming its vital axes until the arrival of Europeans in the subcontinent.

DON'T MISS OUT

Kṛiṣhṇadevarāya, the Vijayanagara ruler, greatly emphasised in his *Amukthamālyadā* the importance of oceanic trade, maintenance of ports, and fair treatment of foreign traders. He writes,

> *Manage your ports well, and let commerce increase in horses, elephants, and gems, pearls, and sandal-paste. When drought, sickness, and calamity make foreigners seek refuge in your lands, shelter them in keeping with their station. Give out gardens, yards, and mines to those whom you wish to favour...*

Fig. 3.30. A translated excerpt from the Amukthamālyadā

© NCERT not to be republished

The World of the Indian Ocean: Continuity and Change

With the turn of the 16th century, two major developments occurred—the arrival of Europeans for trading ventures and the Mughal conquest of northern India. The Europeans, particularly the Portuguese, and the Mughals entered an already established economic system in which local institutions and networks played a crucial role. The Portuguese attempted to establish greater control over oceanic trade and commerce, while the Mughals sought to centralise control over the land revenue system. European involvement, which began with the Portuguese and was later followed by the Dutch, English, Danes, and French, developed into a complex system of interactions between European trading companies and Indian merchant networks. Subsequently, the Indian subcontinent became a major global intersection of commerce and cross-cultural exchange.

Simultaneously, new merchant groups emerged in coastal and hinterland areas. They controlled wealth, production system, supply chains, and at the same time, funded states and supported their political allies. The peasantry was involved in the production of raw materials, while weavers, dyers, bleachers, and other groups were working regularly to ready the deliveries of cotton textiles. Before the 15th century, the Indian Ocean trading network had a huge presence of Arab, Chinese, and Indian merchants. In subsequent centuries, Gujarati merchants in particular emerged as significant

Fig. 3.31. A painting of a woman weaver

© NCERT not to be republished

beneficiaries of the changing commercial order. Alongside them, numerous merchant groups flourished in Malabar, Coromandel, and Bengal, adapting to the growing influence and competition of the British, Dutch, and French.

These merchant groups were not merely involved in the buying and selling of goods, but were closely connected to the political economy, facilitating and financing trade. Indian merchants functioned as traders, shippers, bankers, money-changers, brokers, *dubhaśhīs* (interpreters and translators), diplomats, and bureaucrats.

Mercantile activities were not limited to a few, select communities. For instance, *vellalār*, who were traditionally agriculturists and pastoralists, participated in the Indian Ocean trading network in various capacities. From the 16th century onwards, many peasant groups began to participate actively in commerce. Some of them even learnt new languages, including Portuguese, French, English, and Persian, to facilitate their commercial activities.

THINK ABOUT IT

Identify some cultural and economic pillars that exist in any community (places of faith, traditions, business, and trade, etc.). How do you think these contribute to resilience within a society facing invasions/external pressures?

Between 1000 and 1700 CE, despite frequent invasions, shifts in political authority, and unrest, the Indian economy remained dynamic. The economy was driven by adaptations of agricultural innovations and irrigation systems, markets, powerful merchant groups, advanced financial instruments like the *hunḍī*, and India's pivotal position in transcontinental Indian Ocean trade. This economic strength contributed to resilience and stability, giving people the resources they needed to resist politically and culturally. Thus, this period is best understood as a complex interplay of conflict and cooperation, defined by the deep interconnection between resistance and resilience. The Rajputs, Ahoms, Vijayanagara rulers, Marathas, Sikhs, and Jats, including many others, consistently defended their lands and identities. To safeguard their sovereignty, they used a strategic mix of direct military resistance, highly adaptive guerrilla warfare, knowledge of local terrains, diplomacy, and alliances.

© NCERT not to be republished

The resilience of Indian civilisation extended far beyond the battlefield to preserve its socio-cultural continuity.

Before we move on...

- Resilience is the ability of individuals, communities, and societies to endure difficulties, adapt to changing circumstances, and sustain their way of life despite challenges.
- Cultural traditions, shared beliefs, community support, knowledge, and economic resources can strengthen resilience.
- Resistance means actively opposing or challenging a force, authority, or threat, in order to protect political power, territory, interests, or cultural identity.
- Resistance may take the form of warfare, alliances, diplomacy, negotiation, or other political actions.
- The Bhakti tradition demonstrated resilience by adapting devotional practices, using local languages, encouraging community participation, and preserving traditions even when circumstances changed.
- Economic strength, through agriculture, irrigation, markets, merchant networks, financial practices, and trade, also contributed to resilience by providing resources that helped communities withstand periods of instability.
- The period from 1000 to 1700 CE was not simply a story of invasions and battles. It was also a story of how people resisted threats, adapted to changing circumstances, preserved their cultural identities, and built new forms of cooperation and exchange.

© NCERT not to be republished

Questions and activities

1. Choose the most appropriate answer.

   Resistance and resilience are closely connected because:

   a. Resistance always involves warfare.

   b. Resilience enables communities to endure difficulties and sustain resistance.

c. Resistance is possible only when a kingdom has a large army.

d. Resilient societies avoid all forms of conflict.

2. Why and how did groups such as the Sikhs, Marathas, and Rajputs assert their political power and identity during periods of changing political authority?

3. Why did some Rajput rulers decide to negotiate alliances with the Mughal power?

4. Imagine a market in a port town of India such as Surat, Masulipatnam, or Puducherry. You are a foreign trader from Italy or France and want to make a deal of cotton textiles. How would you secure the product in the local market? Whose help would you seek and what kind of challenges would you face in terms of language, quality of product, prices of commodities, etc.?

5. Watch any video at the given link (*https:// www.indianculture.gov.in/forts-of-india/tales-of-forts*) and analyse the various functions of forts and fortresses. How did rulers perceive the importance of forts in terms of strategic concerns.

6. What architectural changes occurred in temple construction during the period under study? How do these changes reflect upon the resilient nature of Indian civilisation?

7. A kingdom has limited military resources but possesses fertile agricultural land, strong local support, and detailed knowledge of its terrain.

   Explain two ways in which these resources could contribute to the kingdom's resilience when faced with a threat.

8. Consider the following statement:

   "A tradition becomes more resilient when people can carry it with them."

   Do you agree? Explain using examples from the Bhakti tradition.

9. Voices from the Past

   Choose any two of the following and write a short first-person account explaining what resilience means from that person's perspective:

   - A Bhakti saint
   - A Rajput soldier

© NCERT not to be republished

- An Ahom commander
- A Maratha administrator
- A merchant
- A Jat leader

10. Design a Fort

You are a military architect advising a ruler.

Draw a simple, labelled plan of a fort that includes the following:

- Residential complex
- Defensive walls
- Water source
- Food storage
- Escape route
- Watchtower
- Administrative area

Now, write a few sentences explaining how your design would help the kingdom withstand a long siege.

Notes

© NCERT not to be republished

© NCERT not to be republished

Chapter 4
Governance and Public Policy

The Big Questions

1. *What is governance, and how have its meaning and practice evolved over time?*
2. *What is public policy? How does it affect our day-to-day lives, and what makes it 'public'?*
3. *What are the various stages of policy-making and policy implementation?*
4. *Who are the major contributors to policy-making and implementation?*
5. *What role do citizens play in shaping public policy and strengthening good governance?*

0909CH04

© NCERT not to be republished

In the chapters 'Democracy' and 'Elections', we learnt that democracy is a system of self-governance that involves institutions, rules, and practices that enable people to participate in decision-making. However, in a well-functioning democracy, it is not enough to participate only in elections to form the government. A robust democracy requires transparent institutions, responsible representatives, and the continuous participation of people in public life.

Governance

Governance in a democratic system is based on transparency, accountability, participation, and the rule of law. Democratic governance places citizens at the centre of the political process. It is more people-centric and welfare-oriented.

LET'S EXPLORE

Let us see how a government and citizens come together to address various challenges.

Imagine that your town experiences several days of unusually heavy rainfall. Roads become flooded, schools remain closed,

electricity is disrupted in some areas, public health concerns rise, and many people find it difficult to reach schools, workplaces, or even hospitals. During such situations, organisations and individuals come together to help all in need.

The municipal corporation clears drains and removes garbage. The Public Works Department repairs damaged roads. The police manage traffic. School authorities inform parents that schools will remain closed. Health workers prevent the spread of diseases. Local representatives raise people's concerns, while residents volunteer to help vulnerable neighbours and report on flooded areas. The situation improves with collective efforts of all.

Form groups and discuss the following.

- → Who are the different people and organisations involved in dealing with this situation?
- → Why cannot a single department solve the problem on its own?
- → What would happen if these departments did not communicate or coordinate with one another?
- → What role can citizens play before, during, and after the heavy rainfall?
- → What makes the collective response effective?

Fig. 4.1. Collective response to resolve the crisis

Share your ideas with the class. Make a list of the qualities that help the town respond effectively. These qualities are essential whenever governments and society work together to solve public problems.

© NCERT not to be republished

Solving public problems requires much more than a government issuing orders. Different institutions and citizens need to work together, make decisions, implement them effectively, and remain accountable. This process is known as **governance.**

Understanding Government and Governance

Government	Governance
Refers to the institutions that exercise political authority	Refers to the process of decision-making and implementation
Includes the Legislature, the Executive, and the Judiciary	Includes government, citizens, media, civil society, and private organisations
Focuses on who governs	Focuses on how governing is carried out

The terms 'government' and 'governance' are closely related. However, they are not synonymous. Government refers to the institutions and authorities that exercise political power, while governance refers to the process by which decisions are made, implemented, and monitored in the public interest. The government formulates and implements people-centric policies, and good governance ensures that these policies are transparent, accountable, effective, and responsive to people's needs. Governance is the system through which decisions are made, implemented, and monitored for the welfare of the people. It refers to the way a country, state, city, village, school, or organisation is managed. Therefore, understanding governance is essential to know how government impacts our lives.

LET'S EXPLORE

Government refers to the institution that has the authority to provide public services. For example, the municipal corporation or panchayat is responsible for installing street lights. Governance is the process by which this street lighting is planned, implemented,

© NCERT not to be republished

and maintained, involving people in identifying dark spots, reporting non-functional lights, and providing feedback.

It ensures the continuous delivery of public services—in this case, well-lit streets and greater public safety.

Can you identify more such examples from your day-to-day life to understand the difference between government and governance?

Evolution of Governance in India

In the previous section, we studied that while the government is the institutional aspect, governance refers to its functional aspect. The government's institutional setup influences the nature of governance, and governance initiatives, in turn, require institutional adaptations to implement policies and schemes.

We are familiar with the structure of government at different levels in India. But the same structure has not always existed as it does now; it has evolved from certain historical experiences. Let us understand this historical context by looking at the 'big picture' of the world history.

Do you remember the phenomenon of colonialism that you learnt about in Grade 8? We know that European powers colonised many societies, particularly those in Asia, Africa, and the Americas. Before colonial rulers forced their own models of governance and policy-making on colonised people, these societies governed themselves in accordance with local and organic systems. Although most colonies had become independent by the end of the 20th century, colonial institutions largely persisted, and their structures continued to dominate even in contemporary times. India is not an exception to the historical legacy of colonialism. However, India stands out in two important ways. Firstly, unlike many societies that experienced colonial rule, India has preserved most of its knowledge of its pre-colonial institutions and traditions of governance through texts and practices. Secondly, after Independence in 1947, it was not possible to replace all colonial institutions at once. The leaders of independent India therefore framed the Constitution in the spirit of India's own values and ideals.

Since Independence, Indian institutions have continued to draw upon traditional ideas and values of governance and have adapted them to the needs of a modern democracy. For example, the British 'Order of the Star of India' used the phrase, 'Heaven's Light, Our Guide' as its motto but after Independence, we have adopted '*Satyamev Jayate*'

© NCERT not to be republished

(Truth alone triumphs), from the *Muṇḍaka Upaniṣhad* as our national motto. This reflects the continuing importance of Indian ethical values in public life. The motto of the Supreme Court of India was chosen to be '*Yato Dharmastato Jayaḥ*'. This phrase is taken from the *Mahābhārata,* and it means 'Where there is *Dharma* (righteous duty), there is victory'. These changes are not just symbolic or superficial. They signify the core values as well as the ideals of our institutions, which have been bestowed along with the responsibility of ensuring good governance.

LET'S EXPLORE

The *Sengol*—a cultural marker of rulership and good governance—was placed in India's newly inaugurated Parliament building in the year 2023 by Prime Minister Narendra Modi. The tradition of using the *Sengol* as a mark of righteous governance began more than a thousand years ago during the reign of Chola dynasty. To mark the occasion of India's Independence, at the stroke of midnight on 15th August 1947, the first Prime Minister, Jawaharlal Nehru, received the *Sengol* from the Adheenam Saints (an old Shaivite tradition) of Tamil Nadu. Try to find out more about the journey of the *Sengol* through its historic pictures.

Fig. 4.2. Sengol

Mahatma Gandhi visualised an ideal model of governance as *Rām Rājya. Rām Rājya* is rooted in the principles of probity, transparency, compassion, welfare, and people-centric orientation in governance and public policy. Gandhi's views on *Rām Rājya* reflect the collective imagination of Indians, from their distant past to the present day, that *Rām Rājya* is one of the best examples of good governance and a good collective life, as enshrined in the *Rāmāyaṇa* and the sixteenth-century text of *Rāmcharitamānas.*

From the Vedic period to the *Rāmāyaṇa* and the *Mahābhārata,* Indian tradition has consistently viewed governance as a sacred responsibility rather than merely a means of exercising power. *Rājadharma,* the foremost duty of an ideal king, was to protect the people by upholding *Dharma* (righteous duty) and promote the welfare of society. Good governance was measured not only by the ruler's authority but by the peace, prosperity, justice, and well-being in society. Kauṭilya's *Arthaśhāstra* says the following:

© NCERT not to be republished

प्रजासुखे सुखं राज्ञः प्रजानां च हिते हितम्

Prajāsukhe sukhaṁ rājñaḥ prajānāṁ cha hite hitam

(In the happiness of the people lies the happiness of the ruler, and in the interest of the people lies the interest of the ruler.)

LET'S RECALL

You have read in the first part of this textbook that the *Ṛigveda* refers to the *Sabhā* and *Samiti* as important institutions where matters of governance and public welfare were discussed.

Good Governance

Governance affects many aspects of our daily life. It helps maintain law and order so that people can live safely and peacefully. It protects the rights and freedom of citizens, which are essential in a democratic society. It also helps people access important public services, such as education, healthcare, transport, and so on.

Good governance promotes justice and fairness and ensures that people are treated equally before the law. It also helps build trust between citizens and the government.

Governance is the government's responsibility, but good governance depends on how different sections of society and government perform their responsibilities and work with one another. For example, the government makes laws and policies and provides public services. Citizens elect their representatives, follow the law, and participate in public life. The media helps people understand public issues and brings important matters to public attention. Civil society organisations work with communities and raise awareness about social concerns. The private sector contributes through economic activity and innovation.

Therefore, features of good governance include responsiveness, transparency, participation, the rule of law, accountability, effectiveness, and inclusiveness.

When people and institutions perform their responsibilities honestly and work together, governance becomes more effective and public welfare is achieved.

© NCERT not to be republished



Fig. 4.3. Features of good governance

LET'S EXPLORE

Select two cities (one should be from a region other than yours) in India that have received awards for being the cleanest city. Make a visual presentation (chart paper or slideshow) to explain the 'good governance model' used in those cities by looking into the role played by government agencies (local, state, and national), residents, market associations, civil society organisations, etc. Also look into the steps they are taking to continue being clean cities.

not to be republished

LET'S EXPLORE

Form pairs or groups and assign one State or Union Territory to each group. Prepare a short classroom discussion paper on:

1. Good governance initiatives being implemented.
2. Suggestions for further improving governance.

Challenges to Good Governance

The task of governance is always ongoing. With time, the needs, desires, and aspirations of people also evolve, creating new challenges to which the government and the institutions have to respond. For example, weak coordination between different institutions and departments can affect the implementation of government programmes. At the same time, unequal access to public services can leave some groups or communities behind, particularly those who face social, economic, geographical, or other barriers. Malpractices and misuse of public offices can prevent resources and benefits from reaching the people. Misinformation and fake news also pose a serious challenge to good governance. Addressing these challenges requires effective institutions, responsible officials, active citizens, and a continued commitment to the principles of good governance. The initiative of e-governance has contributed significantly towards good governance. Let us understand details about e-governance in the following section.

LET'S EXPLORE

Did you know that 25th December is celebrated as National Good Governance Day? Can you find out why this date was chosen? How is National Good Governance Day celebrated in your district? Discuss in your class.

E-Governance: Technology for Better Governance

Today, digital technology has changed the way the government interacts with people. **E-governance** refers to the use of information and communication technology by governments to provide public services, share information, communicate with citizens, receive feedback, and improve administrative processes. It can make

© NCERT not to be republished

governance more transparent, accessible, and convenient and quick for the citizens. E-governance substantially reduces paperwork and allows people to access services without visiting government offices.

LET'S EXPLORE

Below is a chart of a few e-governance initiatives. Complete the chart and also add two such initiatives undertaken by your state government.

Initiative	Objective
UMANG	
Aadhaar	
GeM (Government e-Marketplace)	
DigiLocker	
CPGRAMS	
APAAR	

E-governance is particularly valuable in a large country like India, as it enables governments to deliver public services more efficiently, transparently, conveniently, and quickly to citizens across vast geographical areas.

However, e-governance is only effective when people have access to digital devices, reliable internet, and the skills needed to use them. Therefore, while technology can strengthen good governance, the government must also ensure that digital services remain inclusive and accessible to everyone.

© NCERT not to be republished

LET'S EXPLORE

Let us try to understand the quality of life of citizens before and after e-governance. Form five groups and interview your seniors, teachers, security guards, administrative staff, and parents regarding the issues listed below. Did they have access to the internet and a smartphone or computer to make use of these e-governance facilities? Find out what problems they had faced before e-governance and whether they felt the same issues were easily handled after e-governance.

1. Obtaining a birth certificate
2. Obtaining a admit card
3. Collecting and storing marksheets
4. Receiving salary
5. Booking rail/flight tickets
6. Registering a vehicle

So far, we have understood that governance is the process through which decisions affecting people are made, implemented, and monitored with governments, institutions, both public and private, and citizens playing an active role in the process. But governance ultimately needs concrete instruments to address public problems and meet people's needs. Public policy provides that link; it translates governance into planned action by turning public concerns and government priorities into programmes, decisions, and solutions.

Public Policy

The Meaning of Public Policy

Every day, we experience the impact of public policies, often without even noticing it. The roads we travel on, the traffic signals that help us cross safely, the clean drinking water supplied to our homes, the electricity that lights our classrooms, the public parks where we play, and the waste collected from our neighbourhood are all examples of public services made possible through public policies. These policies help make our daily lives safer, healthier, and more convenient.

Suppose your school notices that many students bring single-use plastic bottles and wrappers in their lunchboxes and schoolbags

© NCERT not to be republished

every day. As a result, a large amount of waste is generated, and the campus becomes dirty, leading to environmental degradation in the long run. To address this problem, the principal discusses the issue with teachers, students, and parents. Together, they decide to introduce a 'Plastic-Free Campus Policy'. Under this policy, students are encouraged to carry reusable water bottles; plastic bags are discouraged; dustbins for waste segregation are placed around the campus; monthly awareness programmes are organised; and teachers are assigned with the responsibility of monitoring the campaign. These decisions form a policy because they provide a planned course of action to solve a problem and achieve a sustainable goal.

Similarly, governments make public policies to address problems that affect society as a whole. Public policy is a result of a course of action adopted by the government to solve public problems, meet people's needs, and promote the welfare of society. Through this course of action, governments decide what should be done, why it should be done, who will do it, how it will be implemented, and how its success will be measured. Further, public policy is monitored and evaluated through a feedback loop, and necessary changes are made to the policy if required.

What is 'Public' about Public Policy?

The word 'public' refers to all the people living in a society or community. A policy becomes public policy when it is made for the public benefit, implemented by public institutions, and often financed with public money collected through taxes. Public policies address issues that concern society as a whole, such as education, healthcare, transportation, sanitation, environmental protection, and public safety.

Public policy is about responding to the needs and aspirations of the people. Therefore, people play an important role in shaping them. People identify issues, express their concerns, participate in consultations, provide suggestions, and share feedback after a policy is implemented. Governments use this feedback to improve policies over time.

© NCERT not to be republished



Fig. 4.4. Public policy: What makes it 'public'?

However, not every policy is a public policy. Schools, companies, hospitals, sports clubs, and even families often have their own policies to guide the way they function. For example, a school may have a policy on the use of mobile phones, a company may have a work-from-home policy, or a housing society may have rules for parking vehicles. These policies apply only to a particular organisation or a limited group of people. Public policies, on the other hand, are formulated by governments to address issues that affect society on a larger scale.

LET'S EXPLORE

Read each of the following examples carefully. Identify whether they are a **policy** or a **public policy**. Give a reason for your answer.

Example	Policy/ Public Policy	Why?
The government introduces a sports policy.		
The government launches a campaign to provide safe drinking water to every household.		

© NCERT not to be republished

Example	Policy/ Public Policy	Why?
A company allows employees to work from home twice a week.		
A municipality introduces waste segregation in the city.		
A housing society fixes visiting hours for guests.		
The government introduces free vaccination for children.		

Participants in the Public Policy Process

Have you ever wondered who decides whether new schools are to be built, roads are to be repaired, and taxes are to be decreased or increased? Is it only the government? No, it takes the combined efforts of many individuals, organisations, officials, and even ordinary citizens in identifying issues, providing solutions, and putting them into action.

© NCERT not to be republished

Table 4.1. Key Stakeholders in Policy-making and Implementation

Contributors	What do they do?	Example
Citizens	Identify problems, vote, participate, give suggestions, and provide feedback.	Residents request a zebra crossing near a school.
Elected representatives (MPs, MLAs, and local representatives)	Represent people, raise public issues, participate in law-making, and approve budgets.	An MLA raises the issue of drinking water shortage in the Assembly.
Government officials, departments, and ministries (Central, State and Local Governments)	Prepare and implement policies and programmes, coordinate departments, deliver public services, and monitor their progress.	A district collector coordinates the implementation of a government scheme in the district.
Civil society organisations, NGOs, experts, researchers, and the media	Study problems, suggest solutions, create awareness, monitor programmes, and provide feedback.	An NGO conducts a water-conservation campaign, and the media highlights pollution concerns.
Private sector	Facilitate technical know how, innovation, resources, and expertise, often working with the government.	A company installs solar panels in government schools through a public-private partnership.
International organisations	Bring in international experience, facilitates technical know how and financial support.	The World Health Organization (WHO) assists countries in controlling infectious diseases.

© NCERT not to be republished

LET'S EXPLORE

Your school's main gate faces a road that connects residential areas and a major market area. There is heavy traffic congestion on the road, especially during morning and afternoon hours. Pedal rickshaws, electric rickshaws, school buses, private vehicles, and pedestrians—all struggle to get their way.

Form groups in your class and choose a course of action from the options given below.

1. Form a group of volunteers to regulate traffic in rush hours.
2. Write an application to the principal about the issue.
3. Meet the principal, along with all the class representatives of the school, to discuss the gravity of the situation and then impress upon the principal the need to take up the issue with the local people's representative so that a traffic signal can be installed.
4. Request the school management to construct and open another gate on the other side of the school.
5. Suggest that the school shift its pick-up and drop-off point to a location slightly away from the main gate.
6. Change school timings so that the school's opening and closing hours do not coincide with the busiest traffic hours in the market.

Answer the following based on the information given above.

→ Which option did you choose and why?

→ Can you suggest a better solution to address the given problem? Compare your suggestion with other options.

© NCERT not to be republished

→ Which stakeholders would be involved in solving this problem in your suggested solution? Explain their role in solving the problem.

→ Suggest a feedback loop to ensure that the problem does not recur.

Case Study—A Ramp to Better Healthcare

Smt. Shanti Devi, a 72-year-old woman, visits the hospital for a health check-up. On arriving the hospital, she finds that she has to climb stairs to reach the Outpatient Department (OPD). There is no ramp or handrail to support her. At the same time, a man in a wheelchair arrives but is unable to enter the building because the entrance has only steps, with no wheelchair-accessible ramp. A visually impaired person may be able to climb the steps to enter the hospital but finds it difficult to locate different hospital departments because there are no tactile paths or Braille signs.

Many patients and their family members realise that the hospital infrastructure is not accessible to everyone. They decide to raise this issue with the hospital authorities and local representatives. A local disability rights organisation also highlights the problem through newspapers and social media. The district administration takes note of the issue and asks the Public Works Department (PWD) and the Health Department to inspect the hospital. After consulting doctors, hospital staff, architectural experts, organisations working with persons with disabilities (PwDs), senior citizens, and residents, a plan is prepared to make the hospital more accessible. The government approves the funds needed to construct ramps, lifts, handrails, tactile pathways, and accessible toilets, and to install clear signboards. Once the work is complete, the hospital becomes easier to use for older persons, persons with disabilities, pregnant women, patients, and children.

© NCERT not to be republished

This is an example of how a public policy moves from identifying a problem to implementation.

LET'S EXPLORE

Read the case study and follow the journey of the issue from identifying the problem to implementing a solution. As you read, identify the problem, the people and institutions involved, the actions taken, and the steps through which the solution was developed and implemented. Then, answer the questions below:

1. Arrange the various stages of the policy process in sequence for upgrading the hospital to be more patient-friendly.
2. Which stakeholders were involved in solving this problem? Identify at least three.
3. Can you think of any public building in your locality that could be made more accessible? What improvements would you suggest?

The Making of a Public Policy

A public policy is developed through a systematic process rather than a single decision. It usually begins when citizens, government officials, researchers, or civil society organisations realise that a new need has to be met, an existing problem has to be resolved, or a facility has to be made better in the interest of the people. Then the government studies the issue, collects information, and consults experts, stakeholders, and the public to understand different viewpoints and possible solutions. Based on these discussions, the government authorities prepare, review, and approve a draft policy. Once the policy is approved by the concerned authorities, it is translated into programmes and schemes, which provide a clear framework for different ministries, departments, and local governments to take specific action. The implementation of any policy is continuously monitored and evaluated to assess whether it is achieving its objectives. Feedback from citizens and other stakeholders is used to improve the policy over time. Thus, public policy is a continuous cycle of problem identification, consultation, policy formulation, implementation, monitoring, evaluation, and improvement. This process helps the government respond effectively to the changing needs of society.

© NCERT not to be republished

Fig. 4.5. Exemplar of a policy cycle

© NCERT not to be republished

DON'T MISS OUT

National Education Policy (NEP) 2020: A Collaborative Journey

The National Education Policy (NEP) 2020 is an excellent example of how public policy is developed through consultation, expert advice, and public participation. India's previous National Policy on Education was introduced in 1986.

Over time, society changed rapidly. These changes created a need to rethink India's education system.



Recognising this need, the Government of India initiated the process of developing a new education policy in 2015. For drafting this policy, the government set up an expert committee in 2017, which was chaired by renowned scientist Dr K. Kasturirangan. The committee included experts from education, science, technology, social sciences, and public administration. A unique feature of NEP 2020 was the large-scale public consultation. The draft policy was made available for feedback by citizens and all stakeholders. During the formulation of the policy, 2.5 lakh Gram Panchayats, 6600 blocks, 6000 Urban Local Bodies, and 676 districts were consulted, and about 2 lakhs suggestions were received. The expert committee carefully examined the suggestions. Several recommendations from citizens and institutions were incorporated before the final policy was prepared. After discussions within the Government of India, the National Education Policy 2020 was approved by the Union Cabinet in July 2020.

Stakeholder Role-Play

Divide the class into groups. Each group represents one of these stakeholders:

- The Union Government, a state government, a school principal, a teacher, a parent, a student, an NGO, and a journalist
- Discuss how the stakeholder group you belong to can contribute to the successful implementation of the NEP. Present your ideas to the class. You can access the policy document at *https://static.pib.gov.in/WriteReadData/userfiles/NEP_Final_English_0.pdf*

THINK ABOUT IT

If any step in policy-making and implementation is skipped, what would be the implications? Discuss with a suitable example.

For a policy to be implemented effectively, it is always further organised into programmes and schemes. A policy is a broad goal

© NCERT not to be republished

or direction adopted by the government to address an important public issue. It tells us what the government wants to achieve and why. A programme explains the plan or approach for achieving that goal. A scheme is a specific action or initiative through which the programme is implemented so that its benefits reach the people. In simple terms, policy provides direction, programmes provide the plan, and schemes put the plan into action. Let us understand this through the example of the National Health Policy 2017, given in the following infographic.

Fig. 4.6. Difference between a policy, programme, and scheme

© NCERT not to be republished

Policy Coordination: Key to Good Governance

Public policymaking and implementation require multi-level planning and decision-making. This exercise becomes more complex and challenging in a country as vast and diverse as India.

Let us try to understand this with an example. The Government of India, recognising the transformative power of sports in nation-building and holistic development, launched the Khelo Bharat Niti in 2025 with the aim of transforming India's sports landscape. The government may plan a policy, but its success depends on many stakeholders—in this case, states, districts, local bodies, schools, coaches, families, and athletes. They all have different yet important roles to play. Families need to support a sports career for their children, especially their daughters; national or state governments need to encourage students, including specially abled students to take up sports; local authorities have the responsibility to maintain sports grounds or parks; scientists and innovators are expected to conduct research on better nutrition or equipment; and the Central Government has to visualise the importance of sports for holistic health as well as for international diplomacy.

Thus, the success of a policy, like Khelo Bharat Niti 2025, depends on the coordination between various



Fig. 4.7. Khelo Bharat Niti: A policy coordination exemplar

© NCERT not to be republished

stakeholders. The policy document of Khelo Bharat Niti says, "Strengthening the sporting culture and ecosystem from the block level to the national level is a key focus of the Khelo Bharat Niti 2025". At the national level, the role of the Union Government is primarily focused on providing the larger policy framework, including the policy objectives. Also, it is supposed to provide funding as well as identifying the sources of funding for its agencies located at lower vertical levels of states, districts and blocks. Khelo Bharat Niti mandates state governments to strengthen sporting ecosystems through initiatives such as 'Model Sports State'. State governments are expected to host major national games and tournaments and attract private investments through the public-private partnership (PPP) model to build sports infrastructure. Similarly, individual districts are encouraged to become 'Model Sports Districts' by enhancing their sports capabilities. Further at the level of blocks, sporting programmes are to be organised on a regular basis to attract mass participation and facilitate talent scouting.

Apart from the role of the government and its agencies, the Khelo Bharat Niti 2025 seeks an active role of private organisations and individual citizens as well. Private organisations can come forward to sponsor sportspersons and sports teams. They can invest in supporting scientific research programmes to develop better nutrition and equipment, and better medical facilities for sportspersons.

LET'S EXPLORE

1. As a student, what role can you play in the successful implementation of Khelo Bharat Niti 2025?
2. Your school is designated as the 'state's sports ambassador'. What actions should it take to fulfil its role as sports ambassador?
3. Which ministries of the government can contribute towards the success of Khelo Bharat Niti 2025? How?

Governance may sound like government, but it is more about how decisions are made, implemented, and connected to people's everyday lives. Public policy provides an important link between governance and public life. Through public policies, governments decide how resources should be used and how public services should be provided. Elected representatives, government officials, local institutions, civil society organisations, researchers, the media, the

© NCERT not to be republished

private sector, and people, all have different but connected roles in good governance. People, therefore, have an important contribution to make in the process of governance. By voting, following laws, raising concerns, participating in public affairs, and giving feedback on government services, they can help improve the way public institutions function. In a democratic country like India, governance is guided by the constitution, which lays down the framework for governing the nation.

Good governance is essential to strengthening democracy, promoting sustainable development, and ensuring national progress. It depends on transparent institutions, accountable leadership, active citizen participation, and a strong commitment to the rule of law. Public policy is integral to good governance. Good governance and public policy are crucial foundations for achieving national development goals. Good governance is, therefore, an ongoing effort that will help realise the vision of making India a developed, prosperous, and self-reliant nation.

Before we move on...

- Governance refers to the process of making, implementing, and monitoring decisions for the welfare of people, while government refers to the institutions that exercise political authority to govern.
- Good governance is based on principles such as participation, transparency, accountability, the rule of law, responsiveness, and efficiency, ensuring that public institutions serve the people effectively.
- India's understanding of governance has evolved from the ideas and values reflected in *Sabhā* and *Samiti*, *Rām Rājya*, and *Rājadharma* to the modern democratic system based on the Constitution and citizen participation.
- Public policy consists of decisions and actions taken by the government to solve public problems and promote the welfare of the people. Effective public policies are developed, implemented, monitored, and improved through a systematic policy process.
- Governance and public policy involve the combined efforts of many actors, including the government, institutions, civil society organisations, private sector, the media, and citizens, each performing complementary roles.

© NCERT not to be republished

- Policy coordination among different government departments, institutions, and stakeholders is essential for addressing public problems, responding to emergencies, and delivering public services efficiently.
- Active citizen participation through voting, providing feedback, obeying laws, community involvement, and holding public authorities accountable strengthens democracy and promotes good governance.

Questions and activities

1. "Good governance is the responsibility of the government alone." Do you agree with this statement? Give reasons to support your answer.
2. Do you think students can contribute to good governance? Write a short note describing any five ways in which students can become more responsible and active citizens.
3. Choose any one public policy [for example, Right to Education (RTE), Swachh Bharat Mission, PM POSHAN, Ayushman Bharat, Digital India, or Jal Jeevan Missio] and prepare a chart showing the following aspects:
   - The problem it addresses
   - The major stakeholders involved
   - How different actors coordinate
   - The role of citizens in its success

   Present your findings to the class.
4. Answer the following in one or two sentences.
   a. What is governance?
   b. How is governance different from government?
   c. What is meant by public policy?
   d. Name any four principles of good governance.
5. Compare the following and present your answer in a tabular form.
   a. Government and governance
   b. Policy and public policy

© NCERT not to be republished

6. Imagine you have been appointed to advise the district administration on improving governance. You have proposed six points (given below), but the administration decides to prioritise only three areas for improvement. Which three would you recommend as priority areas, and which one out of the three do you feel is the most important?

   a. Improve drinking water facilities in schools.

   b. Improve sanitation and public toilets in schools and market areas.

   c. Provide tricycles for orthopaedically challenged students.

   d. Install open-area swings and open-air gym in public parks.

   e. Ensure the vaccination of stray dogs to prevent rabies.

   f. Ensure distribution of iron and folic acid tablets for female students in schools.

7. Match the policy action point to its corresponding stage in the policy cycle.

S. no.	Policy action point	Stage of policy cycle
1.	Assessing the impact of the policy	Policy implementation
2.	Putting the policy into action	Policy evaluation
3.	Framing the legislation	Policy adoption
4.	Multi-dimensional consultation with stakeholders	Policy formulation
5.	Addressing a new need of the people	Policy desirability (problem identification)

8. Read the following case and answer the given questions.

   The government launches a programme to plant one lakh trees in a city. Funds are allocated, but only a few saplings survive because they are not watered or protected.

© NCERT not to be republished

a. Which stage of the policy cycle appears to be weak?

b. Which organisations should coordinate to improve the programme?

c. Suggest two measures that could improve the outcome.

9. Read each statement carefully. Do you agree or disagree? Give reasons for your answer.

a. A good public policy can fail if it is not implemented properly.

b. Citizen participation sometimes makes decision-making slower, but it can improve governance.

c. Technology alone cannot ensure good governance.

10. Design a public policy.

You are a member of your school's student representative body. Identify one issue, for example, plastic waste, water wastage, road safety, energy conservation, or littering in public places. Prepare a simple policy proposal that includes the following aspects of policymaking:

- The reason for selecting the issue
- Your proposed solution
- Who should implement it?
- How will students participate?
- How will you know whether the policy has succeeded?

Present your proposal to the class as a chart or slideshow presentation.

Notes

© NCERT not to be republished

Chapter 5

Managing Your Personal Finances

The Big Questions

1. *What is personal finance and why is it important for individuals?*
2. *What are the pillars of personal finance?*
3. *What are some common savings and investment options?*
4. *How can you protect your savings and assets?*
5. *What is income tax?*

0909CH05

© NCERT not to be republished

Have you ever received pocket money or money from relatives during festivals or special occasions? Think about how you usually use that money.

- Do you spend it immediately or save some of it?
- Do you keep your savings in a piggy bank *(gullak)* or somewhere else?
- How do you manage expenses, such as travelling to school, buying stationery, or occasionally purchasing food from the school canteen?
- Have you ever planned your spending to save for something you wanted later, like visiting your grandparents during summer break?

Fig. 5.1. Savings in a piggy bank

Our journey into managing money begins in childhood. As we grow into adulthood, we earn income, and spend it in many ways to fulfil our needs and wants. We also save money and make investments to achieve goals, such as buying a house or funding higher education.

Individuals and households in today's world have to make many decisions involving money. Money is, therefore, an important resource that should be utilised efficiently. This is where an understanding of personal finance becomes important. Personal finance refers to the planning and management of an individual's money to meet their needs and wants. It involves making smart financial decisions, such as how much to spend, how much to save,

where to invest, and how to prepare for future financial needs. For instance, if someone wants to buy a house in the next five years, in order to achieve this goal, they will have to plan and manage their money well.

Pillars of Personal Finance

Income
The money you receive (salary, business income, etc.).

Budgeting
Deciding how much to save, how much to spend, and how one spends that money on needs and wants.

Saving
Setting aside money for future needs or emergencies.

Investing
Deploying your savings in assets like stocks, mutual funds, etc.

Protection and risk management
Safeguarding your money and assets through insurance and debt management.

Fig. 5.2. Pillars of personal finance

Income (Earnings)

Income is the money a person receives regularly or occasionally in return for products sold or services rendered. It is the starting point of personal finance because without income, it is not possible to spend, save, or invest. For example:

- A teacher earns a monthly salary.
- A shopkeeper earns profits from a business.
- A person earns rent from letting out property.
- An investor earns interest from bank deposits.
- A shareholder receives dividends and interest from securities.

THINK ABOUT IT

- Have you ever thought about earning your own money? What kind of skill would you require and which work would you choose?
- There are many 'Earn While You Learn' programmes that allow college students to continue their education while earning an income through part-time work, internships, or apprenticeships. This not only provides financial support but also helps them gain practical skills, work experience, and a better understanding of the real-world workplace.

© NCERT not to be republished

Budgeting (Planning Expenses)

Budgeting means planning in advance how income will be spent. A **budget** is a written plan that aims to balance income and expenses. People often plan to save and make financial decisions with a specific purpose in mind to be achieved in future. For example, a family may decide how much money to save each month or spend monthly on food, rent, school fees, transport, etc. Other examples include:

- Saving for a school trip next month.
- Buying sports equipment after six months.
- Saving for higher education in the future.
- Setting aside money for emergencies.

Setting such financial goals helps people prioritise their needs and make careful decisions regarding spending, saving, and investing.

One simple way to set goals is to ask:

- What do I want to achieve?
- How much money will I need?
- By when do I want to achieve it?
- What steps can help me reach this goal?

Budgeting helps control unnecessary spending, such as excessive eating out or impulse shopping, and enables people to prioritise important expenses. It also helps people live within their means by balancing income and expenditure.

© NCERT not to be republished

THINK ABOUT IT

Suppose you and your friends need to buy new badminton rackets for an upcoming tournament because the old ones have worn out. How would you manage your budget to cover the cost? Would you cut back on other expenses, use your savings, or borrow the amount from your parents or friends?

LET'S EXPLORE

Think of all your expenses and prepare your monthly/weekly budget using the template on Page 122.

Steps in Budgeting

1) Identify your expenses

Begin by listing all your monthly expenses, both large and small. This helps you understand where your money is being spent.

2) Set a savings goal

Decide how much you want to save, what you are saving for, and by when you need to have it saved up. A clear goal makes saving easier. For example, to save ₹3,000 in six months for a new bicycle, you would need to save ₹500 each month.

3) Track your spending

Regularly compare your actual spending with your budget. This helps you identify areas where you may be overspending and make corrections if needed.

4) Review and adjust your budget

A budget should be reviewed periodically to reflect changes in income, expenses, or financial goals. For example, rising transport costs or unexpected medical expenses may require adjustments to the budget. Regular reviews keep the budget realistic and effective.



Fig. 5.3. Steps in budgeting

© NCERT not to be republished

Saving

Saving means keeping aside a part of one's income for future use and represents a financial surplus accumulated over time. Savings are important for comfortable living, and because life is uncertain and emergencies can arise at any time. People also save to make future investments in assets, such as fixed deposits, stocks, mutual funds, and real estate.

THINK ABOUT IT

- What would you do if you received ₹100 today? Would you save some or all of it, or spend it right away?
- In the Grade 9 Part 1 Chapter 'Building Blocks in Economics: The Problem of Choice', you learnt about wants and needs. Would you prefer spending the money on a want or a need?
- Financial experts often suggest saving first and spending what is left. Do you agree?
- Do you think individuals with low income can also save? Why or why not?

Investing (Growing Wealth)

Priya and Sameer both receive ₹500 as a birthday gift. Priya keeps her ₹500 in a piggy bank at home. One year later, she still has ₹500. Sameer puts his ₹500 into a savings scheme that earns 8% interest a year. One year later, he has ₹540. Both are being responsible with money, but are they doing the same thing?

Investing means putting your savings into assets with the aim of protecting their value and generating returns. It is like planting a mango tree—you do not get fruit immediately, but once you do, it continues to provide fruit for many years. While keeping savings in cash provides greater **liquidity**, investing helps increase wealth and protects the value of money. It also allows money to grow faster than the rate of **inflation**. For example, if a school bag costs ₹1,000 today, and inflation is 6% per year, the same bag may cost about ₹1,060 next year. If your money is simply kept at home and does not grow, you may not be able to buy the bag as your **purchasing power** will fall over time.

Do you remember the story of the king and the sage from the Grade 7 Chapter 'Banks and the Magic of Finance'? It explained the principle of compounding, where returns are earned not only on the original

Liquidity: Refers to how quickly and easily an asset can be converted into cash or cash equivalent without affecting its value.

Inflation: The increase in the prices of goods and services over time, which reduces the purchasing power of money. As prices rise, the same amount of money can buy fewer goods and services than before.

Purchasing power: The real-world value of money, measured by the quantity of goods and services a single unit of currency can buy. It determines your standard of living, as higher purchasing power means you get more goods and services with the same amount of money, while a decrease means you can afford less with the same amount of cash.

© NCERT not to be republished

investment (the principal) but also on the returns already earned, thereby accumulating high returns over time. Let us understand this again with an example.

Compounding: The process where an investment's earnings, such as interest or dividends, are reinvested to generate their own additional earnings over time.

Power of Early Investments

Suppose two people, Bhavisha and Dhruv, each save ₹1,000 at the end of every year and earn 7% annual interest. The only difference is that Bhavisha starts saving at the age of 25, while Dhruv begins at the age of 35. Although both save the same amount each year, but since Dhruv invested much later, by the age of 65, he accumulates only about 40% as much money as Bhavisha. This happens because **compounding** allows earlier investments to earn returns for a longer period, and those returns continue to generate additional returns over time.



Fig. 5.4. Power of compounding

LET'S EXPLORE

→ In Fig. 5.4 above, the curves are flatter in the beginning and tend to become steeper in the later years. Why do you think that happens?

→ Talk to your parents and find out the fixed deposit rates of their bank. You can also refer to the bank's website.

© NCERT not to be republished

But where can one invest? Let us explore some common investment options.



Fig. 5.5. Common investment options

a) Fixed Deposits (FDs)

Fixed deposits are among the most common and safest investment options offered by banks and post offices. In a fixed deposit, a person deposits a lump sum amount for a fixed period, such as one, three, or five years. During this period, the bank or post office pays a fixed rate of interest on this amount, which remains unchanged throughout the investment period. Fixed deposits offer assured returns and are suitable for people who prefer safety over high returns.

Other government-backed investment options include the Public Provident Fund (PPF) and small savings schemes, such as the National Savings Certificate (NSC) and the Sukanya Samriddhi Yojana. These schemes encourage long-term savings while providing safe and reasonable returns.

b) Bonds

Bonds are investments through which people lend money to the government or companies (issuers of bonds) for a fixed period. Bondholders earn regular interest. For example, if you buy a bond worth ₹10,000 that pays 5% interest per year, you will receive ₹500 as interest after one year. If the bond matures after one year, you will receive ₹10,500 in total. In reality, the **maturity period** ranges from 1 day to 30 years or more. You may also be able to sell the bond before maturity if you need the money earlier, making them more liquid. Government bonds are generally considered safer than **corporate bonds** and are suitable for those seeking a stable, predictable income.

Maturity period: The duration between its issue date and the point at which the issuer repays the principal amount.

Corporate bonds: Debt securities issued by companies to raise capital from investors. When you buy a corporate bond, you lend money to the company. In return, the company promises regular interest payments and to repay the initial principal amount when the bond matures.

© NCERT not to be republished

BSE SENSEX: The BSE SENSEX (Stock Exchange Sensitive Index) is the benchmark index of the Bombay Stock Exchange (BSE). It tracks the performance of 30 large, financially sound, and actively traded companies from different sectors of the economy and serves as an important indicator of the overall performance of the Indian stock market.

c) Stocks (Equity or Shares)

Shares represent ownership in a company. When a person buys shares, they become a part-owner of that company and may earn returns through dividends as well as an increase in the share price. Investing in shares involves higher risk because share prices fluctuate due to market conditions, company performance, and broader economic changes. However, shares also have the potential to generate higher returns over the long term. They are, therefore, suitable for investors who are willing to take greater risks for higher returns and who invest keeping the long term in mind.

LET'S ANALYSE

Look at the graph below that displays the performance of **BSE SENSEX** over the years. It fluctuates over short time periods; however, it can go up significantly in the long run. Why do you think these fluctuations happen? Discuss possible reasons with your classmates and find out more from newspapers, the internet, or by speaking to your family members.



Fig. 5.6. BSE SENSEX over the years

© NCERT not to be republished

d) Mutual funds

Mutual funds pool money from many investors and invest it in a basket of shares, bonds, or other financial assets. These investments are managed by professional fund managers who decide where to invest the money. If the investments perform well, investors earn returns in proportion to the amount they have invested. However, if the investments perform poorly, investors may incur losses.

Mutual funds are popular because they reduce risk by spreading investments across different types of assets, a strategy known as **portfolio diversification.** They are suitable for people who may not have the time, knowledge, or experience to manage investments on their own.

THINK ABOUT IT

Have you heard this disclaimer in mutual fund advertisements on the television?

"Mutual fund investments are subject to market risks. Please read all scheme-related documents carefully before investing."

Why do you think this is included?

Protection and Risk Management

Life is full of uncertainties, such as illness, accidents, loss of income, or damage to property. These unexpected events can lead to significant financial losses. Therefore, an important aspect of personal finance is protection—safeguarding your income, savings, and assets against such risks.

Insurance

One of the most effective ways to achieve financial protection is through insurance. Insurance is a legal contract in which an individual pays a regular amount, called a premium, to an insurance company. In return, the company agrees to provide financial compensation for specific losses or expenses covered under the policy. For example, a family may pay ₹500 every month for health insurance. If a family member requires medical treatment, the insurance company covers a large part of the hospital expenses. Without insurance, the family might have to use a substantial portion of its savings for the expenses incurred towards the treatment.

Insurance works on the principle of risk sharing. Many people pay premiums into a common pool. In case of any unexpected loss,

© NCERT not to be republished

those insured receive financial support from the insurance company. Therefore, insurance provides financial security during emergencies, reduces the impact of accidents, illness, or property damage, helps families recover from financial setbacks, and encourages people to save and plan their finances through regular premium payments.

Types of Insurance

a) Health Insurance

Health insurance helps cover medical expenses, such as hospitalisation, medicines, diagnostic tests, and treatments. It reduces the financial burden of illness or accidents and allows families to focus on recovery rather than worrying about medical costs. In India, government schemes such as Ayushman Bharat Pradhan Mantri Jan Arogya Yojana provide health insurance coverage to eligible low-income households.

b) Life Insurance

Life insurance provides financial support to a family if the policyholder, who may be the breadwinner of the family, passes away. It helps dependents meet daily expenses, continue children's education, and repay loans. Life insurance is an important tool for ensuring long-term financial security.

c) General Insurance

General insurance protects against losses related to vehicles, homes, businesses, and other property. For example:

- Motor insurance covers repair costs and damages caused by vehicle accidents.
- Property insurance protects homes and businesses against losses caused by fire, theft, flood, earthquake, and other disasters.
- Crop insurance protects farmers from financial losses as it covers damages caused by natural disasters, pests, and market price changes.
- Cattle insurance protects farmers and dairy owners against financial loss in case of death or disability of their animals.

Fig. 5.7. A person applying for a loan in a bank

Borrowing and Credit

Sometimes, people may need to borrow money from banks, relatives, or other sources as loans. Borrowing or using credit can be helpful when it is used for productive purposes, but it can become harmful if misused. For instance, an education loan can help a student pursue higher education, whereas borrowing money to purchase

© NCERT not to be republished

unnecessary consumer goods may lead to a **debt** burden and financial difficulties. Thus, responsible borrowing involves taking loans only when necessary and ensuring that they can be repaid on time.

Debt: Amount of money owed to somebody.

THINK ABOUT IT

Have you ever heard your parents say, "This month's EMI has been paid"? An EMI (equated monthly instalment) is the fixed amount of money a person pays every month to repay a loan.

Suppose a family buys a refrigerator costing ₹30,000 but does not want to pay the entire amount at once. In such a case, they may take a loan and repay it through an EMI of ₹3,000 every month for 12 months. Each EMI includes a portion of the original loan amount (the principal) as well as the interest charged by the lender. EMIs are commonly used to purchase mobile phones, household appliances, two-wheelers, homes, and cars.

- Why might a family choose to buy something on EMI even if it costs more in the long run?
- Can having too many EMIs affect savings and emergency funds?

Risk and Return

When deciding where to invest money, it is important to consider four factors—**risk, return, time horizon, and liquidity**.

Risk

Risk refers to the chance of losing money.

Return

Return is the profit earned from an investment.

Time horizon

Time horizon is the length of time for which money can remain invested.

Liquidity

Liquidity refers to how easily an asset can be converted into cash when needed.

Fig. 5.8. Factors to consider before investment decision

Different investment options have different levels of these factors. For example, fixed deposits (FDs) are generally low-risk options that provide steady but relatively lower returns. Mutual funds may offer higher returns, while shares (equity) have the potential to generate the highest returns over the long term but also involve the highest level of risk.

© NCERT not to be republished

In general, lower-risk investments tend to offer lower returns, while higher-risk investments may offer higher returns. Therefore, people should choose investments based on their financial goals, the amount of risk they are willing to take, and when they are likely to need the money.



Fig. 5.9. Relationship between risk and return

Taxes

Taxes are compulsory payments made by individuals and businesses to the government to fund public services, such as schools, hospitals, transport, defence, and other essential facilities. There are two main types of taxes:

- **Direct taxes,** which are paid directly on a person's or organisation's income or profits, such as the income tax.
- **Indirect taxes,** which are added to the price of goods and services, such as the Goods and Services Tax (GST).

Personal Income Tax

Personal income tax is a tax paid on the income a person earns in a year (called a financial year, say 1 April 2001 to 31 March 2002). All citizens of India with a personal income are required to pay income tax, with the sole exception of individuals who earn below a certain limit and are exempt from paying the tax. As income increases, the tax payable to the government also increases. This system is known as **progressive taxation,** which aims to reduce income inequality by imposing higher tax rates on individuals with higher incomes.

© NCERT not to be republished

The underlying principle is that people with greater financial capacity can afford to contribute a larger share of their earnings towards funding public services, such as schools, hospitals, roads, and security. Paying taxes honestly and on time is an important responsibility of every citizen as it contributes to the well-being of society and the development of the country.

Fig. 5.10. Filing income tax

India follows a slab system for calculating income tax, as shown in Table 5.1. Under this system, taxable income is divided into different ranges, called tax slabs, and each slab is taxed at a specified rate, as seen in Table 5.1. The tax slabs are proposed by the Ministry of Finance as part of the Union Budget presented to the Parliament every year. The Central Board of Direct Taxes (CBDT), under the Ministry of Finance, is responsible for administering the laws relating to direct taxes in India.

Table 5.1. New Tax Regime (Applicable for FY 2025–26)

Annual Income (₹)	Tax Rate (%)
Up to ₹4 lakh	Nil
₹4 lakh–₹8 lakh	5%
₹8 lakh–₹12 lakh	10%
₹12,00,001–₹16,00,000	15%
₹16,00,001–₹20,00,000	20%
₹20,00,001–₹24,00,000	25%
Above ₹24,00,000	30%

Let us understand how a person's income tax liability is calculated. Suppose Priya, a business analyst, earns ₹14 lakh per year. Firstly, her income to be taxed will be calculated as follows:

© NCERT not to be republished

Standard deduction: A fixed amount that salaried employees and pensioners can deduct from their income before calculating income tax, as allowed under the Income-tax Act, 2025

Step 1: Calculate Taxable Income

Particulars	Amount (₹)
Annual Salary	14,00,000
Standard Deduction	75,000
Taxable Income	13,25,000

Step 2: Applying the Tax Rate as per the Tax Slabs

Different portions of income are taxed at different rates. For Priya, the first ₹4 lakh of her income are not taxed; the next ₹4 lakh are taxed at 5%; the next ₹4 lakh are taxed at 10%, and so on, as seen in Table 5.2.

Table 5.2. Calculation of Income Tax as per the Tax Slabs

Portion of Income in the Tax Slab	Tax Rate	Tax on that Portion of Income
Up to ₹4,00,000	0%	0
₹4,00,001–₹8,00,000 (next ₹ 4,00,000)	5%	5% of ₹4,00,000 = ₹20,000
₹8,00,001–₹12,00,000 (next ₹4,00,000)	10%	10% of ₹4,00,000 = ₹40,000
₹12,00,001–₹13,25,000 (remaining ₹1,25,000)	15%	15% of ₹1,25,000 = ₹18,750
Total Tax		**₹78,750**

LET'S ANALYSE

→ Sai's taxable income is ₹3,80,000 in a financial year. How much income tax does he have to pay according to the above tax slabs?

→ Ask your parents, relative or a person in your neighbourhood if they file personal income tax returns. Make a small report on the procedure to file an income tax return. You may refer to the following website: *https://incometaxindia.gov.in/Pages/tax-services/file-income-tax-return.aspx*

© NCERT not to be republished

In conclusion, managing money wisely is not just about earning more—it is about making careful financial decisions at every stage, whether it involves spending, saving, investing, protecting against risks, borrowing responsibly, or paying taxes. The choices individuals make today shape their financial future and determine their ability to achieve financial stability while managing financial opportunities and challenges.

Before we move on...

- Making informed financial decisions from a young age builds financial security, independence, and confidence for the future.
- Personal finance rests on the five pillars—income, budgeting, saving, investing, and protection—to ensure financial security for individuals.
- Budgeting helps individuals plan their expenses, control unnecessary spending, and save for future needs. Saving and investing are important for building wealth, meeting goals, and protecting money from the effects of inflation.
- Different investment options involve different levels of risk and return, so investment choices should match an individual's goals and risk tolerance.
- Insurance protects individuals and families from financial losses during contingencies.
- Income tax helps governments provide essential public services and infrastructure. Paying taxes honestly is a citizen's responsibility, and helps the government provide public services and promote national development.

© NCERT not to be republished

Questions and activities

1. Why is managing money wisely important for all individuals irrespective of their income?
2. How can budgeting help people balance their present needs with their future financial goals? Give examples.
3. **School Reopening Budget Activity**

   Your parents have given you ₹3,000 to prepare for the new school year. Make a list of the items you need, find out their prices (by visiting local stores, or asking a parent or teacher),

and prepare a budget. Calculate the total cost and check whether it stays within ₹3,000.

- If your total is less than ₹3,000, you may add one additional item of your choice.
- If your total exceeds ₹3,000, decide which item(s) you can postpone or avoid buying to stay within your budget.

Use the budget template provided and ensure that all expenses are accurately calculated.

School Reopening Budget

Total Amount	₹3000
Expenses	**Amount**
School bag	₹
Books	₹
Uniform and shoes	₹
Notebooks	₹
Pens	₹
Pencils	₹
Art supplies	₹
Total Expenses	₹
Savings	₹

4. Why is saving alone often not enough to build wealth in the long run? How do investments help increase the value of money over time?

5. **Investment Planning Activity**

   Suppose you received cash gifts worth ₹3000 on your last birthday and decided to save ₹1500. With the help of your teacher, calculate the returns you might have earned if you had invested this amount in different combinations of investments. For example, what returns would you have received if you had invested ₹500 in a fixed deposit, ₹800 in the stock market, and ₹200 in gold? Try other combinations and find information on the returns from different investment options using reliable sources, such as newspapers, magazines, or official websites. Based on your findings, prepare an investment plan explaining why you think each investment option is suitable or unsuitable.

© NCERT not to be republished

6. How does inflation affect the value of money over time? Why should people consider inflation while making financial decisions?
7. Different investment options involve different levels of risk and return. Do you think taking higher risks is always the best way to earn higher returns? How should a person decide which investment option is most suitable for them?
8. Why do people buy insurance policies even though they may never face a major loss? How does insurance provide financial security?
9. Imagine your family receives ₹1,00,000 from farming, a small business, livestock sales, and savings. Help your family decide how to use the money wisely.

Step 1: Prepare a Budget

Allocate the ₹1,00,000 among the following categories:

Category	Amount (₹)	Percentage (%)
Savings		
Education		
Household expenses		
Health and emergency fund		
Farm or business investment		
Home improvement		
Festivals and recreation		
Other		
Total	**1,00,000**	**100%**

Step 2: Needs vs Wants

Classify each expense as a **need** or a **want** and give a reason.

Examples:

- School fees
- New mobile phone
- Better seeds or livestock feed
- Festival celebrations
- Water storage tank

© NCERT not to be republished

Step 3: Save for the Future

Suppose your family saves **₹30,000** at **8% compound interest per year.**

Using the formula **A = P(1 + r)^n**, where **A:** Amount, **P:** Principal, **r:** Rate of compound interest, **n:** number of years, calculate:

1. The amount after 5 years.
2. The interest earned.

Step 4: Save First, Spend Later

Many financial experts recommend:

Expenses = Income – Savings

If your family receives ₹1,00,000 and saves ₹20,000 first, only ₹80,000 is available for spending. This helps ensure that future needs and emergencies can be met.

Step 5: Reflect

1. What percentage of the money did you save?
2. Which expenses were needs and which were wants?
3. How can savings improve a family's financial security?
4. How does compound interest help money grow?

Challenge: Create a pie chart showing how the ₹1,00,000 was allocated across different categories.

Notes

© NCERT not to be republished

Chapter 6
From Ideas to Startups

The Big Questions

1. *How does entrepreneurship impact society and the economy?*
2. *What are some functional areas of a business?*
3. *How to develop a business plan?*

0909CH06

Imagine your school is hosting an annual festival, and you participate in the 'Young Entrepreneurs Challenge', where you have to develop a product or service for parents and children visiting your stall. You come up with an idea for a lemonade *(nimbu pani)* and set up a stall with your classmates. At the end of the day, you prepare and submit a detailed report on the expenses incurred and the **profit** made to your class teacher.

What do you think is required to run the stall? You will have to decide how much to spend on lemons and sugar, where to procure glasses, how much to charge for each glass, and so on. Also, you will have to assess how many people liked the drink and if you made a profit or loss. This simple activity captures the essence of running a business—planning, organising, and learning by doing. This is **entrepreneurship**, a process through which individuals, or a group of individuals, convert a potential idea into a business venture.

Every great business starts with an idea, a need, or a desire to innovate

Fig. 6.1. Elements of entrepreneurship

Profit: Money that is earned in trade or business after paying the costs of producing and selling goods and services.

© NCERT not to be republished



Fig. 6.2. Tasks performed by an entrepreneur

and meet the needs of society. Entrepreneurs are curious individuals who see opportunities where others see challenges and turn that spark into action. Whether it is leading a business that manufactures drones for traffic surveillance or creating eco-friendly jute bags that can replace plastic, an entrepreneur works hard, and is driven by passion and a commitment to creating value for society. Let us understand this through a story.

From a Dead Mouse to Riches

One day, a rich merchant told his king, "Even a dead mouse can be the start of a fortune, if someone works hard and uses their brain." A poor young man overheard this and decided to test it. He picked up a dead mouse and sold it to a shopkeeper for two coins since his cat was hungry. With those coins, the young man bought fruits and water, which he sold to a tired flower picker in exchange for flowers. He then sold the flowers in the city.

Fig. 6.3.

Step by step, he grew his small earnings by clearing fallen branches after a storm and selling them as firewood, trading grass with horse dealers, opening a refreshment shop to later even striking business with foreign merchants.

© NCERT not to be republished

With intelligence, dedication, and hard work the man became very wealthy. But he did not forget how it all started—with the merchant's words. Out of gratitude, he gave the merchant half his fortune. Also, the man used his wealth not just for himself, but to help communities in the city as well.

Fig. 6.4.

The story above is from the famous *Jataka Tales*. What can you take away from the tale? Is it about spotting opportunities or working smart? What kind of traits do you think entrepreneurs need to have? Discuss with your classmates.

Let us learn about stories of a few entrepreneurial minds who turned their ideas into reality.

From Rooftop to Revolution

In 1959, seven ordinary homemakers from a Mumbai **chawl** gathered on a rooftop with borrowed equipment, a recipe, and ₹80. Their goal was modest—earn some extra income by making and selling *papads.* They had no business degrees, no investors, and no master plan; instead, what they had was grit and unity. There were no factories at first; each woman took raw dough home every morning, rolled *papads* through the day between household tasks, and returned the finished pieces by evening with the condition that 'the quality had to be consistent'. They decided to start a cooperative society where every member who joined would be an equal owner, and profits would be shared equally regardless of seniority.

Chawl: A traditional, multi-storey residential tenement building, typically consisting of dense, single-room units.

In 1962, they registered the venture as Shri Mahila Griha Udyog Lijjat Papad, a cooperative society, where 'lijjat' means tasty in Gujarati. Afterwards, many branches opened across India and garnered thousands of members. In the 1980s and 90s, Lijjat expanded into other products like flour, masalas, and soaps, and exports began too, crossing a turnover of ₹100 crore. By 2023, the cooperative had over 45,000 women members, 83 branches, and an annual turnover of ₹1,600 crore.

The women begin work early in the morning, facilitated by pick-up and drop-off bus services. Lijjat also provides scholarships to

© NCERT not to be republished

Fig. 6.5.

the school-going children of the members to encourage them to pursue further education. The organisation has helped thousands of women become financially independent, empowered communities, and built a large-scale business while being completely self-reliant.

THINK ABOUT IT

- What problem was Lijjat solving beyond just selling *papads*?
- What challenges do you think the founders could have faced at the start? How might they have overcome them?
- Can you think of a similar cooperative idea you could start in your community?

The Man who Transformed the Hospitality Industry

Born in Punjab in 1898, Mohan Singh Oberoi faced hardships early in life when his father passed away while he was still an infant. After somehow completing his education, he moved to Shimla and took a job as a hotel desk clerk, earning just ₹50 a month.

Rather than limiting himself to his assigned duties, Mohan learned every aspect of hotel operations, from guest service to billing and administration. His dedication, curiosity, and willingness to take initiative set him apart.

In 1934, he took a bold step by **mortgaging** his wife's jewellery and investing all his savings to buy a small hotel. Despite the risks, he believed in his vision. Through hard work and determination, he

Mortgage: A mortgage is a special type of loan used to buy a house or land with some collateral.

© NCERT not to be republished

transformed struggling hotels into successful businesses, and went on to build one of India's largest hotel chains. He later established luxury hotels, founded a hotel management school, and expanded his business across the world. In 2001, the Government of India accorded him the Padma Bhushan. He passed away in 2002; by then, the Oberoi Group, named after him, had become one of the world's most respected hotel brands.

His journey shows how entrepreneurship is not only about having a good idea. It involves planning, teamwork, decision making, and the effective management of different areas of the business. For example:

- He **hired and trained skilled** staff to provide excellent hospitality services, and constantly worked to improve hotel facilities and guest experiences.
- He carefully **managed the business's finances** to support growth and expansion.
- His hotels were **renovated and operated efficiently** to maintain high standards.
- The company **built a trusted brand** known for luxury and quality service.
- **Customer satisfaction** remained the top priority in all hotel operations.

These are some of the functions that entrepreneurs and their teams perform. There are departments or groups within a company that focus on such distinct tasks and shared skills, also known as functional areas. Let us understand them in detail and learn how a business plan is prepared.

Business Plan—A Road Map for the Business

Let us assume that you and your friends decide to open a bakery together that offers snacks and desserts. How would you go about it? You have to consider many crucial questions, identify challenges, and plan at every stage before starting the bakery to turn this simple idea into a successful business venture. This is when a business plan is developed. It is a written document, a blueprint explaining the goals of the business and the steps to achieve them. It guides the entrepreneur from the initial idea stage to successfully starting and running the business. It also serves as a guide and roadmap for

© NCERT not to be republished

decision making, helping them stay organised, set priorities, and work systematically to grow the business.

Exploring aspects such as those listed below could be especially helpful while creating a business plan.

Fig. 6.6. Key considerations in making a Business Plan

© NCERT not to be republished

1. **Needs and idea:** To understand what people want, you would have to understand customer needs.
    - Do customers prefer fresh bread, cakes, pastries, or healthier options like whole wheat products?
    - Will the bakery provide fresh, affordable, or unique baked goods that were not available in the area before?
2. **Potential customers:** Knowing your customers helps you decide what kind of products to offer. To identify the target consumers, one may think about:
    - Decide whether to specialise in offering cakes, cupcakes for children, or savoury snacks for young adults, or everyday breads and confectionery items for families.
3. **Money and costs:** Your business needs a robust financial start, which begins with planning finances and estimating the initial investment required. This includes the cost of equipment, such as an oven, rent for the premise, staff salaries, ingredients, such as flour and nuts, and packaging.
    - How should funds be arranged? (through savings, loans from banks, friends, relatives, or investors)?
    - How much will the expenses be?
4. **Location:** You may want to choose the right place for your bakery.
    - Can choosing a busy area, such as near schools, colleges, or markets, help attract more customers?
    - Can selling online or taking orders through mobile apps help you reach more people?



Fig. 6.7.

5. **Human resources (people and skills):** You will have to decide how many people have to be hired and trained, and the required skills for the job.
    - Identify people for roles, such as bakers, helpers, and staff for billing or delivery.

© NCERT not to be republished

6. **Pricing and profits:** You may consider fixing prices carefully so that they not only cover your costs and generate profit but also remain affordable for customers.
    - How to balance profitability with affordability when setting prices of goods and services?
    - Can offering a range of pricing options help attract a wider set of customers, for example, cheaper mini cake jars?
7. **Promotion or marketing:** To spread awareness among people about the bakery, you may want to promote it through social media, posters, and provide special offers.
    - What kind of packaging can enhance the appeal and shelf-life of the bakery products?
    - How can customer service be improved to retain customers?

Fig. 6.8.

8. **Challenges and risks:** These are threats that disrupt operations or cause losses, for example, high competition, rising cost of raw materials, changing customer preferences, volatile cash flows, etc. These are an inevitable part of every business venture.
    - How can perishable **inventory** be managed effectively?
    - How can consistent quality in the products be ensured?
    - How should fluctuating customer demand be handled?
    - Are there other bakeries in the locality and how can we compete with them?

Inventory: The goods, materials, and assets a business holds for the purpose of manufacturing, production, or resale.

Accounting: Recording and tracking all the money related to the business so the owner knows how it is performing.

Functional Areas of a Business

The questions in Fig. 6.6 about a business can be grouped into a few main functional areas, like management and operations, finance and **accounting**, human resources, and marketing and sales. Each area has a specific function and helps the business run smoothly. They improve decision making and ensure resources are used properly. Together, they provide structure, better coordination, and help the business grow successfully. Let us learn about them in detail.

© NCERT not to be republished

FUNCTIONAL AREAS OF A BUSINESS

Every successful business runs on four key pillars. Together, they turn goals into growth.

1 Management and Operations

Looking after day-to-day matters

Key Focus: Efficient processes and smooth operations

Examples: Production, quality, supply chain, etc.

2 Finance and Accounting

Managing money wisely

Key Focus: Financial health and smart budgeting

Examples: Budgeting, reporting, cash flow, etc.

3 Human Resources

Managing people

Key Focus: Right people and skills

Examples: Hiring new staff, managing employee benefits, and handling workplace conflict resolution, etc.

4 Marketing and Sales

Spreading awareness and driving sales

Key Focus: Customer awareness and business growth

Examples: Advertising, promotions, sales, etc.

Fig. 6.9. Functional areas of a business

© NCERT not to be republished

Fixed cost: Business expenses that remain constant regardless of production volume or sales levels. They do not change with output in the short term and act as indirect or overhead costs, such as rent, salaries, or insurance.

Variable cost: Expenses that change in direct proportion to the volume of goods or services a business produces or sells. They increase as production rises and decrease as production falls, covering raw materials, packaging, etc.

Investment: The allocation of money or resources into an asset, venture, or project with the expectation of generating future income, profit, or value appreciation.

Management and Operations


Fig. 6.10.

Management and operations are essential for running a business smoothly. Management involves planning, organising, and guiding the use of resources to achieve business goals, such as increasing market share through customer satisfaction. Operations focuses on producing and delivering goods or services efficiently and on time. For example, in a bakery, you must choose the right equipment, arrange ingredients, monitor quality, and plan daily production to ensure fresh and high-quality products are made regularly without delay or wastage.

Finance and Accounting

Finance is the management of money in a business. It involves planning, obtaining, and using funds to help the business operate and grow.

For the bakery, you would have to plan for the following:

- Paying **fixed costs:** rent, equipment costs (ovens, mixers, refrigerators), etc.
- Paying **variable costs:** cost of ingredients, salaries, packaging material, etc.
- Investing in growth opportunities
- Managing profits and cash flow

Accounting is the process of recording, organising, and reporting a business's financial transactions. Every entrepreneur needs to understand basic accounting concepts to know how their business is doing. It means keeping track of the money coming in (revenue) and the money going out (expenses), and making sure all records or documents are correct. One important record is the profit and loss account (or income statement). It shows whether the business has made a profit or a loss over a period of time, such as a month or a year. This helps to make informed decisions about spending and **investment**. We can track what the business owns and how much has been borrowed. It also enables compliance with tax laws and regulations of the country.

Profit = Total Revenue – Total Expenses

Revenue is the total money earned by a business from its main operations or sale of goods and services. For example, ABC bakery

© NCERT not to be republished

may earn ₹2,95,000 in a month, as seen in its profit and loss account shown in Fig. 6.11.

Expenses include the money spent on running and maintaining a business. These include salaries to employees, electricity bills, cost of raw materials, etc. Further, there may be some interest to be paid on a loan and lastly, taxes to be paid to the government.

PROFIT AND LOSS ACCOUNT
*ABC Bakery (Teen enterprise) | For the month ended March 2026

Income		
	Particulars	**Amount (₹)**
	Revenue from operations (sales)	
	Bread and buns	₹1,20,000
	Pastries and cookies	₹75,000
	Cake orders	₹85,000
	Delivery charges	₹15,000
	Total Income	**₹2,95,000**
Expenses		
	Particulars	**Amount (₹)**
	Cost of goods sold (COGS)	
	Raw materials: flour, sugar	₹1,00,000
	Packaging material	₹12,000
	Rent	₹40,000
	Salaries and wages for staff	₹30,000
	Utilities (electricity and gas)	₹15,000
	Advertising and marketing (social media advertisements, posters)	₹8,000
	Miscellaneous expenses	₹7,000
	Interest on loan	₹10,000
	Total Expenses	**₹2,22,000**
Profit Calculation		
	Particulars	**Amount (₹)**
	Total sales	₹2,95,000
	Total expenses	– ₹2,22,000
	Profit before tax (PBT)	₹73,000
	Tax to be paid	– ₹13,000
	Profit after tax (PAT)	₹60,000

Fig. 6.11. A sample profit and loss account for ABC bakery
**This is a fictional name and any similarity in real world is purely coincidental*

Note: Students need not memorise the above categories.

© NCERT not to be republished

Human Resources

People are the heart of every business. Human resources are the individuals employed by the entrepreneur who contribute to the business. For a bakery, functions, such as hiring bakers, helpers, cleaners, and a cashier; training staff in hygiene and baking standards, and ensuring a comfortable and motivating workplace fall under the human resources department. They helps build a strong team with required skills that fosters business growth.

Marketing and Sales

The marketing and sales team helps attract customers and convinces them to buy the products. In a bakery, this includes choosing a catchy name, promoting the business on social media, and offering discounts.

Some simple strategies include:

- Creating unique or seasonal items and customised desserts like mango-flavoured cake.
- Offering discounts, deals, or special offers.
- Providing easy online ordering and delivery.
- Using social media to share photos and videos for awareness among people.
- Promoting eco-friendly practices of recyclable packaging material.

LET'S EXPLORE

→ Interview two people in your vicinity who run a business (tailor, shopkeeper, factory owner, etc.) and find out about their journey of starting the business by asking them the following questions:

- Why did they start the business?
- What were the challenges they faced?
- What were the risks taken?
- What did they learn from the process?

→ Prepare a short report on the tasks an entrepreneur performs at each stage, with reference to Fig. 6.2.

→ Based on the case study of Mohan Singh Oberoi on Page 128, which functional area helped improve the quality of the company's products? How did different functional areas work together to make the business successful? Now that you know about the functional areas of a business, create a business plan for your business idea using the template given on Page 142.

© NCERT not to be republished

India's Traditional Entrepreneurial Community

Entrepreneurship in India has deep roots among traditional communities, where skills, occupations, and occupational knowledge have been passed down through generations. Long before modern startups, these communities practised self-employment, innovation, and trade, forming the backbone of India's local economy.

The Chettiar (Nattukottai Chettiar) community from Tamil Nadu is a well-known traditional entrepreneurial community. Historically, Chettiars were traders, bankers, and moneylenders, operating not only across India but also in Sri Lanka, Burma (now Myanmar), Malaysia, and other parts of Southeast Asia. They were known for:

- Strong business ethics and trust-based lending
- Excellent accounting and record-keeping skills
- Reinvesting profits into trade, temples, education, and community welfare

The Chettiar community built wealth through trade in salt, rice, textiles, and finance, often without formal banks. Even today, Chettiar entrepreneurship inspires modern India by showing how risk-taking, discipline, and long-term vision can build sustainable businesses rooted in tradition.

Fig. 6.12. A traditional Chettiar home

© NCERT not to be republished

LET'S EXPLORE

Find out more about other regional communities who have excelled as entrepreneurs.

Startups and Their Contribution to the Nation

Startup: A young, early-stage company founded by entrepreneurs offering an innovative product or service.

India's vibrant **startup** ecosystem is built not only on innovation but also on perseverance. All entrepreneurs should be aware that there is a chance of their business ending in failure. So while some startups grow rapidly, others struggle or even close down. As with other things in life, there is nothing wrong with failure if an honest effort has been made. Hence, these experiences contribute to entrepreneurial learning, and every unsuccessful attempt offers lessons that help entrepreneurs develop stronger ideas and build better businesses in the future.

As was famously said by Swami Vivekananda:

> *"Arise, awake and stop not till the goal is reached.*

Atmanirbhar Bharat: A national policy framework launched by the government in 2020 to make the country self-sustaining, boost domestic manufacturing, and reduce import dependency.

With consistent hard work and perseverance, today, India is the third-largest startup ecosystem in the world, powered by its young and talented population. The startup world is growing fast, driven by creativity and technological support, with around 120 unicorns (startups valued at over 1 billion dollars) in 2025. These are working in exciting fields, like e-commerce (online shopping), fin-tech (digital payments), health-tech (online healthcare), and agri-tech (farming technology). Cities like Bengaluru, Hyderabad, Mumbai, and Delhi NCR have become major startup hubs. These ventures are creating jobs, supporting sustainability, and driving economic growth.

Viksit Bharat 2047: The Government of India's vision to transform India into a fully developed nation by 2047, marking 100 years of independence.

In recognition of the importance of promoting entrepreneurship, the government has introduced many schemes, such as Startup India, which supports the vision of **Atmanirbhar Bharat**, focusing on making India self-reliant through innovation and local solutions. As India moves towards the vision of **Viksit Bharat 2047**, entrepreneurship will continue to play a vital role in creating employment, driving innovation, empowering communities, and building a more prosperous, self-reliant, and sustainable nation. The next generation of entrepreneurs may well be sitting in your classroom today, ready to transform ideas into solutions that make a meaningful difference to society.

© NCERT not to be republished

IMPROVING QUALITY OF LIFE

Medicines, transportation, technology, and innovations

CREATING JOBS AND INCOME



Employment for households

PAYING TAXES TO THE GOVERNMENT

Funding roads, schools, and hospitals

PRODUCING GOODS AND SERVICES

Boosting economic activity

MAKING INNOVATIONS

Driving economic growth and offering solutions

CORPORATE SOCIAL RESPONSIBILITY

Education, environment, and healthcare

Fig. 6.13. Contribution of businesses to society and economy

© NCERT not to be republished

Before we move on...

- Entrepreneurship is the process of turning ideas into action by identifying opportunities, taking risks, and creating value for society.
- A business plan acts as a roadmap that helps entrepreneurs set goals, organise resources, and make informed decisions.
- Every business has key functional areas—management and operations, finance and accounting, human resources, and marketing and sales—that work together for success.
- Understanding revenue, expenses, profit, and cash flow helps businesses track performance and remain financially sustainable.
- Challenges, risks, and even failures are part of the entrepreneurial journey and provide valuable opportunities for learning and improvement.
- Startups and entrepreneurs drive innovation, create jobs, solve real-world problems, and contribute to the vision of a Viksit Bharat 2047.

Questions and activities

1. Explain why a business can fail even with a great idea if one functional area [finance, human resources (HR), operations, or marketing] is weak. If you were running a bakery, which functional area would you prioritise first and why?
2. Do you think innovation alone is enough to make a business successful? Why or why not?
3. "A business plan is a dynamic roadmap for a startup." Explain this statement with suitable examples. When should one change the business plan?
4. Do you think every entrepreneur should think about the impact of their goods or services on society and the environment? Explain using relevant examples.
5. In 1931, two brothers, Digambar and Govind Dandekar, started a small business in South Mumbai selling ink powder. They began with limited resources, using recycled glass bottles to sell liquid ink. At first, they faced financial problems and struggled to convince customers to trust their products. Instead of giving up,

© NCERT not to be republished

they focused on providing good-quality stationery at affordable prices. As the business grew, they noticed that artists in India did not have access to good art materials. Seeing this as an opportunity, they travelled to Glasgow to study colour chemistry and improve their products. After returning to India, they set up a laboratory to develop colours and art supplies suited to Indian needs. Over time, the company expanded into pencils, crayons, geometry boxes, and paints, eventually becoming a well-known brand.

- What entrepreneurial qualities did the Dandekar brothers display?
- What opportunity did they identify in the market?
- Was travelling to Glasgow a risky decision?
- Which functional area helped the company improve its products?
- How did they serve society apart from earning profits?

6. How do you think entrepreneurship is important for India's goal of becoming a developed nation by 2047?
7. Choose a product or service and develop a business plan for it using the following template:
   - Business name
   - Business idea
   - Target customers
   - Product/service and price
   - Marketing idea
   - Basic cost and expected profit
8. Find out about various government schemes to promote entrepreneurs in India. Learn about the eligibility requirements of these schemes. Prepare a write-up and discuss in the class.
9. Take any popular brand and identify:
   - The problem it tackles
   - Its initial target customers
   - How it differentiated itself from other competitors or brands
   - The resources it may have started with

© NCERT not to be republished

10. Over the next week, observe your daily routine at school and home. Identify 2–3 problems or inconveniences you or others face. For each problem, answer the following questions in a tabular format:
    - Who faces this problem?
    - How often does it occur?
    - Why hasn't it been solved yet?
    - What business idea could solve it?
    - Would people pay for your solution?
11. Think of your startup idea and fill in the business plan template given below:

    a. Business idea

    Name of the company or shop: _____

    Product/service: _____

    Tagline (optional): _____

    b. Entrepreneur profile

    Founder(s): _____

    Why did you choose this business idea?

    _____

    _____

    What problem does your business solve?

    _____

    _____

    c. Target customers

    Who will buy your product or service?

    ☐ Students ☐ Tourists

    ☐ Parents ☐ Farmers

    ☐ Local residents ☐ Businesses

    ☐ Others: _____

    Describe your target customers:

    _____

    _____

© NCERT not to be republished

d. Market research

Find answers to the following questions about potential customers.

Question	Findings
What do the customers need?	
What products or services already exist?	
How is your idea different?	

e. Product or service description

Describe your product or service. List its key features and benefits:

_____

_____

_____

_____

f. Resources required

Resource	What is needed and how much?
Human Resources	
Finance	
Materials	
Technology	
Infrastructure	

g. Operations plan

How will the business work? Write the steps. You may depict this using a flow chart.

h. Marketing plan

How will customers learn about your business?

- ☐ Posters
- ☐ Social media
- ☐ Word of mouth
- ☐ Other: _____
- ☐ School events
- ☐ Local market
- ☐ Newspapers

© NCERT not to be republished

i. Financial plan

Source(s) of finance:

Estimated monthly cost on various items:

Item	Cost (₹)
Total Cost	

Details of expected monthly revenue sources:

Source of Income	Amount (₹)
Total Revenue	

Expected Profit:

Revenue – Cost

₹ _____

j. Risks and challenges

What challenges might your business face?

_____

_____

k. Social and environmental impact

How will your business help people or the environment?

_____

_____

l. Conclusion

Why do you believe your business will succeed?

_____

_____

_____

© NCERT not to be republished

12. **Visit a factory or a production unit.**

Explore how a business operates by visiting a factory or production unit that manufactures a product. Prepare questions for the owner or manager, such as:

- What product does the factory produce?
- Who are its customers?
- How did the business start?
- What challenges did the business face in its early years?
- How does the business manage its finances?
- How are employees recruited and trained?
- How are products supplied to wholesalers, retailers, or consumers?

During the visit, observe the production process carefully. Note the resources used, such as raw materials, machinery and technology, workers, and managers. Interact with the owner or manager and record key information. Take notes and photographs (if permitted).

After the visit:

- Understand the manufacturing process and create a process map showing the journey of the product from raw materials to the final customer.
- Identify barriers to growth, such as:
  - → **Financial Barriers:** Lack of capital, difficulty obtaining loans or credit, etc.
  - → **Technical Barriers:** Outdated machinery, limited access to technology, etc.
  - → **Human Resource Barriers:** Skill shortages, difficulty hiring or retaining workers, etc.
  - → **Market Barriers:** Competition, limited access to suppliers or customers, etc.
  - → **Regulatory Barriers:** Complex procedures, licences, approvals, or paperwork, etc.

Recommend some practical solutions through which the business could overcome these challenges. Share your findings by preparing

© NCERT not to be republished

a presentation and a report highlighting your observations, analysis, and recommendations. The format of the report may be as follows:

- Introduction
- Production or service delivery process (with diagrams or flowcharts)
- Resources required
- Barriers identified (supported by observations or evidence)
- Suggested solutions
- Reflection: key lessons learned from the visit

Notes

© NCERT not to be republished

© NCERT not to be republished

Political Map of India



Physical Map of India

Images and maps from external sources

NCERT thanks the following organisations and individuals for permission to use their images:

1. Organisations and individuals

- Fig. 1.13. https://www.newindianexpress.com/states/tamil-nadu/2017/Dec/26/tamil-nadu-remembers-2004-tsunami-victims-1737199.html
- Fig. 2.9. Courtesy: Petr Kratochvil; https://www.publicdomainpictures.net/en/view-image.php?image=370929&picture=tropical-fish-underwater
- Fig. 2.14. https://commons.wikimedia.org/wiki/File:Advantage_Zone_@_Thenmala_Eco_Tourism_-_panoramio.jpg
- Fig. 2.18.
  - → Jonbeel Mela, Courtesy: Manab Jyoti
- Fig. 2.20. https://ndma.gov.in/sites/default/files/PDF/Newsletters/Aapda-Samvaad-Issue-April-2021.pdf
- Fig. 2.22.
  - → Courtesy: Vikas Choudhary, Centre for Science and Environment (CSE)
  - → Courtesy: Supriya Singh, Centre for Science and Environment (CSE), India, https://ceecec.net/case-studies/mendha-lekha-using-self-governance-to-achieve-ecological-prosperity-and-livelihood-security/
- Fig. 2.23. Credit: Vipul Singh, Delhi University, Delhi
- Fig. 2.24. https://bhuvan-app1.nrsc.gov.in/mwrds/
- Fig. 3.2. Royal Asiatic Society of Great Britain and Ireland; https://royalasiaticsociety.org/haldighati450/
- Fig. 3.3. https://www.india.gov.in/explore-india/travel-and-tourism/details/victory-memorial-in-dewair-3179634927032207
- Fig. 3.4. https://museumsofindia.gov.in/repository/record/alh_ald-AM-MIN-654-1802
- Fig. 3.5. https://arvindsinghmewar.com/coatofarms.php
- Fig. 3.8. https://commons.wikimedia.org/wiki/File:Model_of_Kaile_Bachari_Boat_2A.jpg
- Fig. 3.9. https://commons.wikimedia.org/wiki/File:071017_Vitthala_temple_complex_aerial_view,_Hampi_Karnataka.jpg
- Fig. 3.10. Rare Book Society of India; https://rarebooksocietyofindia.org/grid-layout.php?q=shivaji&page=2
- Fig. 3.11. https://en.wikipedia.org/wiki/Raigad_Fort#/media/File:Nagarkhana,_Raigad_Fort,_India.jpg
- Fig. 3.15. https://en.wikipedia.org/wiki/Golden_Temple#/media/File:1880_photograph_of_the_Golden_Temple,_Darbar_Sahib,_sacred_pool_and_nearby_buildings,_Amritsar.jpg
- Fig. 3.16. https://pt.wikipedia.org/wiki/Ficheiro:Saint_Kabir_with_Namdeva,_Raidas_and_Pipaji._Jaipur,_early_19century,_National_Museum_New_Delhi_%282%29.jpg
- Fig. 3.17. https://en.wikipedia.org/wiki/Chaitanya_Mahaprabhu#/media/File:Chaitanya_Deva_listening_to_the_Bhagabata_-_History_of_Bengali_Language_and_Literature.png
- Fig. 3.18. https://en.wikipedia.org/wiki/Atukuri_Molla#/media/File:Atukuri_Molla_2017_stamp_of_India.jpg

© NCERT not to be republished

- Fig. 3.21. Ministry of Culture, Government of India; https://museumsofindia.gov.in/repository/record/im_kol-D-1-90276
- Fig. 3.23. https://commons.wikimedia.org/wiki/File:Brihadisvara_Temple,_Thanjavur,_Tamil_Nadu,_India_(2017).jpg
- Fig. 3.24. https://kashi.gov.in/listing-details/shri-kashi-vishwanath
- Fig. 3.26. https://commons.wikimedia.org/wiki/File:Jama_Masjid_-_In_the_Noon.jpg
- Fig. 3.27. https://commons.wikimedia.org/wiki/File:Jagdish_Temple_Udaipur.jpg
- Fig. 3.28. Ministry of Culture; https://museumsofindia.gov.in/repository/record/vmh_kol-R6787-23482
- Fig. 3.29. Courtesy: Bibliothèque Nationale de France - https://gallica.bnf.fr/ark:/12148/btv1b10538068s/f89.item#
- Fig. 3.31. Courtesy: BnF or Bibliothèque Nationale de France - https://gallica.bnf.fr/ark:/12148/btv1b10538068s/f71.item
- Fig. 4.2. Courtesy: Vummidi Bangaru Jewellers India Pvt Ltd

2. Royalty free stock from dreamstime.com

- Fig. 1.8, 1.10, 1.12, 1.14
- Fig. 2.3, 2.4, 2.6, 2.7, 2.8, 2.10, 2.11, 2.12, 2.17, 2.18, 2.21
- Fig. 3.7, 3.12, 3.13, 3.22, 3.25
- Fig. 5.10
- Fig. 6.12

3. AI generated images

- Fig. 1.1, 1.11
- Fig. 2.1, 2.5
- Fig. 5.1
- Fig. 6.1, 6.5, 6.10, 6.13

© NCERT not to be republished

NOTES

© NCERT
not to be republished